MILITARY SPECIFICATION

ANTENNA AT-1108( )/ARC

Superseding
MIL-A-55680(EL)
30 September 1969

1. SCOPE

1.1 This specification covers one type of communication airborne antenna which operates within the frequency ranges of 116 to 152 MHz and 225 to 400 MHz and is designated Antenna AT-1108( )/ARC. (See 6.3)

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

| | |
|---|---|
| MIL-P-116 | Preservation, Method of |
| MIL-E-5272 | Environmental Testing, Aeronautical Associated Equipment, General Specification for |
| MIL-P-11268 | Parts, Materials, and Processes Used in Electronic Communication Equipment |
| MIL-M-13231 | Marking of Electronic Items |
| MIL-F-14072 | Finish for Ground Signal Equipment |
| MIL-A-55485 | Antenna AT-1108( )/ARC Packaging and Packing of |

STANDARDS

MILITARY

| | |
|---|---|
| MIL-STD-105 | Sampling Procedures, and Tables for Inspection by Attributes |
| MIL-STD-252 | Wired Equipment, Classification of Visual and Mechanical Defects |
| MIL-STD-454 | Standard General Requirement for Electronic Equipment |
| MIL-STD-810 | Environmental Test Method |

DRAWINGS



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

ELECTRONIC COMMAND USAECOM

SC-D-459388 AT-1108( )/ARC

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity, or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies).

3. REQUIREMENTS

3.1 Description. - Antenna AT-1108( )/ARC shall be a combined UHF/VHF, lightweight airborne antenna utilizing two (2) separate inputs which will operate in the VHF range of 116 to 152 MHz and UHF range of 225 to 400 MHz. The antenna will have vertically polarized type emission and receive either vertically or circularly polarized signals. The antenna shall be small in size with the radiation elements incased in an abrasive resistant epoxy covering, and formed in an air foil design to reduce drag.

3.2 Performance. - The antenna shall be subjected to and meet all the requirements of this specification.

3.3 Preproduction samples. - The contractor shall furnish two (2) pre-production samples for approval, if required by the invitation for bids and contract. (See 4.3 and 6.2)

3.4 Finish, protective. - The equipment shall be finished in accordance with MIL-F-14072. This includes finish of hardware, such as screws, etc, and necessary touch-up after mounting. The final paint film on Type I surface shall be lusterless black epoxy Color No. 3725 in Specification MIL-F-14072. (See 4.4)

3.5 Marking. -

3.5.1 General. - Marking shall conform to Specification MIL-M-13231. (See 4.4)

3.5.2 Visibility. - Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.5.3 Serial numbers. - The antennas on order shall be serial numbered.

3.6 Cleaning. -



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

3.6.1 Parts. - After fabrication, parts shall be cleaned in accordance with good commercial practice or as specified on the equipment drawings. Cleaning processes shall have no deleterious effect. Corrosive material shall be removed completely before the parts are mounted on chassis, panels, etc.

3.6.2 Units. - After assembly, units shall be cleaned thoroughly and shall be free from particles of solder, flux and other foreign material. In addition, when necessary, such cleaning shall also be performed before final assembly of the units.

3.7 Form, fit. - The antennas on this order shall comply with Drawing SC-D-459388.

3.8 Physical construction.- Physical construction of the equipment shall conform to SC-D-459388.

3.9 Connectors, input. - The input connector for the VHF band shall be a BNC Female Type and the connector for the UHF band shall be a TNC Female Type connector as shown on Drawing SC-D-459388.

3.10 Tropicalization of materials. -

3.10.1 Treatment of materials. - Fungus-inert materials shall be used where practicable. These materials shall be in accordance with requirement 4 of MIL-STD-454. When materials are required to be treated, they shall be cleaned in accordance with requirement 9 of MIL-STD-454 and then shall be treated in accordance with 3.10.2 through 3.10.4 and applicable paragraphs of MIL-P-11268. Overall treatment is not required. However, any parts and materials susceptible to moisture and fungi (or whose moisture-and-fungus resistance properties cannot be determined) that have not been treated before assembly shall be individually treated.

3.10.2 Treating compounds. - Treating compounds containing a mercury-bearing fungicide shall not be used. The contractor shall determine that the treating compound is compatible with the material or surface to be treated. Selection of treating compounds shall be such that any increase in flammability of treated material will be held to the practical minimum.

3.10.3 Toxicity. - Treating materials shall cause no skin irritation or other injury to personnel handling the treated material during fabrication, transportation, operation, or maintenance of the equipment, or during use of the finished items when used for the purpose intended.

3.10.4 Flexibility. - Treatment shall not affect the flexibility of treated materials, to the extent that the equipment may fail to meet specified requirements when subjected to specified service conditions.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

3.10.5 Statement of treatment. - The statement of treatment shall indicate whether or not nutrient materials have been employed. If nutrient materials have been used, it shall also describe in detail the materials to be treated and the treating compounds and processes that the contractor proposes to use. (See 6.2)

3.11 Service conditions (See 4.7). - The unit(s) shall meet the service conditions specified in Specification MIL-E-5272 except as otherwise specified herein:

3.11.1 Temperature-Altitude (See 4.7.1).

a. Operating. - Continuous operation conforming to limits specified for natural conditions at altitudes up to 50,000 feet above sea level and at temperatures from -54°C to +55°C. Intermittent operation to +71°C.

b. Non-operating. - At altitudes up to 50,000 feet above sea level at temperatures from -62°C to +71°C there shall be no deterioration.

3.11.2 Relative humidity (See 4.7.2). - The unit(s) shall withstand 95% relative humidity when tested in accordance with 4.7.2.

3.11.3 Vibration (See 4.7.3). - The unit(s) shall withstand vibration normally encountered in both fixed and rotary wing aircraft when tested in accordance with 4.7.3.

3.11.4 Rain (See 4.7.4). - The unit(s) shall meet the performance requirements of this document when subjected to rain as encountered in service.

3.11.5 Sand and dust (See 4.7.5). - The unit(s) shall withstand exposure to sand and dust particles as encountered in desert areas.

3.11.6 Shock (See 4.7.6). - The unit(s) shall withstand the impact shock of 30g.

3.11.7 Acceleration (See 4.7.7). - The unit(s) shall withstand 6g steady state acceleration for one minute.

3.11.8 Salt fog (See 4.7.8). - The units shall be exposed, in normal operating configuration to salt fog for 48 hours and shall show no evidence of corrosion as evidenced by any visible degradation that can be attributed to flaky, pitted, blistered or otherwise loosened finish.

3.12 Electrical requirements (See 4.8). -



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

3.12.1 Impedance, input/output (See 4.8.1). - The unit(s) shall have a nominal 50 ohm impedance over the frequency ranges as specified.

3.12.2 Voltage standing wave ratio (VSWR) (See 4.8.2). - The VSWR shall not exceed 2.0:1.0 over the frequency range of the VHF band from 116 to 152 MHz and the UHF band from 225 to 400 MHz when mounted on a 4 ft ground plane.

3.12.3 Omnidirectional pattern (See 4.8.3). - The antenna pattern shall be within ±3 db of omnidirectional in azimuth plane (parallel to level flight of aircraft) and shall be within ±5 db of omnidirectional in azimuthal cuts of deflection from horizontal to a maximum deflection of 45 degrees.

3.12.4 Gain, Antenna (See 4.8.4). - Utilizing a reference 0.5 wave dipole, the gain of the antenna shall be a minimum of -6 db.

3.12.5 Isolation, bands (See 4.8.5). - The isolation between the bands as measured between the connectors shall be not less than 20 db.

3.12.6 Power input, rf (See 4.8.6). - There shall be no degradation of the VSWR readings greater than 0.1 unit after the equipment is subjected to 50 watts of RF power. The VSWR maximum of 2.0:1.0 shall still apply.

3.13 Operational inspection (See 4.11). - Each unit shall be capable of meeting the specified test after applicable processes, inspections and tests have been completed to determine that each unit on order is operable prior to packaging.

3.14 Interchangeability (See 4.10). - Like units, and replaceable parts shall be physically and functionally interchangeable, without modification of such items or of the equipment. Individual items shall not be hand picked for fit or performance, however, matched pairs or sets, when permitted, may be interchangeable as such. Reliance shall not be placed on any unspecified dimension rating, characteristic, etc.

3.15 Technical literature (See 6.2). - Technical literature shall be furnished if specified in the contract.

3.16 Workmanship. - The unit(s) shall be manufactured and assembled in accordance with requirement nine (9) of MIL-STD-454 and the following paragraphs herein:

| | |
|---|---|
| Cleaning | 3.6 |
| Tropicalization of materials | 3.10 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. - Inspection shall be classified as follows:

a. Preproduction inspection (does not include preparation for delivery). (See 4.3)

b. Inspection covered by subsidiary documents. (See 4.4)

c. Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5)

(2) Quality conformance inspection of preparation for delivery. (See 4.12)

4.3 Preproduction inspection. - This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified for Group A, Group B and Group C (See Tables I, and II, and III respectively). The preproduction inspection will normally be performed in this order: (1) vibration, (2) shock; other preproduction inspection may precede, follow, or be interspersed between the foregoing.

4.4 Inspection covered by subsidiary documents. - The following shall be inspected under the applicable subsidiary documents as part of the inspection of the units before preparation for delivery:

| Item | Where Required |
|---|---|
| Finish Protective | 3.4 |
| Marking | 3.5 |
| Form, Fit | 3.7 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

4.5 Quality conformance inspection of equipment before preparation for delivery. - The contractor shall perform the inspection specified in 4.4 and 4.5.1 through 4.5.4. This does not relieve the contractor of his responsibility for performance of any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government, at its discretion, may perform all of any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.8) Test equipment for Government verification inspection shall be made available by the contractor.

4.5.1 Group A inspection. - Each unit of each lot of equipment shall be inspected for conformance to all the inspection and test requirements of Table I. Each lot will be subject to verification utilizing the procedures of MIL-STD-105 using the general inspection levels and the AQL's indicated in Table I. Group A inspection shall be performed in any order which is satisfactory to the Government, except that the operational inspection 4.11 shall be last (See 6.7).

Table I. - Group A Inspection

| Inspection | Reqt Par | Insp Par | AQL Major | AQL Minor |
|---|---|---|---|---|
| Visual & Mechanical | 3.16 | 4.9 | | |
| Antenna (less cover) | | | 0.65% | 2.5% |
| Antenna AT-1108( )/ARC | | | 1.0% | 4.0% |
| Electrical | | | | |
| Voltage Standing Wave Ratio | 3.12.2 | 4.8.2 | *1% for the combined Group | |
| Power, Input RF | 3.12.6 | 4.8.6 | | |
| Operational Inspection | 3.13 | 4.11 | 0.1% | |

*All electrical defects shall be considered major defects.

4.5.2 Group B inspection. - This inspection, including sampling, shall conform to Table II and to the procedures for small-sample inspection of Standard MIL-STD-105, using special inspection level S-4. The Group B inspection shall normally be performed on inspection lots that have passed Group A inspection



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

and on samples selected from units that have met the Group A inspection.

Table II. - Group B Inspection

| Inspection | Reqt Par | Insp Par | AQL |
|---|---|---|---|
| Impedance, Input/Output | 3.12.1 | 4.8.1 | 6.5% |
| Isolation, Bands | 3.12.5 | 4.8.5 | 6.5% |
| Interchangeability | 3.14 | 4.10 | 6.5% |

4.5.3 Group C inspection. - This inspection shall be as listed in Table III and shall normally be performed on sample units that have been subjected to and met Group A and Group B inspection. No defects shall be allowed. Sample unit(s) shall be selected in accordance with 4.5.3.1.

Table III. - Group C Inspection

| Inspection | Reqt Par | Insp Par |
|---|---|---|
| Subgroup I: | | |
| Temperature-Altitude | 3.11.1 | 4.7.1 |
| Relative Humidity | 3.11.2 | 4.7.2 |
| Vibration | 3.11.3 | 4.7.3 |
| Omnidirectional Pattern | 3.12.3 | 4.8.3 |
| Gain, Antenna | 3.12.4 | 4.8.4 |
| Subgroup II: | | |
| Rain | 3.11.4 | 4.7.4 |
| Sand and Dust | 3.11.5 | 4.7.5 |
| Shock | 3.11.6 | 4.7.6 |
| Acceleration | 3.11.7 | 4.7.7 |
| Salt Fog | 3.11.8 | 4.7.8 |

4.5.3.1 Sampling for inspection of equipment. - Units selected for each Group C inspection shall be selected without regard to their quality in accordance with the following:

4.5.3.1.1 Subgroup I. - For this subgroup, two units from the first 25 production units shall be selected for the first Group C inspection. For



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

subsequent Group C inspection, two units each month shall be selected.

4.5.3.1.2 Subgroup II. - For this subgroup, two units from the first 25 production units shall be selected for the first Group C inspection. For subsequent Group C inspection, two units every two months shall be selected.

4.5.3.2 Noncompliance. - The contractor shall immediately report in writing each Group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on (i) the process and materials, as applicable, and (ii) all units of product which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract through the Product Assurance Representative. After corrective action has been taken, additional sample units shall be subjected to Group C inspection (all inspections, or the inspections which the sample failed, at the option of the Government) and Group A and B inspection may be reinstituted; however, final acceptance and shipment will be withheld until the Group C reinspection results have shown that the corrective action was effective (See 6.4).

4.5.4 Reinspection of conforming group C sample units. - Unless otherwise specified, sample units which have been subjected to and pass Group C inspection may be delivered on the contract or order, provided all damage is repaired, cleaned of all foreign matter, and the sample units are resubjected to and pass Group A inspection

4.6 Standard test conditions. - The following test condition shall apply when specified herein:

a. Ground plane:

(1) Material: Aluminum

(2) Thickness: 1/8 inch minimum

(3) Round

(a) Diameter: 4 feet

(b) Reinforced on back side if required

b. Impedance: 50 ohms nominal



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

c. Free space: Minimum distance to nearest object 25 feet

d. Test frequencies: The frequencies utilized shall spaced at least every 5 MHz in the VHF band and at least every 15 MHz in the UHF band, and shall include the end points of each band.

4.7 Service conditions. - The unit(s) shall be subjected to and meet the service conditions in accordance with MIL-E-5272, unless otherwise specified. The electrical test of 4.8.2 (VSWR) shall be conducted prior to and subsequent to each service condition that requires a test to be conducted. The measurement in this test shall not change more than five (5) percent from the value measured prior to subjection to the test condition.

4.7.1 Temperature-Altitude. - The unit(s) shall be subjected to Procedure I of Specification MIL-E-5272 for compliance with 3.11.1. The following steps of Procedure I shall be altered as indicated:

Step 2 - Before the operational check the equipment shall be maintained at -54°C and atmospheric pressure for 24 hours.

Step 3 - The unit(s) shall be maintained in a non-operative state for 2 hours at -54°C and 50,000 ft. The operational test at -54°C and 50,000 ft. shall be conducted at the midpoint of each frequency range.

Step 5 - Change +85°C to +71°C. Change 2 hours to 4 hours.

Any type of chamber of adequate size to hold the specified ground plane will suffice for this test since only a possible change in the VSWR is looked for. A pre-test VSWR is to be made to obtain a chamber reference VSWR.

4.7.2 Relative humidity. - The unit(s) shall be subjected to Procedure I of Specification MIL-E-5272 for compliance with 3.11.2.

4.7.3 Vibration test. - The unit(s) shall be subjected to Procedure XII of Specification MIL-E-5272 for compliance with 3.11.3.

4.7.4 Rain. - The unit(s) shall be tested in accordance with Procedure II of Specification MIL-E-5272. The antenna shall be mounted with base down for compliance with 3.11.4.

4.7.5 Sand and dust test. - The unit(s) shall be subjected to Procedure I of Specification MIL-E-5272 for compliance with 3.11.5.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

4.7.6 Shock test. - The unit(s) shall be subjected to the Equipment Crash-Safety Test of Procedure V of Specification MIL-E-5272 for compliance with 3.11.6.

4.7.7 Acceleration. - The unit(s) shall be tested in accordance with Procedure III of Specification MIL-E-5272, for compliance with 3.11.7.

4.7.8 Salt fog. - The unit(s) shall be exposed in its normal operating condition to salt fog in accordance with Method 509 of MIL-STD-810 for 48 hours. The unit(s) shall not be opened and shall not be required to be operated. The unit(s) shall meet the requirement of 3.11.8.

4.8 Electrical requirements. -

4.8.1 Impedance, input/output. - Under standard test conditions, mount the antenna on the 4 ft ground plane and measure the impedance. These measurements shall be made for compliance with 3.12.1.

4.8.2 Voltage standing wave ratio (VSWR). - Under standard test conditions, mount the antenna on the 4 ft ground plane and measure the VSWR. These measurements shall be made for compliance with 3.12.2.

4.8.3 Omnidirectional pattern. - Under standard test conditions, mount the antenna on the 4.0 ft diameter ground plane and measure the radiation pattern at the azimuth plane (parallel to level flight of aircraft). The azimuthal cut shall be measured at 90, 80 and 45 degrees. These measurements shall be made at the low, middle and high frequencies of each band for compliance with 3.12.2.

4.8.4 Gain, antenna. - The test procedure utilized for this test shall be that procedure submitted by the bidder with his proposal and approved by the Government. These approved tests shall be conducted to determine compliance with 3.12.4.

4.8.5 Isolation, bands. - Under standard test conditions mount the antenna on the 4 ft ground plane and feed a signal to the VHF or UHF feed connector and measure the resultant signal from the UHF or VHF feed connector, (the cable loss shall be determined at each test frequency when recording the isolation between the feed connectors). These measurements shall be made at standard test frequencies to determine compliance with 3.12.5.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

4.8.6 Power input, rf. - Feed 50 watts of power to the antenna for a period of 10 minutes. The 50 watts shall be applied at three (3) frequencies at the low end, middle and upper end of each frequency band to determine compliance with 3.12.6.

4.9 Visual and mechanical. - The assemblies, prior to assembly, and the complete assembled unit(s) shall be examined for defects in accordance with MIL-STD-252.

4.10 Interchangeability. - The dimensions listed below shall be gaged or measured to determine compliance with the physical interchangeability requirements of 3.14. When a listed dimension is not within specified or design limits, it shall be considered a major defect:

a. External and internal dimensions of moldings, mounting base and insertable parts, when such dimensions affect mating.

b. Dimensions of cavities, when such dimensions affect insertion of items.

c. Locations of holes on separable parts which must mate such as mounting assemblies.

d. Location of connectors, mounting base holes.

e. Size and form of threads.

4.11 Operational inspection. - Each unit shall be inspected for assurance that the equipment is in operating condition prior to packaging.

4.12 Quality conformance inspection of preparation for delivery. - Preparation for delivery inspection shall be in accordance with Specification MIL-P-116 to determine conformance to the packaging requirements.

4.13 Rough handling test (preparation for delivery). - When rough handling test in accordance with Specification MIL-P-116 is required by the contract the operational inspection test 4.11 shall be conducted to determine freedom from operational malfunction caused by rough handling.

5. PREPARATION FOR DELIVERY

5.1 Preparation for delivery shall be in accordance with Specification MIL-A-55485.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. - The antenna is intended to be used with VHF and/or UHF Radio Sets for communication when installed on either fixed or rotary wing aircraft.

6.2 Ordering data.- Procurement documents should specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Level of preservations, packaging and level of packing required for shipment. (Level A, Level B or Level C see Specification MIL-A-55485).

c. The specified paragraphs of Specification MIL-A-55485 which are applicable to the particular procurement.

d. Preproduction inspection. -

(1) Two (2) sample units of each item cited in Section I are generally required so that lengthy environmental tests can be completed on one sample unit while complete performance measurements can be made on the second sample unit. (See 3.3)

(2) Preproduction pack(s) as follows:

(a) Makeup of pack(s).

(b) Number of each kind of pack to be submitted.

(c) Inspection to be performed thereon. (Including rough handling and functional tests).

e. Marking and shipping of samples.

f. Place of final inspection.

g. Technical literature required. (See 3.15)

h. Quality of tools.

i. Submission of the statement of treatment referenced in 3.10 should be sixty (60) days after award of contract. This statement should be



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.

submitted as indicated in the contract.

6.3 Nomenclature. - The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: AT-1108w/ARC. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

6.4 Group C inspection. - Approval to ship may be withheld, at the discretion of the Government, pending results of the corrective action specified in the contract.

6.5 Definition of level B. - Level B packaging requirements detailed in Specification MIL-A-55485 are designed to furnish protection against corrosion, deterioration, and physical damage during domestic shipments; covered storage for a period of three years or less; and distribution within the continental limits of the United States.

6.6 Dimensional data. - Dimensions of packaging materials in the Bill of Materials Table are based on the dimensions of the equipment cited in Specification MIL-A-55485. When dimensions of the items vary, the dimensions of the packaging materials shall be adjusted accordingly.

6.7 Location of operational inspection. - It is desirable that the operational inspection 4.11 be performed at a location that will minimize handling (which might cause damage to the units) after this inspection. It is recommended that the entire lot (including the sample units) be inspected immediately prior to packaging.

6.8 Verification inspection. - Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive Quality Assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Custodian:
Army EL

Preparing Activity
Army EL
Project No. 5821-A087



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:53Z
Check the source to verify that this is the current version before use.