MIL-E-14719A (MU)
21 September 1968
SUPERSEDING
MIL-E-14719 (MU)
29 March 1968

MILITARY SPECIFICATION

EXTENSION, FUZE, BOMB, M1A1 (M1E1)
PARTS FOR

1. SCOPE

1.1 This specification contains special requirements not covered by the drawings and provides quality assurance provisions for the inert parts for one type of stand off device designated as Extension, Fuze, M1A1 (M1E1).

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

TT-C-490 - Cleaning Methods and Pretreatment of Ferrous Surfaces for Organic Coatings.

MILITARY

MIL-D-1000 - Drawings, Engineering and Associated Lists.
MIL-A-2550 - Ammunition and Special Weapons, General Specification for.
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of.
MIL-C-45662 - Calibration of Standards.

FSC: 1325

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

STANDARDS

FEDERAL

Fed. Test Method Standard - No. 151a

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-1167 - Ammunition Data Cards.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components.
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

US ARMY MUNITIONS COMMAND

9231708 - Extension, Fuze, Bomb, M1A1 (M1E1) Loading Assembly
9238810 - Extension, Fuze, Bomb, M1A1 (M1E1) W/Arming Wire Guide

PUBLICATIONS

ET-9231708 - Equipment Tabulation
ET-9238810 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Material.-Materials used in the fabrication of the inert parts shall be in accordance with the applicable specifications and drawings.

3.2 Inert parts.-The inert parts shall comply with all applicable requirements specified on Drawings (dwgs.) 9231708 and 9238810 and with all of the requirements specified in the applicable specifications.

3.3 Hydrostatic test of burster support assembly.-The burster support assembly shall not leak, show evidence of separation of the end components from the tube, rupture, or deform beyond drawing dimensions when subjected to a minimum internal hydrostatic pressure of 5,000 minus 300 pounds per square inch (psi), for a minimum of five (5) seconds.

3.4 Hydrostatic test stamp.-After having satisfactorily complied with the hydrostatic test specified in 3.3 above, the assembly shall be metal stamped with the letter "H" in 1/4 inch high letters on both ends of the assembly, 1 1/2 inch in from the end of the assembly.

3.5 Shipping.-Prior to shipment, the gasket (dwg. 9231715), nose plug (dwg. 9214994) and cap (dwg. 9231714) shall be assembled to the burster support.

3.6 Workmanship.-The inert parts shall be fabricated in a thorough, workmanlike manner. They shall be free from burrs, chips, scale, dirt, grease, rust, and any other foreign matter prior to and after painting. Excess braze material above the exterior surface shall be disregarded. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. The painted surfaces shall be continuous except for a few light scratches not exposing base metal. All required markings shall be neat and sharply defined. Bare areas on either end of the burster tube assembly shall be disregarded.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First Article Inspection

4.2.1 Submission.-Prior to initiating regular production, the contractor shall submit five (5) each burster tube assemblies and painted supports and five (5) complete sets of parts, unpainted, (i.e., 5 each of each component and subassembly excluding those of the burster assembly) to a Government approved facility as designated by the contracting officer (see 6.4) for evaluation in accordance with the provisions of 4.2.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

The first article sample shall consist of material that has been produced by the contractor or furnished by a supplier and manufactured using the same production processes, procedures, and equipment that will be used in fulfilling the contract. The first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply so as to significantly affect product uniformity as determined by the Government. Prior to submission the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects shall not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies, subassemblies and components will be subjected by the Government to any or all of the examinations specified in 4.3.2 and 4.3.3 of this specification and any or all of the requirements of the applicable drawing.

4.2.3 Rejection.-If any assembly, subassembly or component fails to comply with any of the applicable requirements the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon observing any nonconformance of the sample to the specified requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is in no way authorized by the Government to initiate regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

the lot has been produced by one manufacturer, in one unchanged process using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions. Changes to the process, specifications, or drawings, not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the lot. Inspection lots shall comply with MIL-STD-105. Unless otherwise approved by the contracting officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest monthly quantity contractually scheduled for delivery during the contract period. Inspection lots of components or subassemblies, other than the items of delivery, shall be homogeneous and of a size mutually convenient to both the contractor and the Government inspector. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Once agreement has been reached as to which method will be used (group or individual) that method will be used for all of the CD's listed in this specification. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.3.2.1 Burster support, before paint (see dwg. 9231712-1 through -5 (as applicable) covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined.		
Major:	AQL 1.00 percent		
101.	Concentricity of internal diameter to thread at male end.	Gage	01001
102.	Concentricity of internal diameter to thread at female end	Gage	01002
103.	Pitch diameter of external thread	Gage	01003
104.	Major diameter of external thread	Gage	01004
105.	Pitch diameter of internal thread, minimum (min)	Gage	01005
106.	Minor diameter of internal thread, maximum (max)	Gage	01006
107.	Diameter of external thread relief at shoulder, min	Gage	01007
108.	Wall thickness at thread relief at male end, min	Gage	01008
109.	Wall thickness of pipe, min	Gage	01009
110.	Braze material not visible 360 degrees	Visual	01010
111.	Hydrostatic test stamp missing (see 3.4)	Visual	01011
Minor:	AQL 1.50 percent		
201.	Total length, min	Gage	01012
202.	Internal chamfer missing at male end	Visual-Manual	01013
203.	Evidence of poor workmanship (see 3.6)	Visual	01014

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.3.2.2 Burster support, after paint (see dwg. 9231712-1 through -5 (as applicable) covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Internal diameter at male end, min.	Gage	02001
102.	Internal diameter at female end, min.	Gage	02002
Minor: None defined.			

4.3.2.3 Burster tube with crimped end (see dwg. 9231709-1 through -7 (as applicable) covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.65 percent		
101.	Tube curvature excessive (applicable with support dwg. 9231711 only)	Gage	03001
102.	Diameter of end, max.	Gage	03002
103.	Interior surface damaged	Visual	03003
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	03004

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.3.2.4 Burster tube assembly (see dwg. 9231709-1 through -7 (as applicable) covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Cover fitting loosely.....	Manual	04001
Minor:	AQL 0.65 percent		
201.	Total length, max.....	Gage	04002

4.3.2.5 Nose closing plug or cap (see dwg. 9214994 or 9231714 (as applicable) covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Thread not full.....	Visual	05001
102.	Unit damaged to extent it might not be serviceable.....	Visual	05002
Minor: None defined.			

4.3.2.6 Gasket (see dwg. 9213715 covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Material not impregnated.....	Visual-Manual	06001
Minor: None defined.			

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.3.2.7 Burster support shipping assembly (see 3.5 covering a detail of dwg. 9231708).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Component missing.....	Visual	07001
Minor:	AQL 1.50 percent		
201.	Total length, max.....	Gage	07002
202.	Nose plug or cap insecure.....	Manual	07003
203.	Evidence of poor workmanship (see 3.6).....	Visual	07004

4.3.2.8 Cushioned clamp (see dwg. MS21919H38 covering a detail of dwg. 9238810).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major: None defined.			
Minor:	AQL 1.00 percent		
201.	Diameter of bolt hole, min.....	Gage	08001
202.	Evidence of poor workmanship (see 3.6).....	Visual	08002

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.3.2.9 Guide tube (see dwg. 9238811-1 through -4, as applicable, covering a detail of dwg. 9238810).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major: None defined.			
Minor:	AQL 1.00 percent		
201.	Tube deformed or bent.....	Visual	09001
202.	Evidence of poor workmanship (see 3.6).....	Visual	09002

4.3.3 Testing

4.3.3.1 First article sample (see 4.2.1)

4.3.3.1.1 Salt spray testing (see dwg. 9231712, as applicable) Code No. 10001

4.3.3.1.2 Hyrdostatic test of burster support assembly (see 3.3 and 4.4.1) Code No. 01015

4.3.3.2 Production testing

4.3.3.2.1 Salt spray testing (see dwg. 9231712, as applicable) Code No. 10001, Minor defect.-Test panels shall be prepared in accordance with paragraph 4.2.8 of TT-C-490 and shall be exposed to a 5 percent salt spray in accordance with Method 811.1 of Fed. Test Method Standard 151a for 96 hours. The panels shall then be evaluated to the requirements of paragraph 3.9 of TT-C-490. Corrective action in accordance with 4.2.8 shall be implemented when indicated.

4.3.3.2.2 Hydrostatic test of burster support assembly (see 3.3) Major defect, Code No. 01015.-This test shall be performed 100 percent. The test shall be performed as specified in 4.4.1, using test equipment specified in 4.3.4. Any assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.3.4 Inspection Equipment.-Equipment Tabulation Numbers ET-9231708 and ET-9238810 identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed in the ET shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Calibration.-The contractor shall have available a set of master gages, standards, and appropriate instruments for regularly scheduled calibrations of his acceptance inspection equipment. Records of such regularly scheduled calibrations shall be maintained by the contractor and made available for review by the Government. The calibration of gages, standards, and instruments shall be in accordance with Specification MIL-C-45662.

4.4 Test methods and procedures.-The test method and procedures described in each of the following tests represents only one method and one procedure which has been proven in use and is approved by the Government for Government acceptance purposes. Producers and manufacturers have the option of using substitute methods and procedures only after obtaining Government approval. Government approval will be based on an evaluation to determine that the substitute method and procedure will result in an equal or better quality evaluation than that specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

4.4.1 Hydrostatic test of burster support assembly.-One end of the assembly shall be sealed off and the assembly assembled to the applicable test fixture specified in 4.3.4. The assembly shall be held in the test fixture in such a manner that the ends of the assembly are not restrained. The specified internal hydrostatic pressure shall then be introduced at one of the assembly, the pressure isolated, and held for the minimum specified time. Observation shall be made for leaks as evidenced by a drop in the reading on a pressure gage. After relief of the internal pressure the assembly shall be examined to assure that the brazed end components show no evidence of separation from the tube. Any assembly which fails to comply with the specified requirement shall be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Packing

5.1.1 Level C.-The inert burster support, burster tube assemblies, clamps, bolts, flat washers, nuts, pads, guide tubes and lock washers shall be shipped in separate containers which shall be packed and marked in accordance with Standard MIL-STD-1169.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced inspection Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable 5 digit Code Number contained in section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND11. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

6.4 Submission of First Article Samples.-Instructions as to the location for the evaluation of first article sample shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries shall be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-NI, Dover, New Jersey 07801.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1325-A-291

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 OCT 61 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:37Z
Check the source to verify that this is the current version before use.