FEDERAL SPECIFICATION

HAMMERS, ELECTRIC, PORTABLE AND
HAMMER-DRILLS, ELECTRIC, PORTABLE

This amendment, which forms a part of Federal Specification OO-H-103B, dated September 3, 1965, was approved by the Commissioner, Federal Supply Service, General Services Administration, for the use of all Federal agencies.

PAGE 2

Paragraph 3.1 Delete in its entirety.

PAGE 7

Paragraphs 4.2, 4.2.1, 4.2.2 and footnote 1/ Delete in their entirety.

Paragraph 4.5.2 Delete and substitute the following:

4.5.2 Performance test. The sample hammers or hammer-drills shall be tested to determine their ability to meet the minimum requirements of the applicable table I, II, and III. Chisels or points or drills used in these tests may be resharpened as required.

Add the following new paragraphs:

4.5.2.1 Chipping test, type I, style A hammers. Chipping ability shall be tested by making a 3/64 inch deep cut on the edge of a 1/8 inch thick steel plate with a tool feed pressure of 25 pounds. The steel shall be a rimmed AISI 1020 or 1023 steel having an average hardness of Rockwell B75 to B85.

4.5.2.2 Demolition test, type I, class 1, style B and class 2, style B. The hammer, fitted with a bull point or demolition chisel, shall be used to demolish a test slab conforming to 4.7. The bull point may be sharpened or replaced as required. Failure of the hammer to meet the demolition rate requirements of tables I and II as applicable, leaving pieces no larger than 1/2 cubic foot in size, shall constitute failure of this test.

4.5.2.3 Drilling tests, type II hammer-drills. Type II, sizes 1 and 2 hammer-drills shall be fitted with a masonry type twist drill of the size shown in table III for 1-2-4 concrete and used to drill 3 holes. Drilling time to be of one minute duration each in a test slab conforming to 4.7. Failure to maintain the drill rate specified shall be cause for rejection. Type II, size 3 hammer-drills shall be tested using a carbide tipped core drill 1-1/2 inches in diameter. Failure to maintain a drilling rate of 2 inches per minute shall be cause for rejection.

Paragraphs 4.6 thru 4.6.1.1 Delete in their entirety.

PAGE 8

Paragraphs 4.6.1.2 thru 4.6.3 Delete in their entirety.

Paragraph 4.7 Delete and substitute:

4.7 Concrete test block. The demolition tests of 4.5.2.2 shall be conducted using a slab of 1-2-4 concrete approximately 1 foot thick of sufficient area to accommodate a 30 minute test requirement. Solid concrete blocks, commercially available, may be used for the drilling tests of 4.5.2.3 if the slab is not employed. The test slab or the blocks shall be firmly supported on a solid earthen or concrete base.

PAGE 9

Paragraphs 6.3 and 6.4 Delete in their entirety.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:58Z
Check the source to verify that this is the current version before use.