MILITARY SPECIFICATION

PUBLIC ADDRESS SET: AN/UIQ-10

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the production requirements for one type public address set.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of the specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

TT-E-485	-	Enamel, Semi-gloss, Rust-inhibiting.

MILITARY

MIL-T-704	-	Treatment And Painting Of Materiel.
MIL-L-3661	-	Lampholder, Indicator Lights, Indicator-light Housings, And Indicator-light Lenses, General Specification For.
MIL-P-15024	-	Plate, Tags And Bands For Identification Of Equipment.
MIL-E-16400	-	Electronic Equipment, Naval Ship And Shore, General Specification.
MIL-E-17555	-	Electronic And Electrical Equipment, Accessories And Repair Parts, Packaging And Packing Of.
MIL-P-13949	-	Plastic Sheet, Laminated, Copper Clad (For Printed Wiring).
MIL-E-21981	-	Electronics Type Designations, Identification Plates And Markings, Requirements For.
MIL-I-45208	-	Inspection System Requirements.
MIL-I-46058	-	Insulating Compound, Electrical (For Coating Printed Circuit Assemblies).

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:15Z
Check the source to verify that this is the currentversion before use.

STANDARDS

FEDERAL

FED-STD-595	-	Color.

MILITARY

MIL-STD-129	-	Marking For Shipment And Storage.
MIL-STD-242	-	Electronic Equipment Parts, Selected Standards, For Electro Mechanical Parts.
MIL-STD-454	-	Standard General Requirements For Electronic Equipment.
MIL-STD-461	-	Electromagnetic Interference Characteristics Requirements For Equipment.
MIL-STD-470	-	Maintainability Program Requirements (For Systems And Equipments).
MIL-STD-471	-	Maintainability Demonstration.
MIL-STD-756	-	Reliability Prediction.
MIL-STD-781	-	Reliability Tests Exponential Distribution.
MIL-STD-785	-	Reliability Program For Systems And Equipment Development And Production.
MIL-STD-810	-	Environmental Test Methods.
MIL-STD-831	-	Test Reports, Preparation Of.
MIL-STD-1275	-	Electrical Circuit, 28 Volt, DC Transient Characteristics For Military Vehicles.

HANDBOOKS

MIL-HDBK-217	-	Reliability Stress And Failure Rate Data For Electronic Equipment.

DRAWINGS

U.S. LAND WARFARE LABORATORY

030032000	-	Public Address Set AN/UIQ-10.

(Copies of specifications, standards, handbooks and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

3.1 First article. Prior to submission of any complete production units for acceptance, the contractor shall furnish four first articles for testing under the direction and supervision of the cognizant Government inspector to determine conformance to this specification. The first articles shall be identical to production units which the contractor will subsequently produce in fulfillment of the contract. Examination and tests shall be those specified herein. Approval of the first articles by the procuring activity concerned shall not relieve the contractor of his obligation to supply public address sets conforming to this specification. Any changes or deviations of the production units from the first articles shall be subject to the approval of the contracting officer. The first articles shall not be included in the quantity to be delivered to the Government.

3.2 Parts, materials and processes. Parts, materials and processes shall be in accordance with MIL-E-16400 and MIL-STD-454, except as otherwise specified herein.

3.2.1 Fungus nutrient materials. Fungus nutrient materials shall not be used in the public address set. Moisture fungusproofing of the overall public address set shall not be permitted.

3.2.2 Standard parts. Parts shall be selected from MIL-STD-242 wherever possible. All other parts shall be selected in accordance with Drawing No. 030032000 and referenced documentation thereto. Any other nonstandard parts shall be approved by the procuring activity before delivery of any public address set.

3.2.3 Solid state devices. Solid state devices shall be utilized exclusively, i.e,, vacuum tubes shall not be used.

3.2.4 Interchangeability and replaceability. All parts or components having the same manufacturer's part number shall be completely interchangeable or replaceable with respect to installation and performance as specified in MIL-STD-454, Requirement 7.

3.2.5 Wiring. Internal wiring shall be in accordance with MIL-STD-454, Requirement 20.

3.3 Design and construction. The public address set described herein shall be a lightweight, high efficiency, voice/music amplification system, primarily intended to provide the military services with a practical man-pack public address capability in a tactical environment. The public address set shall consist of two distinct man-pack units. The basic

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

man-pack unit shall be a complete public address set designated AN/UIQ-11 with the output limited only by the single loudspeaker with which it is equipped. The second man-pack, designated Loudspeaker Assembly LS-611/UIQ-10, shall consist of three additional speakers to permit use of the full power capability of the amplifier. The complete set shall be carried by two men, and shall provide up to 250 watts (W) output power to drive the four horn-type speakers. Each man-pack shall consist of a base plate (mounting plate) with a set of four telescoping legs which extend and spread to support the equipment in the operating position. All of the public address set components shall be attached to this base plate. The base plate shall be capable of interfacing with the standard military lightweight rucksack frame to form a barrier between the equipment and the man carrying it. The battery powered output circuits shall be of a type wherein amplification is achieved through pulse width modulation rather than conventional audio amplification techniques. The design shall incorporate the flexibility of multiple inputs, remote control, attack/warning tone generation, and varied 28 Volts direct cuttent (Vdc) power input connections.

3.3.1 Design approval. Any modification to the established design shall be submitted to the procuring activity for approval.

3.3.2 Modes of operation. The Public Address Set, AN/UIQ-10, shall be utilized as a basic public address set to satisfy the requirements for modes of operation which include the following:

(a) Stand alone operation of the Public Address Set, AN/UIQ-11.

(b) Master/slave relationship to additional Public Address Sets, AN/UIQ-10 or AN/UIQ-11, whereby the latter as slaves would operate less the control unit (Control, Amplifier, C-8967/UIQ-10).

(c) With different installation hardware, the components shall be utilized in ground vehicular, aircraft, helicopter, and fixed-plant applications.

The public address set shall be capable of being operated from a remote location through the use of a special cable or alternately by the use of field wire.

3.3.3 Public Address Set, AN/UIQ-11. The Public Address Set, AN/UIQ-11, shall consist of the following items which shall be contractor-furnished equipment (CFE) or Government-furnished equipment (GFE) as indicated:

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

Item	Description	Qty	CFE/GFE	
1	Amplifier, Audio Frequency, AM-6482/UIQ-10	1	X	
2	Control, Amplifier, C-8967/UIQ-10	1	X	
3	Loudspeaker, LS-608/UIQ-10	1	X	
4	Accessory Kit (Complete)			
	Microphone	1		X
	Control Cable	1	X	
	Radio Cable	1	X	
	Power Connector	1	X	
	Pouch	1	X	
5	Mounting Plate Assembly, w/legs MT-4455/UIQ-10	1	X	
6	Cable Assembly, Power, Electrical CSX-12942/U	1	X	
7	Mounting Plate Assembly, MT-4537/UIQ	1	X	
8	Rucksack, frame	1		X

3.3.3.1 Amplifier, Audio Frequency, AM-6482/UIQ-10. This amplifier shall be of welded aluminum construction approximately 12 inches wide, 7 inches high, and 5 inches deep. The bottom surface is an interface for any one of the various type I (12-inch by 4-inch) military batteries (but not all of these batteries are necessarily suitable for operating the equipment). The top surface shall be a finned heat-radiator to dissipate the heat produced by four power transistors. On the left side, connectors shall be provided for low-level signal and control interconnections and power input (other than battery). Remote speaker connectors shall be provided on the right side. The amplifier shall be immersion resistant. Access to the interior shall be provided through

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

a removable cover on the back side. All components (except a few large chassis-mounted electrical components) shall be mounted on two printed circuit boards. One circuit board shall be mounted so that it may be removed while still connected to provide access to the second circuit board. The amplifier shall attach to the mounting plate with four quick-disconnect fasteners. The amplifier shall incorporate the major active circuit elements of the public address set. The audio frequency sequel from the control/preamplifier circuit shall be converted, by means of pulse-width modulation techniques, to a high-power audio output capable of driving a low impedance load. Power control circuits shall permit remote control of the system power from the control unit and provide electronic over-current, and over-voltage protection, and protection against reversed polarity supply voltage. Signal and control lines to the amplifier from the control unit shall be carried in a 4-conductor cable 100 feet long.

3.3.3.1.1 Amplifier inputs. The amplifier shall have three methods of connecting the required direct current (dc) supply voltage to the amplifier to control and distribute the power for the public address set and two methods for interconnection of the amplifier as follows:

(a) Battery connector. A special rectangular receptacle on the bottom interface of the amplifier chassis shall be wired to accept the mating connector on the standard type I battery interface. This means that pin 1 is the negative battery terminal, in this case, also chassis ground. Pin 5 is the positive battery terminal. A jumper shall be connected between pins 2 and 4. A BB-451 or BB-626 Battery shall be capable of being connected by the use of an adapter.

(b) Power binding posts. Power binding posts shall be provided and connected in parallel with the positive and negative connections in the battery connector. They shall be used for connection to an external power source when the battery is not used and it is not desirable to use the external power connector. The posts are to be labeled "+28VDC" and "GND" respectively.

(c) External power connector. This connector connects external power to the public address set by way of the PT07C18-11P Power Plug. For this purpose, connections are +28Vdc, pin H ground, pin E (supply negative). A power selection switch shall be provided for selection of either external or battery/binding post power. The main purpose of this arrangement is to insure that the other external power connectors do not carry voltage when the external power connector is used. One Connector PT08E18-115 shall be provided as an auxiliary item.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

(d) Amplifier/control unit interconnection connector. A 5-pin connector shall be provided to facilitate interconnection between the Control, Amplifier, C-8967/UIQ-10 by use of Cable, CSX-12940/U.

(e) Remote control binding posts. Four binding posts shall be provided to accommodate field wire remoting in lieu of Cable, CSX-12940/U. These posts shall be wired in parallel to the amplifier/control unit interconnection connector.

3.3.3.1.2 Amplifier outputs. The amplifier shall have the following three receptacles and one set of three binding posts to be used as outputs from the amplifier:

(a) Remote speaker connector. An 8-pin connector, with nylon cord retained protective cover, shall be provided to mate with the Cable, Electrical, CX-12943/U, in order to connect the Loudspeaker Assembly, LS-611/UIQ-10. The additional pins in this connector shall be provided in order to facilitate the interconnection of up to four loudspeakers in alternate configurations.

(b) Local speaker connector. A 3-pin connector, with nylon cord retained protective cover, shall be provided to mate with Cable, Electrical, CS-12942/U, in order to connect Loudspeaker, LS-608/UIQ-10.

(c) Remote output connector. A 5-pin connector shall be provided to facilitate paralleling the amplifier by use of a second Cable, CX-12940/U.

(d) Remote output binding posts. Three binding posts shall be provided to accommodate field wire interconnection between paralleled amplifiers in lieu of Cable, CX-12940/U.

3.3.3.1.3 Electrical performance characteristics. The circuitry shall be capable of providing amplification on the basis of pulse width modulation at high efficiency and low distortion as follows. Use of protective devices shall be limited to a main power relay under the direct control of fault sensing circuitry and the Control, Amplifier, C-8967/UIQ-10, on-off switch for reset action.

(a) Input power. The amplifier, when driven by Control, Amplifier, C-8967/UIQ-10, shall provide the performance specified herein when operated from any of the following power sources at a total input power not to exceed 350 W, maximum.

(1) Battery, BB-451/U

(2) Battery, BB-626/U

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the current version before use.

(3) 20-32 Vdc vehicle power supply meeting the requirements of MIL-STD-1275.

(4) 26.5 Vdc as provided by Power Supply, C-7674/VCC.

(5) Battery, BB-534( )/U

(6) 26.5 Vdc as provided from Battery Terminal Adapter MX-4430/PRC-47 through electrical power Cable Assembly CX8395/PRC-47.

(b) Warmup. The amplifier shall be functional within 5 seconds after it has been switched on.

(c) Duty cycle. The amplifier shall be capable of continuous operation without degradation of performance.

(d) Overload and reverse polarity protection. The amplifier shall be provided with overload and reverse polarity protection so that no damage shall occur with the output short circuited or the supply voltage polarity reversed.

(e) Audio output power. The amplifier shall be capable of providing the following output power to a 2-ohm resistive load when operated on a 28.0 ±0.5 Vdc source.

(1) Using a 1-kilohertz (kHz) tone, 250 W root mean square (rms), with a total harmonic distortion which does not exceed 18 percent and an efficiency of 85 percent.

(2) Using a 1-kHz tone, 110 W rms, with a total harmonic distortion which does not exceed 10 percent and an efficiency of 85 percent.

(3) Full gain idle noise into a 2-ohm resistive load shall not exceed 2 milliwatts (mW). Full gain idle noise into a 2-ohm resistive load shall not exceed 5 mW from any amplifier employed in a master/slave configuration.

(4) The frequency response shall be within +0, -2 decibels (dB) of 1 kHz at rated output from 450 hertz (Hz) to 3,000 Hz.

(f) Audio output signal. The audio output of Control Amplifier, C-8967/UIQ-10 shall be provided on a 5-pin connector for the parallel operation of additional amplifiers.

Source: https://assist.dla.mil -- Downloaded: 20261O-20T21:15Z
Check the source to verify that this is the current version before use.

(g) On-off function, parallel operation. The on-off, main power relay function shall be provided on the remote output (parallel operation connector) in order to control the on-off function of additional amplifiers.

(h) Standby current drain. The no input signal supply current shall not exceed 600 milliamperes dc.

3.3.3.1.4 Cooling. The amplifier shall be cooled using natural means. Blowers, or other mechanical cooling devices, shall not be used.

3.3.3.2 Control, Amplifier C-8967/UIQ-10. The amplifier control shall be of welded aluminum construction approximately 8 inches long, 5 inches high, and 2 inches thick. It shall contain a clip which will enable it to be carried on the user's web belt during operation. The amplifier control shall contain all the operating controls for the Public Address Set, AN/UIQ-10. When mounted on the belt, all controls shall be on the top surface and visible to the operator. Microphone and other inputs shall face the right hand side, while the interconnection to the amplifier comes off the left hand side. Controls and connections shall be capable of being secured to the amplifier for carrying. All active circuitry shall be contained on a hinged printed circuit board which unplugs for replacement. The amplifier control shall be capable of accepting inputs from an M-80/U Microphone, a field telephone, a tape recorder or radio receiver. Two such inputs shall be accommodated at one time and mixed in the input circuitry. The electronic circuitry shall also generate ALERT and ATTACK alarm signals which shall be capable of being controlled on a continuously variable basis to maximum output. The tone signals shall be generated within this circuit group. The tone for ALERT warning shall be a continuous audio tone, and the ATTACK warning shall be a sawtooth wobbulated signal. These shall be controlled by toggle switches with the ATTACK alarm having override capability.

3.3.3.2.1 Controls. All controls for the public address set shall be located on the control amplifier, except for four speaker "Local/Remote" switches which shall be located on the audio frequency amplifier. The controls shall provide normal functional control as follows:

Controls	Qty	Function
Power ON/OFF	1	1. Main power switch on-off. 2. Current protection reset-the current protection reset shall be accomplished by switching the main power switch off and back on.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the current version before use.

MIL-P-28991(MC)

Controls	Qty	Function
Microphone 1/Radio	1	1. Controls the output level from audio inputs to the microphone 1/radio connector, whether the input is from a microphone or the audio output of a radio set. 2. When the unit is programmed internally for adjustable alarm volume, this control adjusts the loudness of the alarm signal.
Microphone 2/Tape/Phone	1	1. Controls the output level from audio inputs to the microphone 2/tape connector or field phone binding posts.
ALERT ON/OFF	1	1. Controls a continuous tone alarm which shall be internally generated.
ATTACK ON/OFF	1	1. Controls a wobbulated attack tone which shall be internally generated. 2. Actuation of the attack switch shall override the alert tone regardless of its position.

3.3.3.2.2 Connectors. The amplifier control shall incorporate the following connectors to perform functions as specified:

Item	Type	Qty	Function	Impedance and Level
1	U-183/U	1	1. Microphone input	0.01 volts (V) rms, 150 ohms
			2. Radio input	0.1 V rms, 1 ohm
2	U-183/U	1	1. Microphone input	0.01 V rms, 150 ohms
			2. Tape input	0.1 V rms, 1,000 ohms
3	Binding Post, Spring Action	2	1. TA-312/EE-8 Telephone input 2. Protection from damage due to 20-Hz ringing voltage shall be provided to a maximum level of 130 V.	0.1 V rms, 600 ohms

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

Item	Type	Qty	Function	Impedance and Level
4	U-228/U	1	Equipment interconnect	1. +28 Vdc 2. Audio 3. Ground 4. Control
5	Binding Post, Spring Action,	4	Parallel operation of item 4	

3.3.3.2.3 Indicators. An indicator lamp, with mechanical dimmer, shall be provided to indicate the presence of properly polarized and turned on dc voltage. The mechanical dimmer shall be in accordance with MIL-L-3661.

3.3.3.2.4 Cooling. Cooling shall be accomplished by natural means.

3.3.3.2.5 Alert tone. The alert tone shall be a square wave output at 400 Hz ±10 percent.

3.3.3.2.6 Attack tone. The attack tone shall be a square wave output, frequency modulated by a ramp function at a repetition rate of 2.5 Hz ±25 percent; the tone shall rise linearly from 400 Hz to 720 Hz and repeat continuously.

3.3.3.3 Loudspeaker, LS-608/UIQ-10. This loudspeaker shall consist of one Driver, Speaker, Electro-Voice model 1823 or equal and one Horn, Speaker, Electro-Voice AR-400, or equal.

3.3.3.4 Accessory Kit, ( )/UIQ-10. The accessory kit shall provide the essential components required to operate the Public Address Set, AN/UIQ-10. The following items shall be included.

ITEM	TYPE	QTY	FUNCTION
1	M-80/u Microphone	1	Microphone
2	Cable Assembly, Special Purpose, Electrical CX-12940/U (100 feet, control)	1	1. Interconnection of Control, Amplifier C-8967/UIQ-10 and Amplifier, Audio Frequency, AM-6482/UIQ-10. 2. Interconnection of two Amplifiers, Audio Frequency, AM-6482/UIQ-10. 3. Series connection of like cable for additional length.

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

ITEM	TYPE	QTY	FUNCTION
3	Cable Assembly, Special Purpose, Electrical, CX-12941/U	1	1. Interconnection of radio receivers and Control Amplifiers, C-8967/UIQ-10.
4	Power Connector	1	1. Mating part for alternate power input on Amplifier, Audio Frequency, AM-6482/UIQ-10.
5	Pouch	1	1. Securely contains items 1 through 4 of accessory kit. 2. Attaches to web belt.
6	Adapter, Blower Air MX 9309( )/U	1	1. Allows BB-451/BB-626 battery connection to the amplifier battery connector.
7	Connector PTO8E18-115	1	1. Allows cable installation of power system.

3.3.3.5 Mounting Plate Assembly, with Legs, MT-4455/UIQ-10. The configuration and design features of the mounting plate assembly shall provide rapid, positive attachment of public address set components and, in turn, the assemblage to the rucksack frame.

3.3.3.6 Cable Assembly, Power, Electrical CS-12942/U. This cable shall provide the required interconnection of Amplifier, Audio Frequency, AM-6482/UIQ-10 and Mounting Plate Assembly, MT-4537/UIQ.

3.3.3.7 Mounting Plate Assembly, MT-4537/UIQ. This mounting assembly shall provide the proper mounting of Loudspeaker, LS-608 (UIQ-10) to mounting plate assembly with Legs, MT-4455/UIQ-10 and electrical interconnection with Cable, Electrical, ( )/UIQ-10. Permanently attached (captive) mounting screws shall be provided. Binding posts and quick-disconnect electrical fitting shall be provided and marked for interconnection with Cable, Electrical, CS-12942/U and Loudspeaker, LS-608/UIQ-10.

3.3.4 Loudspeaker Assembly, LS-611/UIQ-10. The Loudspeaker Assembly, LS-611/UIQ-10 shall consist of the following items which shall be CFE or GFE as indicated:

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

Item	Description	Qty	CFE/GFE
1	Loudspeaker, LS-608/UIQ-10	3	X
2	Mounting Plate Assembly, MT-4456/UIQ-10	1	X
3	Mounting Plate Assembly, MT-4538/UIQ	3	X
4	Cable Assembly, Power Electrical CX-12943/U	1	X
5	Rucksack, frame	1	X

The total weight of the loudspeaker assembly shall not exceed 31 pounds.

3.3.4.1 Mounting Plate Assembly, MT-4456/UIQ-10. The configuration and design features of Mounting Plate Assembly, MT-4456/UIQ-10, shall provide rapid positive attachment of three Mounting Assemblies, MT-4538/UIQ, and Cable, Electrical, CS-12943/U. The assemblage shall be attached to the rucksack frame.

3.3.4.2 Mounting Plate Assembly, MT-4538/UIQ. Mounting Plate Assembly, MT-4538/UIQ, shall provide the proper mounting of Loudspeaker, LS-608 (UIQ-10), to Mounting Plate Assembly, MT-4456/UIQ-10, and Cable, Electrical, CS-12942/U. The mounting assembly shall contain the following provisions:

(a) Permanently attached (captive) mounting screws.

(b) The three individual loudspeakers shall be capable of rotation in a horizontal plane to provide wide acoustic coverage and shall be capable of being secured in any horizontal position without the use of any tools.

(c) A permanently attached (captive) retaining pin shall be provided to lock the loudspeakers in the transport position.

(d) Binding posts and quick-disconnect electrical fittings shall be provided and marked for interconnection with Cable, Electrical, CS-12943/U.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the current version before use.

3.3.4.3 Cable, Electrical, CS-12942/U. Cable, Electrical, CS-12943/U shall provide the required interconnection of Amplifier, Audio Frequency, AM-6482/UIQ-10, Loudspeaker Assembly, LS-611/UIQ-10, and the Loudspeakers LS-608/UIQ-10 attached thereto.

3.3.5 Auxiliary items. The following auxiliary items shall be utilized to adapt the public address set for operation with various batteries and connection of remote speakers.

Item	Description	Qty
1	Adapter-Blower, Air, MX-9309( )/U	1
2	Cable-Junction Box, Adapter ( )	1

3.3.5.1 Adapter-Blower, Air, MX-9309( )/U. Adapter-Blower, Air, MX-9309( )/U shall be fabricated to interconnect various batteries with the public address set.

3.3.5.2 Cable-Junction Box, Adapter ( ). Cable-Junction Box, Adapter shall be fabricated to interconnect four remote speakers, and the audio output of Amplifier, Audio Frequency, AM-6482/UIQ-10.

3.3.6 Modular construction. The public address set shall employ modular design and construction. The modular requirements of MIL-E-16400 shall not apply. The modularity shall be to major functional assemblies within the components.

3.3.6.1 Module identification. Each module shall be constructed and marked so that replacement of similar appearing modules shall not be possible.

3.3.6.2 Printed circuit boards. The printed circuit boards shall conform to the requirements of MIL-P-13949. Conformal coating of assembled printed circuit boards shall be in accordance with MIL-I-46058.

3.3.6.3 Test points. Test points shall be incorporated for major circuit maintenance/repair test without the requirement to remove or extend modules.

3.3.6.4 Controls. All controls required for setup, operation, and application of the public address set in other configurations shall be contained on Amplifier, Audio Frequency, AM-6482/UIQ-10 and Control, Amplifier, C-8967/UIQ-10. Tactical identification of controls is not required. All controls and adjustments shall not be altered when the public address set is subjected to the service conditions specified in 3.6.3 and 4.9.6.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the current version before use.

3.4 Reliability. The public address set shall meet the following reliability requirements.

3.4.1 Mean time between failure (MTBF). The public address set shall possess a MTBF of no less than 1,500 hours when tested and demonstrated as specified herein. This is the specified MTBF as defined in MIL-STD-781. A failure shall be defined as any degradation below this minimum MTBF. Operation of the equipment on 28.0 ±5 Vdc and into a 2-Ohm load shall be required. A single test shall not be allowed.

3.4.1 Reliability program. The required reliability shall be obtained through a reliability program performed in accordance with MIL-STD-785 1/ with exceptions or additions as follows:

(a) The contractor shall perform an analysis of the proposed design of the amplifier and control to determine compatibility with the required MTBF. A failure rate shall be assigned to each part in accordance with data presented in MIL-HDBK-217. Parts not included in MIL-HDBK-217 shall be assumed to possess the failure rate of the most similar part in MIL-HDBK-217. Where this is unrealistic, any valid existing data shall be used upon approval of the procuring activity. The analysis shall include a comparison of the predicted with the required MTBF. Where the predicted figure is less than the requirement, the contractor shall accomplish such changes in design as are necessary to raise the predicted MTBF to the required value.

(b) The reliability analysis shall be revised periodically to consider design changes or improved data on part stress levels.

(c) As the fabrication is completed so that the public address set performance is possible, the contractor shall prepare and submit to the procuring activity a final prediction of the reliability of the components. If the prediction indicates a lesser reliability than that required, the contractor shall accomplish such changes in design, part application and part stress level as are necessary to yield a MTBF of the required level.

1/ Quantitative reliability shall be predicted in accordance with MIL-STD-756, type II.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the current version before use.

3.5 Maintainability. The public address set shall meet the following maintainability requirements.

3.5.1 Maintainability program. The contractor shall prepare, for approval, a maintainability program plan in accordance with the requirements of MIL-STD-470.

3.5.2 Maintenance provisions. The public address set shall be designed to include, to the greatest extent practicable, the following provisions for facilitating maintenance:

(a) The construction of the equipment shall permit the replacement of malfunctioned parts without departing from the performance requirements specified herein.

(b) The equipment shall be so constructed that no damage to any component or undue distortion to any structural member shall be caused by placing any of the six sides of any equipment on a flat horizontal surface.

(c) The design of the equipment shall be such that no special tools shall be required for tuning, adjusting, or servicing.

(d) All parts having the same part number shall be functionally and dimensionally interchangeable.

3.5.3 Mean time to repair (MTTR). The MTTR of the public address set shall not exceed 30 minutes to the major functional module level.

3.5.4 Maintainability demonstration. A maintainability demonstration shall be performed in accordance with the requirements of MIL-STD-471.

3.6 Performance. The public address set shall perform as specified herein when operated on 28.0 ±0.5 Vdc and into a 2-ohm resistive load. As an acoustical system, the public address set shall provide an output of 116 dB at a distance of 30 feet from the four loudspeakers.

3.6.1 Equipment life. The public address set components shall exhibit a minimum individual operating life of 45,000 hours with reasonable servicing and replacement of parts.

3.6.2 Standard conditions. The following conditions shall be used as a basis for establishing normal performance requirements and for conducting tests of the public address set:

(a) Barometric Pressure 28 to 32 inches mercury

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

(b)	Temperature	15°C to 35°C
(c)	Humidity	50 percent ±30 percent
(d)	Supply Voltage	28.0 ±0.5 Vdc

3.6.3 Service conditions. The public address set shall be capable of operating under the following service conditions:

(a)	Ambient temperature range	-40°C to 65°C
(b)	Ambient humidity range	0 to 100 percent relative
(c)	Vibration	MIL-STD-810, Method 514, Procedure I, Curve W of Figure 514-4
(d)	Shock	MIL-STD-810, Method 516, Procedures I, II and V.
(e)	Leakage	MIL-STD-810, Method 512, Procedure I
(f)	High temperature	MIL-STD-810, Method 501, Procedure I
(g)	Low temperature	MIL-STD-810, Method 502, Procedure I
(h)	Temperature shock	MIL-STD-810, Method 503, Procedure I
(i)	Humidity	MIL-STD-810, Method 507, Procedure I
(j)	Altitude	MIL-STD-810, Method 504, Procedure I
(k)	Salt fog	MIL-STD-810, Method 509, Procedure I
(l)	Fungus	MIL-STD-810, Method 508, Procedure I
(m)	Dust	MIL-STD-810, Method 510, Procedure I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

3.6.4 Storage conditions. The public address set shall be capable of being stored under the following conditions without degradation:

(a)	Ambient temperature range	-62°C to +75°C
(b)	Altitude	Sea level to 70,000 feet
(c)	Ambient humidity range	0 to 90 percent relative humidity

3.7 Electromagnetic interference and susceptibility.

3.7.1 Electromagnetic interference. The public address set shall be designed, fabricated and produced with the requirements of MIL-STD-461, equipment type 1C, as a design goal.

3.7.2 Electromagnetic susceptibility. The public address set shall not detect and amplify electromagnetic induced signals of 1 V per meter to less than 40 4B below standard output.

3.8 Weight. The weight of the public address set shall be as follows:

(a)	AN/UIQ-11 Public Address Set, consisting of: Amplifier, Audiofrequency AM-6482/UIQ-10 Control, Amplifier C-8967/UIQ-10 Loudspeaker, LS-608/UIQ-10 Accessory Kit (complete) Battery, BB-534	35 lbs
(b)	Loudspeaker Assembly LS-611/UIQ-10 consisting of: 3 Loudspeakers, LS-608/UIQ-10 on back plate All integral cables	31 lbs
(c)	AN/UIQ-10 Public Address Set, consisting of (a) and (b) above	66 lbs

3.9 Dimensions. Dimensions shall be in accordance with Drawing No. 030032000 and referenced documentation thereto.

3.10 Treatment and painting.

3.10.1 Exterior. The public address set shall be painted and treated in accordance with MIL-T-704, type A, and shall be finished with semigloss enamel conforming to TT-E-485. Color shall match Marine Corps green, No. 23 (see 6.3).

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the current version before use.

3.10.2 Interior surfaces. Interior surfaces shall be finished, if required, in accordance with MIL-E-16400.

3.10.3 Panel markings. Panel markings and other engraved or stamped nomenclature shall be white, color No. 37875 of FED-STD-595.

3.10.4 Nonmetallic materials. If fiberglass, plastic or other nonmetallic material not readily lending itself to painting is used, the material shall be impregnated with pigment approximating Marine Corps green, No. 23, as closely as possible.

3.11 Identification and marking. The public address set shall contain identification name plates and instruction plates in accordance with MIL-E-16400. Nomenclatures, when required, shall be requested in accordance with MIL-E-21981.

3.11.1 Nameplates. Nameplates and nomenclature shall be in accordance with MIL-P-15024 and shall be approved by the Government prior to installation.

3.11.2 Markings. Clear, concise and durable markings shall be provided for all controls, lamps, switches, fuses, jacks, test points and other components as necessary. All areas or portions of equipment which present a potential safety hazard to personnel, shall be clearly and concisely marked in accordance with MIL-STD-454, requirement 1.

3.11.3 Plug identification. All plugs shall be suitably identified.

3.12 Government-furnished property. The Government will furnish the equipment specified herein for incorporation in, and shipment with, the public address set. The contractor shall be responsible for furnishing all other items required.

3.13 Workmanship. The public address set, including all parts and accessories, shall be manufactured and finished in accordance with the requirements of MIL-E-16400.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:15Z
Check the source to verify that this is the current version before use.

of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. The contractor's quality control and inspection system shall conform to the provisions of MIL-I-45208.

4.1.1 Contractor product assurance. The contractor shall provide and maintain a means of determining product conformance in accordance with the requirements specified herein or elsewhere in the contract. The Government, at its option, may perform any evaluation deemed necessary to assure the adequacy of the means employed and the effectiveness of the contractor's product assurance methods and systems.

4.1.2 Government verification. All quality assurance operations required of the contractor shall be subject to Government verifications at scheduled or unscheduled intervals. Verification will consist of the following:

(a) Surveillance of the contractor's operations to determine that practices, methods, and procedures of the contractor's product assurance system are being applied and are, in fact, accomplishing the objectives of total compliance of the product with the requirements of this specification.

(b) Government product inspections to determine compliance of the specification requirements.

4.1.3 Accommodation and assistance. The Government quality assurance representative shall have the right to accesss of any area of the contractor's or his subcontractor's premises where any part of the work is being performed. The Government quality assurance representative shall be afforded unrestricted opportunity to verify conformance of the product with specification requirements. The contractor shall make his inspection equipment available for use by the Government quality assurance representative for verification purposes. The contractor's personnel shall be made available for operation of such inspection equipment as required.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) First article (see 4.3).

(b) Production (see 4.4).

(c) Sample (see 4.5).

(d) Preparation for delivery (see 4.6).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

4.3 First article inspection and tests. First article tests indicated in Table I shall be conducted at the contractor's plant or a laboratory designated by the contractor. The contracting officer, however, reserves the right to make additional first article tests to insure compliance with this specification. Prior to commencement of any first article tests, the contractor shall prepare and submit for approval to the contracting officer a complete first article test procedure.

4.3.1 Presubmission tests. Prior to the submission of the first article for testing, the contractor shall conduct such tests as may be necessary to insure that, to the best of his knowledge, the public address set meets all the requirements of this specification.

4.3.2 Approval of first article. Approval of the first article shall be in writing from the contracting officer upon satisfactory completion of all tests. No additional public address sets shall be delivered prior to the approval of the first article.

4.3.3 First article test report. The contractor shall prepare and submit to the procuring activity the first article test report after completion of the first article tests.

4.3.4 Noncompliance. Failure of any one of the first article tests shall constitute noncompliance with the requirements of this specification and shall be reason for rejection. The contractor shall immediately investigate the cause of failure, and shall report to the Government inspector and the responsible technical agency the results thereof and details of the corrective actions taken. The first article shall then be resubmitted for test. If the contractor cannot determine the cause of failure, the matter shall be referred to the contracting officer.

4.4 Production inspection. All public address sets shall be subjected to the production tests indicated in Table I.

4.5 Sample inspection. During the production phase, sample tests shall be conducted. The sample tests shall consist of all tests indicated in Table I. A minimum of one sample public address set shall be randomly selected by the cognizant Government inspector from each block of cumulative quantity produced as indicated below:

Sample Number	Cumulative Qty Produced	Qty to be tested
1	1 - 10	3
2	11 - 60	3
3	61 - 150	3
		1 for each additional 25 or fraction thereof.

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

TABLE I - Tests

Test	Requirement Paragraph	Test Para	First Article	Sample	Pro-duction
Visual Inspection	3.2, 3.3, 3.8, 3.9	4.9.1	X	X	X
Electrical:	3.3.3.1.3				
Continuity		4.9.2.1	X	X	X
Electrical Measurement		4.9.2.2	X	X	X
Standard Performance:					
Input power	3.3.3.1.3(a)	4.9.3	X	X	X
Warmup	3.3.3.1.3(b)	4.9.3	X	X	X
Duty cycle	3.3.3.1.3(c)	4.9.3	X	X	X
Overload and reverse polarity protection	3.3.3.1.3(d)	4.9.3	X	X	X
Audio output power	3.3.3.1.3(e)	4.9.3	X	X	X
250 W	3.3.3.1.3(e)(1)	4.9.3	X	X	X
110 W	3.3.3.1.3(e)(2)	4.9.3	X	X	X
Idle noise	3.3.3.1.3(e)(3)	4.9.3	X	X	X
Frequency response	3.3.3.1.3(e)(4)	4.9.3	X	X	X
Audio output signal	3.3.3.1.3(f)	4.9.3	X	X	X
On-Off function, parallel operation	3.3.3.1.3(g)	4.9.3	X	X	X
Standby current drain	3.3.3.1.3(h)	4.9.3	X	X	X
Modes of operation	3.3.2	4.9.3	X	X	X
Alert tone warning	3.3.3.2.5	4.9.3	X	X	X
Attack tone warning	3.3.3.2.6	4.9.3	X	X	X
Reliability:	3.4				
First Article		4.9.4.1	X		
Sample		4.9.4.2		X	
Analysis of Failures		4.9.4.3	X	X	
Service Conditions:	3.6.3				
Low Temperature	3.6.3, 3.6.4	4.9.5.5	X		
High Temperature	3.6.3, 3.6.4	4.9.5.4	X		
Vibration	3.6.3	4.9.5.1	X	X	
Shock	3.6.3	4.9.5.2	X		
Leakage	3.6.3	4.9.5.3	X	X	
Temperature shock	3.6.3	4.9.5.6	X		
Humidity	3.6.3	4.9.5.7	X		
Altitude	3.6.3	4.9.5.8	X		
Salt fog	3.6.3	4.9.5.9	X	X	
Fungusproofness	3.6.3	4.9.5.10	X	X	
Dust	3.6.3	4.9.5.11	X		
Electromagnetic Interference	3.7	4.9.6	X		
Maintainability	3.5	4.9.7	X		

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

4.6 Preparation for delivery inspection. The preparation for delivery inspection shall be performed on public address sets which have passed inspections specified herein and have been prepared for delivery. Inspection shall insure compliance with the requirements of Section 5 of this specification.

4.7 Test plans. Test plans describing in detail first article, production and sample testing shall be prepared by the contractor in accordance with the requirements of MIL-STD-831 and submitted to the contracting officer for approval prior to initiation of testing within the scope of the test plan. Approval of the test plan by the contracting officer or his representative is required prior to commencement of the testing under the plan. The test plans shall include all test procedures deemed necessary and practicable by the contractor to demonstrate compliance with this specification.

4.8 Rejections. Any rejected public address set shall be suitably marked to indicate cause of rejection. Resubmitted public address sets shall be plainly marked, giving full particulars for the rejection and the corrective action taken to prevent reoccurrence.

4.9 Tests and inspection. All inspection and testing shall be performed in the manner specified herein. Any damage, deterioration or change in any component which could in any manner prevent the equipment from meeting performance, maintenance, or service requirements during service life (unless excepted herein) shall be considered cause for failure to pass the particular test or inspection. Inspection records of all examinations and tests shall be kept complate and available to the Government.

4.9.1 Visual inspection. The public address set shall be given a thorough visual inspection to determine that the quality of all materials and workmanship is in compliance with the requirements of this specification, MIL-STD-454 and MIL-E-16400. Particular attention shall be given to the following:

(a) Completeness

(b) Nameplates, identification markings and labels

(c) Ease of operation of connector mating, thumb screws, controls and switches and any other part intended for adjustment, movement or operation.

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:15Z
Check the source to verify that this is the current version before use.

(d) Finishes

(e) Welded joints

(f) Check of solder joints

(g) The fit of components in their respective positions.

(h) Check of mounting means

(i) Check of safety features

(j) Fastening and securing devices or parts

(k) Accessibility of components and parts for servicing.

(l) Cable run between components, including plugs and receptacles.

(m) Fit of sealing gasket on cover, and wear on gasket.

(n) Check of all connector fittings

(o) Overall dimensions.

(p) Weight.

(q) Other visual defects.

4.9.2 Electrical tests. The public address set shall be given all electrical tests necessary to conform that all circuits are inherently sound and in compliance with the requirements of this specification. The electrical tests shall include, but not necessarily be restricted to, the following:

4.9.2.1 Continuity. Each electrical component, and each cord and cable, shall be given a continuity test to ascertain if it is wired and connected correctly, if good electrical contact is obtained, and if it is wired in accordance with the wiring diagrams to be delivered under the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

4.9.2.2 Electrical measurements. Measurements of important operating voltages at module pins, connector terminals, and all electrical junctions throughout the equipment shall be checked and recorded for conformance to those shown on the circuit labels, schematic drawings, wiring diagrams and troubleshooting charts. This shall be done with all controls set for normal operation of the public address set. The circuit labels, schematic drawings, wiring diagrams and troubleshooting charts shall be provided as part of the test procedures. Circuit labels shall include voltage levels and waveshapes. Instruments of the vacuum-tube-voltmeter-type or solid state equivalent shall be used for these tests. Conclusive agreement shall be reached between the contractor and the procuring activity on the specific values of voltage, etc., in these tests.

4.9.3 Standard performance tests. The public address set shall be given the standard performance tests indicated in Table I to confirm that the equipment meets the performance specified herein. The standard performance tests shall be performed in conjunction with each environmental test.

4.9.4 Reliability tests. The reliability specified in 3.4.1 shall be demonstrated as specified herein.

4.9.4.1 First article reliability test. This test shall be performed in accordance with MIL-STD-781 as follows:

(a) Test level. Test level F of MIL-STD-781, modified with temperature limits of -40°C to +55°C, shall apply.

(b) Sample size. No more than three first article units shall be subjected to the reliability test.

(c) Test plan. Test Plan III of MIL-STD-781 shall apply.

(d) Duty cycle. For purposes of reliability testing, the duty cycle shall be 10 minutes on (250 W), 1 minute off. The public address set shall be turned off during the temperature cooling cycle.

4.9.4.2 Sample reliability test. Each sample production unit selected for testing shall be tested in accordance with MIL-STD-781 as follows:

(a) Test level. Test level shall be as 4.9.4.1(a).

(b) Test plan. Test plan shall be as 4.9.4.1(b).

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

4.9.4.3 Analysis of failures. Failures shall be analyzed in accordance with MIL-STD-781.

4.9.5 Environmental tests. The public address set shall be subjected to the following environmental tests. These tests shall be performed in accordance with MIL-STD-810 in the sequence specified by Table I, group 1 E, of MIL-STD-810. To determine compliance with the requirements of 3.6, the standard performance tests indicated in Table I shall be performed.

4.9.5.1 Vibration. The public address set shall be subjected to a vibration test in accordance with Method 514, Procedure I, curve W, of Figure 514-5 of MIL-STD-810.

4.9.5.2 Shock. Shock test shall be in accordance with Method 516, Procedures I and V of MIL-STD-810. The shock pulse shape shall be in accordance with Figure 516-2, amplitude a and time duration c. The public address set shall be turned on and operated in the 250-W mode.

4.9.5.3 Leakage. Leakage test shall be in accordance with Method 512, Procedure I of MIL-STD-810.

4.9.5.4 High temperature. High temperature test shall be in accordance with Method 501, Procedure I, of MIL-STD-810. Test operation of the public address set at +55°C, using 22, 28 and 32 Vdc source. Maximum temperature shall be +55°C. Reduced performance shall be obtained at +65°C.

4.9.5.5 Low temperature. Low temperature test shall be in accordance with Method 502, Procedure I, of MIL-STD-810, except that after 72 hours at -62°C, the temperature shall be raised to -20°C to test operation using 22, 28 and 32 Vdc source. Reduced performance shall be obtained at -40°C.

4.9.5.6 Temperature shock. Temperature shock test shall be in accordance with Method 503, Procedure I, of MIL-STD-810 with the following exceptions:

(a) High temperature shall be +65°C.

(b) The test shall be concluded at the end of three cycles.

4.9.5.7 Humidity. Humidity test shall be in accordance eith Method 507, Procedure I, MIL-STD-810 with the following exceptions:

(a) Maximum temperature shall be +55°C.

(b) The test will be concluded at the end of three cycles.

(c) Moisture may be removed by wiping.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:15Z
Check the source to verify that this is the currentversion before use.

4.9.5.8 Altitude. Altitude test shall be in accordance with Method 504, Procedure I, of MIL-STD-810, equipment Class 1B, except the maximum temperature shall be +55°C.

4.9.5.9 Salt fog. Salt fog test shall be performed with the public address set in a test chamber in operating condition in accordance with Method 509, Procedure I, of MIL-STD-810.

4.9.5.10 Fungusproofness. Fungusproofness shall be tested in accordance with Method 508, Procedure I, of MIL-STD-810.

4.9.5.11 Dust. Dust test shall be in accordance with Method 510, Procedure I, of MIL-STD-810.

4.9.6 Electromagnetic interference test. The public address set shall be subjected to the test defined in MIL-STD-461, equipment type 1C.

4.9.7 Maintainability demonstration test. The maintainability as specified in 3.5 shall be demonstrated in accordance with the requirements of MIL-STD-471.

4.9.7.1 Module replacement. This test shall be performed in accordance with Method II of MIL-STD-471.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging and packing. Preservation, packaging and packing shall be the level of shipment specified in the contract or order in accordance with MIL-E-17555 (see 6.2).

5.2 Marking. In addition to any special marking required by the contract or order, unit packages, intermediate packages, and shipping containers shall be marked in accordance with the requirements of MIL-STD-129.

6. NOTES

6.1 Intended use. The Public Address Set, AN/UIQ-10, is a tactical public address set, intended for tactical field use in several configurations suitable for fixed or man-pack application.

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:15Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Purchasers should exercise any desired options offered herein, and procurement documents should specify the following.

6.2.1 Procurement requirements.

(a) Title, number and date of this specification.

(b) Levels of preservation, packaging and packing (see 5.1).

6.2.2 Contract data requirements. Data conforming to Data Item Descriptions DI-E-4528, DI-E-4542, DI-R-4802, DI-R-4806, DI-R-4808, DI-R-4809, DI-R-4811, DI-T-4901, DI-T-4902, DI-T-4903, DI-T-4904, DI-T-4907 and DI-T-4908, will usually be required for delivery in connection with this specification. When so required, such data will be specified for delivery on a DD Form 1423 included in the contract.

6.3 Color. Color chips for Marine Corps green, No. 23, may be obtained from the Commandant of the Marine Corps (Code CSY-10, Headquarters U. S. Marine Corps, Washington, D. C. 20380.

6.4 First article instructions. The first article shall be examined and tested for approval at the contractor's plant or at an independent commercial testing laboratory acceptable to the procuring activity. Selected first article tests will be witnessed by a representative of the procuring activity. Tests not witnessed by a representative of the procuring activity shall be witnessed and certified by the appropriate defense contract administration services district representative. Approval of the first article shall be by the contracting officer.

Preparing activity:
Navy - MC
Project No. 5830-N045

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 68 WHICH MAY BE USED

S/N 0102-014-1802

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:15Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

DoD-317

Commandant of the Marine Corps
(Code CSY-10)
Headquarters, U. S. Marine Corps
Washington, D. C. 20380

FOLD

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:15Z
Check the source to verify that this is the current version before use.