MILITARY SPECIFICATION

TEST SET, BATTERY-STARTER

1. SCOPE

1.1 This specification covers the requirements for one type of battery-starter test set suitable for testing 6- and 12-volt (V) storage batteries, starter-motor amperage draw, starter circuits, and switches used in 6-, 12-, and 24-V battery-starter systems.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on the date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-591	- Box, Fiberboard, Wood-cleated.
PPP-B-601	- Box, Wood, Cleated-plywood.
PPP-B-621	- Box, Wood, Nailed And Lock-corner.
PPP-B-636	- Box, Fiberboard.

MILITARY

MIL-P-116	- Preservation, Methods Of.
MIL-T-152	- Treatment, Moisture- And Fungus-resistant, Of Communications, Electronics, And Associated Electrical Equipment.
MIL-V-173	- Varnish, Moisture- And Fungus-resistant, (For The Treatment of Communications, Electronic And Associated Electrical Equipment).
MIL-M-10304	- Meters, Electrical Indicating, Panel Type, Ruggedized, General Specification For.

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:08Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures And Tables For Inspection By Attributes.

MIL-STD-129 - Marking For Shipment And Storage.

(Copies of specifications and standards required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS

Handbook H28 - Screw-Thread Standards For Federal Services

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, D. C. 20402.)

3. REQUIREMENTS

3.1 First article. Prior to submission of any complete production units, the contractor shall furnish one first article for examination and test to determine conformance to this specification. The first article shall consist of one complete test set identical to the product which the contractor will subsequently deliver in fulfillment of the contract. Approval of the first article shall not relieve the contractor of the responsibility to furnish test sets conforming to the requirements of this specification. The first article may be included in final shipment as part of the total quantity to be furnished under the contract or order, provided it is completely refurbished.

3.2 Materials. All materials used in the fabrication of the test set shall be new and of sufficient quality and strength to meet normal use of the equipment under field conditions. Contact between dissimilar metals, especially brass, copper, or steel in contact with aluminum or magnesium, shall be avoided wherever possible. All surfaces shall be smooth and free from burrs or sharp edges. Molding fins and excess metal shall be removed from castings.

3.3 Design and construction. The test set shall consist of an ammeter, voltmeter, carbon pile variable resistance load unit, controls, test leads and a portable carrying case. The test set shall perform its intended function without removal of any components (except test leads) from the

Source: https://assist.dla.mil -- Downloaded: 20261O-20T21:08Z
Check the source to verify that this is the current version before use.

carrying case and without disconnecting or removing the storage battery from the battery-starter system to be tested. All parts shall be new, of first class quality and of the latest approved design. All parts shall be of such size, material and strength as to sustain properly the maximum allowable work loads and capacities imposed upon them, with an adequate factor of safety, maximum working efficiency and minimum wear.

3.3.1 Ammeter and voltmeter. The ammeter and voltmeter shall be flush mounted on the instrument panel (i.e. the major portion of the meter mass shall be located behind the instrument panel). The design and construction of each meter shall conform to MIL-M-10304. The overall size of the meters shall be sufficiently large without compromising or crowding the instrument panel. The voltmeter shall have three scales selectable by a control knob on the meter instrument panel.

3.3.2 Carbon pile variable resistance load unit. The resistive load unit shall consist of a bank of carbon composition resistance sections, a control knob, and if necessary, a cooling fan. The load unit and fan (when utilized) shall be located behind the instrument panel in the meter compartment or in a compartment separate from the meter compartment. The load unit control knob shall be appropriately located on the instrument panel in a position suitable to its purpose and function. In the event operation of load unit is capable of causing a temperature rise greater than 40°F above ambient air temperature in the instrument panel, the interior walls of the meter, or the load compartments, a cooling fan shall be provided. The cooling fan shall be of sufficient capacity and shall be appropriately located to provide maximum heat dissipation and cooling so that 48 hours of continuous operation shall not cause a temperature rise of more than 40°F above ambient air temperature in the instrument panel, the interior walls of the meter, or the load compartments. The fan shall automatically be in the "on" state when the test set is connected for test and shall operate from a nominal direct current (dc) of 6, 12, or 24 V.

3.3.3 Test leads. Each test lead shall be a minimum length of 5 feet, color-coded for identification, and terminated in insulated spring clips. The negative ammeter lead may be permanently connected to the test set. The positive ammeter lead shall be attached by a wing nut to the 6-, 12-, or 24-V terminal. Each of the voltmeter leads shall be permanently attached.

3.3.4 Meter instrument panel. The meter instrument panel shall be constructed of sheet steel not less than 0.0359 inch nominal thickness, Manufacturer's Standard Gage No. 20. The panel shall have a dull finish. All electrical component parts shall be mounted directly on the panel or on a chassis attached to the panel so that when the panel is removed from the case all components are removed from the case. All binding posts and switches passing through the instrument panel shall be insulated from the panel to withstand the mechanical and electrical stresses specified herein. Dials, markings and controls on the instrument panel shall be located to be read from the front of the test set.

Source: https://assist.dla.mil -- Downloaded: 20260410-20T21:08Z
Check the source to verify that this is the current version before use.

3.3.5 Portable carrying case. The portable carrying case shall include a test lead storage compartment, a meter instrument panel compartment, carrying handle, rubber rest buttons, hinged removable cover, tension cover fasteners and a circuit diagram. The maximum overall dimensions of the case shall be 12 inches wide across the front, 15 inches long front-to-back, and 9 inches high. The overall dimensions include the rubber rest buttons, hinges, and carrying handle. The case shall be constructed to provide for dissipation of heat from the variable resistance load unit. The case shall be waterproof when it is resting on its bottom surface. (Bottom surface is defined as the side opposite the cover.) The case shall be constructed of sheet steel not less than 0.0359 inch nominal thickness, Manufacturer's Standard Gage No. 20.

3.3.5.1 Compartments. A storage compartment shall be provided in the carrying case to store all test leads separately from the meters and load unit. At least one compartment shall be provided for the meters and load unit. Partitions between all compartments shall be constructed of sheet steel not less than 0.0329 inch nominal thickness, Manufacturer's Standard Gage No. 21.

3.3.5.2 Removable cover. The removable cover shall be hinged to the case on one end and fastened to the case by two tension fasteners on the end opposite the hinges. A storage compartment for an instruction handbook shall be located in the cover.

3.3.5.3 Carrying handle. The carrying handle shall be of sufficient size to provide a comfortable hand grip. The handle shall be located on the same side of the case as the hinges for the removable cover but shall not be affixed to the cover. The handle shall be capable of being folded against the case to facilitate stacking. If a wire type handle is furnished, it shall be 1/4-inch diameter minimum at the grip part of the handle.

3.3.5.4 Rubber rest buttons. The rubber rest buttons shall be oil resistant. One rubber rest button shall be located on the case bottom and one on the side opposite the carrying handle.

3.3.5.5 Circuit diagram. A complete circuit diagram, including component values and part numbers, shall be legibly marked on the inside bottom of the case. The circuit diagram shall be located so it is not visible until the instrument panel is removed.

3.3.6 Fastening devices. All screws, pins, bolts, and similar parts shall be installed, wherever practical, with a positive means to prevent loss of tightness. Such parts shall not be swaged, peened, staked or otherwise permanently fixed. All threaded parts shall conform to H28.

3.3.7 Electrical connections. With the exception of screw-type electrical terminal connections, electrical connections shall be mechanically secured before being soldered or brazed; however, connections on screw-type terminals shall be mechanically secured with a positive means to prevent

Source: https://assist.dla.mil -- Downloaded: 20261O-20T21:08Z
Check the source to verify that this is the current version before use.

their becoming loose. The use of soldering acids, acid fluxes, or soldering salt which might cause corrosion shall be avoided wherever possible.

3.3.8 Corrosion resistance. All components shall be inherently corrosion resistant, or shall be finished or treated to resist corrosion.

3.3.9 Fungus control. Unless otherwise specified (see 6.2), the test set shall be treated for fungus resistance in accordance with type 1 requirements of MIL-T-152 using material conforming to requirements of MIL-V-173.

3.3.10 Safety devices. The test set shall be fitted with safety devices or protective covering for all parts or components which present safety hazards.

3.3.11 Interchangeability. All parts or components shall be constructed to standards which will permit their replacement or adjustment without modification to any items in the test set.

3.3.12 Accessibility. All parts or components subject to wear, breakage, or distortion shall be accessible for adjustment and repair.

3.3.13 Instruction handbook. The contractor shall furnish one instruction handbook with each test set. The handbook shall contain necessary operating instructions, drawings, illustrations, parts lists, circuit diagrams and safety precautions to ensure proper operation and maintenance of the test set.

3.4 Performance characteristics. The performance characteristics of the test set shall be as follows.

3.4.1 Accuracy. The accuracy of the test set at an ambient temperature of 80°F ±10°F with the test set placed in a horizontal position shall be within 0.5 percent at 1/3 scale, 1 percent at 2/3 scale, and 2 percent at full-scale for amperage measurements and 0.5 percent at 1/2 scale and 1 percent at full-scale for voltage measurements.

3.4.2 Ammeter and voltmeter. The performance characteristics of the ammeter and voltmeter shall be within the parameters specified in MIL-M-10304 and shall have sufficient range and increment gradations for the intended purposes.

3.4.3 Carbon pile variable resistance load unit. The load unit shall provide an infinitely variable load of sufficient capacity for the intended purposes. A control knob shall be provided to electrically disconnect and vary the load bank resistance.

3.4.4 Test leads. All test leads shall be of sufficient rating for the intended purposes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:08Z
Check the source to verify that this is the current version before use.

3.4.5 Momentary overload capacity. Under normal ambient air temperature, and with the test leads connected properly or reversed, the test set shall be capable of withstanding momentary overload situations equal to ten times the meter end-scale value.

3.4.6 Sustained overload capacity. Under normal ambient air temperature, and with the test leads connected properly or reversed, the test set shall be capable of withstanding sustained overload situations equal to a value 20 percent greater than the meter end-scale value.

3.4.7 Dielectric strength. The test set shall withstand a potential of 500 V alternating current (ac) at 60 hertz (Hz) for a period of 1 minute without showing evidence of smoking, arcing, flashover, charred insulation, or other damage caused by such a high voltage application.

3.4.8 Environmental conditions. The test set shall be capable of withstanding and operating under the following environmental conditions.

3.4.8.1 Vibration. The test set shall be capable of undergoing the vibration normally encountered in transport by air, sea and land vehicles.

3.4.8.2 Shock. The test set shall be capable of undergoing the shock normally encountered in vehicular transportation under military field conditions (including accidental drops).

3.4.8.3 Temperature. The test set shall meet temperature requirements as follows:

(a) Storage. The test set shall withstand, without damage, storage in a temperature of -65°F to +155°F.

(b) Operating. The test set shall operate in ambient air temperatures of -25°F to +115°F.

3.4.8.4 Humidity. The test set shall withstand exposure to 93 to 100 percent relative humidity at air temperatures from +80°F to +85°F and 5 percent relative humidity at +110°F to +115°F.

3.4.8.5 Waterproofing. With the cover closed, the case shall not show evidence of leakage, at or above the panel elevation, when subjected to heavy rain.

3.5 Painting. Unless otherwise specified (see 6.2), the test set shall be painted in accordance with the manufacturer's standard commercial practice.

3.6 Identification marking of product. The test set shall be marked for identification using a metal identification plate permanently attached to the instrument panel. The information to be included on the plate shall be

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:08Z
Check the source to verify that this is the current version before use.

as follows:

TEST SET, BATTERY-STARTER

Federal Stock No._____
Manufacturer's Part No._____
Name of Manufacturer (or Contractor)_____
Date of Manufacture_____

3.7 Workmanship. Workmanship shall assure good quality equipment of a neat general appearance. Workmanship standards shall be consistent with the requirements specified herein.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

(a) First article (see 4.3).
(b) Quality conformance (see 4.4).
(c) Preparation for delivery (see 4.7).

4.3 First article inspection. The first article shall be subjected to the examinations and tests indicated for first article in Table I. Failure of the first article to pass any of the examinations or tests shall be cause for rejection. After first article tests have started, only adjustments made by externally available controls, without the use of tools, shall be permitted. Any other adjustment, repair, or replacement shall be considered a failure.

4.4 Quality conformance inspection. The quality conformance inspection shall consist of the following inspections:

(a) Individual. Each test set manufactured for delivery in fulfillment of the contract or order shall be subjected to tests indicated in Table I.

(b) Sample. Sample test sets selected in accordance with MIL-STD-105, inspection level S-3, Table II-A shall be subjected to tests indicated in Table I. The percent defective shall be as indicated in Table I.

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:08Z
Check the source to verify that this is the current version before use.

Table I. Examinations and tests

Type of inspection			Examination or test	Requirement paragraph	Test paragraph	Percent defective acceptable (Sample)
First article	Quality conformance Individual	Quality conformance Sample				
X		X	Examination	Section 3	4.5	0
X	X	X	Operation		4.6.1	
X		X	Accuracy	3.4.1	4.6.2	1.5
X	X	X	Cooling	3.3.2	4.6.5	1.5
X		X	Momentary overload capacity	3.4.5	4.6.3.1	1.5
X		X	Sustained overload capacity	3.4.6	4.6.3.2	1.5
X		X	Dielectric strength	3.4.7	4.6.3.3	1.5
X	X	X	Vibration	3.4.8.1	4.6.4.1	2.5
X	X	X	Shock	3.4.8.2	4.6.4.2	2.5
X	X	X	Storage temperature	3.4.8.3	4.6.4.3	1.5
X	X	X	Operating temperature	3.4.8.3	4.6.4.4	1.5
X	X	X	Humidity	3.4.8.4	4.6.4.5	1.5
X	X	X	Waterproofing	3.4.8.5	4.6.4.6	2.5
X		X	Preparation for delivery	Section 5	4.7	1.0

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:08Z
Check the source to verify that this is the current version before use.

4.5 Examination. The test sets selected for examination shall be visually examined for the following defects. Presence of one or more defects shall be cause for rejection.

(a) Materials not as specified
(b) Test leads not as specified
(c) Meter instrument panel not as specified
(d) Portable carrying case not as specified
(e) Fastening devices not as specified
(f) Electrical connections not as specified
(g) Fungus control not as specified
(h) Safety devices not as specified
(i) Interchangeability not as specified
(j) Accessibility not as specified
(k) Identification missing or not as specified
(l) Workmanship not as specified

4.6 Tests.

4.6.1 Operation. The test set shall be sequentially connected to a 6-, 12-, and 24-V dc source. The voltmeter shall indicate, respectively, 6, 12, and 24 V dc. The test set shall be connected to a 24-V dc source and the ammeter reading shall vary inversely with changes in the position of the load unit control.

4.6.2 Accuracy. The test set shall be placed in a horizontal position and shall be allowed to stabilize, for approximately 2 hours, in an ambient air temperature of 80°F ±10°F. After the test set has stabilized, the accuracy, with the unit connected to a calibrated load, shall be within the parameters specified in 3.4.1.

4.6.3 Reliability. The reliability tests shall be as follows:

4.6.3.1 Momentary overload capacity. The test set shall be allowed to stabilize in ambient air temperature between 25°F and 115°F. With the test leads connected properly, and then reversed, each test set meter circuit shall be subjected to: (1) a minimum of nine momentary overload situations wherein each momentary overload situation is equal to ten times the meter end-scale value for a period of one-half second (spaced at 1-minute or greater interval-periods; and (2) one momentary overload situation equal to ten times the meter end-scale value for a period of 5 seconds. At the conclusion of this test, the test set shall be tested for serviceability employing the test specified in 4.6.2.

4.6.3.2 Sustained overload capacity. The test set shall be allowed to stabilize in ambient air temperature between 25°F and 115°F. With the test leads connected properly and then reversed, each test set meter circuit shall be subjected to a sustained overload situation equal to a value 20 percent greater than the meter end-scale value for a period of 8 hours.

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:08Z
Check the source to verify that this is the current version before use.

At the conclusion of this test, the test set shall be tested for serviceability employing the test specified in 4.6.2.

4.6.3.3 Dielectric strength. The test set shall be allowed to stabilize in ambient air temperature between 25°F and 115°F. Both test set meters shall be disconnected and the test set shall be subjected to a dielectric strength test of 500 V ac at 60 Hz for a period of 1 minute. This test shall be performed between conductor and ground, conductor and conductor, between mutually insulated portions of the test set, and between insulated portions and ground. During and after this dielectric strength test, the test set shall be examined for evidence of smoking, arcing, flashover, charred insulation, or other damage possibly caused by application of the high voltage.

4.6.4 Environmental. The environmental tests shall be as follows:

4.6.4.1 Vibration. The test set, while enclosed in the carrying case, shall be rigidly mounted on a vibration machine and subjected to vibrations (simple harmonic motion) having an amplitude of 0.03 inch (0.06 inch maximum excursion) through a frequency range of 10 to 35 Hz for a period of one-half hour in the direction of each of the three major axes. The frequency shall be continuously varied and the entire frequency range shall be traversed in approximately 1 minute. At the conclusion of the test, the test set shall be examined for evidence of breakage, permanent deformation, and loosening of parts, and shall be tested for serviceability employing the test specified in 4.6.2.

4.6.4.2 Shock. The test set shall be dropped three times onto a concrete surface from a height of 8 inches through each of the major three axes. At the conclusion of the test, the test set shall be examined for breakage, permanent deformation, and loosening of parts, and shall be tested for serviceability employing the test specified in 4.6.2.

4.6.4.3 Storage temperature. The test set shall be subjected to an ambient air temperature of -60°F to -65°F for a period of 72 hours and a 24-hour cycling of temperature starting with 10 hours at +90°F, followed by 5 hours of steady increase to +155°F, 4 hours at +155°F, and 5 hours of steady decrease to +90°F. After these tests, the test set shall be examined for physical damage and shall be tested for serviceability employing the test specified in 4.6.2.

4.6.4.4 Operating temperature. The operating temperature tests shall be as follows:

4.6.4.4.1 Low ambient. The test set shall be allowed to stabilize in an ambient air temperature of -20°F to -25°F and, while at that temperature, it shall be tested employing the test specified in 4.6.2.

4.6.4.4.2 High ambient. The test set shall be allowed to stabilize in an ambient air temperature of +110°F to +115°F and, while at that temperature, shall be tested employing the test specified in 4.6.2.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:08Z
Check the source to verify that this is the current version before use.

4.6.4.5 Humidity. The test set shall be subjected to 20 hours exposure with relative humidity between 93 and 97 percent at an air temperature between +80°F and +85°F, followed by 4 hours of 100 percent relative humidity with condensation at +75°F to +80°F. In addition, the test set shall be subjected to 4 hours of 5 percent relative humidity at +110°F to +115°F. Air movement and radiation shall be negligible. At the conclusion of the humidity test, the test set shall be inspected for evidence of corrosion damage and shall be tested employing the test specified in 4.6.2.

4.6.4.6 Waterproofing. With the cover closed, the test set shall be subjected to a spray of water for 1 hour at the rate of 2-1/2 gallons per hour, per square foot, uniformly spread over the top of the case. At the conclusion of this test, the test set shall show no evidence of leakage at or above the panel elevation.

4.6.5 Cooling. The test set shall be allowed to stabilize in ambient air temperature between 25°F and 115°F. A 24-V dc source shall be connected to the test leads and the load unit control shall be adjusted for maximum indication on the ammeter. The 24-V dc source shall be alternately connected and disconnected from the test set at a duty cycle of 3 minutes "on" and 27 minutes "off" for 48 hours of continuous operation. This procedure shall not cause a temperature rise of more than 40°F above the ambient air temperature in the instrument panel, the interior walls of the meter, or the load compartments.

4.7 Preparation for delivery inspection. An inspection shall be made to determine that the packaging, packing, and marking comply with the requirements in Section 5. Defects shall be scored in accordance with the list below. The sample unit shall be one shipping container fully prepared for delivery. Sampling shall be in accordance with MIL-STD-105. The lot size shall be the number of shipping containers to be shipped at one time, to one destination, on one contract or order. The inspection level shall be S-1, and the Acceptable Quality Level shall be 1.0 defect per hundred units.

Examine	Defects
Markings (exterior and interior)	Omitted; incorrect; illegible; improper size, location, sequence, or method of application
Materials	Any component missing or damaged
Workmanship	Inadequate application of components such as incomplete closure of container flaps or loose strapping.
	Distortion of container

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:08Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Cleaning. The test set shall be thoroughly cleaned using cleaning process C-1 of MIL-P-116.

5.1.1.2 Drying. The test set, cleaned as described in 5.1.1.1, shall be dried using drying procedure D-1 or D-4 of MIL-P-116.

5.1.1.3 Interior packaging. All empty cavities within the carrying case shall be filled with a cushioning material to prevent any movement of parts. The instruction manual shall be placed in its compartment in the carrying case. The cover shall be secured on the carrying case by means of the fasteners provided.

5.1.1.4 Exterior packaging. Following completion of interior packaging in accordance with 5.1.1.3, each test set shall be packaged in conformance to Method II of MIL-P-116. The test set shall then be placed in a close fitting container conforming to style RSC, type CF, class domestic, variety DW, grade 175 of PPP-B-636. Closure shall be in accordance with the appendix thereto.

5.1.2 Level C. The test set shall be preserved and packaged in accordance with the contractor's normal practices providing such practices assure protection against corrosion and physical damage during shipment.

5.2 Packing. Packing shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A. Test sets, packaged as specified in 5.1.1, shall be packed in close fitting containers conforming to one of the following specifications. Boxes shall be closed in accordance with the applicable box specification or appendix thereto. The maximum number of test sets placed in each container shall be limited by the gross weight listed below.

Specification	Gross weight
PPP-B-591, class II (overseas), style A	200 lbs.
PPP-B-601, overseas type, style A	200 lbs.
PPP-B-621, class 2 (overseas), style 4, grade B	250 lbs.
PPP-B-636, style IC, type CF, class weather resistant, variety DW grade V11c	See table I of PPP-B-636

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:08Z
Check the source to verify that this is the current version before use.

5.2.2 Level B. Test sets, packaged as specified in 5.1.1, shall be packed in close fitting containers conforming to one of the following specifications. Boxes shall be closed in accordance with the applicable box specification or appendix thereto. The maximum number of test sets placed in each container shall be limited by the gross weight listed below.

Specification	Gross weight
PPP-B-591, class I (domestic), style A	225 lbs.
PPP-B-601, domestic type, style A	300 lbs.
PPP-B-621, class 1 (domestic), style 4, grade B	250 lbs.
PPP-B-636, style RSC, type CF, class domestic, variety DW, grade 600	See table II of PPP-B-636

5.2.3 Level C. The test set shall be packed in accordance with the contractor's normal practices provided such practices assure carrier acceptance and adequate protection during shipment.

5.3 Marking. In addition to any special marking required by the contract or order, interior packages and shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The battery-starter test set is intended to be used with military vehicles in the field or in maintenance shops.

6.2 Ordering data. Purchasers should exercise any desired options offered herein, and procurement documents should specify the following:

6.2.1 Procurement requirements.

(a) Title, number, and date of this specification.
(b) When fungus resistance treatment shall be other than as specified in 3.3.9.
(c) When test set shall be painted other than as specified in 3.5.
(d) Level of preservation, packaging, and packing required (see 5.1 and 5.2).

6.2.2 Contract data requirements. Data conforming to Data Item Descriptions DI-M-4707 and DI-T-4902 will usually be required for delivery in connection with this specification. When so required, such data will be specified for delivery on a DD 1423 included in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:08Z
Check the source to verify that this is the current version before use.

6.3 First article instructions. The procuring activity shall specify the date and the location to which the first article is to be furnished for examination and test. Records of the first article inspection shall be kept complete by the supplier and shall be made available to the Government upon request.

6.4 Supersession data. This specification includes the requirements of MCSA Purchase Description PD-1A, Test Set, Battery-Starter, dated 1 August 1964.

Preparing activity:
Navy-MC
Project No. 6625-N468

Source: https://assist.dla.mil Downloaded: 2026-10-20T21:08Z
Check the source to verify that this is the current version before use.