INCH POUND

MIL-T-83809(84)

26 APRIL 1991

M I L I T A R Y S P E C I F I C A T I O N

TRUCK, LIFT, FORK, ELECTRIC, ORDER SELECTOR, HIGH LIFT RIDER, 3000 POUND CAPACITY, 193 INCH MINIMUM LIFT

This specification is approved for use within WR-ALC Department of the Air Force, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the requirements for a battery powered, order selector, industrial type, forklift truck.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

MILITARY

MIL-P-514	Plates, Identifications, and Marking, Blank

STANDARDS

FEDERAL

FED STD No. 595	Colors

Beneficial comments {recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed 10: WR-ALC/LZMD Robins AFB3,GA 31098-5365, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3%30

DISTRIBUTION STATEMENT A: Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-STD-889 Dissimilar Metals

Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, Section D, 700 Robbins Avenue Philadelphia, PA 19111-5094.

2.2 Non-Government The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN NATIONAL STANDARDS INSTITUTE, INC. (ANSI)

B56.1 - Safety Standards for Powered Industrial Trucks.
B56.11.3- Load Handling Symbols for Powered Industrial 'Trucks.

(Application for copies should be addressed to the American National Standards Institute, Inc., 1430 Broadway, New York, NY 10018)

DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION 29 CFR, Chapter XVII, Part 1910.178
Occupational Safety and Health Standards

(Application for copies should be addressed to the Superintendent of Documents, U.S. Government Printing Off Ice, Washington D.C. 20402).

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA Standards

(Application for copies should be addressed to the National Electric Manufacturers Association, 155 East 44th Street, New York, NY 10017).

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

J514	Hydraulic Tube Fittings, Standard
J534	Lubrication Fittings, Standard
J754	Lubrication Types-Construction Industrial Machinery, Information Report
J833	Human Physical Dimensions, Recommended Practice

(Application for copies should be addressed to the Society of Automotive Engineer, Inc., 400 Commonwealth Drive, Warrendale, PA 15096).

U.S. AIR FORCE DRAWING

U.S. Air Force drawing number 8838302

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:45Z
Check the source to verify that this is the current version before use.

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specifications, specification sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 **Description**. The truck shall be a commercial, order selector, high lift rider (in accordance with ANSI B56.I) electric powered forklift. The forklift shall be equipped with standard instruments, components, and accessories normally required for the safe and effective operation of the truck. The truck shall be complete with all components that are standard with the contractor's products, whether stipulated herein or not, together with such accessories, and options, as maybe specified herein. The truck shall be equipped with all other components and parts not specifically mentioned but necessary to provide a functional machine and shall conform in quality to that normally provided to the commercial industry.

3.1.1 First article. The supplier shall furnish one truck for examination and testing to prove that his production methods and choice of design detail will produce trucks that comply with the requirements of this specification. Examinations and tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government. Approval of the first article truck by the activity concerned shall not relieve the supplier of his obligation to furnish trucks conforming to this specification. The approved first article truck shall be presented for acceptance as the last unit for delivery under the contract after being rehabilitated to a new condition.

3.1.2 DESIGN

3.1.2.1 Design. The truck shall be designed for 3000 pounds minimum capacity at 24 inch load center, up to the maximum lift height of the truck. The load center is measured from the forward vertical load carrying surface of the forks.

3.1.2.2 Safety. The truck shall conform to the applicable requirements of ANSI B56.1 and Occupational Safety and Health Standards requirements of 29 CFR, Chapter XVII, Part 1910.178.

3.1.2.3 **Environmental requirements**. The truck shall operate in any ambient temperature from 0°F to 110°F.

3.1.2.4 Lubrication. Lubrication means shall be provided for all moving parts that require periodic lubrication. The types of lubrication shall be selected from and in accordance with SAE J754. Grease lubrications fittings shall conform to SAE J534.

3.1.2.5 Maintainability. All maintenance and servicing functions shall be capable of being performed using common hand tools or special tools (see 3.8) furnished by the contractor. Provision shall be made for adjustment, servicing, and replacement of ail electrical assemblies and components, hydraulic system components, battery, wearing parts of lift and tilt mechanism, brakes and components, wearing parts of steering assembly, tires, wheels, and horns without removal of any major parts other than covers. There shall be no interference with servicing or draining of oils and lubricants to or from any assembly or components by frame members or other obstructions. Drain holes with removable drain plugs shall provide for complete drainage without disconnection of lines. All drain plugs shall be the magnetic type.

3.1.2.6 Fluid level indicator. All fluid level indicators shall be located where they are readily accessible without danger of injury to the operator. if a panel must be opened to reach a level indicator, it shall open without the need of tools, and shall be hinged to stay on the truck when open.

3.1.2.7 Dissimilar metals. Unless protected against electrolytic corrosion, dissimilar metals shall not be used in intimate contact. Dissimilar metals are defined in MIL-STD-889.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

3.1.2.8 Fasteners. All fasteners of Grade 5 or higher shall meet the quality assurance requirements of U.S. Air Force drawing 8838302.

3.1.2.9 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the forklift trucks may be newly fabricated from recovered materials to the maximum extent practicable, provided the forklift trucks produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the forklift trucks.

3.1.3 Electric motors. Motors shall be industrial type with a high starting torque. The insulation for motors shall be class B, F or H as defined in NEMA standards.

3.1.4 Battery. The battery shall have a capacity of at least 765 ampere hour for 24 volts or at least 510 ampere hour for 36 volts. In addition, the battery shall be of sufficient capacity to provide at least 8 hours of continuous operation of the forklift when tested in accordance with 4.4.13 of this specification, without recharging or replacement. The charged battery shall be furnished by the contractor.

3.1.5 Hydraulic system. The hydraulic system shall consist of all hydraulic components necessary for operation of the forks and mast and does not include brake system components. Unless otherwise specified herein all hydraulic system components shall withstand a proof pressure that is equal to or greater than 1-1/2 times the maximum working pressure (1-1/2 times relief valve setting) without external leakage, damage or permanent deformation. Hydraulic fittings on pumps, valves, and cylinders shall be the O-ring straight thread type as specified in SAE J514. A pipe tap or straight thread O-ring boss test point shall be located at the outlet of each pump or pressure inlet of each control valve for measuring pressure. The system shall provide for lowering of rated load at not more than 60 feet per minute in the event of failure of or damage to hydraulic hose(s) supplying the lift cylinder.

3.1.5.1 Hydraulic system filtration. A system filter shall be furnished in either the suction or return line.

3.1.6 Uprights and carriage assembly. Uprights shall be the telescopic roller type. Rollers shall be of the permanently lubricated for life type. Adequate means shall be provided in the uprights to compensate, by replacement or adjustment, for wear which may develop between lateral rolling contracts. Positive means shall be provided to prevent over-travel of thecarriage or channel in both upper and lower positions.

3.1.6.1 Forks. The forks and fork carrier shall conform to ANSI B56.1. Forks shall be 2 inches maximum thickness and 5 inches maximum width. The forks shall extend beyond the operators platform at least 40 inches. Fork thickness shall not exceed 1/2 inch at the tip and the taper shall be not less than 14 inches long. Taper shall be on the underside of the forks. The tip of the fork shall be chamfered or rounded to provide smooth edges. Forks shall be laterally adjustable without the need of hand tools. With the forks at their widest spacing, they shall spread at least 28 inches, measured from the outside of the forks. With the forks at their narrowest spacing, they shall spread not more than 22 inches, measured from the outside of the forks. The forks shall be capable of being secured when in position to prevent lateral movement.

3.1.7 Operato s platform The operator's platform shall be at least 20 inches wide and approximately as long as the width of the truck. The platform shall have railings on both sides running from the floor of the platform to approximately half the height of the overhead guard. There shall be a tether safety belt that fastens around the operator's waist. The operator's platform shall be capable of towering to ground level, at a speed of not more than 60 feet per minute, with the operator on the platform and the rated load on the forks in the event of hydraulic, electrical, or some other failure that interferes with the normal operation of the truck.

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:45Z
Check the source to verify that this is the current version before use.

3.1.8 Operator's overhead guard. An overhead guard in accordance with ANSI 856.1 shall be furnished. Guard height shall not exceed 95 inches measured from ground level to top of guard with the forks and operator's platform at lowest position, and with no load on the forks.

3.1.9 Wheels and tires.

3.1.9.1 Wheel rims. The wheel rims shall be steel, malleable iron or cast iron and equipped with roller bearings.

3.1.9.2 Tires. Tires shall be new rubber or synthetic, manufacturer's standard and designed for hard surfaces.

3.1.10 Steering. Power steering shall be furnished.

3.1.11 Brakes.

3.1.11.1 Service brakes. Service brakes conforming to the requirements of ANSI B56.1 shall be provialed.

3.1.11.2 Parking brake. A parking brake, independent of, or part of the service brakes shall be furnished. If part of the service brake system, the brakes shall be applied until some action by the operator disengages them. The parking brake shall conform to ANSI B56.1.

3.1.12 Horn. The truck shall be equipped with an electric horn with a pushbutton located within reach of the operator. The horn button shall be moisture and weather resistant.

3.1.13 Controls and instrumentation. All controls and instrumentation shall be provided with position markings conform to ANSI B56.11.3. 'The controls shall be operable and the instruments shall be viewable by the 5th to 95th percentile male and female, according to the dimensions in SAE J833.

3.1.14 BatteBattery indicator. A battery discharge indicator that will prevent the battery from reaching a damaging low state of charge shall be provided. The indicator shall have a "fuel gauge" that shows the charge of the battery. When the battery reaches a predetermined low charge the lift control circuit shall be interrupted, making the lift mechanism inoperative until the battery has been replaced or recharged.

3.1.15 Master switch. A key operated master switch shall be provided. When key is removed, all electrical circuits shall be opened or interrupted making it impossible for any electrical system to be activated. Two keys shall be supplied with each truck. All keys shall be identical for every truck delivered on this contract.

3.1.16 Hour meter. An electrically operated hour meter shall be provided. It shall operate only when the forklift is traveling; both forward and reverse. It shall be capable of registering at least 9999 hours.

3.1.17 Brake light. There shall be one brake light on the rear of the truck.

3.1.38 Floodlights. There shall be two floodlights, each with a rating of at least 25 watts. One shall be mounted on the lift side of mast, facing forward and the other mounted at or near the rear of the truck, facing rearward. Directional adjustment for these lights shall be at least 45 degrees above and below the horizontal plane, and 90 degrees to both sides of the fore and aft longitudinal center-fine of the truck. One switch, mounted within reach of the operator, shall control both floodlights.

3.1.19 Battery cable connector. The battery cable shall be equipped with a two contact, type SB locking half connector. The connector shall be used to connect the battery to the motor during operation, and to connect the battery charger during recharging. The connector shall be located where it cannot be accidentally unfastened, or opened, by the operator during entry, exit or operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

3.1.20 Pallet clamp. A mechanically or hydraulically operated pallet clamp and guide shall be mounted to the front carriage between the forks, below and integral with the operator's platform. The pallet clamp shall be capable of clamping to the center stringer of a pallet to prevent shifting or tilting of the pallet.

3.2 performance.

3.2.1 Lifting speed. Speed of lift with rated load on the forks shall be not less than 35 feet per minute over the entire distance from ground level to maximum fork height.

3.2.2 Lowering speed. Speed of lowering unloaded forks shall be not less than 25 feet per minute over the entire distance from maximum fork height to ground level. Speed of lowering forks with rated load shall be not more than 60 feet per minute over the entire distance from maximum fork height to ground level. The hydraulic control system shall be damped, metered, or easily manually regulated to reduce shock and prevent the truck from overturning when a rated load is lowered at maximum speed and stopped quickly.

3.2.3 Service brake. With rated load, the truck shall be capable of meeting the stopping distance requirements of ANSI B56.1.

3.2.4 Parking brake. The parking brake shall hold the truck with rated load in both directions, on the grade specified in ANSI B56.1.

3.2.5 Right angle turn. The truck, carrying rated capacity load, shall be capable of backing through a turn in either direction between two parallel walls not more than 130 inches apart.

3.2.6 Speed. While carrying the rated capacity load on a level surface, truck shall be capable of attaining a speed of at least 4 miles per hour and not greater than 10 miles per hour forward and reverse.

3.2.7 Slope ascension, forward direction. The truck shall be capable of ascending a 5 percent grade in both forward and reverse directions on a dry concrete surface, with and without rated load. The truck shall be able to accelerate from a dead stop on this slope when carrying rated load.

3.2.8 Collapsed mast height. Collapsed mast height of unloaded truck measured from the ground to the top of the uprights, with the operator's platform at the lowest position, shall not exceed 95 inohes.

3.2.9 Lift height. The lift height with rated load on the forks shall be at least 193 inches.

3.2.10 Lift assembly drift. The lift assembly shall be capable of holding the rated load at maximum height for 10 minutes with not more than one inch of vertical drift.

3-2.11 Stability. The truck shall conform to stability requirements of ANSI B56.1.

3.3 Paint. All exterior surfaces and all surfaces normally painted by the forklift manufacturer shall be prepared and primed using materials compatible with the final paint. Unless otherwise specified (see 6.2), the truck shall be painted with polyurethane paint, color number 24052 of FED-STD-595. All exterior trim (wheel rims, rims on lights, etc.) shall match the exterior color and paint type.

3.4 Walkway coating. Floor plates and step surfaces shall be in accordance with ANSI B56.1.

3.5 Identification marking. Each truck shall be identified with an identification plate conforming to MIL-P-514, type 1, style 1, composition C, of type 1, grade A, class 1 material which shall be located in a visible and permanent location on the truck. The identifying data shall be stamped in letters in accordance with MIL-P-514. The plate shall be securely attached to the truck with screws, bolts or rivets and shall be furnished and mounted by the contractor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

3.6 Truck marking. Unless otherwise specified (see 6.2), markings on trucks shall be black, color number 37038 of FED-STD-595. Characters shall be block type capitals and Arabic numerals. Location, information, and character size shall be as follows:

Information	Example	Location	Character Size In Inches
Agency	US Air Force	On each side and rear	1 1/2
Registration Number	10D315	On each side and rear	1 1/2
Capacity	3000 POUNDS	On each side of mast	2
Safety	NO RIDERS	On each side of mast	2

3.7 Identical items. All forklifts furnished under this specification shall be physically and mechanically identical to the first article that is approved by the Government, except that product improvements incorporated in the contractor's product lines are permitted at no cost to the Government subject to the following:

(a) Physical and performance characteristics defined herein have not been infringed.

(b) New components involving Government selected repair parts are directly interchangeable with the superseded component or part.

(c) The Government is notified of all changes and alterations a minimum of 30 days in advance of production commitment dates, and production effectivity, by serial number and date, has been identified.

(d) Appropriate changes are issued to the Government validating operating, maintenance, and parts manuals.

3.8 Special tools. Any special tools (tools that are peculiar to this truck) that are needed to perform scheduled or unscheduled maintenance shall be provided by the contractor. One set of special tools shall be supplied with each truck.

3.9 Workmanship. Defective components or parts and assemblies which have been repaired or modified to overcome deficiencies shall not be furnished. Welded, bolted or riveted construction utilized shall be in accordance with the highest standards of the industry.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.2 **Classification of inspection.** evaluation demonstrations. Inspections, evacuations and demonstrations shall be classified as follows:

(a) First article evaluation and demonstration (see 4.3).

(b) Production run-in (see 4.5).

(c) Inspection of packing (see 4.6).

4.3 First article evaluation and demonstration. Prior to delivery, the manufacturer shall make one forklift available for first article evaluation and demonstration. The forklift and its components shall be compared with this document, calculations, and test data to verify compliance with this specification. The forklift shall then be subjected to a demonstration as specified herein. Permanent deformation, overheating, malfunction, failure to meet performance requirements, any wear evidenced by removal of material, failure to complete any demonstration, or leakage of hydraulic oil, or lubricants shall be cause for rejection of the forklift.

4.4 **Demonstrations.**

4.4.1 **Demonstration conditions.** Unless otherwise specified herein, demonstration shall be at the ambient temperature and climatic conditions existing at the place of demonstration. Only that maintenance established by the contractor and submitted as a maintenance schedule prior to commencement of the demonstration shall be performed during the demonstration.

4.4.2 Rated load. During the demonstrations specified herein, the rated load shall be a 3000 pound (plus 100, minus 0 pounds) cube, 48 inches (plus 1/2, minus 0 inches) with a center of gravity located at the geometrical center of the cube. The cube shall be provided by the contractor.

4.4.3 **Maximum** fork height and collapsed mast height. With no load on the forks and the platform at the lowest position, measure and record collapsed mast height. With rated load raised to maximum lift height, measure vertical distance to the top surface of the forks at the 24 inch load center. Nonconformance with 3.2.8 and 3.2.9 shall be cause for rejection.

4.4.4 Lifting and lowering speed. Record time in seconds required to raise rated load from floor to maximum fork height. Record time required to lower rated load from maximum fork height to floor, at maximum lowering speed. Measure and record distance in inches from floor to top surface of forks in fully lowered position. Record time required to lower unloaded forks from maximum fork height to fully lowered position. The raising and lowering shall be performed three times and averaged. Nonconformance to 3.2.1 and 3.2.2 shall be cause for rejection.

4.4.5 Right angle turn. Starting with the front of the rated toad against a wall (or a line on the floor) and the forklift perpendicular to the wall, back the truck through a right angle (90 degree) turn. Mark the point where the outside envelope of the forklift is farthest from the wall during the turn. Measure the perpendicular distance from this point to the wall. It shall be cause for rejection if this dimension exceeds the distance specified in 3.2.5. Repeat the procedure turning in the opposite direction, again not exceeding the distance in 3.2.5.

4.4.6 Travel speed. Operate the truck with rated load in carry position. Truck shall attain speed specified in both forward and reverse directions. The truck shall be driven a distance necessary to attain maximum speed prior to entering a measured distance. The truck shall be driven over the course at least

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

two times in each direction. The speed shall be the average of the two runs in each direction. Inability of the truck to attain the speed as specified in 3.2.6, failure of any component, overheating, malfunction or leakage of fluid shall be cause for rejection.

4.4.7 Slope ascension. Drive truck forward with rated load along a horizontal approach and onto a ramp of specified grade (see 3.2.7) and bring to a complete stop halfway up the ramp. Start from a dead stop and proceed up the ramp to another horizontal surface. Repeat the procedure without the load. Repeat both with and without rated load, except drive truck in reverse.

4.4.8 Service brake. Demonstrate that the service brakes can stop the truck with rated load in accordance with ANSI B.56.1. Failure to meet this requirement shall be cause for rejection (see 3.2.3).

4.4.9 Parking brake. Demonstrate capability of parking brake to hold truck with the rated load, in both forward and reverse direction, on the grade specified in ANSI B56.1. Failure to meet these requirements shall be cause for rejection (see 3.2.4).

4.4.10 Lift assembly drift. Operate the lift system for at least three minutes to heat the hydraulic fluid to normal operating temperature. Raise rated load to maximum fork height. Turn master switch (3.1.15) to "OFF" position. Measure the vertical distance from ground to under side of load. Hold the load in this position for time specified in 3.2.10. Remeasure to the same point on the load. Load lowering in excess of the amount specified in 3.2.10 shall be cause for rejection.

4.4.11 Stability. Conduct "forward stacking," "forward travel," "lateral stacking," and "lateral travel" tilting platform tests in accordance with ANSI B56.1. Nonconformance with the stability requirements of ANSI B56.1 shall be cause for rejection.

4.4.12 Overhead height. With no load on the truck and the platform at the lowest position, measure vertically from the ground to the highest point on the overhead guard. Nonconformance with 3.1.8 shall be cause for rejection.

4.4.13 Fork operation. The forklift, carrying the rated capacity load shall be operated for a minimum of 500 cycles over a surface paved with concrete, asphalt, macadam or equivalent. Each cycle shall consist of the following:

(1) Raise the rated load to the carrying position.

(2) Travel forward a sufficient distance to operate a minimum of 100 feel at maximum speed.

(3) Slow truck to safe speed and negotiate a 90 degree turn. Drive at least 30 feet, stop truck and raise the load to maximum lift height at maximum lift speed.

(4) Lower the load at maximum lowering speed to the ground. Raise to carry position.

(5) Drive truck in reverse over the same course and return to initial start point. This constitutes one cycle. Repeat steps 2 thru 6 until 500 cycles have been completed.

(6) Two hundred and fifty (250) cycles shall be performed making a right hand 90 degree turn, and 250 shall be performed making a lift hand 90 degree turn.

(7) The key switch and horn shall be operated once each 50 cycles of operation.

Inability of the forklift to lift the rated load, overheating, leakage of fluid, malfunction, any wear evidenced by removal of material, failure of any component, or failure to complete the operation shall be cause for

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

rejection. Normal battery changes are permitted, if required, to conduct the test. Inability to operate 8 continuous hours on one battery charge (without charging or replacing the battery) shall be cause for rejection.

4.5 Production run-in. Each forklift carrying a rated load shall be subjected to a production run-in and servicing as specified herein. Inability to complete the run-in, overheating, failure of any components, malfunction of any control, or evidence of leakage of fluids shall be cause for rejection of the forklift by the Government.

4.5.1 Travel. Demonstrate starting, ascending, and descending a 5 percent ramp, steering, braking and high speed travel. Operate all lights, horns, and brake system not less than two times during this demonstration.

4.5.2 Mast assembly. Demonstrate maximum lifting and towering speed. Each operation shall be performed at least three times with the rated load on the forks.

4.5.3 Servicing and adjustment. Prior to delivery, the manufacturer shall service and adjust each forklift for proper operational use, including at least the following:

(a) Adjustment of mast assembly.

(b) Adjustment of solid state control modules.

(c) Adjustment of service and parking brake systems.

(d) Adjustment of steering.

(e) Continuity check of the electrical system, including filling and charging the battery.

4.6 Inspection of packaging. Each truck shall be completely prepared for shipment, shall be inspected for the correct methods for presentation, packing and marking as specified in 5.1. Nonconformance to 5.1 shall be cause for rejection of packaging.

5. PACKAGING

5.1 Preservation, packaging, and marking. Shall be as specified in the contract.

6. NOTES

(This section contains information of a general or explanatory nature that maybe helpful but is not mandatory.)

6.1 Intended use. Trucks described herein are intended for stacking, unstacking and moving cargo in and around commissary warehouses; also for moving cargo in and out of highway trailers and railroad cars. The trucks are intended for operation over paved, and other hard surfaces.

6.2 ordering data. Procurement document, documents should specify the following:

{a) Title, number and date of this specification.

{b) When final color shall be other than as specified (see 3.3).

(c) When color of markings shall be other than specified (see 3.6).

(d) Time frame for submitting first article demonstration report (see 6.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

6.3 First article demonstation report. The contractor shall prepare and submit the first article demonstration report to the contracting officer for approval within the time trame specified (see 6.2). The report shall include a detailed description of the examination and demonstration performed. All deficiencies encountered and actions taken to correct the deficiencies shall be included.

6.4 Subject term (key word) listing.

Material handling
Narrow aisle
Order selector
Stand-up operator

Custodians:
Air Force-99

Preparing activity
Air Force-84

(Project 3930-F015)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:45Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
3. DOCUMENT TITLE		

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER		
a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY		
a. NAME DAVE OWEN	b. TELEPHONE (Include Area Code) (1) Commercial 912-926-2074	(2) AUTOVON 932-2074
c. ADDRESS (Include Zip Code) WR-ALC/LZMD Robins AFB GA 31098-5609	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- Downloaded: 20261023T09:45Z
Check the source to verify that this is the current version before use.