INCH-POUND

MIL-T-44400(GL)
11 APRIL 1990

MILITARY SPECIFICATION

TENT, FABRIC ASSEMBLIES, STANDARDIZED INTEGRATED COMMAND POST SYSTEM

This specification is approved for use by the Natick Research, Development, and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the fabric components of a frame supported tent which can stand alone or be complexed with other tents or vehicles.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

A-A-50083 - Bag, Plastic, Folded, Garment
DDD-L-20 - Label: For Clothing, Equipage and Tentage (General use)
PPP-B-601 - Boxes, Wood, Cleated-Plywood

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 8340

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

PPP-B-636 - Boxes, Shipping, Fiberboard
PPP-B-640 - Boxes, Fiberboard, Corrugated, Triple-wall

STANDARDS

FEDERAL

FED-STD-595 - Colors
FED-STD-601 - Rubber: Sampling and Testing
FED-STD-751 - Stitches, Seams, And Stitchings

MILITARY

MIL-STD-105 - Sampling Procedures and Tables For Inspection by Attributes
MIL-STD-129 - Marking For Shipment and Storage
MIL-STD-147 - Palletized Unit Loads
MIL-STD-731 - Quality of Wood Members For Containers and Pallets

(Unless otherwise indicated, copies of federal and military specifications, standards and handbooks are available from the Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19120-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein Unless otherwise specified, the issues are those cited in the solicitation.

DEPARTMENT OF THE ARMY FIELD MANUAL

FM 10-16 - General Repair of Tents, Canvas and Webbing

(Copies of documents required by contractors in connection with the specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

5-4-6341 - Fabric Assemblies Overview

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

(Copies of drawings are available from the U.S. Army Natick Research, Development, and Engineering Center, ATTN: STRNC-EMSS, Natick, MA 01760-5014.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3950 - Standard Specification for Strapping, Plastics (and Seals)
D 3951 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103-1187.)

(Non-Government standards and other publications are normally available from organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.2 Materials and components. The materials and components used shall conform to the applicable referenced specifications, standards, and requirements specified herein. Where materials are not definitely specified, they shall be of the quality normally used for by the manufacturer in his standard commercial practice provided the completed items comply with all provisions of this specification. It is encouraged that recycled material be used when practical as long as it meets the requirements of this specification.

3.2.1 Alternate components. Components offered as equivalent to components specified hereinafter and on the referenced drawings as a specific manufacturer's part or model number or equal, shall be functionally equal to the manufacturer's model number identified, and of equal or better quality. The incorporation and inclusion of such a component in the design of the specified end product shall not require modification or change to any other specified component, and shall not reduce ease of maintenance to it or any other components, unless such modification or change is specially approved by the contracting officer. Prior to the manufacture of the first article, or if none is required, prior to commencing production, the contractor shall submit for the contracting officer's approval, a list identifying each component,

Source: https://assist.dla.mil -3 Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

together with proof that each listed component complies with requirements specified above. The contracting officer, at his option, may require a sample of the proposed substitution. Approval of the submitted listing, together with the necessary supporting data, authorizes commencement of manufacture but does not relieve the contractor of responsibility that these components perform in accordance with specified requirements when incorporated into the end product.

3.3 Design and construction. The design and construction shall conform to Drawing 5-4-6341 and all subsidiary drawings and parts lists and as specified herein.

3.3.1 Fusing of ends of synthetic cord, webbing and tape. All ends of synthetic cord, webbing and tape shall be fused. The apparatus used to fuse the cord, webbing, and tape ends shall be capable of providing sufficient heat to provide a smooth edge with the cut ends of the cord, webbing and tape yarns all fused together. Fusing of the cord, webbing and tape shall be accomplished prior to being assembled for stitching.

3.3.2 Stitching, machine.

3.3.2.1 Types of stitching. All stitch types, except bartacking, shall conform to FED-STD-751 as follows:

For all stitching except zig-zag stitching and stitching indicated by "Z" on drawings	-	Type 301, 5 to 7 stitches per inch
For stitching indicated by "Z" on drawings	-	Type 401, 5 to 7 stitches per inch
	-	Chain portion of stitching shall not appear on outside of tent or cover
For bartacking	-	Bartack, length as specified on drawings 1/8-inch in width (bight) and shall be free of thread breaks and loose stitching

3.3.2.2 Thread breaks. Thread breaks in stitching shall be overstitched not less than 1 inch at each break on stitch type 301; and not less than 1-1/2 inches at each break on stitch type 401. Thread breaks, in type 401 may be overstitched with stitch type 301. Thread breaks noted during inspection shall be repaired by overstitching the existing stitching starting from a distance of 1 inch beyond the break, across the defective area, to a distance of 1 inch beyond the break. The ends of repair stitching are not required to be backstitched.

3.3.2.3 Stitching ends. The ends of type 301 stitching shall be overstitched not less than 1 inch except where ends are turned under in a hem or held down by other stitching. Where 301 stitching is performed automatically on stitch patterns such as box, box with cross-stitch, "W" stitching or straight line tacking, at least three tying, overlapping, or back stitches shall be used to secure the ends of stitching.

Source: https://assist.dla.mil --Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

3.3.2.4 Skipped stitches. Two or more consecutively skipped stitches occurring in types 301 stitching shall be overstitched not less than 1 inch. Any skipped stitches in type 401 stitching shall be overstitched not less than 1-1/2 inches. Skipped stitches in 401 stitching may be overstitched with type 301 stitching. Skipped stitches noted during inspection shall be repaired as specified for thread breaks. (See 3.3.2.2).

3.3.2.5 Lubrication of thread. The addition of any lubrication to the polyester sewing thread prior to or during the sewing operations is prohibited.

3.3.2.6 Automatic stitching. Automatic stitching machines may be used to perform any of the required stitch patterns provided the requirements of the stitch pattern, stitches per inch, size and type of thread are met, and at least three or more tying, overlapping or backstitches are used to secure the ends of the stitching.

3.3.2.7 Thread ends. All thread ends that are visible on the finished item shall be trimmed to a length of not more than 1/4 inch.

3.3.2.8 Stitching margins. Unless otherwise specified, all stitch margins shall be 1/8, +1/16 -0 inch.

3.3.3 Splicing of cloth. There shall be no splicing of roof, wall, liner or floor panels. The number of panel seams shall not exceed requirements specified on the applicable drawings.

3.3.4 Setting of grommets. Holes punched to receive the grommets shall be smaller than the outside diameter of the grommet barrel so that the barrel must be forced through the hole. The grommets shall be securely clinched without cutting the materials.

3.3.5 Wicking of sewing thread (cup test). There shall be no wicking of water through the stitching on the wall assemblies when they are tested as specified in 4.5.1. The cup test is intended to insure that non-wicking thread has been utilized and that no lubrication has been added to the polyester thread prior to or during the sewing operation. Repairs required as a result of failure of the cup test and when authorized by the contracting officer, shall be performed by treating exposed stitching on the wall assembly with seam sealant specified in 3.3.6.

3.3.6 Leakage of sealed seams. All exposed stitching on the exterior of the roof cap assemblies and rain gutter shall be treated with Neece Coated Fabric's ACMETEX 2200 seam sealant or equal (see 6.4). Seam sealant shall be pigmented to approximate Camouflage Green Shade No. 34094 of FED-STD-595, however the requirements for infrared reflection does not apply to seam sealant. The fabric surface shall be cleaned so that it is free of dirt and moisture prior to application of seam sealant. Sealant shall be applied with a brush or roller, and shall evenly cover an area 1/2-inch wide on each side and on top of all stitching. There shall be no leakage of water through the seams when tested as specified in 4.5.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

3.3.7 Seam strength. The strength of the seams shall be 80 percent of the fabric strength when tested as specified in 4.5.3.

3.3.8 Repairs to liner assembly fabric. All necessary repairs shall be effected in accordance with the Department of the Army Field Manual FM 10-16, except that hand sewn patches, other than specified herein, will not be acceptable. Patches on holes, cuts, or tears not more than 1 inch in diameter or length shall be permitted. A maximum of one patch per liner assembly shall be allowed without prior authorization from the contracting officer. Each patch shall be large enough to overlap the damaged area with a margin of at least 3/4 inch on all sides. Patches shall be placed on the outside of the liner assemblies and shall not be permitted over seams or in hardware areas. All other repairs shall require authorization by the contracting officer.

3.3.9 Repairs to roof cap, walls, rain gutter and transport covers. No more than one repair to holes, cuts, tears or burn throughs resulting from the heat sealing operation shall be allowed. Repairs on holes, cuts, tears or burn throughs not more than one inch in diameter or length shall be performed as follows:

a. Repairs shall be accomplished by the application of cemented patches. Cemented patches shall be large enough to overlap the damaged area with a margin of at least 3/4-inch on all sides, using cement per Minnesota Mining and Manufacturing 847 or equal (see 6.5).

b. For repairs of burn-throughs on panel lap seams, the width of the patch shall be such that the overlap on each side of the burn-through shall be equal to the width of the seam.

c. Patches shall be applied to the top side of the assemblies and the patched area shall be smooth, i.e., with the torn or cut edged securely and completely sealed and corners shall have a radius.

3.4 Marking. All markings and labels shall conform to DDD-L-20.

3.4.1 Special markings. The letters "US" and the item nomenclature on the roof cap assemblies, and transport covers shall conform to type IV, class 9 in the size characters and in the locations shown on the drawings. Class 9 markings shall be clearly legible after subjection to accelerated weathering.

3.4.2 Identification label. Identification labels shall conform to type VI, class 6 and shall be 3-1/2 inches by 5-1/2 inches minimum and a blank space of at least 1-1/4 inches shall be provided on the bottom of the label for the Department of Defense inspector's stamp. Identification label shall be stitched to the tent components in the locations shown on the drawings.

3.5 Workmanship. Cloth components shall be clean and free of holes, cuts, tears, and cloth defects such as multiple floats or broken or missing yarns. Webbing and tape shall not have frayed or scalloped edges and rope components shall be free of cuts and breaks. Thread tension shall be maintained with

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

seams properly sewed so that no runoffs, twists, pleats, or open seams shall result. Care shall be taken in sewing to see that no metal chews occur. All thread ends shall be trimmed to 1/2 inch or less. Metal components shall be free of burns, sharp edges, and corroded areas and shall not be broken or malformed. Heat welded seams shall be free of wrinkles, pleats and folds. A heat welded seam, regardless of its length, shall not have more than a total of two wrinkles, pleats, or folds.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of section 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for ensuring that all specified dimensions have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point or at all points in the manufacturing process necessary to ensure compliance with all dimensional requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3)
b. Quality conformance inspection (see 4.4)

4.3 First article inspection. When a first article is required (see 6.2), it shall be examined for the defects specified in 4.4.3 and 4.4.4 and tested as specified in 4.4.5. Any nonconformance or failure of any test shall be cause for rejection of the first article.

Source: https://assist.dla.mil/ -- Downloaded: 202640-22T01:54Z
Check the source to verify that this is the currentversion before use.

4.4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this specification or applicable purchase document.

4.4.2 In-process examination. Examination shall be made of the following fabrication operations to establish conformance with specified requirements.

a. There shall be no lubrication of polyester thread prior to or during sewing operations for compliance with 3.3.2.5.

b. Holes punched to receive grommets are in compliance with 3.3.4.

c. Heat sealing operation shall be monitored. A sample seam specimen of sufficient size to conduct testing in accordance with 3.3.7 shall be produced each time the heat sealing equipment is started and every 300 linear feet of sealed seam there after.

Whenever nonconformance is noted, correction shall be made to the items affected and to the process. When correction cannot be made the item affected shall be removed from the process.

4.4.3 End item visual examination. The end item units of roof cap, walls, rain gutters, floor assemblies, liners, transport covers and pin container shall be examined for the defects listed in table I. The lot size shall be expressed in units of end items. The sample unit shall be one end item. The inspection level shall be II. The acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 10 for major defects and 25 for major and minor A combined and 100 for total (major, minor A and minor B combined) defects.

TABLE I. End item visual defects

Examine	Defect	Classification Major	Minor A	Minor B
Screening	Cut or tear:			
	- 1/4 inch or less in length			301
	- more than 1/4 inch in length but not more than 2 inches in length		201	
	- more than two inches in length	101		
Tape & Webbing	Edge frayed or scalloped			302
	Cut or tear			303

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Cloth for Roof, Wall, and Gutter Assemblies	Cut, tear, or hole (including exposed drill holes) greater than 1/8-inch in length or diameter:			
	- on roof, wall or gutter assemblies	102		
	Cut, tear, or hole (including exposed drill holes) 1/8-inch or less in length or diameter:			
	- more than four:			
	- on roof or gutter assemblies	103		
	- more than five but less than ten:			
	- on wall assemblies		202	
	- more than ten:			
	- on the wall assemblies	104		
Cloth for liner	Cut, tear, or hole (including exposed drill hole) greater than 1/8-inch in length or diameter		203	
	Cut, tear, or hole (including exposed drill hole) less than 1/8-inch in length or diameter		204	
	- more than ten		205	
	- more than five but less than ten			304
Cloth for transport covers or tent pin container	Cut tear, or hole (including exposed drill holes) greater than 1/8-inch in length or diameter		206	
	Cut tear or hole (including exposed drill holes) less than 1/8-inch in length or diameter			
	- more than ten		207	
	- more than five but less than ten			305
Cloth for floor	Cut, tear, or hole (including exposed drill hole) greater than 1/8-inch in length or diameter	105		
	Cut tear or hole (including exposed drill holes) less than 1/8-inch in length or diameter			
	- more than ten	106		
	- more than five but less than ten		208	

Source: https://assist.dla.mil - Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Hardware and metal components	Broken	107		
	Malformed:			
	- fails to perform intended function	108		
	- but will perform intended function		209	
	Corroded area			306
	Burn or sharp edge which may cause injury in handling or damage to fabric	109		
Grommets	Improperly set, two or more teeth exposed (except where grommet is set as specified but is in an area of uneven thickness which prevents uniform clinching			307
	Clinched loosely, allowing grommet to rotate around hole			308
	Clinched excessively tight; i.e., cutting cloth:	110		
	Insecurely clinched; i.e., grommets or washers become disengaged:	111		
	Grommet set with barrel inserted from top of webbing instead of bottom			309
	Roll of a grommet contains more than three scores (splits)			310
Rope, tent lines, and cord components	Any cut or break:			
	on eave guy line		210	
	Eye splice omitted		211	
	Eye splice not as specified			311
	Free end not finished as specified			312
Seams and stitching	Open seam on stitch type 301:			
	- for more than 1/4 inch but not more than 1 inch			313
	- for more than 1 inch		212	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
	NOTE: A seam shall be classified as open when one or more stitches joining a seam are broken, or when one or more skipped or run-off stitches occur. On double stitched seams, a seam shall be classified as open when either one or both sides of a seam are open.			
	Raw edges caught in stitching:			
	- more than 1 inch but not more than 3 inches			314
	- more than 3 inches		213	
	Thread breaks:			
	- overstitched less than 1-1/2 inches on stitch type 401			315
	- overstitched less than 1 inch on stitch type 301			316
	NOTE: Thread breaks not overstitched shall be classified as open seams.			
	Needle chews resulting in cut, tear or hole (see cut, tear or hole)			
	Skipped stitches:			
	- overstitched less than 1-1/2 inches on stitch type 401		214	
	- overstitched less than 1 inch on stitch type 301 (when two or more skipped stitches occur consecutively)		215	
	NOTE: Skipped stitches not overstitched shall be classified as open seams.			
	One or more required rows of stitching omitted (except on boxstitching)	112		
Heat sealed seams	Pleated, puckered, burned through, wrinkled, or folded	113		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Boxstitching	Incomplete:			
	- one row of stitching omitted			317
	- two or more rows of stitching omitted		216	
	More or less than specified length by more than 1/8-inch			318
Bartacking	More or less than specified length by more than 1/8-inch			319
Stitching ends	Overstitched less than 1 inch on stitch type 301 (except where ends are held down by other stitching or turned under in a hem, or where stitching is performed automatically)		217	
	Secured with less than three tying, overlapping, or back stitches when automatic stitching is performed			320
	Secured with less than 1/4 inch of back stitching, overstitching, or an increased number of stitches per inch at the end of stitch type 304			321
Seams	Pleated:			
	- on all wall, liner or floor assemblies		218	
	- on transport covers			322
Seam type	Wrong seam type	114		
Stitch type	Wrong stitch type	115		
Stitch tension	Loose, resulting in an exposed bobbin or top thread for more than 6 inches		219	
	Tight, as evidenced by puckering on fabric for more than 6 inches		220	

Source: https://assist.dla.mil Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Stitches per inch	Less than minimum specified (except on panel joining seams):			
	- one stitch			323
	- two or more stitches		221	
	Less than minimum specified on panel joining seams		222	
	More than maximum specified:			
	- one stitch			324
	- two or more stitches		223	
NOTE:	Variation in the number of of stitches per inch, caused by the operator speeding up the machine and pulling the fabric in order to sew over heavy places or heavy seams or in turning corners, shall be classified as follows:			
	a. Within the minor "B" defect classification - no defect			
	b. Within the minor "A" defect classification - minor "B" defect			
Stitching gage	Not as specified		224	
Stitching margin	Larger than specified:			
	- for more than 2 inches but not more than 4 inches			325
	- for more than 4 inches in length		225	
	Less than specified:			
	- for more than 2 inches but not more than 4 inches in length			326
	- for more than 4 inches in length		226	
Stitching	Chain portion of stitching shows on outside of tent sections or covers		227	
Mends, darns, or patches	Repairs not in accordance with Department of the Army Field Manual FM 10-16 or not authorized by the contracting officer (see 3.3.8)	116		

Source: https://assist.dla.mil - Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Components and assembly	Any component part omitted, not assembled or fabricated of applicable referenced material	117		
Hems	Constructed with partial turn under when double turn under is required		228	
	Twisted or pleated			327
Reinforcements	Improperly applied, causing excessive fullness on reinforcements or reinforced parts	118		
Cloth splicing	Splice in roof, wall or tent cover panels	119		
	Splices not joined as shown on applicable drawings			328
Marking and labels	Omitted, incorrect, illegible, or misplaced			329
Cleanness	Grease or oil stains			330
	Thread ends not trimmed to 1/2 inch or less			331

4.4.4 End item dimensional examination. The end item units of roof cap, walls, floor, rain gutters, liners, transport covers and pin container shall be examined for the defects listed in table II. The lot size expressed in units of end items of one item number only. The sample unit shall be one end item. The inspection level shall be S-3. The AQL, expressed in terms of defects per hundred units, shall be 2.5 for major defects, 10 for major and minor A combined defects, and 100 for total (major, minor A and minor B combined) defects.

Table II. End item dimensional defects

Examine	Defect	Classification Major	Minor A	Minor B
Overall dimensions of roof cap, window wall, entrance way wall, plain wall; liners, floors, or rain gutters	Smaller than specified dimensions less applicable minus tolerances indicated on drawings	101		
	Larger than specified dimensions and applicable plus tolerance indicated on drawings			301

Source: https://assist.dla.mil - Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

Table II. End item dimensional defects (cont'd)

Examine	Defect	Classification Major	Minor A	Minor B
Overall dimensions of transport bag-frame, transport bag-fabric, tent pin container or support straps	Smaller than specified dimensions less applicable minus tolerance indicated on drawing, but not smaller than the specified dimensions less twice the applicable minus tolerance			302
	Smaller than specified dimensions less twice the applicable minus tolerance indicated on drawing		201	
	Larger than specified dimensions and applicable plus tolerance indicated on drawing			303
Location dimensions (unless otherwise specified)	Not within specified tolerance: - not exceeding twice the applicable tolerance			304
	- exceeding twice the applicable tolerance		202	
Webbing, tie tapes	Finished length less than specified by more than 1 inch			305
Grommets	Set beyond specified location by more than 1/2 inch		203	
Rope components, tent lines	Eye on footstop or line less than specified by more than 1/2 inch			306
	Finished length of guy line less than specified:			
	- by not more than 4 inches			307
	- by more than 4 inches but not more than 12 inches		204	
	- by more than 12 inches	102		
Hems	Required to finish less than 3/4 inch or less in width, less than specified		205	
Reinforcements	Finished dimensions less than specified by more than 1/2 inch		206	
Ventilator opening	Misplaced by more than 1/2 inch		207	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

4.4.5 End item testing. End item shall be tested as specified in 4.5. The lot size shall be expressed in units of end items. The sample size shall be one tent. The inspection level shall be S-2. Any test failure shall be cause for rejection of the lot.

4.4.6 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2. The AQL, expressed in terms of defects per hundred units, shall be 2.5.

Examine	Defect
Markings, (exterior and interior)	Omitted, incorrect, incomplete, illegible; of improper size, location, sequence or method of application
Material	Any component missing, damaged, or not as specified
Workmanship	Inadequate application of components, such as: incomplete sealing or closure of flap, improper taping, loose strapping or inadequate stapling Bulged or distorted container
Content	Other than specified

4.4.7 Palletization examination . The fully packaged and palletized end items shall be examined for the defects listed below. The lot size shall be expressed in units of palletized unit loads. The sample unit shall be one palletized unit load, fully packaged. The inspection level shall be S-1 and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

Examine	Defect
Finished dimensions	Length, width, or height exceeds specified maximum requirement
Palletization	Pallet pattern not as specified Interlocking of loads not as specified Load not bonded as specified
Weight	Exceeds maximum load limits
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application

Source: https://assist.dla.mil - Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

4.5 Method of inspection.

4.5.1 Wicking test. The end item unit shall be tested once on a wall assembly panel feld seam (see 3.3.5). The end item unit shall be laid over a 6 ±1/8 inch diameter hoop as to form a 1 ±1/4 inch deep depression with the seam to be tested running through the center of the depression. A 500-ml quantity of water at 77°F ±4° shall be slowly poured into the depression and the under surface of the seam shall be observed. Any wicking of water along the sewing thread, identified by a discoloration or darkening of the thread within 5 minutes after water is poured, shall be considered a test failure. Water leakage through the needle holes or between the plies of the seamed fabrics shall not be considered a failure.

4.5.2 Seam leakage test. The end item unit shall be tested on one roof cap assembly, one rain gutter assembly and one floor assembly for seam leakage on an area of stitching that has been treated with seam sealant (see 3.3.6). The end item unit shall be laid over a 6 ±1/8 inch diameter hoop as to form a 1 ±1/4-inch deep depression with the seam to be tested running through the center of the depression. A 500-ml quantity of water at 77°F ±4° shall be slowly poured into the depression and the under surface of the seam shall be observed. Any leakage of water through the sealed seam within 5 minutes after water is poured, shall be considered a test failure.

4.5.3 Seam strength test. The end item unit seams shall be tested in accordance with Method 8311 of FED-STD-601. Any break in the seam that indicates the seam strength is less than 80 percent of the fabric strength shall be considered a test failure (see 3.3.7).

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial, as specified (see 6.2).

5.1.1 Level A preservation.

5.1.1.1 Complete tent assembly preservation. One roof cap, one entrance way wall and one single ply floor shall be placed in transport bag-fabric 1. One plain wall, two window walls, three entrance way/window wall liners, one plain wall liner, one rain gutter, and ten support straps shall be placed in transport bag-fabric 2. One pin container and one transport bag-frame shall be placed in a plastic bag conforming to A-A-50083.

5.1.1.2 Components when procured separately (see 6.2). Each component shall be folded or rolled in a manner so as to achieve a compact unit. Each pin container shall be folded to approximately 15-1/2 by 11-1/2 inches and placed in a plastic bag conforming to A-A-50083. Each rain gutter shall be folded to approximately 19 by 15 inches and placed in a plastic bag conforming to A-A-50083. Ten support straps measuring approximately 9-1/2 by 7-1/2 inches shall be placed in a plastic bag conforming to A-A-50083.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

5.1.2 Commercial preservation. One complete tent assembly or each component for bulk preservation shall be preserved in accordance with ASTM D 3951.

5.2 Packing. Packing shall be level A, B or Commercial, as specified (see 6.2).

5.2.1 Level A packing.

5.2.1.1 Complete tent assembly packing. One complete tent, preserved as specified in 5.1.1 shall be packed in a cleated plywood box conforming to overseas type, style A, grade B, type 2 load of PPP-B-601. The inside dimensions of the box shall be approximately 52 inches in length, 36 inches in width and 14 inches in depth. The box shall be provided with skids, closed and strapped in accordance with PPP-B-601.

5.2.1.2 Components when procured separately (see 6.2). Each component or 10 rain gutters, 100 support straps or 20 pin containers, preserved as specified in 5.1, shall be packed in a shipping container conforming to overseas type, style A, grade B of PPP-B-601. Approximate inside dimensions of the box shall be as specified in table III. Each box shall be closed and strapped in accordance with the appendix of PPP-B-601.

5.2.2 Level B packing.

5.2.2.1 Complete tent assembly packing. One complete tent, preserved as specified, shall be packed in accordance with 5.2.1.1, except a domestic type box shall be used.

5.2.2.2 Components when procured separately (see 6.2). Each component or 10 rain gutters, 100 support straps or 20 pin containers, preserved as specified in 5.1, shall be packed in a shipping container conforming to style RSC-L, type CF (variety SW) or SF, class domestic, grade 275 of PPP-B-636. Approximate inside dimensions of the box shall be as specified in table III. Each box shall be closed in accordance with method II as specified in the appendix of PPP-B-636.

5.2.2.3 For shipment to assembler. When bulk shipment to the assembler is required, components, of one type, shall be packed in a triple-wall fiberboard container conforming to class 1, style C of PPP-B-640. The box shall be provided with four-way entry built-up skids in accordance with PPP-B-601. The box shall be closed with a minimum of two plastic straps conforming to type II, III, or IV of ASTM D 3950 with nominal width and thickness of 1/2 by 0.020 inch or greater. Inside dimensions shall be approximately 47 inches in length, 39 inches in width and 29 inches in depth. The quantity of each component per box shall be as cited in table III.

5.2.3 Commercial packing. Components, preserved as specified in 5.1, shall be packed in accordance with ASTM D 3951.

Source: https://assist.dla.mil -- Downloaded: 202610-22T01:54Z
Check the source to verify that this is the currentversion before use.

5.3 Palletization. When specified, (see 6.2), components packed as specified in 5.2, shall be palletized on a 4-way entry pallet in accordance with load type Ia of MIL-STD-147. Pallet types shall be type I (4-way entry). type IV or type V in accordance with MIL-STD-147. Pallets shall be fabricated from wood groups I, II, III, or IV of MIL-STD-731. Each prepared load shall be bonded with straps in accordance with bonding means C and D or film bonding means F or G. Pallet pattern shall be as specified in table III, and shall be in accordance with the appendix of MIL-STD-147.

5.4 Marking. In addition to any special marking required by the contract or purchase order, unit packs, shipping containers and unit loads shall be marked in accordance with MIL-STD-129 or ASTM D 3951, as applicable.

TABLE III. Packing parameters

Components	Inside Box dimensions	Pallet pattern	Bulk quantities
Plain wall	19-1/2 x 15 x 5-1/2	95	35
Window wall	19-1/2 x 15 x 5-1/2	95	35
Entrance way wall	23-1/2 x 19-1/2 x 5-1/2	90	25
Roof Cap	39 x 11-1/2 x 5-1/2	101	20
Plain wall liner	19-1/2 x 11-1/2 x 4-1/2	102	55
Entrance way/window wall liner	19-1/2 x 11-1/2 x 4-1/2	102	55
Transport bag-frame	16 x 9-1/2 x 4-1/2	97	80
Transport bag-fabric	16 x 9-1/2 x 4-1/2	97	80
10 Rain gutters	19-1/2 x 15-1/2 x 13	102	N/A
Single ply floor	19-1/2 x 11-1/2 x 4-1/2	102	55
20 Pin containers	16 x 12 x 11	9	N/A
100 Support straps	15 x 9-1/2 x 7-1/2	14	N/A

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The tent is intended for the standardized integrated command post system (SICPS).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When a first article is required (see 3.1, 4.3, and 6.3).
d. Levels of preservation and packing (see 5.1 and 5.2).
e. When components are procured separately (see 5.1.1.2, 5.2.1.2 and 5.2.2.2)
f. When palletization is required (see 5.3).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in acquisition documents regarding arrangements for selection, inspection, and approval of the first article.

6.4 Commercial seam sealant. The Neece Coated Fabric's ACMETEX 2200 seam sealant has been found to meet the requirements of 3.3.6.

6.5 Commercial adhesive. The Minnesota Mining and Manufacturing 847 adhesive coating has been found to meet the requirements for 3.3.9.

6.5 Subject term (key word) listing.

Liner
Shelter
SICPS

Custodian:

Army - GL

Review activities:

Army - MD
DLA - CT

Preparing activity:

Army - GL

(Project 8340-A533)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:54Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-T-44400 (GL)	90/04/11

3. DOCUMENT TITLE
TENT, FABRIC ASSEMBLIES, STANDARDIZED INTEGRATED COMMAND POST SYSTEM

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
STRNC-ESE	(508) 651-5221	256-5221
c. ADDRESS (Include Zip Code) Natick RD&E Center Kansas St. Natick, MA 01760-5014	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- Downloaded: 2026-02-22T01:54Z
Check the source to verify that this is the current version before use.