INCH-POUND
MIL-C-44404(GL)
6 April 1990

MILITARY SPECIFICATION

COMMAND POST, TENT, STANDARDIZED INTEGRATED COMMAND POST SYSTEM

This specification is approved for use by the Natick Research, Development and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one complete Standardized Integrated Command Post System (SICPS).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

PPP-B-601 - Boxes, Wood, Cleated Plywood

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5410

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-P-501 - Pins, Tent, Metal
MIL-P-2383 - Pins, Tent, Wood
MIL-L-44259 - Light Set, Portable, Fluorescent
MIL-B-44381 - Board, Map, Complexing (SICPS)
MIL-T-44382 - Table, Field, Folding Legs, Metal
MIL-F-44397 - Frame, Tent (SICPS)
MIL-T-44400 - Tent, Fabric Assemblies, Standardized Integrated Command Post System

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129 - Marking for Shipment and Storage

(Unless otherwise indicated, copies of federal and military specifications, standards and handbooks are available from the Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

5-4-6340 - Command Post, Tent (SICPS)
5-4-7473 - Erection Procedure

(Copies of drawings are available from the U.S. Army Natick Research, Development, and Engineering Center, ATTN: STRNC-EMSS, Natick, MA 01760-5014)

2.2 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however supersedes applicable laws and regulations unless a specific exemption has been obtained.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 First article. When specified in the contract or purchase order, a sample shall be subjected to first article inspection (see 4.3, 6.2 and 6.3).

3.2 Materials and components. Materials and components shall be as specified herein and in referenced documents. Materials not definitely specified shall be of the quality normally used by the manufacturer provided the complete item complies with all provisions of this document. It is encouraged that recycled material be used when practical as long as it meets the requirements of this specification. The components in the quantity shown in table I make up one complete SICPS system, and shall be assembled in accordance with 5-4-6340.

TABLE I. SICPS components

Component	Description	Quantity
Plain wall	MIL-T-44400	1
Window wall	MIL-T-44400	2
Entrance way wall	MIL-T-44400	1
Roof cap	MIL-T-44400	1
Plain wall liner	MIL-T-44400	1
Entrance way/window wall liner	MIL-T-44400	3
Rain gutter	MIL-T-44400	1
Floor	MIL-T-44400	1
Support straps	MIL-T-44400	10
Transport bag - frame	MIL-T-44400	1
Transport bag - fabric	MIL-T-44400	2
Pin container	MIL-T-44400	1
Steel pins	MIL-P-501 TYPE II	8
Wood pins	MIL-P-2383 SIZE 2	8

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

TABLE I. SICPS components cont'd

Component	Description	Quantity
Frame	MIL-F-44397	1
Table	MIL-T-44382	2
Mapboard	MIL-B-44381	4
Light set	MIL-L-44259 TYPE II	1
Box, reusable	PPP-B-601 (see 3.2.1)	1

3.2.1 Reusable box. The reusable cleated plywood box shall conform to overseas type, style A, grade B, type 3 load of PPP-B-601. The inside dimensions of the box shall be 75 inches in length, 27 inches in width, and 42 inches in depth.

3.3 Workmanship. The end item shall conform to the quality of product established by this specification.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examination and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of section 3. The inspection set forth in this specification and component specifications listed in table I shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for ensuring that all dimensions specified in the component specifications have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point, or at all points in the manufacturing process necessary to ensure compliance with all dimensional requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

4.3 First article inspection. When a first article is required (see 3.1 and 6.2), it shall be examined for the defects specified in 4.4.2 and 4.4.3. Any nonconformance shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Unless otherwise specified, component conformance inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this specification or applicable purchase document.

4.4.2 End item visual examination. The fully packaged end item (see 5.1 and 5.2) shall be unpacked, then erected in accordance with Drawing 5-4-7473. The mapboards shall be complexed and hung from the frame utilizing the support straps. The light set shall be hung utilizing the light support straps and energized. The system shall examined for the defects listed in table II. The system shall then be repackaged and packed into the shipping container. The lot size shall be expressed in units of systems. The sample unit shall be one complete system. The sample size shall be as indicated below. The presence of any defect shall be cause for the rejection of the lot.

lot size	sample size
1 to 50	1
51 to 150	2
151 to 300	3
301 and over	5

TABLE II. End item visual defects

Examine	Defect
Assembled System	Any component missing Damaged or nonconforming component Any component or assembly not properly connected or joined with companion assembly Frame and tent not properly mated

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

4.4.3 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The sample size shall be expressed in units of shipping containers. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2. The AQL, expressed in terms of defects per hundred units, shall be 2.5.

Examine	Defect
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application
Materials	Any component missing, damaged or not as specified
Workmanship	Inadequate application of components
Content	Number of items per container is more or less than required

5. PACKAGING

5.1 Preservation. Preservation shall be level A.

5.1.1 Level A. The frame shall be placed into its transport bag-frame. Eight steel pins and eight wood pins shall be placed in the pin container. One roof cap, one entrance way wall and one floor shall be placed in transport bag-fabric 1. One plain wall, two windows walls, one plain wall liner, three entrance way/window wall liners, ten support straps and one rain gutter shall be placed in transport bag-fabric 2. Two tables, four mapboards and one light set do not require any preservation.

5.2 Packing. Packing shall be level A.

5.2.1 Level A packing. Components of each SICPS system, preserved as specified in 5.1.1 shall be placed in the reusable box (see 3.2.1). The contents shall be blocked and cushioned to prevent damage during transit. The box shall closed and strapped in accordance with PPP-B-601.

5.3 Marking. In addition to any special marking required by the contract or purchase order, the shipping container shall be marked in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The Standardized Integrated Command Post System is to be used as a stand alone command post, with the M577 Tracked Command Post, and with the SICPS Hard Shelter mounted on the HMMWV/CUCV.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When a first article is required (see 3.1 and 6.3).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in acquisition documents regarding arrangements for selection, inspection, and approval of the first article.

6.4 Subject term (key word) listing.

Frame
Light set
Map board
SICPS
Table

Custodian:

Army - GL

Preparing activity:

Army - GL

(Project 8340-A536)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-C-44404 (GL)	90 APR 6

3. DOCUMENT TITLE

Command Post, Tent, Standardized Integrated Command Post System

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
STRNC-ES	(508) 651-5221	256-5221

c. ADDRESS (Include Zip Code)
Natick RD&E Center
Kansas St.
Natick, MA 01760-5014

IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT:
Defense Quality and Standardization Office
5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466
Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T01:55Z
Check the source to verify that this is the current version before use.