MILITARY SPECIFICATION

ACCELEROMETER, INTEGRATING, ATOMIC WEAPON, TRAINING: M7

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of integrating accelerometer assembly entitled Accelerometer, Integrating, Atomic Weapon, Training: M7 which is used with the Honest John warhead section.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-810 - Enviromnental Test Methods.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components.
MIL-STD-1460 - Soldering of Electrical Connections and Printed Wiring Assemblies, Procedure For.

DRAWINGS

ORDNANCE CORPS

8822411 - Integrating Accelerometer, Training, M7.
EL-8842337 - Equipment List.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The integrating accelerometer shall comply with all requirements specified on the Drawing (dwg) 8822411, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Electrical continuity. The electrical resistance measured between pin pairs of the electrical receptacle shall not exceed 0.030 ohms when tested as specified in 4.4.1

3.5 Insualtion resistance. The insulation resistance between each pin and all other pins and between all pins and the case (except between those electrically connected) shall be not less than 20 megohms when tested as specified in 4.4.2.

3.6 Environmental testing. The accelerometer shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The accelerometer shall also comply with 3.4 and 3.5 before and after each environmental test. Testing shall be as specified in 4.4.3. Tests shall be conducted in the order specified.

3.6.1 Vibration. The accelerometer shall show no evidence of damage such as cracks or loose parts and shall comply with the requirements of 3.4 and 3.5 after being tested as specified in 4.4.3.1.

3.7 Soldering. All soldering shall be in accordance with MIL-STD-1460.

3.8 Workmanship.

3.8.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.8.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.8.3 Burrs. Parts shall be free from burrs.

3.8.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.8.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 8 complete assemblies (see dwg 8822411) for first articln testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table I. Tests shall be conducted in order specified in Table I.

Table I
First article inspection and tests

Inspection or Test	Dest	Non-Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Electrical continuity (see 3.4)		X
3. Insulation resistance (see 3.5)		X
4. Vibration (see 3.6.1)	X	

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. Critical characteristics shall require 100 percent inspection of all items in the inspection lot. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table I and Table I), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Table I
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

Table II
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-9	all	14-16	12	28-33	16	77-121	20
10	9	17-18	13	34-41	17	122-273	21
11	10	19-22	14	42-54	18	over 273	22
12-13	11	23-27	15	55-76	19		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Integrating accelerometer, prior to potting (see dwg 8822411).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Foreign matter	Visual
	102. Any component loose, damaged or missing	Visual/Manual
	103. Solder loose or insufficient (see 3.7)	Visual/Manual
	104. Objective evidence relating to material missing or improper (see 3.1)	Visual
Minor:		
	201. Evidence of poor workmanship (see 3.8)	Visual

4.3.2.1.2 Integrating accelerometer (see dwg 8822411).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Diameter of mounting holes	Gage
	102. Any operation incomplete or missing	Visual
	103. Potting inadequate	Visual
	104. Hardware loose, damaged or missing	Visual/Manual
	105. Any component loose, damaged or missing	Visual/Manual
	106. Objective evidence relating to material missing or improper (see 3.1)	Visual
Minor:		
	201. Marking on identification plate improper, illegible or missing	Visual
	202. Evidence of poor workmanship (see 3.8)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

4.3.2.1.3 Preparation for delivery (see 5).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Preservation, packing and packaging not in accordance with MIL-STD-1169	Visual
	102. Marking not in accordance with MIL-STD-1169	Visual
Minor:		
	201. Evidence of poor workmanship (see 3.8)	Visual

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

Test	Test Classification
a. Electrical continuity	Major
b. Insulation resistance	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Electrical continuity and insulation resistance. Each accelerometer in the lot shall be tested in accordance with 4.4.1 and 4.4.2. If any item fails to comply with 3.4 and 3.5, the item shall be rejected and removed from the lot.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8842337). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Electrical continuity. The electrical resistance measured between the following pin pairs of the electrical receptacle shall not exceed the specified resistance when measured at the terminals of the assembly with a resistance bridge:

1 to 8	12 to 14
2 to 9	14 to 15
9 to 11	

4.4.2 Insulation resistance. The accelerometer shall be subjected to a direct current (d.c.) potential of 500 plus or minus (±) 50 volts until a steady static reading is obtained using an insulation resistance tester from which a direct reading of resistance in megohms can be made.

4.4.3 Environmental testing (see 3.6).

4.4.3.1 Vibration. The accelerometer shall be rigidly mounted on the vibration platform. A simple harmonic motion having an amplitude of 0.03 inch (0.06 inch maximum total excursion) shall be applied, the frequency being varied uniformly between the approximate limits of 10 and 55 to 10 Hertz (Hz) shall be traversed in approximately 1 minute. The motion shall be continuously applied for 30 minutes in each of the mutually perpendicular direction. After completion of this test the accelerometer shall be tested as specified in 4.4.1 and 4.4.2.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The accelerometer shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.1.2 Level C. The accelerometer shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.2 Packing.

5.2.1 Levels A and C. The accelerometer shall be packed in accordance with the applicable instructions contained in MIL-STD-1169(MU).

5.3 Marking. Marking shall be in accordance with MIL-STD-1169(MU).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.

b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 when required on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-N-I.

6.4 Superession data. This specification supersedes the requirements of Purchase Description PA-PD-1804 Revision 1 dated 3 January 1962.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. 1135-A150

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:30Z
Check the source to verify that this is the current version before use.