MILITARY SPECIFICATION SHEET

Mast, AB-1309(V)4/TRC FOR AN/TRC-138A

This specification is approved for use within the Communications-Electronics Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

SCOPE

The requirements for acquiring the Mast AB-1309(V)4/TRC described herein shall consist of this specification and the latest issue of MIL-M-49275(CR).

APPLICABLE DOCUMENTS

SC-D-14158	Ground Rod MX-148/G Assembly and Details
SC-D-68449	Reel RC-405/TR Assembly
SC-D-207771	Cable Assembly, Coaxial (80 ft) CG-3443/U
SM-E-561640	Antenna, AS-1425/GRC Assembly
SC-DL-681550	Ladder, Vehicle Boarding MX-10583/G Assembly
SM-B-683716	Adapter, Cover Flange
SM-B-794072	Antenna, AS-3047/GRC-103(V) Assembly
SC-D-883963	Cable Assembly, Electrical, Power
A3011256	Cable, Coaxial, CG-3860/TRC
A3011257	Waveguide, Coaxial Adapter
13226E5859	Box, Switch

AMSC N/A FSC 5985

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:58Z
Check the source to verify that this is the current version before use.

REQUIREMENTS

Antenna/Transmission line. The Mast AB-1309(V)4/TRC shall provide for the interchangeability of the three AS-1425 Antennas with its (AS-1425) transmission lines and the three AS-3047 Antennas with its (AS-3047) transmission lines.

Hardware. The contractor shall provide all the necessary hardware to mount either antenna/transmission line configuration.

Power lines. The contractor shall provide all the necessary power lines if different from the basic mast system.

Storage. Provisions shall be made for the storage of either antenna/transmission line configuration. In addition, if not previously provided for, mounting and/or storage of the GFP items shall be required.

Government Furnished Property (GFP). The following items shall be GFP for the purpose of design and evaluation of the First Article. They will not be shipped as part of the deliverable mast system.

Antennas.

Three Antenna, AS-1425/GRC Assembly per Drawing SM-E-561640.

Three Antenna, AS-3047/GRC-103(V) Assembly, less Adapter Antenna Mast AB-1281/GRC-103(V), per Drawing SM-B-794072.

Transmission lines.

Transmission line (AS-1425). Three required. One AS-1425 transmission line shall be made by joining three Cable Assembly, RF Coaxial (54 ft), CG-3860/TRC per Drawing A3011256.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:58Z
Check the source to verify that this is the current version before use.

Transmission line (AS-3047). Three required. One AS-3047 transmission line shall be made by joining two Cable Assembly, Radio Frequency, CG-3443/U per Drawing SC-D-207771.

Waveguide adapter. Three Waveguide Assembly, Coaxial, In-line, Adapter per Drawing A3011257.

Adapter, cover flange. Three Adapter, Cover Flange, per SM-B-683716.

Vehicle boarding ladder. One ladder per Drawing SC-DL-681550.

Ground rod shelter. Two rods per Drawing SC-D-14158.

Box, switch. One Box, Switch per Drawing 13223E5859.

Reel (RC-405) with Power Cable. One Reel per Drawing SC-D-68449. One Cable per Drawing SC-D-883963 GRP5.

Generator. Two 10KW MEP 003A Generators. All systems, fuel, electrical, mounting, etc., shall be provided by the contractor.

Function test. The first functional test shall be performed on a complete First Article mast system configured using the AS-1425 Antennas. Subsequently the functional test shall be performed on the same First Article mast system but configured using the AS-3047 Antennas. Later tests may use the GFP items or simulations of them.

Custodian

Army-CR

Preparing Activity

Army-CR

Project 5985-A501-01

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:58Z
Check the source to verify that this is the current version before use.