INCH-POUND

MIL-B-52734C (ME)
21 August 1991
SUPERSEDING
MIL-B-52734B (ME)
5 October 1983

MILITARY SPECIFICATION

BRIDGE, FLOATING: RIBBON, INTERIOR BAY AND RAMP BAY

This specification is approved for use within the USA Belvoir Research, Development and Engineering Center, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers interior bays and ramp bay which, together with the transporter (MIL-T-52735 or MIL-T-53031) constitute the ribbon bridge system.

1.2 Classification. The bridge bays shall be of the following types, as specified (see 6.2).

Type I - Interior bay.
Type II - Ramp bay

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications standards. and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2)

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD.Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-L-2104	- Lubricating Oil, Internal Combustion Engine, Tactical Service.
MIL-E-23765/2	- Electrodes and Rods - Welding, Bare, Solid, Low Alloy Steel.
MIL-C-24667	- Coating System, Non-Skid for Roll or Spray Application (Metric).
MIL-B-43436	- Band, Marker, Blank.
MIL-C-46168	- Coating, Aliphatic Polyurethane, Chemical Agent Resistant.
MIL-T-52735	- Transporter: M812 Chassis, For Ribbon Floating Bridge.
MIL-T-53031	- Transporter: M945 Chassis, For Ribbon Floating Bridge.
MIL-C-53039	- Coating, Aliphatic Polyurethane, Single Component, Chemical Agent Resistant.

STANDARDS

FEDERAL

FED-STD-H28	- Screw Thread Standards for Federal Services.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-209	- Slinging Eyes and Attachments for Lifting and Tying Down Military Equipment.
MIL-STD-889	- Dissimilar Metals.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13218E4002	- Bridge, Floating: Ribbon, Interior Bay.
TA13218E4005	- Bridge, Floating: Ribbon, Ramp Bay.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

(Copies of drawings, publications, and other Government documents required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be. addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY, INC. (AWS)

A5.1 - Covered Carbon Steel Arc Welding Electrodes.
A5.5 - Low-Alloy Steel Covered Arc-Welding Electrodes.
A5.10 - Bare Aluminum and Aluminum Alloy Welding Electrodes and Rods.
A5.18 - Carbon Steel Filler Metals for Gas Shielded Arc Welding.

(Application for copies should be addressed to the American Welding Society, Inc., 550 NW. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein (except for related associated detail specifications, specification sheets or MS standards), the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The bridge bays and bridge bay components shall be in accordance with the applicable top assembly drawings (see 2.1) and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to ensure correct fit, assembly and operation of the bridge bays. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative. Dimensions shown on the drawings shall be verified using parts at 68 degrees Fahrenheit (F) to 70 °F.

3.2 First article

3.2.1 First article. When specified (see 6.2), the bridge bays or separately procured components shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.2.2 Hydraulic system components. In addition to the first article type II bridge bays, the following hydraulic components shall be furnished and tested by the contractor prior to the time the first articles are furnished: One each of all hydraulic fittings, hose assemblies, valves, quick-disconnects, couplings and plugs, and hydraulic cylinders. The hydraulic components shall be identical to those furnished on the first article. Tests shall be those specified in section 4 and shall be subject to surveillance and approval of the Government.

3.3 Materials. Materials shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor, and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. Type I and II bridge bays shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environments to which the items may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and sub-components, and shall make information available, upon request, to the contracting officer or designated representative.

3.3.1.3 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the bridge may be newly fabricated from recovered materials to the maximum extent practicable, provided the bridge produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the bridge.

3.3.2 Welding electrodes. Unless otherwise specified on the end product drawings, the following welding electrodes shall be used.

3.3.2.1 For aluminum. Welding electrodes for aluminum shall conform to AWS

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

A5.10, classification ER5356.

3.3.2.2 For steel.

3.3.2.2.1 High-strength steel. Welding electrodes for high-strength steel, including joints with steel castings, shall conform to AWS A5.5, classification E12015, E12016, E12018-M or MIL-E-23765/2, classification MIL-120S-1.

3.3.2.2.2 Mild steel. Welding electrodes for mild steel, including Joints with steel castings, shall conform to AWS A5.1, classification E7015, E7018, K7028, or AWS A5.18, classification E70 S-3.

3.4 Hydraulic oil. Oil for all hydraulic systems shall conform to MIL-L-2104, grade 10.

3.5 Ramp bay hydraulic system. The assembled hydraulic system shall withstand pressures as specified in 3.5.1, 3.5.2 and 3.5.5 without external leakage (except weepage normally expected at piston rod packing), permanent deformation or rupture to any part of the system. Prior to delivery, the hydraulic system shall be filled with hydraulic oil conforming to MIL-L-2104, grade 10. Unless otherwise specified (see 6.2), the age of rubber products furnished shall not exceed 24 months from the date of issue to the date of acceptance of the bridge bays or separately procured component(s) by the Government. Separately procured hose assemblies shall be provided with suitable plastic protectors for end openings and threads.

3.5.1 Hydraulic cylinder. When tested in accordance with 4.5.2.4, the hydraulic cylinder shall withstand a pressure of 9700 pounds per square inch (psi) on the piston rod end and a pressure of 1500 psi on the cap end without external leakage, permanent deformation or rupture of any part of the system.

3.5.2 Hydraulic pump. When tested in accordance with 4.5.2.8, the hydraulic pump shall withstand a pressure of 1500 psi without external leakage anywhere in the pressurized system, permanent deformation or rupture of any part within the system. All hydraulic lines and components shall be free of any foreign matter, such as metal chips and filings, that may in any way contaminate the oil or damage the system.

3.5.3 Fittings and hydraulic hose. When tested in accordance with 4.5.2.8, fittings and hydraulic hose shall conform to the individual end product drawing requirements and shall withstand the pressure for the system of which they are a part.

3.5.4 Quick-disconnect couplings. When tested in accordance with 4.5.2.8, quick-disconnect couplings and plugs shall conform to the individual end product drawing requirements and shall withstand the pressure specified for the system of which they are a part.

3.5.5 Control valve. When tested in accordance with 4.5.2.6, all of the working sections of the hydraulic pump control valve shall withstand a pressure of 9700 psi without evidence of valve binding or sticking.

3.5.6 Pressure relief valve. When tested in accordance with 4.5.2.5, the relief valve shall be as specified on the applicable end product. In

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

addition1 the valve shall withstand and operate at the applied without malfunction or failure.

3.5.7 Internal leakage. When tested in accordance with 4.5.2.7, the hydraulic oil leakage during the hydraulic cylinder pressure test shall not exceed the rate specified on drawing D13218E4078.

3.6 Threads. All threads not otherwise covered by this specification or the end product drawings shall conform to FED-STD-H28.

3.7 Hydraulic system cleanliness. Prior to installation into the ramp bay, the interior and exterior surfaces of all hydraulic components shall be washed and flushed to remove all visible contaminants, particles and foreign elements. Openings of the components shall be immediately covered until installation. The hydraulic system shall be operated and bled prior to being subjected to the tests specified herein. The hydraulic system shall be kept clean of foreign matter and contamination during all tests and when tested in accordance with 4.5.2.12 shall meet the contamination limits specified in table I prior to acceptance.

Table I. Contamination limits (particles per milliliter).

Quantity (maximum)	Particle Size
1000	Greater than 10 microns
100	Greater than 20 microns

3.8 Performance. When tested in accordance with 4.5.2.11, the bridge bays shall perform as specified herein without evidence of any of the following defects:

a. Malfunctioning of components or failure of bridge bay to unfold and fold as required.
b. Binding of parts during launching and retrieving.
c. Permanent distortions (other than normal wear).
d. Material defects such as cracks or open joints.
e. Failure of latches and pin-drive mechanism to function as required.
f. External hydraulic leakage.
g. Failure of hydraulic systems to operate as required.
h. Bridge bays not connecting.
i. Water leaking into the pontons.
j. Ramp bays not capable of being articulated to 18 degrees from the horizontal.


3.9 Lubrication. Lubrication shall be as shown on the end product drawings or as specified herein.

3.10 Cleaning, treatment and painting. Cleaning, treatment and painting shall be as shown on the end product drawings. Where MIL-T-704, type F or G, paint is required (see 6.2), the finish coat shall be camouflage green 383 conforming to MIL-C-46168 or MIL-C-53039. Nonskid compound conforming to MIL-C-24667, type I, composition G, grade A, class I shall be applied to all topside surfaces which can be used as walkways.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

3.11 Identification marking. The bridge bays and bridge bay components shall be identified in accordance with MIL-STD-130 and as indicated on the end product drawings.

3.11.1 Identification marking for hose assemblies. Each hose assembly shall have identification marking stamped on an aluminum band conforming to MIL-B-43436, except that the band shall be of sufficient width to allow a minimum of two lines of 1/8-inch metal stamping. Unless otherwise specified on the drawings, the marking band shall contain the following information:



3.12 Stenciling. The nomenclature, National Stock Number, weight, and cubage shall be stenciled on the end of each ponton. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be Gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704. Weight of ramp roadway pontons shall include hydraulic system and approach ramp.

3.13 Government-loaned property. Unless otherwise specified (see 6.2), the following property, in the quantities indicated, will be loaned by the Government (see 6.6):

Item	Identification	Description	Quantity
1	MIL-T-52735 or MIL-T-53031	Transporter, Ribbon Bridge	1
2	13218E4319	Test Fixture, Hydraulic Cylinder	1
3	13219E4302	Frame, Pull Test	1
4	13218E4078	Ramp Bay, Hydraulic Cylinder 1/	1
5	13218E4002 13218E4005	Bridge Bay, type I or II 2/	as required
6	P715141 (included in TA's 2.1)	Quality Assurance Pamphlet, "Inspection Equipment for Bridge, Floating: Ribbon, Interior Bay and Ramp Bay" 3/	1
7	TM-5420-209-12	Technical Manual, Operator's and Organizational Maintenance, "Improved Float Bridge (Ribbon Bridge)".	1

1/ When type I bays are procured separately, the Government will furnish a cylinder for use with pull test.
2/ When type I or II bays are procured separately, the Government will loan a sufficient number of other types of bays to accomplish tests.
3/ The contractor is responsible for fabricating the functional inspection equipment and obtaining the necessary optical inspection equipment required by Quality Assurance Pamphlet P715-141.

3.14 Ponton leak. When tested in accordance with 4.5.2.10 each individual ponton shall be capable of maintaining a constant, independent, internally applied air pressure of 1.5 psi1 plus or minus 0.1 psi for at least 5 minutes

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

without leakage.

3.15 Pull. When tested in accordance with 4.5.2.9, each interior roadway ponton shall be capable of withstanding a tensile load of 483,000 pounds for a time period of 5 minutes without evidence of permanent deformation or structural failure anywhere within the ponton.

3.16 Reliability. When tested in accordance with the test plan appearing in 4.5.2.13, an individual type I or type II bay shall possess the following mission specified reliabilities:

a. Type I bridge bays (interior bays), shall exceed acceptance criterion based on an upper test value of 20 Mean Deployment Cycles Between Failure (MDCBF) and a lower test value of 16 MDCBF.
b. Type II bridge bays (ramp bays), shall exceed acceptance criterion based on an upper test value of 14 MDCBF and a lower test value of 10 MDCBF.

3.17 Maintainability. The interior bay and ramp bay shall have maintenance requirements of not more than 0.435 maintenance man-hours per launch and not more than 0.893 maintenance in man-hours per launch, respectively. All active maintenance man-hours required (scheduled and unscheduled) are included in the calculation. Man-hours for repair of replaced components and scheduled before-and-after operation checks are excluded. A maintenance schedule shall be established prior to the start of any testing.

3.18 Tiedown provisions. The tiedown provisions shall conform to MIL-STD-209, class 2 or 3, type IV equipment. The tiedown provisions shall satisfactorily complete the pull testing as specified without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components.

3.19 Slinging provisions. The slinging provisions shall conform to MIL-STD-209, class 1 or 3, type IV. The provisions shall enable the complete bridge bay to be lifted in the normal operating position. The provisions shall be located so that not less than one inch clearance is maintained between slings and all exterior parts and shall be fastened to members which will withstand stresses in the amount and direction of pull specified for the provisions without weld failure, permanent deformation, cracking, loosening or breaking of the provision or its connecting structural components. Slinging provisions may also be used as tiedown provisions when such provisions meet the requirements specified in 3.18. All slinging/tiedown provisions shall be labeled "LIFT", "TIEDOWN" or "LIFT TIEDOWN", as appropriate, in 1-inch (2.54 cm) high letters.

3.20 Interchangeability. All parts, components and assemblies having the same identification number shall be functionally and dimensionally interchangeable. Interchangeability is defined as two or more parts (components and assemblies) possessing such functional and physical characteristics as to be equivalent in performance and durability, and capable of being exchanged one for the other without alteration of themselves or of adjoining parts (components and assemblies), except for built-in adjustment, and without selection for fit or performance.

3.21 Specification-control items. Prior to using any specification-control

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

item other than a suggested source item1 the contractor shall furnish to the contracting officer evidence that the item conforms to all requirements on the applicable drawing. The contractor is responsible for performing all inspections and tests on specification or source control items if not performed by the vendor. No change shall be made to any source or specification control item after approval of the first article without prior approval by the contracting officer.

3.22 Type I. interior bay. The type I bays shall conform to top assembly drawing, TA13218E4002.

3.23 Type II. ramp bay. The type II bays shall conform to top assembly drawing, TA13218E4005.

3.24 Workmanship.

3.24.1 Castings. All casting used on the bridge bays shall be cleaned of harmful extraneous material, such as sand, dirt, sprues, scale, and flux. Rework shall be limited to procedures which do not reduce strength or affect function.

3.24.2 Steel fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing or sawing. All bends shall be made with controlled means to ensure uniformity of size and shape. Precautions shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free from burrs, sharp edges, and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.24.3 Aluminum fabrication. Before any work or layout is done, aluminum shall be straightened. Straightening shall be done by methods that will not result in injury to the metal. Care shall be used in handling aluminum during fabrication to avoid scratching or damage to edges. Finished members shall be free from lamination, kinks, bends, scratches or winds. All bends shall be made to a radius which will not cause cracking or undue stress in the extreme outer fibers. Except for those of a minor nature, bends shall be made with metal dies or fixtures to insure uniformity of size and shape. Sharp instruments shall not be used for making bend lines. Aluminum 3/8 inch thick and over shall be cut by routing or sawing. Aluminum under 3/8 inch thick may be cut by shearing.

3.24.4 Welding. Unless otherwise specified on the end product drawings, welding shall be done in accordance with the requirements of this specification. Prior to the fabrication of any weldment, the contractor shall prepare and submit to the contracting officer for approval, an isometric or perspective drawing showing the location of each joint and the joint welding procedures to cover all welding, including a general outline for the repair of base material and welded joints. These procedures shall also address the proposed method of surface preparation prior to welding. The procedures shall be qualified in accordance with the ASME Boiler and Pressure Vessel Code, Section IX, except that the guided bend test is not required for steel castings. All welds to be qualified shall be made on the same alloy, gauge

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

and temper of material, with the same filler materials, and in the same position as will be used in production. Weld procedures which have been qualified under other equivalent recognized codes may be considered qualified for the purposes of this specification, provided they are approved by the contracting officer. Any change in procedure during fabrication shall require requalification in accordance with the requirements of the ASME Boiler and Pressure Vessel Code, Section IX.

3.24.4.1 Steel Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale and other foreign matter. Parent materials, weld filler metals, and fabrication techniques shall be as required to enable the balk to conform to the examination and test requirements specified in section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more that 0.188 inch unless appropriate bridging techniques are used. Procedures and sequences shall be such that distortion and shrinkage will be held to a minimum. When straightening is required, caution shall be exercised to ensure that the straightening process does not weaken the part and the complete item. Tack welds shall have the same quality requirements as the final weld. Weldments, weld beads, and tack welds shall be:

a. Homogenous in appearance.
b. Smoothly blended into the base metal without spattering or other irregularities.
c. Able to transmit stress without permanent deformation or failure when parts connected by welds are subjected to service loading.

Welding shall be in accordance with the ASME Boiler and Pressure Vessel Code, Section IX. Prior to any welding, welding procedures shall be qualified for each joint as specified in the ASME Boiler and Pressure Vessel Code, Section IX. Guided bend tests shall be used for procedure qualification. Welding procedures shall be available at each welding station for welder's or operator's reference. The welding procedure specifications and qualifications shall be made available for review by the contracting officer or his representative.

3.24.4.2 Aluminum welding. The aluminum surfaces of parts to be welded shall be free from scale, paint, grease, oxide film, and other foreign matter. The welding shall be done by the gas-metal-arc (MIG) method, except as shown on end product drawings. Where material gauge or size prevents use of MIG welding, the gas tungsten-arc (TIG) method may be employed. Welds may be ground, filed, buffed or chipped, but not hammered, and shall be free from defects, such as base metal cracks adjacent to or behind welds, cracks in weld metal, undercutting of base metal, lack of fusion with parent metal or between parts, porosity, lack of penetration, lack of prescribed fit, inclusions or spatter. To assure that all welding variables have been addressed, the welding procedures required by 3.24.4 shall include provisions for daily on the-job aluminum weldbreak test by each production welder during each work shift. The procedure shall require that the welder construct the "weldbreak" specimen using the same materials, alloys, and thicknesses, with the same weld type and size, and cleaned, prepared and welded in accordance with the applicable procedures and techniques developed for the end item weldment being welded at the time the break test is required. The procedures shall also include the steps to be followed for breaking the specimens and examination of the fractured parts to determine the weld quality. The procedures shall also

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

describe the corrective action to be taken in the event that the specimen test demonstrates weld quality that is not acceptable, including disposition of component welding accomplished by the welder since the last acceptable weldbreak test.

3.24.5 Care of welding electrodes. Care of welding electrodes specified for welding high-strength steel shall be as follows:

a. When a container of welding electrodes is opened, the entire contents shall be placed immediately in a baking oven, with electrodes placed not more than three layers deep on a tray, and baked either (1) for a minimum of 1 hour, but not more than 1-1/4 hours, at 800 °F; or (2) for a minimum of 4 hours at 400 °F.
b. The baked electrodes, whilestill warm, shall then be placed in a ventilated holding oven set at 250 °F to 300 °F.
c. Not more than a 1/2-hour supply of welding electrodes shall be taken from the holding oven at one time.
d. If electrodes are out of the holding oven in excess of 1/2 hour but less than 1 hour, they shall be returned to the holding oven for a period of not less than 1 hour.
e. If electrodes are out of the holding oven in excess of 1 hour, they shall be returned to the baking oven and rebaked as described under a.
f. Electrodes removed for use shall not be allowed to come in contact with any moist or wet surfaces, Electrodes that have been in contact with water, grease or oil shall not be used.

3.24.6 Welders. Before assigning any welder or welding operator to fabricate bridge bays covered by this specification, the contractor shall provide the contracting officer with certification that the welder or welding operator has passed qualification tests as prescribed by the ASME Boiler and Pressure Vessel Code, Section IX, for the type of welding operations to be performed and that such qualification is effective as defined by the code. Test specimens shall be made on the same alloy, gauge and temper of material with the same filler materials and in the same position as will be used in production. Welders who have been similarly qualified under other recognized codes may be considered qualified for the purposes of this specification, provided they are approved by the contracting officer. In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator. The test results shall be made available for review by the contracting officer or the contracting officer's representative.

3.24.7 Machine work. Tolerances and gauges for metal fits shall conform to the limits specified on the applicable end product drawings.

3.24.8 Jigs and fixtures. Fabrication, assembly and installation of all bridge bay components (except minor parts) shall be accomplished with production tooling, jigs or fixtures, and parts shall be joined while held in position. Jigs or fixtures shall be designed to minimize distortion of the parts being welded and to assure that the configuration, alignment and location of parts meet the specified requirements. Subsequent straightening and thermal stress relieving is permitted to relieve distortion, provided the straightening process does not damage the component.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined and tested in accordance with referenced specifications, standards and drawings, as applicable.

4.1.3 Disassembly inspection. Failure of any examination or test by the first article shall be cause for disassembly, in the presence of a Government representative, of the first article to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejection of the first article. Reassembly with replacement parts and retesting shall be the responsibility of the contractor.

4.1.4 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection1 the sampling plan, and the basis for acceptance and rejection (see 6.7 and 6.8).

4.2 Classification of inspections. Inspections shall be classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection comparison (see 4.6).
d. Inspection of packaging (see 4.7).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4.3 First article inspection.

4.3.1 First article examination. The first article bridge bays or separately procured components shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 First article tests.

4.3.2.1 Hydraulic system components. Prior to installation of the hydraulic system components into the first article type II bridge bay, the components shall be tested as specified in 4.5.2.1 through 4.5.2.8. Failure of any test shall be cause for performing the disassembly inspection specified in 4.1.3.

4.3.2.2 Assembled bridge bay. After successful completion of the tests specified in 4.3.2.1, the hydraulic system components shall be installed in the first article type II bridge bay, and the bridge bay shall be tested as specified in 4.5.2.10 through 4.5.2.12. The assembled type I bridge bay shall be tested as specified in 4.5.2.9 through 4.5.2.11. Failure of any test shall be cause for performing the disassembly inspection specified in 4.1.3.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination and tests for separately procured bridge bay components shall be in accordance with MIL-STD-105.

4.4.2 Examination.

4.4.2.1 Individual. Each bridge bay shall be examined for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4.2.2 Samples. Samples of separately procured bridge bay components selected in accordance with 4.4.1 shall be examined for the applicable defects specified in 4.5.1. Sample size shall be determined using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found, and rejected when one or more defects are found.

4.4.3 Tests.

4.4.3.1 Individual. Each type II bridge bay shall be tested as specified in 4.5.2.1 through 4.5.2.8 and 4.5.2.10 through 4.5.2.12. Each type I bridge bay shall be tested as specified in 4.5.2.9 through 4.5.2.11. Failure of any test shall be cause for rejection.

4.4.3.2 Samples. Samples of separately procured components selected in accordance with 4.4.1 shall be subjected to the applicable test specified in 4.5.2.1 through 4.5.2.12. Presence of one or more defects shall be cause for rejection.

4.5 Inspection schedule.

4.5.1 Examination. Each type of bridge bay or separately procured components as specified shall be examined as specified herein for the following defects as applicable:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

Major

101. Any part or component not in accordance with QAP requirements as shown on the end product drawings (see 3.1.1).
102. Any dimension other than those identified on the QAP requirements shown on the drawings not as specified (see 3.1.1).
103. Incorrect bolt torque (see 3.1.1).
104. Members not true to dimension and line or containing twists, bends or other imperfections (see 3.1.1 and 3.24.3).
105. Material not as specified (see 3.3).
106. Materials not resistant to corrosion or deterioration, or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environments (see 3.3.1).
107. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
108. Contractor does not have documentation available for identification of material, material finishes or treatment (see 3.3.1.2).
109. Used, rebuilt or remanufactured components, pieces or parts incorporated in the bridge bays (see 3.3.1.3).
110. Leaks in hydraulic lines (see 3.5).
111. Age of hose not as specified (see 3.5).
112. Quick-disconnect couplings not as specified (see 3.5.4).
113. Hydraulic system cleanliness not as specified (see 3.7).
114. Nonskid compound not applied correctly or missing (see 3.10).
115. Components not interchangeable with respect to installation, performance and quality (see 3.20).
116. Workmanship not as specified (see 3.24).
117. Welding not performed in accordance with qualified procedure (see 3.24.4).
118. Welding and welds not as specified (see 3.24.4.1).
119. Weld defects such as base metal cracks adjacent to or behind welds, cracks in weld metal, undercutting of base metal, lack of fusion with parent metal or between parts, porosity, lack of penetration, lack of prescribed fit, incorrect preparation, slag inclusion, spatter, or incorrect size (see 3.24.4.2).
120. Qualification of welders, welding operators or weld procedure not as specified (see 3.24.4 and 3.24.6).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

Minor

201. Warning and instruction signs, decals and stencilling missing (see 3.1.1, 3.11 and 3.12).
202. Lubrication and lubrication fittings not as specified (see 3.9).
203. Treatment and painting not as specified (see 3.10).
204. Identification marking and hose assembly identification missing or incorrect (see 3.11).

4.5.2 Tests.

4.5.2.1 Test conditions. All tests, with the exception of the operational performance test and the reliability test, shall be conducted at an ambient air temperature of from plus 25 °F to plus 100 °F with the hydraulic oil temperature between plus 25 °F and plus 90 °F. The operational performance and reliability tests may be conducted at existing ambient temperatures, except that the contractor shall be responsible for ensuring that icing conditions do not impair performance of the operational test. Hydraulic oil conforming to MIL-L-2104, Grade 10, shall be used for all tests. Prior to assembly of hydraulic components for test or installation into bridge bays, all hydraulic lines and hydraulic components shall be free of any foreign matter, such as metal chips and filings, that may in any way contaminate the oil or damage the system. All equipment shall be operated in accordance with the applicable technical manual.

4.5.2.2 Test schedule. All tests shall be conducted in accordance with table II and in the specified sequence.

TABLE II. Test schedule.

First Art.	Qual. Conf.	Test	Test Para.	Reqmt. Para.
X	X	Test conditions	4.5.2.1	
X	X	1/ Limbering up of hydraulic cylinder	4.5.2.3	
X	X	1/ Hydraulic cylinder pressure	4.5.2.4	3.5.1
X	X	1/ Cylinder relief valve	4.5.2.5	3.5.6
X	X	1/ Control valve	4.5.2.6	3.5.5
X	X	1/ Internal leakage	4.5.2.7	3.5.7
X	X	1/ Ramp articulation system pressure	4.5.2.8	3.5.2, 3.5.3, 3.5.4
X	X	2/ Pull	4.5.2.9	3.15
X	X	Ponton leak	4.5.2.10	3.14
X	X	Operational performance	4.5.2.11	3.8

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

X	X	1/ post-test hydraulic cleanliness	4.5.2.12	3.7
-	-	Reliability and maintainability	4.5.2.13	3.16 and 3.17
-	-	Slinging and tiedown provisions	4.5.2.14 and 4.5.2.15	3.18 and 3.19

1/ Applies to type II bridge bays only.
2/ Applies to type I bridge bays only.

4.5.2.3 Limbering up of hydraulic cylinder. Prior to subjecting the cylinder to the tests specified herein, the cylinder shall be cycled through 25 complete cycles. One cycle shall consist of extension and retraction of the rod through full travel without bottoming. The cycling shall be done by either hydraulic pressure or mechanical means.

4.5.2.4 Hydraulic cylinder pressure. Place the cylinder in the test frame (see 3.13) so that the piston is restrained from bearing against either cylinder head. In accordance with drawing D13218E4078, note 5, subject Port "A" of the cylinder to 9700 psi, plus zero psi minus 200 psi, for 5 minutes. Nonconformance to 3.5.1 shall constitute failure of this test.

4.5.2.5 Cylinder relief valve. The hydraulic cylinder shall be pressurized until the relief valve opens. Do not pressurize the cylinder above 9700 psi. Opening of the valve at any pressure below 9500 psi or failure to open before 9700 psi is reached shall constitute failure of this test. After passing the above test, the pressure shall be reduced to 7000 psi. Failure of the valve to close (as indicated by an internal leakage of no more than 50 drops a minute at Fort "B") before 7000 psi is reached or nonconformance to 3.5.6 shall constitute failure of this test.

4.5.2.6 Control valve. The hydraulic pump control valve shall be subjected to a pressure between 9700 psi and 9900 psi. Evidence of leakage or permanent deformation of the valve or nonconformance to 3.5.5 shall constitute failure of this test.

4.5.2.7 Internal leakage. During the hydraulic cylinder pressure test, leakage shall be measured at Ports "A" and "B", as specified on drawing D13218E4078 of top assembly drawing TA13218E4005. Leakage in excess of the rate specified on D13218E4078 shall constitute failure of this test.

4.5.2.8 Ramp articulation system Pressure. Subject the hydraulic pump, hose and hydraulic cylinder (Ports "A" and "B.") assembly to a pressure between 1500 psi and 1600 psi for least 1 minute. Evidence of external leakage, permanent deformation or nonconformance to 3.5.2, 3.5.3 or 3.5.4 shall constitute failure of this test.

4.5.2.9 Pull. Install the interior roadway ponton in the test frame (see 3.13) and apply a tensile load at each end through the ponton eye and yoke (see drawing D13218E4003 (finds 16 and 17) of top assembly drawing, TA13218E4002). Apply the tensile load through a ramp hydraulic cylinder (see 3.13) pressurized in increments of approximately 925 psi to a pressure of

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

9250 psi. Hold the maximum load for a period of 5 minutes. Nonconformance to 3.15 shall constitute failure of this test.

4.5.2.10 Ponton leak. Internally pressurize with air each individual ponton of the bridge bay to 1.5 psi, plus or minus 0.1 psi, and maintain pressure while soap testing for leaks. If leakage occurs, remove the pressure from the ponton, repair leak area in accordance with the instructions on applicable ponton drawings, and repeat the leak test for each repaired ponton. Evidence of any leakage that cannot be repaired shall constitute failure of this test. After all identified leaks have been repaired, the ponton is to be pressurized to 1.5 psi, plus or minus 0.1 psi, and the air source is to be disconnected and the pressure held for five minutes. Nonconformance to 3.14 shall constitute failure of this test.

4.5.2.11 Operational performance. When ramp bays and interior bays are procured together tests shall be performed on both types of bay. With the bridge bay in folded position, adjust unfolding cables to tension specified on the assembly drawings. Using the ribbon bridge transporter (see 3.13), free-launch the bridge bay in a body of water of sufficient size and depth (a minimum of 4 feet) to accommodate a free-launch without damage to the bridge bay. With the bridge bay unfolded and floating, engage the roadway-to-roadway deck connectors and the bridge latches. For the ramp bay, the roadway pontons will have to be pulled together for these connectors to engage their mating receptacles. The bridge bay shall remain floating for a minimum time period of 30 minutes, after which the pontons shall be inspected for leakage. While the bridge bay is floating, operate the pin-drive mechanism to ensure free movement for the entire pin travel in both directions. The operational performance test shall include connecting both ends of the interior bay to the ramp bay. When interior bays are procured separately, two first article bays shall be provided for the connecting test. When ramp bays are procured separately, the Government shall furnish an interior bay for the connecting test (see 3.13). Prior to retrieval, each ramp bay yoke will be articulated to a minimum of 18 degrees from the vertical and will then be pumped back to the vertical position. Prepare the bridge bay for retrieval and retrieve the bridge bay onto the transporter. Failure of this test shall consist of any of the following defects:

a. Failure of roadway-to-bow foldlock latches to retain bows in folded position while on transporter.
b. Failure of roadway-to-roadway foldlock latches to retain the roadway pontons in folded position while on transporter.
c. Failure of launched bridge bay to unfold due to action of unfolding mechanism without any other aids.
d. Failure of the roadway-to-bow bridge latches to engage their mating bow receptacles when operated manually.
e. Evidence of ponton leakage.
f. Failure of connectors or pin-drive mechanism to function as intended.
g. Failure of bridge bay to fold during retrieval without any assistance other than the winch cable, or binding during folding.
h. Failure of all foldlock latches to engage completely and automatically when the bridge bay is retrieved.
i. Failure of the ramp yokes to be pumped as intended.
j. Failure of the bays to connect as intended.

Failure of latches to function shall be remedied by adjustment where possible.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4.5.2.12 Post-test hydraulic cleanliness. After completion of the operational performance test and prior to delivery of the type II bridge bays to the Government, a sample of hydraulic fluid shall be taken from one of the quick-disconnect couplings and tested for the particle count specified in table I. If the particle count exceeds the values in table I, the system shall be flushed until contamination is reduced to the acceptable level. Inability to conform to the cleanliness levels specified in table I shall constitute failure of this test.

4.5.2.13 Reliability maintainability. Using the parameters specified in 3.16, the bay or bays shall be tested as specified herein. When tested as specified herein, the maintenance requirements shall not exceed the maintenance man-hours specified in 3.17 for the interior bay and ramp bay, respectively. This test will be conducted by the Government at a site selected by the Government. The test bridge system shall consist of a minimum of 12 interior bays, four ramp bays, and 16 transporters (see 3.13). Testing may be performed in still water or in water currents up to 8 feet per second. Maintenance shall be performed in accordance with the technical manual, and at the end of each day's mission, any damage to the bridge bays shall be repaired prior to the next day1s mission. Failure to meet all performance requirements of this specification, when such failure is due to faulty material or workmanship1 shall be cause for rejection and shall be cause for refusal by the Government to continue acceptance of production units until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on all units previously produced. Any such material or workmanship deficiencies will be considered prima facie evidence that all units accepted prior to the completion of this test are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5.2.13.1 Reliability-maintainability test cycle. Reliability-maintainability testing shall be conducted in cycles equivalent to 10 normal bridge missions. Each such cycle shall consist of the following:

a. 9 launch/retrieve cycles.
b. 1 launch and bridge assembly.
C. 500 class 60 vehicle crossings.
d. 1 bridge disassembly and retrieval.
e. 200 miles of transporting.

4.5.2.13.2 Reliability. The test plan utilized will depend on the method of procurement (see 6.2). Failure criteria based on 14 bay bridge.

a. Test Plan I - Utilized for interior bays if procured separately. Test for ten cycles (1200 overall deployments) as specified in 4.5.2.13.1. If less than 67 failures out of 1200 deployments occur, reliability is acceptable. If any time during the test 67 failures occur, reliability is not acceptable and the test is terminated.
b. Test Plan II - Utilized for ramp bays if procured separately. Test each pair of bays for five cycles (50 deployments per bay) 200 deployments overall) as specified in 4.5.2.13.1. If less than 17 failures out of 200 deployments occur, reliability is acceptable. If

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

at any time during the test 17 failures occur, reliability is not acceptable and the test is terminated.

c Test Plan III - Utilized for ramp and interior bays if procured together. Test for ten test cycles (100 missions for each interior bay; 50 missions for each pair of ramp bays) as specified in 4.5.2.13.1. If less than 67 interior bay failures and less than 17 ramp bay failures occur, reliability is acceptable. If at any time more than 66 interior bay failures occur, reliability of interior bays is not acceptable; nevertheless, at this point if less than 17 ramp bay failures have occurred, continue testing until either all missions are complete (in which case, ramp bay reliability is acceptable) or until 17 ramp failures do occur (in which case ramp bay reliability is also not acceptable). The same reasoning may be applied if more than 16 ramp failures have occurred but less than 67 interior bay failures have occurred. If at any time more than 66 interior failures and more than 16 ramp failures occur, terminate all testing; reliability is not acceptable.

d. Test Plan IV - Utilized when interior bays, ramp bays and transporters are procured together. Test for ten test cycles as specified in 4.5.2.13.1 and evaluate reliability. Failure criteria for bridge bays will be as specified in 4.5.2.13.2c of this specification. Failure criteria for transporters will be as specified in MIL-T-52735 or MIL-T-53031, as applicable.

For the purpose of reliability computations, a mission failure is defined as follows:

a. Any malfunction of an interior bay which:
   (1) Causes the bay to fail to deploy from the launcher.
   (2) Causes the bay to fail to unfold.
   (3) Causes the bay to fail to connect to adjoining bays.
   (4) Causes bridge traffic to be halted more than 15 minutes,
   (5) Makes recovery of the bay onto the transporter in less than one hour impossible.

b. Any malfunction of an interior or ramp bay which would cause inability to complete a mission, as defined in 4.5.2.13.1, in less than 14 hours (utilization of repair resources available to the parent deployed unit allowable).

c. Any impending interior or ramp bay malfunction which would require maintenance that cannot be deferred until the end of the mission because of the creation of a safety hazard and results in the situation described in a or b above. Simultaneous related malfunctions are considered one failure. Malfunctions which do not affect mission performance are not considered mission failures.

4.5.2.13.3 Maintainability. The maintenance man-hours required to perform all corrective and preventive maintenance occurring during the reliability test (see 4.5.2.13.1) shall be recorded and classified as to whether it was scheduled or unscheduled. The MR requirement(s) of 3.17 shall be assessed using the following formula:

$$MR = \frac{\text{Total scheduled maintenance man-hrs + total unscheduled maintenance man-hrs}}{\text{Total operating time}}$$

Operator/crew checks and services are excluded from this ratio.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4.5.2.14 Tiedown provisions test. The tiedown provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.18. Inability to meet the requirements of 3.18 shall constitute failure of this demonstration.

4.5.2.15 Slinging provisions test. The slinging provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.19. Inability to meet the requirements of 3.19 shall constitute failure of this demonstration.

4.6 Inspection comparison. The Government may select bridge bays at any time during the contract production period and subject these bridge bays to the examination specified in 4.5.1 and the tests specified in 4.5.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on bridge bays selected at random from those which have been accepted by the Government and will not include the previously inspected first article bridge bays. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison, and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.6.1 Inspection failure. Failure of an inspection comparison bridge bay to meet any requirement specified herein during and as a result of the examination and tests specified in 4.6 shall be cause for rejection of the inspection comparison bridge bay and shall be cause refusal by the Government to continue acceptance of production bridge bays until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on bridge bays previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all bridge bays accepted prior to the completion of inspection comparison are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.7 Inspection of packaging.

4.7.1 Quality conformance inspection of pack.

4.7.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.7.1.2 Sampling. Sampling for examination shall be in accordance wit MIL-STD-105.

4.7.1.3 Examination. Samples selected in accordance with 4.7.1.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection

121.	Bridge bays not preserved as specified (see 5.1.1).
122.	Unfinished exterior metal surfaces not preserved as specified (see 5.1.2.1).
123.	Exposed machined metal surfaces not preserved as specified (see 5.1.2.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

124. Other components not placed and secured as specified (see 5.1.2.3).
125. Marking missing, illegible, incorrect or incomplete (see 5.2)

5. PACKAGING

5.1 Preservation (see 6.9)

5.1.1 Preservatives. Preservatives specified herein shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.1.2 Bridge bays (interior and ramp). Each bridge bay shall be folded and secured in the transport position. Prior to folding, the following shall be accomplished.

5.1.2.1 Unfinished surfaces. Unpainted or unfinished exterior metal surfaces requiring the application of a contact preservative in accordance with MIL-P-l16 shall be coated with type P-l preservative.

5.1.2.2 Machined surfaces. Exposed machined metal surfaces for which a grease coating has not been specified on the drawings shall be coated with type P-6 or type P-11 preservative.

5.1.2.3 Other components. Other components, such as ramp connecting tool and pump handle, shall be placed and secured as provided for.

5.2 Marking (see 6.9). In addition to any special marking specified in the contract or purchase order (see 6.2), marking for shipment and storage shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature which is helpful, but is not mandatory)

6.1 Intended use. The bridge bays are intended to be used with transporters conforming to MIL-T-52735 and MIL-T-53031. The ramp bays and interior bays can be assembled to form bridges of variable length or rafts. The assembled bridge is capable of carrying class 60 vehicle loads in currents up to 8 feet per second, and the rafts are capable of carrying a class 60 vehicle load in currents up to 9 feet per second.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type of bridge bay required (see 1.2).
C. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
d. When first article bridge bays or separately procured components are required for inspection and approval and the number of each type of bridge bay or components required (see 3.2).
e. Age of rubber products if other than specified (see 3.5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

f. Color required when other than specified (see 3.10).
g. When Government-loaned property is required (see 3.13).
h. Which reliability/maintainability test plan will be utilized (see 4.5.2.13.2).
i. Any special marking (see 5.2).

6.3 First article. When a first article inspection is required, the bridge bays or separately procured components may be either the first article or first-produced items. The first article should consist of one or more bridge bays or separately procured components. The contracting officer should include specific instructions in the acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first article. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operational manual to be furnished with each bridge bay.

6.5 Provisioning. The contracting officer should include provisioning requirements, if required, for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of bridge bays or separately procured components.

6.6 Government-loaned property. The contracting officer should arrange to loan the property specified in 3.13.

6.7 Quality assurance provisions (QAP). The contracting officer should require the contractors to maintain records of all QAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include, as a minimum, lot size, sample size, drawing requirements, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, and corrective action taken when applicable."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

6.8 Definitions.

6.8.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of this specification. QAP indicates the minimum requirements which must be inspected on the end product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.9 Levels of preservation and packing. Levels of preservation and packing have not been included as the preservation specified is the minimum acceptable for any level of protection, and no packing is required. For purposes of preservation/packing level marking, the bridge bays shall be marked A/A.

6.10 Subject term (key word) listing.

Bridge
Bridge bay
Bridge bay, type I
Bridge bay, type II
Bridge, floating, ribbon
Bridge, ribbon
Interior bay
Ramp bay
Ribbon bridge

6.11 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project 5420-A369

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.