INCH-POUND

MIL-B-2213D
21 July 1992
SUPERSEDING
MIL-B-2213C(ME)
20 April 1973

MILITARY SPECIFICATION

BRIDGE CONVERSION SET, FIXED BRIDGE:

BAILEY; CONSTRUCTION OF ONE PANEL CRIB PIER,

31 FEET 7 INCHES HIGH, 145-TON

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers structural components of a bridge conversion set, fixed bridge: Bailey; construction of 1 panel crib pier, 31 feet 7 inches in height, 145 ton (SC5420-97-CL-E29).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

FF-B-575	- Bolts, Hexagon and Square.
FF-N-836	- Nut, Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding and Single Ball Seat.
FF-S-111	- Screw, Wood.
FF-T-791	- Turnbuckle.
FF-W-92	- Washers, Flat (Plain).
RR-C-271	- Chains and Attachments, Welded and Weldless.
TT-E-527	- Enamel, Alkyd, Lusterless, Low VOC Content.
TT-P-645	- Primer, Paint, Zinc-Molybdate Alkyd Type.
TT-W-550	- Wood Preservative, Chromated Copper Arsenate Mixuture.
TT-W-571	- Wood Preservation, Treating Practices.
PPP-B-601	- Boxes, Wood, Cleated Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-T-704	- Treatment and Painting of Material.
DOD-P-15328	- Primer Wash, Pretreatment.
MIL-R-52243	- Retainer, Bridge Pin.

STANDARDS

FEDERAL

FED-STD-595	- Colors Used in Government Procurement.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking, and Waterproofing, with Appropriate Test Methods.

(Unless otherwise indicated, copies of federal and military specifications and standards are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government drawings. The following other Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues shall be those cited in the solicitation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

DRAWINGS

ME

D2674	- Bridge, Fixed: Steel, Portable Panel-M2 Widened Roadway (12'-6")(Bailey Type).
D2738	- Portable Panel Bridge (Bailey Type) Parts for Crib Construction.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center. ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 27	- Steel Castings, Carbon, for General Applications.
A 36	- Structural Steel.
A 53	- Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless.
A 108	- Steel Bars, Carbon, Cold-Finished, Standard Quality.
A 183	- Carbon Steel Track Bolts and Nuts.
A 331	- Steel Bars, Alloy, Cold-Finished.
A 513	- Electric-Resistance Welded Carbon and Alloy Steel Mechanical Tubing.
A 519	- Seamless Carbon and Alloy Steel Mechanical Tubing.
A 572	- High Strength Low-Alloy Columbium-Vanadium Steels of Structural Quality.
A 668	- Steel Forgings, Carbon and Alloy, for General and Industrial Use.
D 3953	- Strapping, Flat Steel and Seals.
D 4675	- Selection and Use of Flat Strapping Materials.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

AMERICAN WELDING SOCIETY (AWS)

A5.1	- Carbon Steel Electrodes for Shielded Metal Arc Welding.
A5.18	- Carbon Steel Filler Metals for Gas Shielded Arc Welding.
D1.1	- Structural Welding Code - Steel.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

AMERICAN WOOD-PRESERVERS' ASSOCIATION (AWPA)

C1	- All Timber Products - Preservative Treatment by Pressure-Process.
C2	- Lumber, Timbers, Bridge Ties and Mine Ties - Preservative Treatment Pressure Process.
C14	- Wood for Highway Construction - Preservative Treatment by Pressure Process.

(Application for copies should be addressed to The American Wood-Preservers' Association, P.O. Box 849, Stevensville, MD 21666.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC., AGENT

National Motor Freight Classification Rules.

(Application for copies should be addressed to the American Trucking Association, Inc., ATTN: Traffic Order Section, 2200 Mill Road, Alexandria, VA 22314.)

SOUTHERN PINE INSPECTION BUREAU

Standard Grading Rules for Southern Pine Lumber.

(Application for copies should be addressed to the Southern Pine Inspection Bureau, Box 1170, New Orleans, LA 70150.)

UNIFORM CLASSIFICATION COMMITTEE AGENT

Uniform Freight Classification Rules.

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

WESTERN WOOD PRODUCTS ASSOCIATION

Standard Grading Rules.

(Application for copies should be addressed to the Western Wood Products Association, 522 SW 5th Avenue, Portland, OR 97204.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The structural components shall be in accordance with the following drawings, and as specified (see 6.2):

Drawing D2674-2

BRACE, sway.
PIN, sway brace.

Drawing D2674-5

BOLT, bracing.
BOLT, connector chord.
CLAMP, transom.
FRAME, bracing, bridge.
PIN, connector, panel, 8.313 inches long.
PLATE, tie.
RAKER, side strut.

Drawings D2738-1 through -6

BEARING, crib.
BEARING, junction link.
CAPSILL, crib.
CHESS, junction, M2.
CLAMP, chord.
LINK, junction.
LINK, launching nose, MK II.
POST, junction, span, female.
POST, junction, span, male.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the bridge conversion set. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or the designated representative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Materials. Materials shall be as specified herein and on the drawings. Materials not specified shall be selected by the contractor, and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The bridge conversion set shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the bridge conversion set may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.3.2 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the bridge conversion set may be newly fabricated from recovered materials to the maximum extent practicable, provided the bridge conversion set produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the bridge conversion set.

3.3.3 Structural steel. Structural steel shall conform to ASTM A 36.

3.3.4 Low-alloy structural steel. Low-alloy steel shall conform to ASTM A 572, grade 50.

3.3.5 Steel castings. Steel castings shall conform to ASTM A 27, grade 70-40, full annealed.

3.3.6 Steel bars and rods. Steel bars and rods except for the panel connector pins shall conform to ASTM A 108, UNS G10200.

3.3.7 Steel forgings. Steel forgings shall conform to ASTM A 668, class C, annealed or normalized.

3.3.8 Lumber. The minimum grade of lumber shall be southern pine no. 1 dense or no. 1 longleaf conforming to Standard Grading Rules for Southern Pine Lumber, or lumber shall be Douglas fir dense no. 1 conforming to Standard Grading and Dressing Rules for Lumber. Lumber shall not be painted but shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

be pressure-treated after all cutting has been completed in accordance with TT-W-571, using chromated copper arsenate (CCA) which conforms with TT-W-550. Alternately, the lumber may be treated with the water-borne preservative CCA in accordance with processes described in the American Wood Preservers' Association (AWPA) standards C1, C2, and C14, see figure 1 and 6.5. Such treatment shall result in the minimum net retention of 0.50 lb/cu. feet. Any fasteners that come in contact with the treated wood shall be hot-dip galvanized.

3.4 Welding electrodes. Welding electrodes shall conform to AWS A5.1 or A5.18, classification and size as required for the operation.

3.5 Turnbuckles. Turnbuckles shall conform to FF-T-791, type I, form optional, class 2, self colored, equipped with one jam nut as shown for type III, except that the size be 1.125 by 6 inches.

3.6 Chain. Chain shall conform to RR-C-271, type I, grade C, class 5, style 1; rings, when required, shall be type VI.

3.7 Steel pipe. Steel pipe shall conform to ASTM A 53, black, standard weight, except that the ends shall not be threaded and the hydrostatic test will not be required.

3.8 Steel tubing. Steel tubing shall conform to ASTM A 513, grade MT1020, type 1 or ASTM A 519, grade MT1020, condition HF.

3.9 Wood screws. Wood screws shall conform to FF-S-111, type I, styles 1s and 2s, steel.

3.10 Bolts, nuts, and washers.

3.10.1 Bolts. Bolts except for chord bolts shall conform to FF-B-575, type II, grade 2 steel, UNC-2A.

3.10.2 Nuts. Nuts shall conform to FF-N-836, type II, style 4, grade A steel.

3.10.3 Washers. Washers shall conform to FF-W-92, type A, grade I, class A, zinc plated.

3.10.4 Chord bolts. Chord bolts shall be fabricated from steel conforming to ASTM A 183.

3.11 Panel connector pin. Panel connector pins shall be fabricated from steel conforming to ASTM A 331, grade 4140, quenched-and-tempered and cold-finished to produce a minimum yield strength of 125,000 pounds per square inch (psi), minimum ultimate tensile strength of 140,000 psi, and a minimum elongation of 15 percent in 2 inches.

3.12 Bridge pin retainer. The bridge pin retainer for the connector panel pin shall conform to MIL-R-52243, nominal length 5.563 inches.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

3.13 Transom clamps. Transom clamps shall be either steel forgings or weldments.

3.14 Identification marking. Each component shall be identified in accordance with MIL-STD-130 and shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.15 Treatment and painting. All parts of the structural components except as specified herein shall be treated and painted in accordance with MIL-T-704, using DOD-P-15328 (formula no. 117 for metals), 1 coat of TT-P-645 and 1 coat of TT-E-527 to color number 36231 of FED-STD-595. Transom clamps, pins, bolts, nuts, washers, and threaded surfaces of components shall not be painted but shall be coated with preservative (see 5.1.1).

3.16 Stenciling. The nomenclature, National Stock Number, weight, and cubage shall be stenciled on each major structural component on one side and one end of the part. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be gothic-type capitals and Arabic numerals .750-inch high. Stenciling shall conform to MIL-T-704.

3.17 Workmanship. The fabricated bridge conversion set or component shall be free of sharp edges, slivers, or burrs.

3.17.1 Steel fabrication. Steel used in the fabrication of the structural components shall be free from laminations, kinks, and sharp bends. Steel shall be cut by shearing, sawing, or flame cutting. Burned surfaces of flame-cut material shall be ground or machined to remove ash and cooling checks. The straightening of material shall be done by methods that will not cause injury to the metal. Precautions shall be taken to avoid overheating, and heated metal shall be allowed to cool slowly.

3.17.2 Welders and welding.

3.17.2.1 Welders and welding operators. Before assigning any welder or welding operator to welding work covered by this specification, the supplier shall provide the contracting officer with certification that the welder or welding operator has passed qualification tests as prescribed by either of the following listed codes for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined by the particular code: AWS D1.1 Structural Welding Code - Steel and ASME Boiler and Pressure Vessel Code, Section IX.

In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator. The test results shall be made available for review by the contracting officer or the contracting officer's representative.

3.17.2.2 Welding. The surface of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of the ASME or AWS code. All welded parts shall be free from

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wirebrushed clean. Quality of welds shall be in compliance with AWS D1.1, section 8.15.1.

3.17.2.2.1 Welding jigs. Components shall be assembled in steel jigs or frames and welded while held in position. The jigs or frames shall be of a design that will limit the distortion to an amount that can be removed without changing the physical characteristics of the metal of the parts being welded.

3.17.3 Pin connections. All pin holes shall be accurately drilled or bored full size through steel drilling templates after all welding has been completed. As an alternate the pin holes may be subpunched in the plates or shapes or cored undersize in the castings prior to assembly and welding, and then reamed to full size through steel drilling templates after assembly and welding. The cored or subpunched holes shall have a maximum diameter 0.375-inch less than the hole size specified and shall be accurately located so that the entire surface of the cored or subpunched hole will be cut during reaming. The holes shall be drilled, bored, or reamed straight through the various parts and shall be within the tolerances specified for position and size. Special care shall be taken to keep panel pin holes in line where so noted on the drawings. The steel drilling template shall be equipped with hardened steel drilling bushings accurately located.

3.17.4 Interchangeability. Like components shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

3.17.5 Machine work. Tolerances and gages for metal fits shall conform to the limitations specified herein and on the applicable drawings. Tolerances for positioning of holes and parts shall be referenced from one end or side of the member and shall not be cumulative.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements; however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance or rejection (see 6.4 and 6.5.1).

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article structural component(s) shall be examined as specified in 4.4.2.1 as applicable and for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling for examination. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.2 Examination.

4.4.2.1 Individual. Each structural component shall be inspected for conformance to the dimensions covered by the quality assurance provisions (QAP) shown on the drawings under "Major - 100 percent inspection". Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedures.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

4.5.1 Examination. The structural components shall be examined as specified herein for the following defects:

Major

101. All dimensions designated major on the QAP other than those under 100 percent inspection not as specified (see drawings).
102. Components missing, not interchangeable or not as specified (see 3.1 and 3.17.4).
103. Material not as specified (see 3.3).
104. Materials are not resistant to corrosion or deterioration or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environment as specified (see 3.3.1).
105. Dissimilar metals as specified in MIL-STD-889 are not effectively insulated from each other as specified (see 3.3.1.1).
106. Contractor does not have documentation available for identification of material, material finishes, or treatments (see 3.3.1.2).
107. Workmanship not as specified (see 3.17).
108. Weld defects such as cracks, flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusion with parent metal (see 3.17.2.2).
109. Welders and welding operators not certified as specified (see 3.17.2.1).
110. Welding and welds not as specified (see 3.17.2.2).
111. Components are not interchangeable as required (see 3.17.4).

Minor

201. All dimensions not designated major on the QAP not as specified.
202. Identification marking, incorrect, missing, or illegible (see 3.14).
203. Treatment and painting not as specified (see 3.15).
204. Stenciling not as specified (see 3.16).
205. Machine work not as required (see 3.17.5).

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection of pack.

4.6.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Sample selected in accordance with 4.6.1.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

112. Unpainted metal surfaces requiring a contact preservative in preservative (see 5.1.1).
113. Components of unlike description packed together and shipping containers not as specified for level A or B (see 5.2.1 and 5.2.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

114. Gross weight exceeds the weight limitation of the box for level A or B (see 5.2.1 and 5.2.2).
115. Contents not blocked, braced, anchored, or immobilized in accordance with the referenced document for level A or B (see 5.2.1 and 5.2.2).
116. Strapping not zinc coated for level A (see 5.2.1).
117. Marking illegible, incorrect, or incomplete (see 5.3).

5. PACKAGING

5.1 Preservation (see 6.6).

5.1.1 Unprotected surfaces. Unpainted metal surfaces of components requiring the application of a contact preservative in accordance with MIL-P-116 shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2 Packing. Packing shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A. The components of like description, preserved as specified in 5.1, shall be packed together in close-fitting boxes conforming to PPP-B-621, class 2, style optional, or PPP-B-601, overseas type, style optional. The quantity of components of like description to be packed together shall be determined by the gross weight limitation of the box, in accordance with the applicable box specification. The components shall be blocked, braced, anchored, or otherwise immobilized within the box in accordance with MIL-STD-1186. Box closure shall be in accordance with the appendix to the applicable box specification. Strapping shall be in accordance with ASTM D 3953, type 1 or 2, zinc-coated, size as applicable and ASTM D 4675.

5.2.2 Level B. The components of like description, preserved as specified in 5.1, shall be packed as specified in 5.2.1, except boxes shall be domestic type or class as applicable and strapping is not required to be zinc coated.

5.2.3 Level C. The components shall be packed to assure carrier acceptance and safe delivery to destination at lowest rating in wooden containers complying with Uniform Freight Classification Rules or National Motor Freight Classification Rules.

5.3 Marking. In addition to any special marking specified in the contract or purchase order (see 6.6), marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The structural components are intended for use with standard Bailey bridge parts to make up a panel crib pier and to provide for a flexing action at supports.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DoDISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Component required (see 3.1).
d. When first article is not required for inspection and approval, and the number of units required (see 3.2).
e. Level of preservation and packing required (see 5.1 and 5.2).

6.3 First article. When a first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Quality Assurance Provisions (QAP). The contracting officer should require the supplier to maintain records of all QAP inspections. A suggested paragraph is as follows:

"The supplier shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirements, actual measurements, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

6.5 Sample instructions. An example of an EPA approved set of instructions for the proper handling of CCA (see 3.3.8) is shown on figure 1. Other formats may be utilized provided the instructions included in the format are EPA approved.

6.6 Definitions.

6.6.1 Quality Assurance Provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

6.7 Levels of preservation. Levels of preservation have not been included as the requirements specified are the minimum acceptable for any level of protection. For purposes of preservation/packing level marking, the marking shall be A/A, A/B, or A/C as applicable.

6.8 Subject term (keyword) listing.

Bailey bridge
Bridge connection pin
Panel connection pin
Structural components, bridge

6.9 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activity:
DLA - CS

Project 5420-0168

User activity:
Navy - MC

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.

Consumer Information Sheet

INORGANIC ARSENICAL PRESSURE-TREATED WOOD

(Including: CCA; ACA, and ACZA)

CONSUMER INFORMATION

This wood has been preserved by pressure-treatment with an EPA-registered pesticide containing inorganic arsenic to protect it from insect attack and decay. Wood treated with inorganic arsenic should be used only where such protection is important.

Inorganic arsenic penetrates deeply into and remains in the pressure-treated wood for a long time. Exposure to inorganic arsenic may present certain hazards. Therefore, the following precautions should be taken both when handling the treated wood and in determining where to use or dispose of the treated wood.

USE SITE PRECAUTIONS

Wood pressure-treated with waterborne arsenical preservatives may be used inside residences as long as all sawdust and construction debris are cleaned up and disposed of after construction.

Do not use treated wood under circumstances where the preservative may become a component of food or animal feed. Examples of such sites would be structures or containers for storing silage or food.

Do not use treated wood for cutting boards or countertops.

Only treated wood that is visibly clean and free of surface residue should be used for patios, decks and walkways.

Do not use treated wood for construction of those portions of beehives which may come into contact with the honey.

Treated wood should not be used where it may come into direct or indirect contact with public drinking water, except for uses involving incidental contact such as docks and bridges.

HANDLING PRECAUTIONS

Dispose of treated wood by ordinary trash collection or burial. Treated wood should not be burned in open fires or in stoves, fireplaces, or residential boilers because toxic chemicals may be produced as part of the smoke and ashes. Treated wood from commercial or industrial use (e.g., construction sites) may be burned only in commercial or industrial incinerators or boilers in accordance with state and Federal regulations.

Avoid frequent or prolonged inhalation of sawdust from treated wood. When sawing and machining treated wood, wear a dust mask. Whenever possible, these operations should be performed outdoors to avoid indoor accumulations of airborne sawdust from treated wood.

When power-sawing and machining, wear goggles to protect eyes from flying particles.

After working with the wood, and before eating, drinking, and use of tobacco products, wash exposed areas thoroughly.

If preservatives or sawdust accumulate on clothes, launder before reuse. Wash work clothes separately from other household clothing.

Approved by the U.S. Environmental Protection Agency 9/85

FIGURE 1. An example of an EPA approved set of instructions for proper handling of CCA.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16114:342
Check the source to verify that this is the current version before use.

X-4792

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-B-2213D	2. DOCUMENT DATE (YYMMDD) 920721

3. DOCUMENT TITLE
Bridge Conversion Set, Fixed Bridge: Bailey; Construction of One Panel Crib Pier, 31 Feet 7 Inches High, 145-Ton

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (if applicable) (2) AUTOVON	7. DATE SUBMITTED

8. PREPARING ACTIVITY

a. NAME Geraldine F. Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3468 (2) AUTOVON 654-3468
c. ADDRESS (Include Zip Code US Army Belvoir RDE Center ATTN: STRBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:34Z
Check the source to verify that this is the current version before use.