MIL-C-2233E
10 August 1984
SUPERSEDING
MIL-C-2233D
18 August 1970

MILITARY SPECIFICATION

CABINET, DOUGH PROOFING; INSULATED, PORTABLE, 36 PAN CAPACITY, FOR MOBILE FIELD BAKERY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This document covers an electrically heated, portable, dough proofing cabinet.

2. APPLICABLE DOCUMENTS

* 2.1 Government documents. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-A-200/9	-	Aluminum Alloy Bar, Rod, Shapes, and Tube, Extruded, 6063
QQ-A-250/8	-	Aluminum Alloy 5052, Plate and Sheet
QQ-B-654	-	Brazing Alloys, Silver
TT-E-529	-	Enamel, Alkyd, Semi-Gloss

Beneficial comments (recommendations, additions, deletions) and any other pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research and Development Center, Natick, MA 01760-5014 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 7320

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

SCREWS SHALL BE TYPE

TT-P-1757	-	Primer Coating, Zinc Chromate, Low Moisture Sensitivity
WW-T-700/6	-	Tube, Aluminum Alloy, Drawn, Seamless 6061 and 6062
MMM-A-1617	-	Adhesive, Rubber Base, General Purpose

MILITARY

MIL-B-2316	-	Bakery Equipment, Including Units, Assemblies, Repair Parts and Tools, Preparation for Delivery Of
MIL-C-5541	-	Chemical Film and Chemical Film Material for Aluminum and Aluminum Alloy
MIL-R-7885	-	Rivets; Blind, Structural, Pull-Stem and Chemically Expanded
MIL-STD-7947	-	Steel, Sheet and Strip (1095) Aircraft Quality

STANDARDS

FEDERAL

FED-STD-595	-	Colors

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-130	-	Identification Marking of U.S. Military Property

PUBLICATIONS

DEPARTMENT OF THE ARMY TECHNICAL MANUALS

TM-10-7360-201-0	-	Operators' Manual, Bakery Plant, Mobile
TM-10-410	-	Bread, Baking

DRAWINGS

US ARMY NATICK RESEARCH AND DEVELOPMENT CENTER

5-11-966	-	Cabinet, Dough Proofing, Insulated, Portable, 36 Pan Capacity - Assembly Complete
5-11-967	-	Frame Assembly and Details
5-11-968	-	Heater Rack, Tray and Door Support Assemblies and Details
5-11-969	-	Panel and Bumper Assemblies and Details
5-11-970	-	Door Assembly and Miscellaneous Details
5-11-971	-	Control Box and Heat Rack, Wiring Assemblies and Details
5-11-972	-	Lamp Box Assembly and Details

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

(Copies of documents required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

NATIONAL SANITATION FOUNDATION (NSF)

Listing of Food Service Equipment

Standard No. 4 - Cooking and Hot Food Storage Equipment

(Application for copies should be addressed to the National Sanitation Foundation, NSF Building, Ann Arbor, MI 48105.)

UNDERWRITERS LABORATORIES, INC.

(Application for copies should be addressed to the Underwriters Laboratories, Inc., 333 Pfingsten Road, Northbrook, IL 60062.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 167 - Stainless and Heat-Resisting Chrominum - Nickel Plate, Sheet and Strip

A 507 - Steel, Sheet and Strip, Alloy, Hot Rolled and Cold Rolled, General Requirements for

D 1056 - Flexible Cellular Materials - Sponge or Expanded Cell Rubber

D 1565 - Standard Specification and Tests for Flexible Foams made from Polymers or Copolymers of Vinyl Chloride

D 1621 - Compressive Properties of Rigid Cellular Plastics

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Technical society and technical association documents are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

* 2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 20261O-16T14:36Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Alternate components. Components offered as equivalent to components specified herein and on the referenced documents as a specific manufacturer's part number or equal shall be functionally equal, of equal or better quality, with the manufacturer's part number identified. The incorporation and inclusion of such a component in the design of the specified end product shall not require modification to any other specified component and shall not reduce ease of maintenance to it or any other component, unless such modification is specifically approved by the contracting officer. Prior to manufacture of the preproduction sample, the contractor shall submit for the contracting officers' approval a list identifying each proposed alternate component, together with proof that each listed component complies with the requirements specified above. The contracting officer, at his option, may require a physical sample of the proposed substitution. Approval of the submitted listing, together with necessary supporting data, authorizes the commencement of preproduction sample manufacture and does not relieve the contractor of the responsibility that these components perform in accordance with specified requirements when incorporated into the end product.

3.2 First article. When specified, a sample shall be subjected to first article inspection (see 4.3, 6.2, and 6.3).

* 3.2.1 Inspection comparison testing sample. When specified (see 6.2), the contractor shall furnish a sample for comparison inspection and approval (see 4.4 and 6.6).

3.3 Standard component. Each component of the dough proofing cabinet (except Military Standard components), shall be the current standard product of its manufacturer except for any changes necessary for compliance with the requirements of this document. No obsolete or discontinued items shall be used.

3.4 Standards compliance. Electrical components of the dough proofing cabinets delivered under this document shall conform to the requirements of applicable UL Standards.

3.4.1 UL certification. Prior to the approval of the preproduction sample, if one is submitted, or prior to the approval of the first shipment, the contractor shall submit to the contracting officer or his authorized representative satisfactory evidence that all electrical components he proposes to furnish under this document meet the requirements of applicable UL Standards. Acceptable evidence of meeting the requirements of the applicable UL Standards shall be the UL Listing Mark, or a certified test report from a recognized independent testing laboratory acceptable to the Government, indicating that the electrical components have been tested and conform to the requirements of applicable UL Standards.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

3.4.2 NSF certification. The contractor shall submit satisfactory evidence to the contracting officer or his authorized representative that the dispenser he proposes to furnish under this document meets the applicable requirement of NSF Standard No. 4 as follows:

(1) Listing in the current edition of the NSF "Listing of Food Service Equipment" or display of the NSF seal on the finished dispenser shall be submitted prior to approval of the first article, if one is submitted, or prior to commencing production, or

(2) A certification for the dispenser issued by NSF under their special one-time evaluation certification service shall be submitted prior to approval of the first article, if one is submitted, or prior to commencing production, or

(3) A certified test report from a recognized independent testing laboratory acceptable to the medical department of the service for which the dispensers are being procured, indicating that the dispensers have been tested and conform to NSF Standard No. 4 shall be submitted prior to approval of the first article, if one is submitted or prior to commencing production.

3.5 Materials (see 6.4) and components. Material and components not definitely specified shall be of the quality normally used by the manufacturer for his dough proofing cabinets. Unless otherwise specified herein or on referenced drawings commercial mill tolerances shall apply to metal thicknesses and diameters.

3.5.1 Carbon steel sheet and strip. Carbon steel sheet and strip shall conform to the requirements of hot rolled, commercial quality or cold rolled, commercial quality of ASTM A 507.

3.5.2 Spring steel sheet or strip. Spring steel strip shall conform to the requirements of MIL-S-7497.

* 3.5.3 Corrosion-resisting and stainless steel plate, sheet and strip. Corrosion-resisting and stainless steel plate, sheet and strip shall conform to type 302 or 304 of ASTM A 167.

3.5.4 Aluminum alloy.

3.5.4.1 Plate and sheet. Aluminum alloy plate and sheet shall conform to the requirements for alloy 5052-H32 of QQ-A-250/8.

3.5.4.2 Bar and shapes. Aluminum alloy bar and shapes shall conform to the requirements for alloy 6063-T5 of QQ-A-200/9.

3.5.4.3 Tube. Aluminum alloy tube shall conform to the requirements for alloy 6061-T6 of WW-T-700/6.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

3.5.5 Blind rivets. Blind rivets shall be the pull-stem, self-plugging type with protruding or flush heads conforming to the requirements for type II, class 1 or 2 of MIL-R-7885.

3.5.6 Adhesive. Adhesive shall conform to the requirements for type II of MMM-A-1617.

3.5.7 Sealant. The sealant shall be commercial type nontoxic, translucent, nontinted silicone rubber and shall have no adverse effect on the health of personnel when used for its intended purpose. Questions pertinent to this effect shall be referred by the contracting activity to the appropriate departmental medical service who will act as an advisor to the contracting activity (see 4.5.1.2).

3.5.8 Silver solder. Silver solder shall conform to class 5 of QQ-B-654.

3.5.9 Primer. Primer shall conform to TT-P-1757.

3.5.10 Enamel. Enamel shall conform to TT-E-529 and shall be olive drab conforming to color number 24087 of FED-STD-595.

3.5.11 Sponge rubber. Sponge rubber shall conform to SC012 of ASTM D1056.

3.5.12 Assembly hardware. Unless otherwise specified herein, assembly hardware, nuts, bolts, screws, washers and rivets shall be standard commercial items conforming to the materials, types, and sizes specified on the applicable referenced drawings.

3.5.13 Rubber, cellular insulation. The insulation shall be expanded, close cell, rubber hardboard with a water absorption rate not greater than 10 percent; a density of not less than 4 pounds and not more than 6 pounds per cubic foot; and a compressive strength of not less than 40 pounds per square inch when tested as specified in 4.5.1.1.

3.5.14 Strip heater. The strip heater shall be 500-watt and shall be for operation on a 208-volt system. The strip heater shall be nominal 1-1/2 inches wide, 3/8 inch thick, and 23-3/4 inches overall length. Flat mounting tabs shall be provided on each end of the heater with a 5/16-inch diameter by 1/2-inch long slotted hole in each tab located on 22-3/4-inch centers. The strip heater shall be provided with a chromium steel sheath and shall have a two-bolt terminal at one end.

3.5.15 Wiring cable. The wiring cable shall be hard service cord type SO, neoprene covered, 600 volts, Number 12 American Wire Gauge (A.W.G.), 2 conductors flexible, stranded, and ungrounded. The connector used in passing the cable from the control box through the wall of the proofing cabinet (see Drawing 5-11-971) shall be of the threaded type;watertight, with a rubber compression grommet.

Source: https://assist.dla.mil -- Downloaded: 2026l0-16T14:36Z
Check the source to verify that this is the currentversion before use.

3.5.16 Thermostat. The thermostat shall be rated at 25 amperes and shall be designed for operation on a 208-volt system. The thermostat shall be of the direct acting bulb type having a normally closed circuit, which opens on temperature rise. The thermostat shall include a temperature selector and indicator plate. The indicator plate shall have an "OFF" position and a temperature range of at least 60°F to 150°F when tested as specified in 4.6.1.

3.5.17 Power cable with connecting plug. The power cable shall be as specified in 3.5.15, except it shall be 2 conductor with ground. The cable shall be 25 feet long. One end of the cable shall be connected to a plug, equal and interchangeable with that of Anderson Type NG, Catalogue C-2643-2, or equal. The rubber cable packing of the plug shall be used with a nominal 0.60-inch diameter cable.

* 3.6 Design and construction. The dough proofing cabinet and all components and assemblies of the cabinet shall be of the design and construction specified herein and on Drawing Nos. 5-11-966 through 5-11-972 inclusive. The internal temperature of the cabinet shall be thermostatically controlled. The thermostat shall be located in the control box and shall maintain the internal temperature of the cabinet within ± 5°F of the thermostatic control setting when tested as specified in 4.6.1. The cabinets shall operate without evidence of malfunction and shall satisfactorily proof (see 6.5) one full load of bread dough when tested as specified in 4.6.2.

3.6.1 Panels. Panels shall have an inner frame constructed from square aluminum alloy tube specified in 3.5.4.2 or 3.5.4.3. The interior of the panel shall be filled with cellular rubber insulation hardboard specified in 3.5.13. The panels shall be covered with aluminum alloy sheet conforming to 3.5.4.1. The insulation board shall be bonded to the aluminum alloy sheets with the adhesive specified in 3.5.6.

3.6.2 Doors. When tested as specified in 4.6.1 the doors shall operate without binding and the locking devices shall lock when the doors are closed. The gasket shall be fabricated from sponge rubber specified in 3.5.11. The adhesive for cementing the gasket to the metal shall be as specified in 3.5.6.

3.6.3 Hinges. Hinges shall be a plain continuous type and of the size specified on the drawings, and shall be fabricated of the stainless steel specified in 3.5.3.

3.6.4 Trays. Trays shall be fabricated of the stainless steel specified in 3.5.3 and conform to the dimensions shown on Drawing 5-11-968.

3.6.5 Base. The base shall be fabricated of aluminum alloy angle specified in 3.5.4.2 and shall be welded, constructed, and reinforced as shown on Drawing 5-11-970.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

3.6.6 Lamp box. The lamp box shall contain an indicator lamp to indicate when the heater rack is energized.

3.6.7 Electrical characteristics. The dough proofing cabinet shall operate on nominal 208-volt, 60 hertz, single-phase electric power.

3.7 Identification marking. Each proofing cabinet shall have a nameplate fabricated of the stainless steel specified in 3.5.3 and marked with the manufacturer's name, trade name, or trademark identifiable with said manufacturer. Marking shall be applied in accordance with MIL-STD-130. The nameplate shall be fastened to the control box door as shown on Drawing 5-11-966.

3.8 Instruction plate. Each cabinet shall have an instruction plate fabricated of the stainless steel specified in 3.5.3 and located and fastened to the control box door as shown on Drawing 5-11-966. The following information shall be indented or embossed on the inspection plate:

OPERATING INSTRUCTIONS

1. Water pans must be one-half full of water.
2. Power cable must be connected to one of four top receptacles of the electrical control panel on the dough mixer and make-up trailer.
3. Doors must be closed.
4. Set thermostat for desired operating temperature and allow cabinet to warm up.
5. Cabinet is ready for use when correct operating temperature is indicated on the thermometer.
6. After use, disconnect power cable and store cable on the cable reel inside control box door.

3.9 Wiring diagram. A copy of the wiring diagram shown on Drawing 5-11-971 shall be attached to the inside surface of the control panel door. The diagram shall be covered with one coat of clear shellac, clear varnish or other clear waterproofing material in accordance with the manufacturer's standard practice.

3.10 Finish.

3.10.1 Cleaning and priming. All exterior metal surfaces of the dough proofing cabinet shall be cleaned in accordance with the cleaning instructions of MIL-C-5541 and spray coated with the primer specified in 3.5.9. When tested as specified in 4.5.2.2 the dry film thickness of the primer shall be between 0.6 and 1.0 mil.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

be as shown on the applicable drawings listed in ... Welding methods shall

3.10.2 Enameling. After cleaning and priming as specified in 3.10.1 and after the primer has dried, the exterior surfaces of the dough proofing cabinet shall be covered with one coat of the enamel specified in 3.5.10. The combined dry film thickness of the enamel and the primer shall be not less than 1.2 nor more than 2.0 mils.

3.11 Workmanship. The finished dough proofing cabinets shall be complete and clean and free of scratches, dents, breaks, sharp edges, sharp corners, deformities, burrs, and slivers.

3.11.1 Welding and brazing. Fusion welds and brazes shall be continuous and sound and free of slag, pits, buildups, and undercuts. All rough areas shall be ground smooth and all scale and flux shall be removed. Spot welds shall be sound and free of discoloration, spatter, or burn through. All welding shall be accomplished prior to applying the primer specified in 3.10.1.

3.11.2 Riveting. Rivets shall be tight and rivet heads and peened or expanded ends shall be in full contact with the joined metal surfaces. There shall be no empty rivet holes or broken rivets. All riveting shall be accomplished prior to applying the primer specified in 3.10.1.

3.11.3 Soldering. Soldered joints shall be completely filled and wiped smooth after soldering. All flux and spatter shall be removed. All soldering shall be accomplished before applying the primer specified in 3.10.1.

3.11.4 Adhesive and sealing compound. Adhesive and sealing compounds shall be uniformly applied and all excesses shall be removed.

3.11.5 Threaded fasteners. Threaded fasteners shall be drawn tight and shall be free of stripped or crossed threads. There shall be no missing fasteners or bolts.

3.11.6 Electric wiring. Electric wiring shall be free of loose connections or terminals and free of cuts and abrasions and excessive stripping of insulation. There shall be adequate slack between connections and terminals.

3.11.7 Enameling. The enamel finish coat shall be continuous, smooth, and uniform in appearance and shall be free from wrinkles, streaks, drops, orange peel, runs, and drips. There shall be no areas of poor or no coverage and the finish coat shall be free of scratches, rough areas, and imbedded foreign matter.

Source: https://assist.dla.mil -- Downloaded: 20261O-16T14:36Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

* 4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Comparison sample inspection (see 4.4).
c. Quality conformance inspection (see 4.5).

* 4.3 First article inspection. When a first article is required (see 6.2), it shall be examined as specified in 4.6.1 and 4.6.2. The presence of any defects or failure to pass any test shall be cause for rejection of the first article.

4.4 Comparison sample inspection. When a comparison sample is required (see 6.2), it shall be examined for the defects specified in 4.5.3 and 4.5.4 and tested as specified in 4.6.1 and 4.6.2. The presence of any defect or failure to pass any test shall be cause for rejection of the comparison sample.

4.5 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.5.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents, unless otherwise excluded, amended, modified, or qualified in this document or applicable purchase document.

4.5.1.1 Insulation. The insulating material shall be tested for water absorption in accordance with ASTM D 1056; density in accordance with ASTM D 1565; and compressive strength in accordance with ASTM D 1621. The lot shall be the number of square feet of insulation offered for inspection at one time. The sample unit shall be 3 square feet of the insulation. The inspection level shall be S-1 and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 2.5.

4.5.1.2 Toxicological data and formulations. The contractor shall furnish the toxicological data and formulations required to evaluate the safety of the material for the proposed use (see 3.5.7).

Source: https://assist.dla.mil -- Downloaded: 202610-16T14:36Z
Check the source to verify that this is the current version before use.

4.5.2 In-process inspection.

4.5.2.1 In-process examination. In-process examination shall be made of the following operations to establish that no deviations are made from the specified requirements. When ever nonconformance is noted, corrections shall be made to the process and items affected:

(a) Cleaning as specified in 3.10.1.
(b) Welding and brazing requirements as specified in 3.11.1.
(c) Riveting requirements as specified in 3.11.2.
(d) Soldering requirements as specified in 3.11.3.

4.5.2.2 Intermediate test of primer thickness. After application and drying of the primer coat and prior to application of the finish coat, the thickness of the primer coat shall be measured to determine compliance with the dry film thickness requirements of 3.10.1. The lot shall consist of all primed and dry cabinets offered for inspection at one time. The sample unit shall be one primed and dry cabinet. The inspection level shall be S-2. Whenever nonconformance is noted correction shall be made to the affected items and the lot in process.

* 4.5.3 End item visual examination. The end item shall be examined for the defects listed in table I. The lot size shall be expressed in units of dough proofing cabinets. The sample unit shall be one dough proofing cabinet. The inspection level shall be II and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 2.5 for major defects and 6.5 for total (major and minor combined) defects.

TABLE I. End item visual defects

Examine	Defects	Classification Major	Minor
Finish	Dirty		X
	Not color specified, not type specified, unfinished areas	X	
	Not smooth, not continuous, not uniform, rough areas		X
	Areas of poor coverage (primer shows through)		X
	Wrinkles, streaks, drops or drips, orange peel, runs, imbedded foreign matter		X

Source: https://assist.dla.mil -- Downloaded: 202610-16T14:36Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defects	Classification Major	Classification Minor
Construction and workmanship	Component missing or not as specified	X	
	Scratches, dents		X
	Sharp edges, sharp corners, deformities, burrs, slivers	X	
Fusion welds and brazing	Not continuous, not sound, not ground smooth where required	X	
	Pits, buildups, undercuts	X	
	Dirty, scale or flux deposits not removed		X
Spot welds	Discoloration, spatter		X
	Burn through, unsound	X	
Soldering	Joints not completely filled, not wiped smooth	X	
	Solder spatter not removed		X
	Flux and flux spatter not removed	X	
Adhesive and sealing compounds	Not uniformly applied, excess not removed		X
Threaded fasteners	Missing, crossed or stripped threads	X	
	Loose		X
Electric wiring	Loose connections or terminals	X	
	Inadequate slack, cuts, abrasions, excessive stripping of insulation		X
Rivets	Missing, not type specified, loose, not in full contact with joined metal surfaces, broken	X	

Source: https://assist.dla.mil -- Downloaded: 202610-16T14:36Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor
Wiring diagram	Missing, incorrect	X	
	Not covered with clear shellac, varnish, or waterproofing material		X
	Not attached to inside surface of control panel door	X	
Instruction plate	Not located as specified	X	
	Instructions not as specified	X	
Marking for identification	Missing, incorrect, illegible or incomplete		X

* 4.5.4 End item dimensional examination. The end item shall be examined for conformance to dimensions specified on the drawings. Any dimension not as specified shall be classified as a defect. The lot size shall be expressed in units of dough proofing cabinets. The sample unit shall be one dough proofing cabinet. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

* 4.5.5 End item testing. The end item shall be tested as specified in 4.6.1. The lot size shall be expressed in units of dough proofing cabinets. The sample unit shall be one dough proofing cabinet completely assembled in accordance with the manufacturer's instructions. Failure of a test shall be recorded as a defect. The inspection level shall be S-2. Any nonconformance with specified requirements shall be cause for rejection of the lot.

* 4.5.6 Examination of preparation for delivery. An examination shall be made to determine that preparation for delivery as specified in section 5 is in accordance with MIL-B-2316.

4.5.7 Standards compliance. Proof of compliance with the requirement of 3.4 shall be submitted to the Government representative.

4.6 Methods of inspection.

4.6.1 Operational test. The dough proofing cabinet shall be connected to a nominal 208 volt, 60 Hertz, single phase electric current. The water pans shall be one-half full of water and in place. The thermostatic control shall be in the "OFF" position. A thermometer, graduated from 60° to 160°F. with not more than 1 degree divisions and certified accurate to ± 2 degrees shall be suspended inside the cabinet near the actuating remote thermostatic control. The thermometer shall be suspended in such a manner as to not be in

Source: https://assist.dla.mil -- Downloaded: 202610-16T14:36Z
Check the source to verify that this is the current version before use.

contact with any metal parts of the dough proofing cabinet. The doors shall be closed. The thermostatic control shall be set at 65°F. The cabinet shall be allowed to heat until the indicator lamp goes out. Allow 5 minutes for stabilization and then check the reading on the suspended thermometer. Repeat this process with the thermostatic control set at 95°F and again at 150°F to determine compliance with the operation and temperature range requirements of 3.5.16 and accuracy requirements of 3.6. During this test all doors shall be opened and closed and locked and unlocked to determine compliance with 3.6.2. Any nonconformance with specified requirements shall constitute failure of this test.

* 4.6.2 Performance test. Connect the dough proofing cabinet to applicable electric power and operate in accordance with the operating cycle instructions of TM-10-7360-201-10. A full load of 36 pans each containing 6 doughs prepared and molded in accordance with TM-10-410 shall be processed. The proofed dough shall be examined to determine compliance with the satisfactory proofing requirements of 3.6. All doors and locking devices shall be observed during the entire period of the test to determine compliance with the nonbinding and locking device operation requirements of 3.6.2. Any nonconformance with specified requirements shall constitute failure of this test.

5. PACKAGING

5.1 Preservation, packaging, packing and marking. Preservation, packaging, packing and marking for level A, B, or C shall be in accordance with MIL-B-2316 (see 6.2).

6. NOTES

6.1 Intended use. The dough proofing cabinet is a component of the mobile field bakery and is intended for the proofing of dough prior to baking.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this document.
b. When a first article is required (see 3.2, 4.3 and 6.3).
c. Selection of applicable levels of preservation and packaging and packing (see 5.1).
d. When inspection comparison testing sample is required (see 3.2.2, 4.4 and 6.6).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample or initial production sample. The first article should consist of one unit. The contracting officer should include specific instructions in all acquisition documents regarding arrangements for inspection and approval of the first article.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

contracting officer's preproduction sample. The contractor shall submit for the

* 6.4 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the document (see 3.4).

* 6.5 Definition. Panned loaves shall be considered to be satisfactorily proofed when the loaves have risen approximately one-half inch above the tops of the pans.

* 6.6 Inspection comparison test. When a comparison test sample is required, the contracting officer should include specific instructions in all procurement instruments regarding arrangements for inspection and approval of the comparison test sample.

* 6.7 Contract data requirements. Any data items to be delivered under any contract for items covered by this document should be specifically called for in the contract in accordance with the applicable regulations of the contracting activity.

6.8 Changes from previous issue. The margins of this document are marked with an asterisk (*) to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodians:

Army - GL
Navy - SA
Air Force - 99

Review activities:

Army - MD
Navy - MC
Air Force - 84
DLA - GS

Preparing activity:

Army - GL

Project No. 7320-0745

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
US Army Natick Research and Development Center
Natick, Massachusetts 01760-5014

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300
STRNC-ES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick Research and Development Center
ATTN: STRNC-ES
Natick, MA 01760-5014

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL–C–2233E	Cabinet, Dough Proofing; Insulated, Portable, 36 Pan Capacity, for Mobile Field Bakery

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 1426 82 MAR

PREVIOUS EDITION IS OBSOLETE.

NATICK OP, 1 Apr 84

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T14:36Z
Check the source to verify that this is the current version before use.