MIL-C-55126D(CR)

18 September 1980
SUPERSEDING
MIL-C-55126C(EL)
5 AUGUST 1970

MILITARY SPECIFICATION
CONTROLS, INTERCOMMUNICATION SET C-2296( )/VRC, C-2297( )/VRC, C-2298( )/VRC and CONTROL, RADIO SET C-2299( )/VRC

This specification is approved for use by Communication Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers four types of control units for use in vehicular communication systems, as follows: (See 6.1 and 6.7)

(a) Control, Intercommunication Set C-2296( )/VRC provides remote control of Receiver-Transmitter RT-246( )/VRC and intercom facilities to other control units.

(b) Control, Intercommunication Set C-2297( )/VRC is used in a vehicular communication system and controls an external control unit.

(c) Control, Intercommunication Set C-2298( )/VRC is used in vehicular communication system and performs various functions.

(d) Control, Radio Set C-2299( )/VRC is a compact control unit for use in vehicular communication systems.

1.2 Only the control set(s) specified in the bid request and contract shall be furnished by the contractor.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Communications Research and Development Command, ATTN: DRDCO-CM, Fort Monmouth, New Jersey 07703, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 5820

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids, or request for proposal, form a part of this document to the intent specified herein.

SPECIFICATIONS

FEDERAL

NN-P-71	Pallet, Material Handling, Wood, Stringer, 2 Way and 4 Way (Partial)
PPP-B-20	Bag, Cotton
PPP-T-45	Tape, Gummed, Paper, Reinforced and Plain, for Sealing and Securing
PPP-T-76	Tape, Packaging Paper (For Carton Sealing)
PPP-T-0097	Tape, Packaging Industrial, Filament Reinforced
PPP-P-291	Paperboard, Wrapping and Cushioning
PPP-F-320	Fiberboard, Corrugated and Solid, Sheet Stock (container Grade) and Cut Shapes
PPP-T-495	Tube, Mailing and Filling
PPP-B-566	Box, Folding, Paperboard
PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, Nailed and Lock Corner
PPP-B-636	Box, Shipping, Fiberboard
PPP-B-640	Box, Fiberboard, Corrugated, Triple-wall
PPP-S-760	Strapping, Non-metallic (And Connectors)
PPP-C-843	Cushioning, Material, Cellulosic
QQ-S-781	Strapping, Steel, and Seals

MILITARY

MIL-P-116	Preservation-packaging, Methods of
MIL-S-901	Shockproof Equipment, Class HI (High Impact), Shipload
MIL-I-6869	Impregnants for Aluminum and Magnesium
MIL-P-11268	Parts, Materials, and Processes Used in Electronic Equipment
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Electronic Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

STANDA

MILI

MI D-105	Sampling Procedures and Tables for Inspection by Attributes
MII TD-109	Quality Assurance Terms and Definitions
MII STD-129	Marking for Shipment and Storage
MIL STD-147	Palletized Unit Loads 40 inch by 48 inch 4-Way Partial and 4-Way Pallets
MIL-STD-210	Climatic Extremes for Military Equipment
MIL-STD-252	Wired Equipment, Classification Visual and Mechanical Defect
MIL-STD-276	Impregnation of Porous Nonferrous Metal Castings
MIL-STD-280	Definition of Item Levels, Item Exchangeability, Models, And Related Terms
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-810	Environmental Test Methods
MIL-STD-1188	Commercial Packaging of Supplies and Equipment

DRAWINGS

ELECTRONICS COMMAND

SC-DL-415185	Control, Intercommunication Set C-2299( )/VRC
SC-DL-415220	Control, Intercommunication Set C-2297( )/VRC
SC-DL-415240	Control, Intercommunication Set C-2296( )/VRC
SC-DL-415260	Control, Intercommunication Set C-2298( )/VRC
SC-A-324072	Test Procedure for Testing A80 Module

(Copies of specification, standards, and drawings required by supplier in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Construction. The units shall be constructed in accordance with the applicable Drawing and Data List as follows, and the requirements of this specification.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

UNIT	DRAWING and DATA LIST
C-2296( )/VRC	SC-DL-415240
C-2297( )/VRC	SC-DL-415220
C-2298( )/VRC	SC-DL-415260
C-2299( )/VRC	SC-DL-415185

3.2 First Article. The Contractor shall furnish five First Article samples of units on order for approval, provided the invitation for bids and the contract requires samples. (See 4.3)

3.3 Parts, Materials, and Processes; General. In addition to the requirements of this specification, the requirements of MIL-P-11268 including the selection requirements therein, shall apply.

3.4 Finish, Protective. Equipment shall be given protective finish in accordance with Specification MIL-F-14072. This includes finish of hardware, such as handles, hinges, screws, etc, and necessary touch up after mounting. The final paint film on Type I surfaces shall be forest green, lusterless enamel.

3.5 Marking.

3.5.1 General. Marking shall conform to Specification MIL-M-13231. (See 4.4). Front panel marking shall be Group I as described in that specification.

3.5.2 Visibility. Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.5.3 Serial Numbers. The following items shall have serial numbers:

(a) Control, Intercommunication Set C-2296( )/VR.

(b) Control, Intercommunication Set C-2297( )/VRC

(c) Control, Intercommunication Set C-2298( )/VRC

(d) Control, Radio Set C-2299( )/VRC

3.6 Die Castings (See 4.4).

3.6.1 Quality of Die Castings. Quality of die castings shall be as follows:

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

(a) Surface condition shall be clear, dry and free from chips.

(b) Cast surface finish shall be of a painting grade which allows some streaks and chill marks which can be covered and hidden by paint.

(c) Flash must be removed by grinding of filing.

(d) The casting, after impregnation, shall be air tight, and no leakage shall be allowed under a pressure of 10 psi gage.

(e) Flatness shall be as specified in the government furnished drawings.

(f) Dimensions shall be as specified in the government furnished drawings.

3.6.2 Impregnation of Aluminum Die Castings. All aluminum sand and die castings shall be impregnated in accordance with Standard MIL-STD-276 using impregnating material Type II per Specification MIL-I-6869. Castings which have been impregnated shall be marked "IMP". The impregnation shall be to correct general seepage only and shall not be used to correct poor foundry techniques or significant porosity (See 4.4).

3.7 Service Conditions. The equipment shall meet the following service conditions:

3.7.1 Temperature. During the testing, as specified in 4.13.1.1 and 4.13.1.2, measurements shall be taken with the equipment operating with 22-Volt input and with 30-Volt input and the equipment shall meet the following requirements:

PARAGRAPH	MEASUREMENT
3.9.3	Audio output power
3.9.7	Distortion

After testing, the equipment shall meet full specification performance for these measurements.

3.7.2 Humidity (Moisture-Resistance). During testing as specified in 4.13.2, the equipment shall meet the following requirements:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

PARAGRAPH	MEASUREMENT
3.9.3	Audio output power
3.9.7	Distortion

After testing, the equipment shall meet full specification performance for these measurements.

3.7.3 Altitude (elevation). The equipment shall meet full specification performance for the following both during and after testing as specified in 4.13.3:

PARAGRAPH	MEASUREMENT
3.13	Operational Inspection

3.7.4 Vibration and Shock.

3.7.4.1 Vibration, Internal. The equipment shall withstand vibration associated with vehicular transport as tested in accordance with para. 4.13.4. There shall be no physical damage and the equipment shall meet the requirements of para. 4.16.

3.7.4.2 Shock. The equipment shall be capable of meeting the requirements of Table I.

TABLE I - SHOCK

PARAGRAPH HEADING	PARAGRAPH	PERFORMANCE AFTER TEST
Shock, Basic Design	4.13.5	Specified performance (Note A). No physical damage.
Shock; ballistic	4.13.6	Operable (Note A). Any physical damage shall be minor only, as classified in MIL-STD-252.

NOTE A: The equipment shall meet the requirements of paragraph 4.16.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

3.7.5 Immersion. The equipment shall show no evidence of leakage after it is tested as specified in 4.13.7.

3.8 Preconditioning. (See 4.6).

3.8.1 Bounce Preconditioning. The equipment shall be capable of meeting the requirements herein, without subsequent processing, after subjection to the bounce preconditioning of 4.6.1.

3.8.2 Burn-in (debugging). Each Control, Intercommunication Set on order shall be subjected to a burn-in operation of 24 hours at 25.5 volts dc input. The last six hours of the 24 hour burn-in shall be failure free. Control, Intercommunication Set shall meet the requirements specified herein, without subsequent processing after subjection to paragraph 4.6.2.

3.9 Electrical Requirements for C-2296( )/VRC.

3.9.1 Input Voltage Range. The control unit shall be capable of meeting full specification requirements when operating from a 22 to 30 Volt DC source (See 4.9.6).

3.9.2 Microphone Amplifier Output Circuit. This circuit shall have an output impedance of 1200 ohms minimum when measured in accordance with 4.9.1.

3.9.3 Microphone Amplifier Audio Output Power. The output level shall be .22 v $\pm$ 2 db into a 150 ohm load when measured in accordance with 4.9.2.

3.9.4 Microphone Amplifier Input Circuit. This circuit shall have an impedance of 150 ohm $\pm$ 15% when measured in accordance with 4.9.7.

3.9.5 Volume Control. The volume control located on the bottom of the control unit shall simultaneously vary the output levels. At minimum setting of the control, there shall not be more than .02 mw at either the headphone output or the speaker output. At maximum setting of the control, the output levels shall be a minimum of 90 mw when tested in accordance with 4.9.3.

3.9.6 Audio Response. The audio response of the microphone amplifier shall be within $\pm$ 2 db of 1000 Hz reference from 500 to 3000 Hz when tested in accordance with 4.9.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

3.9.7 Distortion. When measured in accordance with 4.9.5 the overall total harmonic distortion shall not exceed 2 percent.

3.9.8 Control Function. The C-2296( )/VRC control unit shall provide the following functions:

3.9.8.1 Signalling of Operator Located at C-2297( )/VRC. Test in accordance with 4.9.8.

3.9.8.2 Controls Radio Transmission. Test in accordance with 4.9.9.

3.9.8.3 Controls Interphone. Test in accordance with 4.9.10.

3.9.8.4 Provides Line Connections. Test in accordance with 4.9.11.

3.10 Electrical Requirements for C-2297( )/VRC.

3.10.1 Input Voltage Range. Same as 3.9.1.

3.10.2 Microphone Amplifier Output Circuit. Same as 3.9.2.

3.10.3 Microphone Amplifier Audio Output Power. Same as 3.9.3.

3.10.4 Microphone Amplifier Input Circuit. Same as 3.9.4.

3.10.5 Volume Control. Same as 3.9.5.

3.10.6 Audio Response. Same as 3.9.6.

3.10.7 Distortion. Same as 3.9.7.

3.10.8 Control Functions. The C-2297( )/VRC control unit shall provide the following functions:

3.10.8.1 Receives Signal From External Control Box. Test in accordance with 4.10.8.

3.10.8.2 Connects External Control Box Into System. Test in accordance with 4.10.9.

3.10.8.3 Selects Monitoring Functions. Test in accordance with 4.10.10.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

3.10.8.4 Selects Transmission Function. Test in accordance with 4.10.11.

3.10.8.5 Signalling. The operator at C-2297( )/VRC shall be able to signal an operator at C-2296. Test in accordance with 4.10.12.

3.11 Electrical Requirements of C-2298( )/VRC.

3.11.1 Input Voltage Range. Same as 3.9.1.

3.11.2 Microphone Amplifier Output Circuit. Same as 3.9.2.

3.11.3 Microphone Amplifier Audio Output Power. Same as 3.9.3.

3.11.4 Microphone Amplifier Input Circuit. Same as 3.9.4.

3.11.5 Volume Control. Same as 3.9.5

3.11.6 Audio Response. Same as 3.9.6.

3.11.7 Distortion. Same as 3.9.7.

3.11.8 Control Functions. The C-2298( )/VRC control unit shall provide the following functions:

3.11.8.1 Selects Monitoring Function. Test in accordance with 4.11.8.

3.11.8.2 Selects Transmission Function. Test in accordance with 4.11.9.

3.11.8.3 Provides a Pathway for the Line Function Between the Two receptacles. Test in accordance with 4.11.10.

3.12 Electrical Requirements for C-2299( )/VRC.

3.12.1 Input Voltage Range. Same as 3.9.1.

3.12.2 Microphone Amplifier Output Circuit. Same as 3.9.2.

3.12.3 Microphone Amplifier Audio Output Power. Same as 3.9.3.

3.12.4 Microphone Amplifier Input Circuit. Same as 3.9.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

3.12.5 Volume Control. Same as 3.9.5.

3.12.6 Audio Response. Same as 3.9.6.

3.12.7 Distortion. Same as 3.9.7.

3.12.8 Control Function. The C-2299( )/VRC Control unit shall provide the following functions:

3.12.8.1 When in the normal position, provides proper termination for the monitor amplifier outputs of the two receiver-transmitters. Test in accordance with 4.12.8 to determine that the impedances are 150 ohm, ± 15 percent.

3.12.8.2 Provides for control of transmission of either receiver-transmitter. Test in accordance with 4.12.9.

3.12.8.3 When in the retransmit position, provides for interconnection of monitor amplifier outputs to proper microphone inputs. Test in accordance with 4.12.10.

3.12.8.4 When in retransmit position, provides for interconnection of control functions with the retransmit functions. Test in accordance with 4.12.11.

3.12.8.5 When in the retransmit position, provides for interruption of transmit control for all operators at control boxes. Test in accordance with 4.12.12.

3.12.8.6 When in the retransmit position, provides for interruption of the monitor output of A2 going into the interphone amplifier. Test in accordance with 4.12.13.

3.13 Operational Inspection. The units shall be given a final inspection, as specified in 4.16, after all other inspections and test are completed, to determine that they are operable prior to packaging.

3.14 Interchangeability. Like units, assemblies, subassemblies and replaceable parts shall conform to Requirement 7 of MIL-STD-454. (See 4.14)

3.15 Air Seal. The equipment case shall provide means for enabling performance of the air-seal test. When tested as specified in 4.7, the decrease in vacuum shall not exceed 0.01 pounds per square inch, gauge, per minute.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

3.16 Technical Literature and Running Spare Parts. Technical literature and running spare parts shall be furnished if specified in the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order. (See 6.2)

3.17 Plug-In Subassemblies. The control units shall contain a plug-in microphone amplifier assembly.

3.18 Fungus. Equipment and assemblies shall show no evidence of viable fungus or corrosion * when subjected to 28 days of fungus test in accordance with paragraph 4.13.9.

* Corrosion is defined as any visible degradations that can be attributed to flaky, pitted, blistered, or otherwise loosened finish or metal surface.

3.19 Salt Fog. The equipment and assemblies shall be exposed, in their operating configuration, to 48 hours of salt fog in accordance with paragraph 4.13.8, and shall show no evidence of corrosion as evidenced by any visible degradation that can be attributed to flaky, pitted, blistered or otherwise loosened finish or metal surfaces. There shall also be no impairment of operation of any control feature of the equipment.

3.20 Workmanship. The equipment shall be manufactured and assembled in accordance with Requirement 9 of MIL-STD 454 and the applicable portions of the following paragraphs:

(a) In MIL-P-11268:

General requirements for plastic material and plastic parts.
Wiring and cabling, including
- Slack.
- Protection.
- Clearance.
- Splicing.
- Connections, general
- Grounding, general.
- Shielding on wire and cable.
- Soldering and brazing.

Cleaning of units.

General requirements for securing of parts.

Controls
Self-tapping screws.

(b) In this specification:

3.4 Finish, protective.
3.5 Marking.
3.6 Die Casting.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility For Inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) First Article inspection (does not include packaging (See 4.3)

(b) Inspection covered by subsidiary documents. (See 4.4)

(c) Quality conformance inspection.

(1) Quality conformance inspection of equipment before packaging. (See 4.5)

(2) Quality conformance inspection of preparation for packaging. (See 4.17)

4.3 First Article Inspection. This inspection shall consist of the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified for group A, group B and group C (See Tables III, IV and V respectively). The first article inspection shall be performed in the order shown in Table II according to the number of samples specified in the contract or order.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE II - ORDER OF ENVIRONMENTAL TESTS

INSPECTION	NUMBER OF SAMPLES				
	UNIT 1	UNIT 2	UNIT 3	UNIT 4	UNIT 5
Non-damaging					
Temperature					
Low				1	
High				2	
Altitude (elevation)			1		
Potentially damaging					
Salt Fog				3	
Vibration (internal)	1				
Shock, basic design	2				1
Shock, Ballistic	3				
Humidity (Moisture Resistant		1			
Fungus			2		
Immersion	4				

NOTE 1: Other First Article inspection may precede, follow, or be interspersed between the non-damaging tests.

NOTE 2: The order on non-damaging tests and the choice of units subjected to the non-damaging tests may be varied if convenient, except that the vibration test should be performed on the same unit used for the bounce and shock test.

NOTE 3: The vibration test shall be performed on the same unit used for the basic design and ballistic shock tests as shown for sample unit 1.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

4.4 Inspection Covered by Subsidiary Documents. The following shall be inspected under the applicable subsidiary documents as part of the inspection of equipment before preparation for delivery:

ITEM	WHERE REQUIRED
Parts, Materials and Processes used in Electronic Equipment.....	3.3
Finish.....	3.4
Marking.....	3.5
Casting, impregnation and quality.....	3.6

4.5 Quality Conformance Inspection of Equipment Before Packaging. Each unit of each lot of equipment produced under this specification shall be subjected to bounce preconditioning (see 3.8.1) and then to a 24 hour electrical preconditioning burn-in (see 3.8.2) prior to selection of samples for inspection. The contractor shall perform the inspection specified in 4.4 and 4.5.1 through 4.5.3.2. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control thequality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedure s and examine the contractor's inspection records. In addition the Government -- at its discretion -- may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.9) Test equipment for Government verification inspection shall be made available by the contractor.

4.5.1 Group A Inspection. Each unit of each lot of equipment shall be inspected for conformance to all the inspection and test requirements of Table III. Each lot will be subject to verification, utilizing the procedures of MIL-STD-105 using the general inspection levels and the AQLs indicated in Table III, Group A Inspection shall be performed in any order which is satisfactory to the Government, except that air seal test (4.7) shall be next to last and the operational inspection (4.16) shall be last. (See 6.7)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE III - GROUP A INSPECTION

Inspection	Req Para	Insp Para	AQL Major	AQL Minor
C-2296( )/VRC				
Visual and Mechanical				
Microphone Amplifier, A-80	3.20	4.15	0.65%	2.5%
Control with Cover off	3.20	4.15	1.0%	4%
Control C-2296( )/VRC	3.20	4.15	1.0%	4%
Electrical				
Module A-80	SC-A-324072		0.65%	N/A
Control Box C-2296( )/VRC				
Microphone Amplifier Output Impedance	3.9.2	4.9.1		
Audio Output	3.9.3	4.9.2		
Microphone Amplifier Input Impedance	3.9.4	4.9.7	1% for the group	N/A
Volume Control	3.9.5	4.9.3		
Audio Response	3.9.6	4.9.4		
Distortion	3.9.7	4.9.5		
Air Seal	3.15	4.7	1%	N/A
Operation	3.13	4.16	1%	N/A
C-2297( )/VRC				
Visual Mechanical				
Microphone Amplifier, A-80	3.20	4.15	0.65%	2.5%
Control with cover off	3.20	4.15	1.0%	4%
Control C-2297( )/VRC	3.20	4.15	1.0%	4%
Electrical				
Module A-80	SC-A-324072		0.65%	N/A
Control Box C-2297( )/VRC				
Microphone Amplifier Output Impedance	3.10.2	4.10.1		
Audio Output	3.10.3	4.10.2		
Microphone Amplifier Input Impedance	3.10.4	4.10.7	1% for the Group	N/A
Volume Control	3.10.5	3.10.3		
Audio Response	3.10.6	3.10.4		
Distortion	3.10.7	4.10.5		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE III - GROUP A INSPECTION (Cont'd)

Inspection	Req Para	Insp Para	AQL Major	AQL Minor
Air Seal	3.15	4.7	1%	N/A
Operation	3.13	4.16	1%	N/A
C-2298( )/VRC				
Visual and Mechanical				
Microphone Amplifier, A80	3.20	4.15	0.65%	2.5%
Control with cover off	3.20	4.15	1%	4%
C-2298( )/VRC	3.20	4.15	1%	4%
Electrical				
Module A-80	SC-A-324072		0.65%	N/A
Control Box C-2298( )/VRC				
Microphone Amplifier output Impedance	3.11.2	4.11.1		
Audio output	3.11.3	4.11.2		
Microphone Amplifier input Impedance	3.11.4	4.11.7	1% for the Group	N/A
Volume Control	3.11.5	4.11.3		
Audio Response	3.11.6	4.11.4		
Distortion	3.11.7	4.11.5		
Air Seal	3.15	4.7	1%	N/A
Operation	3.13	4.16	1%	N/A
C-2299( )/VRC				
Visual and Mechanical				
Microphone Amplifier, A-80	3.20	4.15	0.65%	2.5%
Control with cover off	3.20	4.15	1%	4%
Control C-2299( )/VRC	3.20	4.15	1%	4%
Electrical				
Module A-80	SC-A-324072		0.65%	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE III- GROUP A INSPECTION (cont'd)

Inspection	Req Para	Insp Para	AQL Major	AQL Minor
Control Box C-2299( )/VRC				
Microphone Amplifier output Impedance	3.12.2	4.12.1		
Audio Output	3.12.3	4.12.2		
Microphone Amplifier input Impedance	3.12.4	4.12.7	1%	N/A
Volume Control	3.12.5	4.12.3	for the	
Audio Response	3.12.6	4.12.4	Group	
Distortion	3.12.7	4.12.5		
Air Seal	3.15	4.7	1%	N/A
Operation	3.13	4.16	1%	N/A

4.5.2 Group B Inspection. This inspection, including sampling, shall conform to Table IV and to the special procedure for small-sample inspection of Standard MIL-STD-105. Group B inspection shall normally be performed on inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection. Inspection Level shall be S-4.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE IV - GROUP B INSPECTION

Inspection	Req Para	Insp Para	AQL
Electrical			
Control Box C-2296( )/VRC			
Control functions			
Signalling	3.9.8.1	4.9.8	
Transmission	3.9.8.2	4.9.9	4%
Interphone	3.9.8.3	4.9.10	for the
Line Connections	3.9.8.4	4.9.11	Group
Input voltage Range	3.9.1	4.9.6	
Immersion	3.7.5	4.13.7	6.5%
Interchangeability	3.14	4.14	6.5%
Control Box C-2297( )/VRC			
Control Functions			
Signalling	3.10.8.1	4.10.8	
System test	3.10.8.2	4.10.9	
Selects Monitoring Functions	3.10.8.3	4.10.10	4.0%
Selects Transmission Function	3.10.8.4	4.10.11	
Signalling (Operator)	3.10.8.5	4.10.12	
Input Voltage Range	3.10.1	4.9.6	
Immersion	3.7.5	4.13.7	6.5%
Interchangeability	3.14	4.14	6.5%
Control Box C-2298( )/VRC			
Control Functions			
Selects Monitoring functions	3.11.8.1	4.11.8	
Selects Transmission functions	3.11.8.2	4.11.9	4%
Line Function	3.11.8.3	4.11.10	
Input Voltage Range	3.11.1	4.9.6	
Immersion	3.7.5	4.13.7	6.5%
Interchangeability	3.14	4.14	6.5%

Source: https://assist.dla.mil -- Downloaded: 20261O-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE IV-GROUP B INSPECTION (Cont'd)

Inspection	Req Para	Insp Para.	AQL
Control Box C-2299			
Control Functions			
Input Impedance of Al Monitor Rec-Trans Control	3.12.8.1	4.12.8	
Retransmit Audio	3.12.8.2	4.12.9	
Retransmit Controls	3.12.8.4	4.12.11	4% for the Group
Interruption of Transmit control	3.12.8.5	4.12.12	
Al Monitoring interruption	3.12.8.6	4.12.13	
Input voltage range	3.12.1	4.9.6	
Immersion	3.7.5	4.13.7	6.5%
Interchangeability	3.14	4.14	6.5%

4.5.2.1 Order of Inspection Within Group B. Group B inspection shall be performed in any order which is satisfactory to the Government.

4.5.3 Group C Inspection. This inspection shall consist of the tests specified in Table V and shall be performed on sample units that have been subjected to and met Group A and Group B inspection. Each sample unit used for the humidity, salt fog, or fungus test need meet only those environmental group B inspections indicated for that unit in Table IV. Sample units shall be selected in accordance with paragraph 4.5.3.1.

4.5.3.1 Sampling for Group C Inspection. Units selected for each Group C inspection shall be selected without regard to their quality in accordance with the following:

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE V - GROUP C INSPECTION
Group C Inspection for each of the Control Boxes
C-2296, C-2297, C-2298, C-2299

Inspection	Req Para	Insp Para
SUBGROUP I		
Vibration, Internal	3.7.4.1	4.13.4
Shock, Ballistic	3.7.4.2	4.13.6
Shock, basic design	3.7.4.2	4.13.5
SUBGROUP II		
Temperature	3.7.1	4.13.1.1
Humidity	3.7.2	4.13.2
Altitude	3.7.3	4.13.3
SUBGROUP III		
*Salt Fog	3.19	4.13.8
*Fungus	3.18	4.13.9

*Unless otherwise specified in contract or order, a different sample unit shall be used for each of these tests.

4.5.3.1.1 Subgroup I. For this subgroup, two units of each type control for each 50 units or fraction thereof produced shall be selected from the first two production lots. For subsequent Group C Inspection, ten units shall be selected every 4 months or 2000 units, whichever occurs first.

4.5.3.1.2 Subgroup II. For this subgroup, two units of each type control shall be selected from the first 50 production units for the First Group C Inspection. For subsequent Group C Inspection, two units shall be selected every 6 months or 3000 units, whichever occurs first.

4.5.3.1.3 Subgroup III. For this subgroup, one unit of each type of control shall be selected from the first production lot for the First Group C Inspection. For subsequent Group C Inspections; one unit shall be selected every 8 months.

4.5.3.2 Non-compliance. Actions relative to Group C failures shall be as specified in the contract or purchase order.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:14Z
Check the source to verify that this is the current version before use.

4.5.4 Reinspection of Conforming Group B and C Sample Units. Unless otherwise specified, sample units which have been subjected to and passed both Group B and Group C inspection may be accepted on contract or order provided all damage is repaired and the sample units are resubjected to and pass Group A inspection.

4.6 Preconditioning. (See 3.8)

4.6.1 Bounce Preconditioning. The unit, with shock mounts (if any) removed or blocked, shall be placed on its cover on the table of the Package Tester, Type 1000-S_C, as made by the L.A.B. Corporation, Skaneatales, New York, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32 inch-thick strip of material under one corner or edge of the unit to a distance of 3 inches as the unit bounces. The unit shall be subjected to this preconditioning for 1 minute. After bounce preconditioning, the unit shall not be repaired, cleaned, or otherwise changed prior to subjection to inspection. (See 3.8.1)

4.6.2 Burn-in (debugging). Each Control, Intercommunication Set on order shall be subjected to a burn in period of 24 hours with an input signal voltage of 7.0 mv RMS at a frequency of 1000 Hz; the microphone amplifier should deliver .22 v + 2 db RMS to a 150 ohm load at a temperature of 40°C ± 5° (95°F to 113°F). While the unit is in this operating mode, vibration shall be performed as follows: 2.2 G ± 10% any non resonant frequency between 20 and 60 Hz measured at the mounting points of the equipment. This vibration shall be applied for 10 minutes during each hour of equipment operating time. After preconditioning, there shall be no repair, cleaning, realignment, or other changes prior to acceptance inspection. (See 3.8.2)

4.7 Air Seal Test. The equipment shall be opened and closed again in such manner as to break and remake the seal. Immediately thereafter, the equipment shall be subjected to a vacuum of 1 pound per square inch (1 pound per square inch less than the atmospheric pressure surrounding the equipment) applied to the interior of the transit case or the interior of the equipment inclosure when no transit case is provided. The vacuum then shall be valved-off and the interior pressure measured during the onsuing period of 1 minute. During this 1-minute period the decrease in vacuum shall not exceed 0.01 pound. The gage used for measurement of the vacuum shall be of such accuracy that a difference of 0.01 pound can be determined readily. Control lamp cover shall be removed to provide connections for air seal test on C-2297( )/VRC; a screw plug shall be provided, per USAECOM Drawings, for air-seal test on C-2296( )/VRC, C-2298( )/VRC and C-2299( )/VRC. Air seal test on the C-2296( )/VRC shall be conducted prior to installation of the handset assembly, with the point of entry of the handset cord into the C-2296( )/VRC plugged.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.8 Standard Test Conditions. All Tests shall be conducted under the following conditions, except as specified for the individual tests.

Temperature	Room ambient
Humidity	Room ambient
Input voltage	25.5 volts dc
Input voltage, audio	7.0 mv RMS
Audio load, impedance	600 ohms
Audio frequency	100 Hz
Source impedance	150 ohms
Microphone load impedance	150 ohms

4.9 Electrical Tests, C-2296( )/VRC.

4.9.1 Microphone Amplifier Output Impedance. Under standard test conditions except no load, measure the output voltage. Terminate the output with a 1200 ohm resistor and measure the output voltage. The open circuit voltage shall be at least twice the loaded value (See 3.9.2)

4.9.2 Microphone Amplifier Audio Output. Under standard test conditions measure the output voltage for compliance to 3.9.3.

4.9.3 Volume Control. The control unit shall be operated under standard test conditions. The loudspeaker and headphone outputs shall be measured for full clockwise rotation and counterclockwise settings of the volume control with an input voltage of 7.75 volts RMS to establish compliance with 3.9.5.

4.9.4 Audio Response. The control unit shall be operated under standard test conditions. The output voltage shall be measured, then change the frequency of the input signal to 500, 2000 and 3000 Hz. The output shall conform to 3.9.6.

4.9.5 Distortion Test. The control unit shall be operated under standard test conditions and shall comply with 3.9.7.

4.9.6 Input Voltage Range Tests. To determine compliance with 3.9.1.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:14Z
Check the source to verify that this is the current version before use.

(a) Microphone Amplifier Audio output level (4.11.2).

(b) Distortion (4.11.5).

4.9.7 Input Impedance Test. Input Impedance shall be measured at 1000 Hz to establish compliance with 3.9.4.

4.9.8 Signalling. Connect a lamp identical to one used in the control box to the J62 receptacle. Connect one terminal of another lamp to pin B of receptacle J61 and the other terminal of the lamp to the 25.5 dc voltage supply. Both lamps should light when the microphone switch on the handset is keyed. (See 3.9.8.1)

4.9.9 Transmission. Place selector switch in RAD position and key microphone switch on handset. There should be continuity to ground at the R/T lead. (See 3.9.8.2)

4.9.10 Interphone. Place selector switch in INT position and key microphone switch on handset. There should be continuity to ground at the Int Rel lead. (See 3.9.8.3)

4.9.11 Line Connections. Test for continuity between line binding posts and input receptacle for compliance with 3.9.8.4.

4.10 Electrical Tests, C-2297( )/VRC.

4.10.1 Microphone amplifier output impedance. Same as 4.9.1.

4.10.2 Microphone amplifier output. Same as 4.9.2.

4.10.3 Volume control. Same as 4.9.3.

4.10.4 Audio response. Same as 4.9.4.

4.10.5 Distortion test. Same as 4.9.5.

4.10.6 Input voltage range tests. Same as 4.9.6.

4.10.7 Input impedance test. Same as 4.9.7.

4.10.8 Signalling. With switch on OFF position, connect a lamp identical to one used in control box between signal and lead and ground. Both lamps should light. Turn switch to EXT position. Lamp on control box should remain on; other lamp should go out in accordance with 3.10.8.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.10.9 External switching. Turn OFF-EXT Sig switch to OFF position and monitor switch to ALL position. There shall be no continuity between corresponding pins of receptacles J901 and J904 as indicated below:

1901 pins	1904 pins
J - Headphone audio.....	L - int output
K - Microphone Amp output.....	K - A1 Microphone
H - R/T Line.....	D - A1 R/T
D - Intercom Relay.....	H - int relay
E - Field Line.....	N - Field line
F - Field Line.....	U - Field line
C - +25.5 VDC.....	C - +25.5 VDC

With OFF-EXT Sig Switch in EXT position, there shall be continuity between the above corresponding pins.

4.10.10 Monitoring functions. Turn volume control to maximum clockwise, apply standard load and connect 7.75 volts 1000 Hertz to A1 headphone lead. Measure 7.35 volts min. across 600 ohms load when selector switch is placed in A position. Repeat above for other Selector Switch position as follows: (See 3.10.8.3)

Apply audio to Aux Receiver headphone lead, Selector in B position.

Apply audio to A2 headphone lead, Selector in C position.

Apply audio to INT output lead, Selector in ALL position.

Apply audio to INT ONLY out lead, Selector in INT ONLY.

4.10.11 Transmission control.

(a) A1 control. Ground R/T control pin at Rad audio connector. The A1 R/T lead should be grounded in the following MON Positions: A, B and ALL. (See 3.10.8.4)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

(b) A2 control. Same as above except A2 R/T lead should be grounded in C position.

(c) Int control. Place MON switch in ALL position, and ground control pin at Int audio connector. The Int Rel lead should be grounded in all positions. Place MON switch in INT ONLY position. Grounding control at Rad audio connector, or Int audio connector grounds Int Rel lead.

4.10.12 Signalling. Connect a lamp identical to one used in control box between the Signal pin and Int Rel pin of 9 pin receptacle. Operate switch to SIG. Both lamps shall light. (See 3.10.8.5)

4.11 Electrical tests, C-2298( )/VRC.

4.11.1 Microphone amplifier output impedance. Same as 4.9.1.

4.11.2 Microphone amplifier output. Same as 4.9.2.

4.11.3 Volume control. Same as 4.9.3.

4.11.4 Audio response. Same as 4.9.4.

4.11.5 Distortion test. Same as 4.9.5.

4.11.6 Input voltage range tests. Same as 4.9.6.

4.11.7 Input impedance test. Same as 4.9.7.

4.11.8 Monitoring functions. Same as 4.10.10.

4.11.9 Transmission control. Same as 4.10.11.

4.11.10 Line pathway. Test for continuity between the two receptacles in accordance with 3.11.8.3.

4.12 Electrical tests, C-2299( )/VRC.

4.12.1 Microphone amplifier output impedance. Same as 4.9.1.

4.12.2 Microphone amplifier output. Same as 4.9.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.12.3 Volume control. Same as 4.9.3.

4.12.4 Audio response. Same as 4.9.4.

4.12.5 Distortion test. Same as 4.9.5.

4.12.6 Input voltage range tests. Same as 4.9.6.

4.12.7 Input impedance test. Same as 4.9.7.

4.12.8 Monitor amplifier termination, C-2299( )/VRC. With RETRANS switch in normal position (OFF), measure input impedance of A1 monitor input and A2 monitor impedance to determine compliance with 3.12.8.1. Place switch in RETRANS position (ON) and measure to check that above terminations have been removed.

4.12.9 Control of receiver-transmitter. Ground R/T cont. pin of audio connector. Place RETRANS switch in OFF position and RAD TRANS switch in position 1. A1 R/T lead should be grounded. Place RAD TRANS switch in position 2. A2 R/T lead should be grounded. Measure continuity in the above positions for compliance with 3.12.8.2.

4.12.10 Retransmit audio interconnection. Place RETRANS switch in retrans position (ON). There shall be continuity between A1 Mon and A2 Mic and between A2 Mon and A1 Mic for compliance with 3.12.8.3.

4.12.11 Retransmit controls. Place RETRANS switch in retrans position (ON). There shall be continuity between A1 Retrans and A2 R/T and between A2 Retrans and A1 R/T for compliance with 3.12.8.4.

4.12.12 Transmission Interruption. Place RETRANS switch in retrans position (ON). There shall be an interruption of continuity between A1 R/T and A1 R/T SW and between A2 R/T and A2 R/T SW for compliance with 3.12.8.5.

4.12.13 A1 monitoring interruption. Place RETRANS switch in retrans position (ON). There shall be an interruption of continuity between A2 Mon and A2 Mon Return for compliance with 3.12.8.6.

4.13 Service test conditions for C-2296( )/VRC, C-2297( )/VRC and C-2298( )/VRC and C-2299( )/VRC.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.13.1 Temperature test.

4.13.1.1 Low Temperature. The equipment shall be tested in accordance with Method 502, Procedure 1, of MIL-STD-810. The storage temperature shall be -80°F and shall be maintained until equipment stabilization and the operating temperature shall be -40°. Prior to testing, the equipment shall meet full specification performance for the measurements specified in 3.7.1.

4.13.1.2 High Temperature. The equipment shall be tested in accordance with Method 501, Procedure II, of MIL-STD-810. The operating temperature shall be + 150°F. Prior to testing, the equipment shall meet full specification performance for the measurements specified in 3.7.1.

4.13.2 Humidity (moisture-resistance) test. The equipment shall be tested in accordance with Method 507, Procedure II of MIL-STD-810. Prior to testing, the equipment shall meet full specification performance for the measurements specified in 3.7.2. Measurements shall be made during the periods shown on the figure for the cycle. Do not move equipment from the humidity chamber for measurements, and do not leave power on after measurements have been completed. If any equipment fails to meet the specified performance during cycling, or fails subsequently, it does not pass the test. No repair or replacement of parts shall be permitted. The test shall be performed with the cover off.

4.13.3 Altitude (elevation) test. The equipment shall be tested in accordance with Method 500, Procedure 1, of MIL-STD-810. Prior to testing, the equipment shall meet full specification performance for the measurements specified in 3.7.3.

4.13.4 Vibration. The equipment shall be tested in accordance with Method 514, procedure VIII, using curve W, of MIL-STD-810. (See 3.7.4)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.13.5 Shock, basic design. The equipment shall be tested in accordance with Method 516, procedure I, figure 516.2-1, parameters b and d of MIL-STD-810. (see 3.7.4.2). The equipment shall be energized at the end of each 3/4 hour period. The equipment shall be tested for compliance with paragraph 4.16 (operation inspection).

4.13.6 Shock test; ballistic.

(a) Test Method. The test shall be conducted on the "Shock Testing Machine for Light Weight Equipment" shown in Specification MIL-S-901. The control unit shall be secured in its normal operating position to test plate fixture 4A, figure 5 of MIL-S-901, by means of the same fasteners used for vehicular installation of the control. The test shall consist of a total of 9 blows: one each 1 foot blow, 3 foot blow, and 5 foot blow on the back, side and top of the test plate. As an alternative to reorienting the test plate for the blows on the side of the plate, equivalent rotation of the control under test is permissable. (See 3.7.4)

(b) Performance. Upon completion of the test and before repairs are made, tests shall be made for compliance with the following test: para 4.16 (operation inspection).

4.13.7 Immersion test. (See 3.7.5). The equipment shall be tested in accordance with Method 512, Procedure 1, of MIL-STD-810.

4.13.8 Salt Fog. The equipment and assemblies shall be exposed in their operating configuration to salt fog in accordance with Method 509, Procedure I of MIL-STD-810 for 48 hours. (See 3.19)

4.13.9 Fungus. The equipment and assemblies shall be subjected to 28 days of the fungus test specified in Method 508 of MIL-STD-810. For gasket or other non-hermetically sealed equipments, the parts and materials of the chassis shall be sprayed with the spore suspension. The interior of the case shall also be sprayed. The equipment shall be subjected to the test in this open condition, for compliance with paragraph 3.18.

4.14 Inspection for Interchangeability. The mechanical dimensions on gage list for items below shall be gaged or measured to determine compliance with the physical interchangeability requirements of 3.14. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

(a) Control, Intercommunication Set C-2296( )/VRC - SC-GL-323148.

(b) Control, Intercommunication Set C-2297( )/VRC- SC-GL-323145.

(c) Control, Intercommunication Set C-2298( )/VRC - SC-GL-323146.

(d) Control, Radio Set C-2299( )/VRC - SC-DL-323144.

4.14.1 Electrical Performance of A-80 Module. Prior to assembly in the control, the A-80 module shall be tested to determine compliance with the performance requirements specified in SC-A-324072.

4.15 Visual and mechanical inspection. The equipment shall be examined for the defects listed in Standard MIL-STD-252.

4.16 Operation inspection. The control shall be operated under the standard test conditions specified in 4.8 and shall comply with the microphone amplifier audio output, distortion, and control functions requirements specified for it in the requirements section of this document. (See 3.13)

4.17 Quality conformance inspection. Quality conformance inspection of Section 5 requirements shall be in accordance with Group A, Group B, and when required (see 6.2.g), the Group C (rough handling) requirements of MIL-P-116. Inspection lots shall be in accordance with MIL-P-116.

5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be in accordance with SPI1G0031."

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Controls, Intercommunication Sets C-2296( )/VRC, C-2297( )/VRC, C-2298( )/VRC, and C-2299( )/VRC, are units normally used as parts of the Radio Set AN/VRC-12 vehicular communication systems.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number and date of this specification and any amendment thereto.

b. Type required.

c. Level A or level B preservation and packing (see section 5).

d. Preproduction pack(s) as follows:
Makeup of pack(s) as follows:

Number of each kind of pack to be submitted.
Inspection to be performed thereon.

e. Marking and shipping of samples.

f. Place of final inspection.

g. When rough handling test is required (see 4.17).

6.3 Nomenclature. The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: C-2299W/VRC. The contractor should apply for nomenclature in accordance with the applicable clause in the contract (see 1.1).

6.4 Location of operational inspection and air-seal test. It is desirable that the operational inspection (4.16) and the air-seal test (4.7) be performed at a location that will minimize handling (which might cause damage to the equipment) after this inspection is completed. Any preparation for shipment which would require breaking of the equipment seal should be accomplished prior to the air-seal test so that the seal may remain intact thereafter. It is recommended that the entire lot (including all previously inspected sample units) be sampled and inspected immediately prior to packaging.

6.5 Group C inspection Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of correct action (see 4.5.3.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

6.6 Verification inspection. Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product, and will normally be identified by the categories listed below:

a. Type A. The total of that inspection set forth in the Quality Assurance Provisions of this specification or the contract. Included in this category is that amount of inspection referred to as normal and tightened inspection by MIL-STD-105.

b. Type B. That inspection set forth in the Quality Assurance Provisions of this specification or the contract reduced in amount under the reduced inspection provisions of MIL-STD-105.

c. Type C. A reduced inspection procedure resulting in a material reduction in the amount of inspection set forth in the Quality Assurance Provisions of this specification. The amount of inspection is less than that provided for in type B and is based upon a consistently acceptable produce resulting from a planned quality control system voluntarily employed by the contractor in the production of the product.

6.7 Size data. Size limitations cited herein are based on the dimensions of the equipment for which these requirements were established. Requests to exceed these limitations must be supported by data indicating why limitations cannot be met and recommended a revised limitation.

6.8 Environmental. Environmental pollution prevention measures are contained in the packaging material specifications referenced herein. Refer to material specifications or preparing activity for recommended disposability methods.

Custodian

ARMY CR

Preparing Activity:

ARMY-CR

Project No. 5820-A714

☆U.S. GOVERNMENT PRINTING OFFICE: 1980—703-023/4266

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE MIL-C-55126D (CR)

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

HQ, USA CORADCOM
ATTN: DRDCO-CM-DM
Fort Monmouth, NJ 07703

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

FOLD

HQ. USA CORADCOM
ATTN: DRDCO-CM-DM
Fort Monmouth, NJ 07703

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

POSTAGE AND FEES PAID



HQ. USA CORADCOM
ATTN: DRDCO-CM-DM
Fort Monmouth, NJ 07703

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.