MILITARY SPECIFICATION

PROCESSING MACHINE, PHOTOGRAPHIC FILM AND PAPER EH-29( )

This specification is approved for use by the Electronics Research and Development Command, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one type of continuous photographic processing machine, designated as Processing Machine, Photographic Film and Paper EH-29( ) (see 6.7).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified, the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116	- Preservation, Methods Of.
MIL-P-4672	- Paper, Photographic, Black And White, Sensitized.
MIL-M-13231	- Marking Of Electronic Items.
MIL-F-14072	- Finishes For Ground Electronic Equipment.

STANDARDS

MIL-STD-105	- Sampling Procedures And Tables For Inspection By Attributes.
MIL-STD-252	- Wired Equipment, Classification Of Visual And Mechanical Defects.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Electronics Research and Development Command, ATTN: DELCS-PE, Fort Monmouth, New Jersey 07703-5304, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

MIL-STD-454	- Standard General Requirements For Electronic Equipment.
MIL-STD-461	- Electromagnetic Emission And Susceptibility Requirement - For The Control Of Electromagnetic Interference.
MIL-STD-462	- Electromagnetic Interference Characteristics Measurement Of.
MIL-STD-810	- Environmental Test Methods.

2.1.2 Other Government documents. The following Government documents form a part of this specification to the extent specified herein:

DRAWINGS

ELECTRONICS COMMAND

DL-SC-A-612436	- Temperature Control Unit, Photographic Processing FH-6B.
DL-SC-A-612437	- Processing Machine, Photographic Film And Paper EH-48B
SPI 1G00382	- Special Packaging Instructions.

(Copies of specifications, standards, and drawings required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The processing machine, photographic film and paper EH-29( ) (hereinafter call equipment) shall consist of the following;

a. Processing Machine, Photographic Film and Paper EH-48( ).
b. Temperature Control Unit, Photographic Processing FH-6( )

3.2 First article. When specified in the contract (see 6.2) a sample shall be subjected to first article inspection (see 4.3 and 6.3).

3.3 Material. The material shall be as specified herein and as shown on the applicable drawings. However, when a definite material is not specified, a material shall be used which will enable the equipment to meet the performance requirements of this specification. Acceptance or approval of any constituent material shall not be construed as a guaranty of the acceptance of the finished product (see 6.4 and 6.5).

3.3.1 Cleaning. Materials, parts and equipment shall be cleaned to remove such contaminants as corrosion products, dust, fingerprints, lubricating oils, mold release agents, sand, solder, flux residues, outgassing products and any other contaminant. The cleaning procedure and cleaning agents shall have no deleterious effect on the performance requirements of the materials, parts and equipments. The same cleaning procedure shall be applied to all equipment produced and delivered. All cleaning of material, parts and equipments shall be in accordance with MIL-STD-454, Requirement 9 .

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

3.3.2 Recycled, virgin and reclaimed material. It is required that, to the maximum extent possible, recovered or reclaimed materials, in lieu of virgin materials, shall be used without jeopardizing the intended use of the manufactured item.

3.4 Design and construction.

3.4.1 Processing Machine, Photographic Film and Paper EH-48( ). The photographic processing machine shall be in accordance with drawing and data list DL-SC-A-612437.

3.4.2 Temperature Control Unit, Photographic Processing FH-6( ). The photographic temperature control unit shall be in accordance with drawing and data list DL-SC-A-612436.

3.4.3 Light-tightness. Photographic film shall not be fogged under normal handling condition with ambient light level (illuminance) of 107.6 to 161.5 Lux (10 to 15 footcandle) around the outside of the quipment.

3.4.4 Input voltage and frequency.

3.4.4.1 Processing machine, photographic film and paper EH-48( ). The processing machine shall operate from a 110/220 ±10 volts, 60 ±3 Hertz (Hz), single phase, 4-wire alternating current (AC) source.

3.4.4.2 Temperature control unit, photographic processing FH-6( ). The temperature control unit shall operate from a 115 ±10 volts, 60 ±3 Hz, single phase AC source.

3.5 Leak-proof operation. When tested as specified in 4.6.2 the equipment pumps shall operate for not less than 1000 hours without leakage.

3.6 Safety (personal hazard). Provisions for personal safety shall be in accordance with MIL-STD-454, Requirement 1.

3.7 Performance characteristics.

3.7.1 Processing capability. The processing machine shall process the following sizes of roll film and paper (see 4.6.3.1):

Type	Width	Roll/run	Length (max)
Film	2.75 inches (70mm)	3	200 ft (61 meters)
Film	5 inches (127mm)	1	200 ft (61 meters)
Film	9.5 inches (241.3mm)	1	200 ft (61 meters)
Paper	9.375 inches (238.1mm)	1	200 ft (61 meters)

3.7.1.1 Film processing. The following types of film shall be processed to a gamma of approximately 1.3 without any physical damage such as cracks, scratches, or abrasions on either the base or emulsion (see 4.6.3.2.1).

a. Eastman Kodak, Plus-X, Aerecon, Type 8401 or equal, at a rate of not less than 2.1 meters (7ft) per minute.
b. Eastman Kodak, Tri-X, Aerecon, Type 8403 or equal, at a rate of not less than 0.5 meter (1.5ft) per minute.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the currentversion before use.

3.7.1.2 Paper processing. The equipment shall process and dry 61 meters (200ft) of photographic roll paper conforming to MIL-P-4672, type IV, subtype E, at a rate of not less than 3.05 meter (10ft) per minute. The paper shall not show any physical damage such as cracks, scratches or abrasions on either the base or emulsion (see 4.6.3.2.2).

3.7.2 Drying chamber. The temperature of the drying chamber shall be adjustable within 1°C (2°F) of any temperature from 43.3°C to 65.5°C (110°F to 150°F) (see 4.6.3.3).

3.7.3 Drive system. The film or paper shall be transported through the processor at any rate up to 4.5 meters (15ft) per minute (see 4.6.3.4).

3.7.4 Solution temperature control (see 4.6.3.5).

a. Solutions in processing tanks 1 and 2 shall be maintained at a temperature of 32.2°C ±1°C (90°F ±2°F).

b. Water in processing tank 4 shall be maintained at a temperature of 32.2°C ±2.2°C (90°F ±4°F).

c. Solutions in processing tanks 1 and 2, and water in tank 4 shall be cooled by means of the temperature control unit from 40.5°C (105°F) to 32.2°C (90°F) or below in not more than 70 minutes when the liquid level is 63.5 ±12mm (2.5 +0.5 inches) from the top of the tanks and the ambient air temperature is 21°C to 23.9°C (70°F to 75°F).

3.7.4.1 Alarm. When an overheat condition is in existence, an alarm shall signal the operator audibly and visually. The alarm circuit shall shut down the heater when the temperature of the water exceeds 71.1°C (160°F) (see 4.6.3.5.1).

3.8 Environmental.

3.8.1 Operating temperatures. The equipment shall operate as specified herein before, during, and after testing, in any ambient temperature between 4.4°C (40°F) and 46.1°C (115°F).

3.8.2 Humidity. When subjected to 95 percent relative humidity, the equipment shall exhibit no physical damage, corrosion, rust, blistering, swelling, deterioration of parts or materials.

3.8.3 Altitude (elevation). The equipment shall operate as specified herein at an altitude of not less than 15,000 feet (4.57km).

3.8.4 Vibration. When tested as specified in 4.6.4.5 the equipment shall be operable without degradation in specified performance and shall sustain no physical damager.

3.9 Breakdown voltage. When tested as specified in 4.6.5 the electrical insulation shall withstand a breakdown voltage 4 times the operating voltage, and there shall be no visible deterioration of the equipment.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

3.10 Electromagnetic interference characteristics. The equipment shall meet the electromagnetic interference requirements specified in MIL-STD-461.

If the contractor considers it desirable to modify the equipment in order to facilitate conformance to the specified test limits, he shall obtain approval from the contracting officer before proceeding with the modification.

3.11 Interchangeability. Like units, assemblies, subassemblies and replaceable parts shall be in accordance with MIL-STD-454, Requirement 7.

3.12 Finish. The equipment shall be finished in accordance with MIL-F-14072 and as specified on the drawings.

3.13 Marking.

3.13.1 General. Marking shall be in accordance with MIL-M-13231.

3.13.2 Visibility. Whenever practicable, parts shall be mounted that their identification marking will be readily visible with minimum disassembly of the equipment.

3.13.3 Serial numbers. The following items shall have serial numbers:

Processing Machine, Photographic Film and Paper EH-48( ).
Temperature Control Unit, Photographic Processing FH-6( ).

3.14 Workmanship. The equipment shall be manufactured and assembled in accordance with MIL-STD-454, Requirement 9, and as specified herein.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Inspections covered by subsidiary documents (see 4.4).
c. Quality conformance inspection (see 4.5).
d. Packaging inspection (see 4.6.9).

4.3 First article.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:14Z
Check the source to verify that this is the current version before use.

4.3.1 First article units. The contractor shall furnish two first article units of the equipment.

4.3.2 First article inspection. The first article inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4 and the inspections specified for group A, group B, and group C (see table I, II and III respectively). The inspection shall be performed in the following order: 4.4, group A, group B, and group C. After completion of group C environmental tests, conforming units shall be reinspected and shall pass all group A inspection. Failure of any inspection shall be cause for rejection.

4.4 Inspection covered by subsidiary documents. The following shall be inspected under the applicable subsidiary documents as part of the inspection requirements.

Item	Where required
Safety	3.6
Finish	3.12
Marking	3.13

4.5 Quality conformance inspection.

4.5.1 Inspection. Quality conformance inspection shall be as specified in 4.4 and 4.5.2 through 4.5.4.

4.5.2 Group A inspection. Each equipment shall be subjected to the inspections specified in table I. Discrete lots shall be formed from units that pass this inspection. Factors of lot composition not defined, or as specified herein, shall be in accordance with MIL-STD-105.

TABLE I. Group A inspection.

Inspection	Requirement paragraph	Test paragraph	AQL (percent defective) Major	AQL (percent defective) Minor
Visual and mechanical	3.14	4.6.8	1.0	4.0
Operational				
Drying chamber	3.7.2	4.6.3.5	1.0	1/
Drive system	3.7.3	4.6.3.4	1.0	1/

1/ All defects are considered major.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.5.2.1 Group A lot sampling. Sampling of group A lots shall be in accordance with MIL-STD-105, inspection level II. Acceptable quality level (AQL) shall be as specified in table I.

4.5.2.2 Order of inspection within group A. Group A inspection shall be performed in any order satisfactory to the Government.

4.5.3 Group B inspection. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspections. This inspection shall be as specified in table II.

TABLE II. Group B inspection.

Inspection	Requirement paragraph	Test paragraph	AQL (percent defective)
Interchangeability	3.11	4.6.7	6.5
Light-tightness	3.4.3	4.6.1	4.0
Leak-proof operation	3.5	4.6.2	4.0
Voltage breakdown	3.9	4.6.5	4.0
Processing			
Film	3.7.1.1	4.6.3.2.1	4.0
Paper	3.7.1.2	4.6.3.2.2	4.0
Temperature control	3.7.4	4.6.3.5	4.0
Alarm	3.7.4.1	4.6.3.5.1	4.0

4.5.3.1 Group B sampling. Sampling for group B shall be in accordance with MIL-STD-105, inspection level S-4. AQL shall be as specified in table II.

4.5.3.2 Order of inspection within group B. Group B inspection shall be performed in any order satisfactory to the Government.

4.5.4 Group C inspection. Group C inspection shall be performed on units that have passed group A and group B inspections. The inspection shall consist of the inspections specified in table III.

4.5.4.1 Sampling for group C inspection. One sample unit shall be selected at random for all inspections in table III from every 25 units, or fraction thereof, produced. The first sample selected shall be at the start of the contract from the first quality conformance inspection production lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE III. Group C inspection.

Inspection	Requirement paragraph	Test paragraph	Order of inspection
Electromagnetic interference	3.10	4.6.6	1
Low temperature	3.8.1	4.6.4.1	2
High temperature	3.8.1	4.6.4.2	3
Altitude (elevation)	3.8.3	4.6.4.4	4
Humidity	3.8.2	4.6.4.3	5
Vibration	3.6.4	4.6.4.5	6

4.5.4.2 Order of inspection within group C. Group C inspection shall be performed as specified in table III.

4.5.4.3 Group C failure. Action required relative to group C failure shall be as specified in the contract (see 6.2).

4.6 Tests.

4.6.1 Light-tightness. Two cassettes shall be loaded with unexposed film in total darkness. One cassette shall be attached to the equipment and the film threaded in total darkness. The light level around the outside of the equipment shall be 10 to 15 footcandle while the equipment is operated for processing the film. The film in the other cassette shall be processed in total darkness. The processed film which had been subjected to the light source shall be compared with the film which had been processed in total darkness for any differences in density. A standard laboratory densitometer shall be utilized for this comparison. Nonconformance to 3.4.3 shall constitute failure of this test.

4.6.2 Leak-proof operation. The equipment pumps shall be examined for leakage before, during, and after operation as specified herein. Nonconfomrance to 3.5 shall constitute failure of this test.

4.6.3 Performance characteristics.

4.6.3.1 Operational. The equipment shall be tested to determine that all components are functioning and operable both mechanically and electrically. Nonconformance to 3.4.4 and 3.7 shall constitute failure of this test.

4.6.3.2 Processing capability.

4.6.3.2.1 Film. The equipment shall be set up for operation for processing film. The tanks shall be filled with the following solutions:

Tank No. 1 - Armed Forces Developer #4.

Tank No. 2 - Rapid Fix.

Tank No. 3 - Hypo Clearing Agent.

Tank No. 4 - Water.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

The processing machine shall be operated to bring the temperature of the solution to 90 ±2°F (32.2 ±1°C). Three rolls of Plus X, Aerecon, 70mm film, exposed to yield aerial negatives and step wedges, shall be loaded into the equipment. After the film has been developed, it shall be inspected for any defects. The gamma shall be determined using a standard laboratory photographic densitometer capable of measuring diffuse transmission density (see 3.7.1.1). While performing this test, the tanks and plumbing shall be inspected for leaks. Nonconformance to 3.7.1.1 shall constitute failure of this test.

4.6.3.2.2 Paper. The equipment shall be loaded with a roll of photographic paper conforming to MIL-P-4672. type IV, subtype E and shall process and dry 61 meters (200 ft) of paper at a rate of 3.05 meters (10ft) per minute. Nonconformance to 3.7.1.2 shall constitute failure of this test.

4.6.3.3 Drying chamber. Set the drying chamber adjustable temperature control to any temperature setting between 43.3°C and 65.5°C (110°F and 150°F). Activate the drying chamber and allow to stabilize. While still stabilized, compare the drying chamber temperature with the adjustable control setting. Nonconformance to 3.7.2 shall constitute failure of this test.

4.6.3.4 Drive system. The equipment shall be loaded with dummy film and the drive system activated to transport the film through the processor. Noncompliance to 3.7.3 shall constitute failure of this test.

4.6.3.5 Temperature control. The equipment tanks shall be filled with photographic solutions and water as specified in 4.6.3.2.1. The temperature of the liquid at the start of the test shall be 105 ±2°F (40.5 ±1°C). The time required to stabilize the temperature at 90 ±2°F (32.2 ±1°C) for tanks 1 and 2, and 90 ±4°F (32.2 +2.2°C) for tank 4, shall be measured as specified in 3.7.4. After stabilization, the temperature of the liquid shall be checked, using a standard laboratory termometer accurate to ±1°, every 30 minutes for a period of 8 hours. Nonconformance to 3.7.4 shall constitute failure of this test.

4.6.3.5.1 Alarm. Activate the water heating chamber and allow the temperature of water to reach not less than 71.1°C (160°F). Nonconformance to 3.7.4.1 shall constitute failure of this test.

4.6.4 Environmental.

4.6.4.1 Low temperature. The equipment shall be subjected to the test of MIL-STD-810, Method 502.1, Procedure I. The temperature in step 2 shall be maintained for a period of not less than 2 hours following stabilization of the test item. Low operating temperature (step 4) shall be 4.4°C (40°F). Nonconformance to 3.8.1 shall constitute failure of this test.

4.6.4.2 High temperature. The equipment shall be subjected to the test of MIL-STD-810, Method 501.1, Procedure II. The temperature for step 7 shall be 46.1°C (115°F). Nonconformance to 3.8.1 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

4.6.4.3 Humidity. The equipment shall be tested in accordance with MIL-STD-810, Method 507.1, Procedure II with the exception that step 6 shall be limited to two 48-hour cycles. Operation and measurements shall only be performed during the last 5 hours of the last cycle. Nonconformance to 3.8.2 shall constitute failure of this test.

4.6.4.4 Altitude. The equipment shall be tested in accordance with MIL-STD-810, Method 500.1, Procedure I. The test procedure shall include a 40,000 feet (12,192m) altitude non-operational exposure for not less than one hour previous to the 15,000 feet (4,592m) altitude operational portion of step 2. Altitude rate changes should not exceed 2,000 ft/min. (610m/min). Nonconformance to 3.8.3 shall constitute failure of this test.

4.6.4.5 Vibration. The equipment shall be subjected to sinusoidal vibration having a double amplitude of 0.762mm (0.030 in), with the frequency being varied uniformly between the limits of 10 Hz and 55 Hz. The rate of frequency change shall be linear and shall be such that a complete cycle (10 to 15 to 10 Hz) shall be transversed in 30 minutes. One cycle shall be performed along each of the three major axes of the equipment for a total test time of 90 minutes. Nonconformance to 3.8.4 shall constitute failure of this test.

4.6.5 Breakdown voltage. The equipment shall be subjected to a breakdown voltage not less than 4 times the operating voltage for a period of not less than 10 seconds. During testing, disconnections shall be made where necessary to protect circuit elements. Nonconformance to 3.9 shall constitute failure of this test.

4.6.6 Electromagnetic interference. The equipment shall be tested for electromagnetic interference characteristics in accordance with MIL-STD-462. Nonconformance to 3.10 shall constitute failure of this test.

4.6.7 Interchangeability. The dimensions listed below shall be gaged or measured to determine conformance to the physical interchangeability requirement of 3.11. When a listed dimension is not within specified limits, it shall be considered a major defect.

a. Dimensions affecting the insertion of dip rod assembly into the processing tanks.

b. Dimensions affecting the insertion of the dip rod into the drying chamber.

c. Location of hinges and fasteners on separate parts or assemblies which must mate.

4.6.8 Visual and mechanical inspection. The equipment shall be examined for the defects listed in MIL-STD-252 and table IV. Nonconformance to 3.14 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

TABLE IV. Classification of visual and mechanical defects.

Classification	Defects
Major	1. Cuts or kinks in hoses. 2. Controls inoperative. 3. Hinge or fastener attached to wrong side. 4. Latch fasteners missing. 5. Counterweight mechanism in mast not operable.
Minor	1. Pilot light missing or broken. 2. Loose or missing screws.

4.6.9 Packaging inspection. Packaging inspection requirements specified herein are classified as follows:

a. First article inspection of packaging.
b. Quality conformance inspection of packaging.

4.6.9.1 First article inspection of packaging. Unless otherwise specified in the contract, first article inspection of packaging shall be in accordance with the unit pack design validation requirements of MIL-P-116.

4.6.9.2 Quality conformance inspection of packaging.

4.6.9.2.1 Materials inspection. All materials to be used in packaging shall be inspected in accordance with the applicble material specification.

4.6.9.2.2 Preservation inspection. Inspection of preservation and interior markings shall be in accordance with group A and B quality conformance inspection requirements of MIL-P-116. Lot formation and sampling procedures shall be as specified therein.

4.6.9.2.3 Packing inspection. Inspection of packing and the marking for shipment and storage shall consist of the examinations specified in table V "Packing inspection provisions." Lot formation shall consist of all packs made of the same material during an identifiable period and submitted at one time for acceptance. Sampling procedures shall be in accordance with MIL-STD-105, using a single sampling plan and acceptable quality level of 4.0 percent defective.

TABLE V. Packing inspection provisions.

No.	Characteristic	Method of Inspection
101	Intermediate container not as specified.	Visual
102	Improper closure of intermediate container.	Visual
103	Shipping containers not in accordance with specification.	Visual
104	Excessive cube.	Visual
105	Improper blocking and bracing.	Visual
106	Closure not in accordance with specification.	Visual
107	Weight and size exceed container limitations.	Weight & measure
108	Strapping not in accordance with specification, incorrectly applied or omitted.	Visual
109	Marking omitted, incorrect, or illegible.	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be in accordance with SPI 1G00382.

6. NOTES

6.1 Intended use. Processing Machine, Photographic Film and Paper EH-29( ) is used to process 70mm, 5-inch and 9.5-inch wide roll film and 9.375-inch wide roll photographic paper. It is a daylight operable, continuous, immersion type processor using submerged spray agitation and contains an integral forced hot air drier. The processing temperature is automatically maintained by the temperature control units.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. When a first article is required for inspection and approval (see 3.2, 4.3 and 6.3).
c. Group C failure action (see 4.5.4.3).
d. Level A or B preservation and packing (see section 5).
e. When first article inspection rough handling tests are not required.
f. When first article packaging inspection test reports require acquisition activity approval prior to production unit packing.

6.3 First article. When a first article inspection is required, the item will be tested and should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, test, and approval of first article.

6.4 Level B preservation. When level B preservation is specified, this level of protection will only be used under known favorable conditions during transportation, storage and handling.

6.5 Environmental. Environmental pollution prevention measures are contained in the packaging material specification referenced herein. Refer to material specification or preparing activity for recommended disposability methods.

6.6 Group C inspection. Approval to ship may be withheld at the discretion of the Government, pending the decision from the contracting officer on the adequacy of the corrective action (see 4.5.4.3).

6.7 Nomenclature. The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example EH-29W. The contractor should apply for nomenclature in accordance with the applicable provision in the contract (see 1.1).

6.8 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the prvious issue due to the extensiveness of the changes.

Custodian:
Army - ER

Preparing activity:
Army - ER
(Project 6740-A136)

Review activity:
DLA - GS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

NSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in ubmitting comments and suggestions for improvements. All users of military standardization documents are invited to provide uggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and nailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was oo rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the roblems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an cknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being onsidered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of pecification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization o waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
ENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON, D.C.

POSTAGE WILL BE PAID BY DEPARTMENT OF THE ARMY

Headquarters
US Army ERADCOM
Combat Surveillance and Target Acquisition Lab
ATTN: DELCS-PE
Fort Monmouth, New Jersey 07703-5304

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-P-55159B(ER)	PROCESSING MACHINE, PHOTO, FILM/PAPER EH-29( )

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 EDITION OF 1 OCT 75 IS OBSOLETE

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:14Z
Check the source to verify that this is the current version before use.