MILITARY
SPECIFICATION

MIL-A-55062(SigC)
12 February 1959

SUPPORT, ANTENNA AB-461( )/GL

1. SCOPE

1.1 Scope.- This specification covers the requirements for an antenna support designated as Support, Antenna AB-461( )/GL.

2. APPLICABLE DOCUMENTS

2.1 Documents.- The following documents, of the issue in effect on date of invitation for bids, form a part of this specification:

SPECIFICATIONS

FEDERAL

PPP-B-585	Boxes; wood, wirebound
PPP-B-601	Boxes; wood, cleated plywood
PPP-B-621	Boxes; wood, nailed and lock-corner
PPP-B-636	Boxes; fiber

MILITARY

MIL-P-116	Preservation, methods of
MIL-B-117	Bags, interior packaging
MIL-T-152	Treatment, moisture-and-fungus-resistant, of communications, electronic, and associated electrical equipment.
MIL-M-11473	Magnetic particle inspection; soundness requirements for weldments.
MIL-M-13231	Marking of electronic items
MIL-F-14072	Finishes for ground signal equipment

STANDARDS

MILITARY

MIL-STD-22	Welded-joint designs
MIL-STD-105	Sampling procedures and tables for inspection by attributes
MIL-STD-129	Marking for shipment and storage
MIL-STD-169	Extreme-temperature cycle
MIL-STD 170	Moisture resistance test cycle for ground signal equipment
MIL STD-202	Test methods for electronic and electric component parts

FSC 5985

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

DRAWINGS

SIGNAL CORPS

SC-A-19100	Hardware for chests and cases
ES-DL-175901	Antenna Support AB-461( )/GL Drawing and Data List

PUBLICATION

SIGNAL CORPS

List of Military standards covering fasteners.

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

2.2 Other publications.- The following documents form a part of this specification. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

NATIONAL BUREAU OF STANDARDS

Handbook H28 Screw-Thread Standards for Federal Services.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington 25, D. C.)

AMERICAN TRUCKING ASSOCIATION

National Motor Freight Classification No. A-3 and No. 14

(Application for copies should be addressed to the American Trucking Association, 1424 16th Street, N. W., Washington 6, D. C.)

ASSOCIATION OF AMERICAN RAILROADS

(1) Uniform Freight Classification No. 4

(2) Consolidated Freight Classification Rule 21

(Application for copies should be addressed to the Consolidated Classification Committee, 202 Union Station, Chicago 6, Ill.)

3. REQUIREMENTS

3.1 Description.- Support, Antenna AB-461( )/GL, which includes Rodome CW-104( )/AP, consists of the following:

Pedestal, Antenna AB-594( )/GL
Case, Antenna Support CY-2212( )/GL
Guy, Cable assembly with turnbuckle
Ring, connecting round

3.2 Construction.- The equipment shall be constructed in accordance with Drawing and Data List ES-DL-175901.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

3.3 Radome CW-104( )/AP.- Radome CW-104( )/AP shall be provided to protect the antennas and associated auxilary equipment components used with Support, Antenna AB-461( )/GL, from the environmental elements. Radome CW-104( )/AP shall be fabricated to conform with Virginia Lincoln Corp, part No. GL-2422-1, Brunswick Balke Collender Co, or equal.

3.4 Case, Antenna Support CY-2212( )/GL

3.4.1 Handles.- Case, Antenna Support CY-2212( )/GL shall be provided with at least four spring-loaded handles in accordance with Drawing SC-A-19100. The handles, two on each end, shall be so located that the weight of the equipment mounted in the case shall be equally distributed on them.

3.4.2 Catches.- Case, Antenna Support, CY-2212( )/GL shall be provided with spring-loaded catches in accordance with Drawing SC-A-19100 to secure the cover. There shall not be less than five catches on each side and not less than four on each end.

3.4.3 Immersion proof.- Case, Antenna Support CY-2212( )/GL shall not exhibit any leakage after being submitted to the test specified in 4.6.

3.5 Screws, other threaded devices, and related items.-

3.5.1 Form and fit.- Unless otherwise specified, screw threads shall conform to Handbook H28 and supplement thereto; the Unified Thread Form and Series shall be class 2A or 2B fit, and the American National Thread Series shall be class 2 fit.

3.5.2 Selection.- When practicable, machine screws, cap screws, and lockwashers shall be selected from the List of Military Standards Covering Fasteners.

3.6 Castings.- Castings shall be of uniform quality and condition, and free from cracks, harmful shrinkage, porosity, gas holes, foreign matter, hard spots, and other injurious defects. The surface of the castings shall be free from pits, parting lines, porous areas, fins, ridges, nodules, raised metal and scale. Castings shall not be plugged or welded unless approval is granted by the procuring agency.

3.7 Riveting.- Thickness of counter-sunk metal which accepts the heads of flush rivets shall be not less than the height of the rivet heads. The distance from the centers of rivet holes to the edges of the material in which the holes are formed shall be at least 1-1/2 times the rivet diameter. Rivets shall be used where practicable in preference to other means of securing aluminum structural parts if the joint is subjected to dynamic tension loads when the equipment is exposed to specified service conditions and if the parts do not require removal when the equipment is serviced. After riveting, the joints shall be tight, the joined parts shall be undamaged, and the rivet heads shall be properly seated and tight against their bearing surfaces.

3.8 Welding.- Welds shall be of ample size. Where tack or spot welds are employed, the number of welds shall be sufficient to provide adequate strength and at least two welds shall be used to hold each welded part. Spot or tack welds in aluminum or magnesium shall be limited to lightly stressed, noncritical structures. Wherever practicable, the welded joint shall conform to Standard MIL-STD-22, and shall be such that grinding on the finished weld will be unnecessary.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

3.8.1 Cleaning.- Surfaces to be welded shall be cleaned in accordance with good commercial practice and shall be free from rust, scale, paint, grease, and other foreign material. Welded assemblies shall be cleaned to remove scale, oxidation products, and excess flux by sandblasting, wire brushing, or other suitable means. Acid used for cleaning shall be completely neutralized and removed.

3.8.2 Process.- Preheating shall be employed where distortion is likely to result from welding. Welds shall have thorough penetration and good fusion and shall be free from scabs, blisters, abnormal pock marks, and other harmful defects. Where undesirable internal stresses are likely to result from welding, the welded assembly shall be stress-relieved. Inert-gas-shielded arc welding shall be used, when practicable, for welding of aluminum or magnesium.

3.8.3 Non-visual defects.- Welding, when subjected to the test of 4.15, shall evidence good fusion and shall be free of cracks, voids, and slag inclusions.

3.9 Tropicalization.-

3.9.1 Treatment of assembled equipment.- Assembled equipment shall be treated in accordance with Specification MIL-T-152 unless both of the following conditions are met:

(a) Each component part and subassembly meets one of the following:

(1) It is furnished under an individual, detailed Government document (specification, standard, drawing, etc.) which is applicable on contract.

(2) It does not incorporate any material listed in 3.9.3 unless the material has been given the treatment specified herein or a treatment approved by the contracting officer.

(3) It does not comply with (1) or (2) above but its use has been approved by the contracting officer for the particular application.

(b) The finish of the interior of the equipment meets the requirements of Specification MIL-F-14072.

3.9.2 Treatment of materials.-

3.9.2.1 Treating materials.- Treating materials containing a mercury-bearing fungicide shall not be used. The contractor shall determine that the treating material is compatible with the material or surface to be treated. Selection of treating materials shall be such that any increase in flammability of treated material is held to the practical minimum.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

3.9.2.2 Toxicity.- Treatment of materials shall cause no skin irritation or other injury to personnel handling the treated material either during fabrication of the equipment or when carrying, operating, or maintaining the equipment, or in use of the finished items when used for the purpose intended.

3.9.2.3 Flexibility.- Treatment shall not affect flexibility of treated materials, to the extent that the equipment may fail to meet specified requirements when subjected to specified service conditions.

3.9.2.4 Statement of treatment.- The contractor shall submit, to the contracting officer for approval, a statement describing in detail the materials to be treated and the treating materials and processes that he proposes to use. When assembled equipment is treated in accordance with Specification MIL T-152, the above statement shall be incorporated in the statement of treatment required by that specification.

3.9.3 Materials not resistant to moisture and fungi.- The following materials are considered not resistant to moisture and fungi:

(a) Cellulose, regenerated.
(b) Cotton.
(c) Cork.
(d) Felt, hair or wool.
(e) Jute.
(f) Leather.
(g) Linen
(h) Paper, paperboard, cardboard, organic fiberboard, vulcanized fiber, etc.
(i) Thermosetting plastic materials using cotton, linen, or wood-flour as a filler or base.

3.10 Finish, protective.- Units shall be given protective finish in accordance with Specification MIL-F-14072. This includes finish of hardware, such as handles, hinges, screws, etc, and necessary touch up after mounting. The final paint film on type I surfaces shall be green color (olive drab), semigloss enamel matching a color chip provided by the procuring agency. (See 6.4.)

3.11 Marking.- Marking shall conform to Specification MIL-M-13231.

3.11.1 Visibility.- Wherever practicable, parts and assemblies shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.11.2 Serial numbers.- The following items shall be serial numbered:

(a) Pedestal, Antenna AB-594( )/GL

(b) Case, Antenna Support, CY-2212( )/GL

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

3.12 Interchangeability.- Corresponding units and replaceable assemblies, subassemblies, and parts on contract shall be physically and functionally interchangeable as complete items without modification thereof or of other articles with which the items are used. (See 4.7.)

3.13 Service conditions.-The equipment shall meet the following service conditions:

3.13.1 Equipment nonoperating.-The equipment shall comply with the operational requirements of 3.13.2 after subjection to any of the following nonoperating conditions successively or in combinations encountered during worldwide short-term storage and transit:

(a) Temperature.- Exposure in the range of +160°F to -80°F; however, exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 24 hours at any one time. (See 4.12).

(b) Relative humidity.- Relative humidity up to 97 percent, for an indefinite period of time; and exposure at 100 percent relative humidity, with condensation, for 4 hours. (See 4.8.)

(c) Elevation.- Elevation up to 25,000 feet above sea level.

(d) Immersion.- Three feet of water for 2 hours. (See 4.6.)

(e) Vibration, and shock.- As described in 3.14.

3.13.2 Equipment operating.- The equipment shall meet the performance requirements of this specification while subjected to any of the following conditions successively or in combinations likely to be encountered during worldwide operations:

(a) Temperature.- Ambient temperature in the range of +125°F to -25°F. (The 125°F temperature includes effect of sun-load.) Exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 72 hours. (See 4.12.)

(b) Relative humidity.- Relative humidity up to 97 percent; and exposure at 100 percent relative humidity, with condensation, for 4 hours. (See 4.8.)

(c) Elevation.- Elevaton up to 10,000 feet above sea level.

(d) Rain. - Two inches of rainfall per hour, with wind at nominal 20 miles per hour. (See 4.9.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

(e) Winds.- Winds up to 100 miles per hour. When mounted on a flat surface and within the inherent design limits when installed atop Mast AB-275( )/U or Tower TR-29( ).

(f) Salt spray.- Exposure to salt laden air as encountered in coastal areas. (See 4.10)

3.14 Vibration and shock.-

3.14.1 Vibration.- Except for internal resonance of specified parts and sub-assemblies, the equipment shall have no mechanical resonance below 55 cycles per second.

3.14.2 Shock.- The equipment shall meet the full specification requirements after being subject to drop shock test specified in 4.11. Minor mechanical damage is permissible.

3.15 Preproduction samples.- The contractor shall furnish preproduction samples for approval, as required by the invitation for bids and contract. (See 6.2(c)(1).)

3.16 Technical literature, tools, and running spare parts.- Technical literature, tools, and running spare parts shall be furnished as specified in the contract. Running spare parts shall be identical to corresponding parts in the items furnished on the order. (See 6.2.)

3.17 Workmanship.- The item shall be manufactured and assembled in accordance with the applicable portions of the following paragraphs herein:

3.6	Castings	3.8	Welding	3.9	Tropicalization
3.7	Riveting	3.8.1	Cleaning of welding	3.10	Finish
		3.8.2	Process for welding	3.11	Marking

4. QUALITY ASSURANCE PROVISIONS

4.1 Contractor responsibility.- Unless otherwise specified herein the supplier is responsible for the performance of all inspection requirements prior to submission for Government inspection and acceptance. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order.

4.2 Classification of inspection.- Inspection shall be classified as follows:

(a) Preproduction inspection (does not include preparation for delivery). (See 4.3.)

(b) Procurement inspection.- (Procurement inspection shall be the inspection performed by the contractor and by the Government, as specified by 4.4 and 4.17.)

(1) Procurement inspection of items before preparation for delivery. (See 4.4.)

(2) Procurement inspection of preparation for delivery. (See 4.17 and section 5.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

4.3 Preproduction inspection.- This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the preproduction inspection specified in table I and the group A and group B inspection specified in table II and III, respectively. Other nondestructive tests on preproduction samples may be performed to determine compliance with specified requirements. The preproduction inspection will normally be performed in this order: (1) vibration, (2) shock, drop, and (3) immersion; other preproduction inspection may precede, follow, or be interspersed between the foregoing.

Table I .- Preproduction Inspection

Inspection	Req Par	Insp Par
Altitude	3.13.2	4.5
Immersion	3.13.1	4.6
Moisture Resistance	3.13.2	4.8
Rain	3.13.2	4.9
Salt Spray	3.13.2	4.10
Shock, drop	3.14.2	4.11
Temperature	3.13.2	4.12
Vibration	3.14.1	4.13
Winds	3.13.2	4.16

4.4 Procurement inspection of items before preparation for delivery.- The contractor shall perform the inspection specified by (a) through (c) below, to demonstrate compliance with specified requirements. However, this does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government--at its discretion--may perform all or any part of the inspection specified in (a), to verify the contractor's compliance with specified requirements. (The amount of such verification inspection will depend on the extent to which the contractor's inspection procedures and records insure that the equipment on contract meets the specified procurement inspection. Also see 6.5.)

(a) Procurement inspection shall consist of group A and group B, inspection as specified in 4.4.1 through 4.4.3.

(b) When Standard MIL-STD-105 specifies actions by the Government, the Government may authorize the contractor to perform any of such actions except that responsibility for acceptance rests with the Government.

(c) Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. However, the order may be varied when it is considered more practical to select separate samples for group B inspection.

4.4.1 Group A inspection.- This inspection (including sampling) shall conform to table II and Standard MIL-STD-105. Unless otherwise specified, normal inspection shall be used at thestart of the contract. Group A inspection shall be performed in any order which is satisfactory to the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

Table II. - Group A inspection

Inspection	Rqt. Par.	Insp. Par.	AQL Major	AQL Minor
Visual and mechanical	3.17	4.14		
Support, Antenna AB-461( )/GL	3.2	4.14	1.0%	4.0%
Pedestal, Antenna AB/594( )/GL	3.2	4.14	1.0%	4.0%
Guys	3.2	4.14	2.5%	6.5%
Mast support ring	3.2	4.14	2.5%	6.5%
Radome CW-104( )/AP	3.3	4.14	1.0%	4.0%
Case, Antenna Support CY-2212( )/GL	3.4	4.14	1.0%	4.0%
Welding	3.8	4.15	1.0%	

4.4.2 Group B inspection.- This inspection (including sampling) shall conform to table III and the Appendix to Standard MIL-STD-105. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R-1. Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with 4.4.3 and the requirements of Standard MIL-STD-105 for disposition of rejected product. The AQL shall be 6.5 percent defective and the inspection level shall be L-7 for normal and tightened inspection and L-5 for reduced inspection.

4.4.2.1 Order of inspection with group B.- Group B inspection shall be performed in any order which is satisfactory to the Government.

Table III.- Group B inspection

Inspection	Rqt Par	Insp Par	AQL
Interchangeability	3.12	4.7	6.5%

4.4.3 Disposition of nonconforming product.- When defective sample units or failed inspection lots are submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

4.5 Altitude test.- The equipment, in its transit case, shall be placed in a pressure chamber and the pressure reduced to 11.1 inches of mercury, simulating an elevation of 25,000 feet above sea level, and maintained in this condition for one hour. The pressure shall than be raisei to 20.6 inches of mercury, simulating an elevation of 10,000 feet above sea level, and maintained in this condition for one hour. The pressure shall then be raised to 29.9 inches of mercury simulating ambient atmospheric pressure at sea level and the equipment shall be inspected for any degradation in performance.

4.6 Immersion test.- The equipment, as prepared for field transportation, shall be immersed to a minimum depth of 3 feet of fresh water for 2 hours. Immediately prior to immersion, the temperature of the equipment shall be 40°F, or more, above the temperature of the water. The tank in which the equipment is immersed shall be of sufficient capacity to maintain the water within ±2°F of its initial temperature, or the temperature of the water shall be maintained within those limits by other means. After completion of the 2-hour period of immersion, the equipment shall be removed from the water and wiped dry on exterior surfaces. When the case is opened, there shall be no evidence of leakage.

4.7 Inspection for interchangeability. - All removable and replaceable components shall be inspected to determine compliance with the physical interchangeability requirement of 3.12. The dimensions listed below shall be gaged or measured.

(a) External and internal dimensions of cases and covers when such dimensions affect mating of parts.

(b) Location of fasteners on separable parts which must mate, such as cases, covers, and mountings.

4.8 Moisutre-resistance test for equipment. - The equipment shall be tested as follows:

4.8.1 Test method. -

(a) Dry at 130° ±5°F for 24 hours.

(b) Condition at 77° ±5°F and 40 to 50 percent relative humidity for 24 hours.

(c) Make inspection as specified in 4.8.2.

(d) Subject to continuous cycling for five 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Standard MIL-STD-170.

(e) After cycling has been completed, condition the equipment for 24 hours at 77° ±5°F and 40 to 60 percent relative humidity. No repair or replacement of parts shall be made. The equipment shall meet full specified performance for the inspection specified in 4.8.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

4.8.2 Performance. - Inspection made during test, and specified performance during cycling, shall be as follows:

Paragraph	Measurement	Performance during cycling
4.14	Visual and mechanical	Full specification requirements

4.9 Rain test. - The equipment, out of its transit case, shall be tested, step by step, as follows:

4.9.1 Dry at 125° ±5°F for 48 hours.

4.9.2 Condition for 4 hours at 77° ±5°F and 40 to 60 percent relative humidity.

4.9.3 Open and inspect the interior of the housing. There shall be no evidence of moisture, in any form.

4.9.4 Place the component, in its normal operating position, in a test chamber maintained at 77° ±5°F. Allow simulated rainfall to fall on exposed surfaces of the component. The water shall be at a temperature of 65° ±5°F and shall fall freely at a rate of 2 inches per hour. Maintain this condition for 1 hour.

4.9.5 With the rainfall continuing at the 2-inch rate, introduce a simulated wind blowing horizontally at 20 ± 5 miles per hour against one side of the component. The water shall fall on exposed surfaces and be blown by the wind against one side of the component. Maintain this condition for 1 hour.

4.9.6 Rotate the component 90 degrees horizontally, to expose a second side of the component to the wind and rain. Maintain this condition for 1 hour.

4.9.7 Continue as in 4.9.6, until all four sides of the component have been exposed to the wind and rain, each side for 1 hour.

4.9.8 Open the component. There shall be no visible evidence of leakage.

4.10 Salt spray.- The equipment shall be subjected to a salt spray test in accordance with Method 101A, condition B of Standard MIL-STD-202. No permanent degradation in the finish or performance shall be evident.

4.11 Shock test; drop.- The equipment, in its transit or combination case, shall be subjected to the drop test in accordance with table IV. The floor or barrier receiving the impact shall be of 2-inch fir backed by concrete or a rigid steel frame.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

Table IV.- Drop test

Weight of equipment including case	Largest dimension of case (inches)	Notes	Height of drop (inches)	Number of drops
Under 100 pounds	Under 36	A	48	Drop on each face, edge, and corner. Total of 26 drops.
	36 and over	B	30	
100 to 200 pounds inclusive	Under 36	A	30	
	36 and over	B	24	
Over 200, through 1000 pounds	Under 36	B	24	Drop on each corner. Total of 8 drops.
	36 to 60	C	36	
	60 and over	C	24	
Over 1000 pounds	60 and over	C	12	

NOTE A: Drops shall be made from a quick-release hook; or pendulum tester as made by the L.A.B. Corporation, Skaneateles, New York.

NOTE B: Drops shall be made from a quick-release hook.

NOTE C: With its longest dimension parallel to the floor, the transit or combination case, with the equipment within, shall be supported at the corner of one end by a block 5 inches in height, and at the other corner of the same end by a block 12 inches in height. The opposite end of the case shall then be raised to the specified height and allowed to fall freely.

4.12 Temperature test for equipment.- The equipment shall be subjected to the temperature cycle shown on Standard MIL-STD-169. Inspections shall be made as follows:

Paragraph	Step	Measurement	Test results
4.14	4 and -25°F	Visual and Mechanical	Full specification requirements

4.13 Vibration test.- The equipment shall be tested for resonant frequencies below 55 cycles per second, to determine compliance with 3.14.1, as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

(a) The equipment shall be fastened in its normal mounting position on a vibration table that can be controlled within 10 percent of the specified amplitude. The vibration table shall provide approximately sinusoidal vibration. (See 4.13(d).)

(b) The equipment shall be vibrated successively in three mutually perpendicular directions that are parallel respectively to the edges of the equipment, over a frequency range of 10 to 55 cycles per second, in 1-cycle-per second steps. The total excursion shall be constant at 1/64 inch.

(c) Mechanical resonance, if any, of the complete structure, of subassemblies, and of component parts shall be determined visually by means of a Strobotac, as made by the General Radio Corporation, Cambridge, Massachusetts, or equal, or by energizing the equipment and detecting mechanical vibration through electrical output indications.

(d) If it is not practical to determine completely any mechanical resonances on the assembled equipment unit because the unit weighs more than 250 pounds or because of its compactness or the inaccessibility of its subassemblies or component parts, the unit shall be broken down into logical subassemblies for the above vibration test. Such subassemblies shall be secured to the vibration table in the same manner as they are secured in the equipment unit.

4.14 Visual and mechanical inspection.- Parts and components shall be inspected for workmanship, mechanical fit, loose nuts, screws, and markings and miscellaneous defects. Fastening devices shall be inspected for mechanical operation. Welds, finishes, etc., shall be inspected for workmanship. Clearances, dimensions, and mechanical adjustments shall be measured. Labels and markings shall be inspected for conformance with approved facsimiles, when facsimiles are required. Examination also may be made of other visual or mechanical defects, similar to those described above, that are contrary to specified requirements for the equipment. Visual and mechanical defects shall be classified by the Government as major or minor in accordance with the definitions of Standard MIL-STD-105.

4.15 Welding inspection.- Welding shall be inspected by the magnetic particle method specified in Specification MIL-M-11473 and by the ultrasonic method using a Reflectoscope, as made by Sperry Products, Incorporated, Danbury, Connecticut, or equal. Both tests shall be performed on each sample unit.

4.16 Winds.- The assembled equipment, in operating position, shall be subjected to forces which simulate wind blowing horizontally at 100 miles per hour for a period of two hours. There shall be no evidence of damage to the equipment after being subjected to this condition.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

4.17 Procurement inspection of preparation for delivery.- The contractor shall perform the inspection specified by 4.17.1 and 4.17.2, to demonstrate compliance with specified requirements. However, this does not relieve the contractor of responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government--at its discretion--may perform all or any part of the inspection specified in 4.17.1 and 4.17.2, to verify the contractor's compliance with specified requirements. (The amount of such verification inspection will depend on the extent to which the contractor's inspection procedures and records insure that the equipment on contract meets the specifies procurement inspection. Also see 6.5.) When Standard MIL-STD-105 specified action by the Government, the Government may authorize the contractor to perform any of such actions except that responsibility for acceptance rests with the Government.

4.17.1 Preservation and packaging.- Inspection of preservation and packaging shall be as specified in Specification MIL-P-116. Classification of defects shall be as shown on table V.

TABLE V

PRESERVATION, AND PACKAGING AND MARKING THEREOF

MAJOR	MINOR
1. Use of improper or defective material.	1. Item not properly blocked or braced within the unit package to prevent movement.
2. Cushioning inadequate for the physical and mechanical protection of the item.	2. Packaging material damaged.
3. Stock number omitted, incorrect, or illegible.	3. Any item of marking information other than 3 thru 5 omitted, incorrect, or illegible.
4. Nomenclature omitted, incorrect, or illegible.	
5. Marking of quantity of items in package omitted, incorrect or illegible.	

4.17.2 Packing and marking of exterior containers.- Packing and marking of exterior containers shall be given visual inspection for the defects listed below and to determine conformance with the approved process sheet furnished by the contractor as required by the contract. This inspection shall conform to the Appendix to Standard MIL-STD-105. Inspection level L-8 shall be used for normal inspection and L-6 for reduced inspection. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R-1. The AQL for major defects shall be four percent and the AQL for minor defects shall be ten percent. Classification of defects shall be as shown on table VI.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

TABLE VI

PACKING, AND MARKING THEREOF

MAJOR	MINOR
1. Use of improper or defective material.	1. Unsealed carton.
2. Box closure not as specified.	2. Defective taping or sealing of carton.
3. Type, grade, class, and style of the shipping container not as specified.	3. Any other box defect which may be considered minor by definition of Standard MIL-STD-105.
4. Strapping omitted.	4. Any item of required marking information other than 7 thru 13 listed under major defects omitted, incorrect, or illegible.
5. Strapping inadequate or incorrectly applied.	
6. Shipping documents or packing list omitted.	
7. Stock number omitted, incorrect, or illegible.	
8. Nomenclature omitted, incorrect, or illegible.	
9. Marking of quantity of items in pack omitted, incorrect, or illegible.	
10. Destination marking omitted, incorrect, or illegible.	
11. Service designation (color marking) omitted.	
12. Specified special marking and labeling such as MAP labels, shipment digit markings, etc., omitted, incorrect, or illegible.	
13. Overseas code marking omitted, incorrect, or illegible.	

4.17.2.1 Inspection lot.- A lot for visual inspection of the pack shall be all completed packs which are identical and will be submitted for acceptance at one time.

4.17.2.2 Disposition of nonconforming product.- Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with the requirements of Standard MIL-STD-105 for disposition of rejected product. When submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.18 Rough handling test (preparation for delivery). - When rough handling test in accordance with Specification MIL-P-116 is required by the contract (see 6.2(c)), the following functional tests shall be conducted to determine freedom from operational malfunction caused by the rough handling:

4.14 Visual and mechanical

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 Level A.- Support Antenna AB-461( )/GL shall be preserved, packaged and tested in accordance with the procedures specified for the designated methods as prescribed in Specification MIL-P-116 and as described herein.

5.1.1.1 Technical manual.- Each technical manual shall be packaged Method IC-3 as follows: Inclose each technical manual within a close-fitting type II class b bag conforming to Specification MIL-B-117. Heat seal the bag to effect closure.

5.1.1.2 Ancillary items.- No packaging is required.

5.1.1.3 Stowage in Case CY-2212( )/GL.- Stow and secure all of the ancillary items of Support Antenna AB-461( )/GL within the assigned compartments of the case. Close the case and secure all fastenings.

5.1.1.4 Case CY-2212( )/GL with contents.-Each case with contents shall be packaged Method IC-5 as follows: Cushion each case on all surfaces with cells or pads or both fabricated of corrugated fiberboard designed to absorb the shock of impact encountered in handling and transit. Fiberboard shall have a dry bursting strength and water resistant qualities equal to the box in which they shall be placed. Placed the cushioned case within a close-fitting regular slotted style corrugated fiber box class 2 W5c conforming to Specification PPP-B-636. Box closure shall be in accordance with the referenced box specification.

5.1.2 Level C.- Support Antenna AB-461( )/GL shall be packaged in accordance with commercial practice and in a manner that will afford protection against corrosion, deterioration and physical damage during direct shipment to the first receiving activity.

5.2 Packing.-

5.2.1 Level A.- Support Antenna AB-461( )/GL, packaged as specified in 5.1.1 shall be packed for shipment, one each within a wood, nailed lock-corner box, wood wirebound box, or cleated plywood box, conforming to Specification PPP-B-621, PPP-B-585 or PPP-B-601. Boxes shall be overseas class or type and shall be fabricated to fit the contents snugly. Place the technical manual (see 5.1.1.1) between the contents and lid of the box. Box closure shall be in accordance with applicable box specification or appendix thereto.

5.2.1.1 Metal strapping.- Shipping containers shall be strapped in conformance with the appendix of the applicable container specification only for direct shipment to ports.

5.2.2 Level B.- Support Antenna AB-461( )/GL shall be packed for shipment as specified in 5.2.1 except boxes shall be domestic class or type. No strapping required.

5.2.3 Level C.- Support Antenna AB-461( )/GL shall be packed for shipment in a manner conforming to Uniform Freight Classification No.4 and Consolidated Freight Classification Rules 21 for rail shipment, National Motor Freight Classification No. A-3 and No. 14 for truck shipment and the regulations of other carriers as applicable to the mode of transportation employed at lowest transportation rate.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

5.3 Marking.- Interior packages and exterior shipping containers shall be marked in accordance with the applicable provisions of Standard MIL-STD-129.

6. NOTES

6.1 Intended use.- Support, Antenna AB-461( )/GL is primarily intended as a mounting for antenna components of Direction Finder Group AN/APA-69( ) on top of Mast AB-275( )/U, Tower TR-29( ), or any flat surface when so desired.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendment thereto.
(b) Level of packaging and level of packing required for shipment. (Level A, level B, level C.)
(c) Preproduction inspection:

(1) Two samples of each item cited in section 1 are generally required so that lengthy environmental tests can be completed on one sample while complete performance measurements can be made on the second sample. (See 3.15)

(2) Preproduction pack(s) as follows:

a. Makeup of pack(s).
b. Number of each kind of pack to be submitted.
c. Inspection to be performed thereon--including rough handling test, which will not be performed as procurement inspection.
d. Five copies of process sheet, using format shown on Drawing SC-C-33073 and accompanied by such drawings, sketches, and other data as may be necessary to completely describe the procedure followed in fabrication of the preproduction pack(s) and to identify the items therein. These data should be submitted to the contracting officer with the preproduction pack.
e. A packaging technician from the procuring agency will evaluate to preproduction pack(s).

(d) Marking and shipping of samples.
(e) Place of final inspection.
(f) Technical literature required. (See 3.16)
(g) Quantity of tools and running spare parts required. (See 3.16)
(h) Submission of the statement of treatment referenced in 3.9, as soon as possible after award of contract. This statement should be submitted to the contracting officer.

6.3 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: AB-461W/GL. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.

6.4 Color.- The color chip furnished by the procuring agency will match color chip No. 2430 of superseded Specification TT-C-595, and may be obtained upon request to Commanding Officer, U. S. Army Signal Supply Agency, 225 South Eighteenth Street, Philadelphia 3, Pennsylvania, ATTN: SIGSU-J4b. This color chip does not match any color chip of Federal Standard Number 595.

6.5 Verification inspection.- Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product, and will normally be identified by the categories listed below:

(a) Type A--The total of that inspection set forth in the Quality Assurance Provisions of this specification or the contract. Included in this category is that amount of inspection referred to as normal and tightened inspection by Military Standard 105.

(b) Type B--That inspection set forth in the Quality Assurance Provisions of this specification or the contract reduced in amount under the reduced inspection provisions of Military Standard 105.

(c) Type C--A reduced inspection procedure resulting in a material reduction in the amount of inspection set forth in the Quality Assurance Provisions of this specification. The amount of inspection is less that the provided for in type B and is based upon a consistently acceptable product resulting from a planned quality control system voluntarily employed by the contractor in the production of the product.

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:13Z
Check the source to verify that this is the current version before use.