MIL-D-44144A(GL)
22 December 1986
SUPERSEDING
MIL-D-44144(GL)
27 September 1984

MILITARY SPECIFICATION

DRYING TUMBLER, LAUNDRY

This specification is approved for use by the U.S. Army Natick Research, Development, and Engineering Center, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense,

1. SCOPE

1.1 Scope. This document covers a fuel fired drying tumbler (see 6.1) with a load capacity of not less than 120 pounds dry weight of laundry per hour.

2. APPLICABLE DOCUMENTS

2.1 Government documents,

2.1.1 Documents. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

SPECIFICATIONS

FEDERAL

HH-I-553 - Insulation Tape, Electrical (Rubber, Natural and Synthetic)
QQ-S-571 - Solder, Tin Alloy: Tin Lead Alloy; and Lead Alloy

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3510

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-T-152	Treatment, Moisture and Fungus-Resistant, of Communications, Electronic, and Associated Electrical Equipment
MIL-T-704	Treatment and Painting of Material
MIL-B-844	Blankets, Bed, Wool, Shrink Resistant and Mothproofed
MIL-L-3153	Laundry and Dry Cleaning Machinery and Equipment (For Fixed Installations), Preparation For Delivery Of
MIL-S-36868	Sheet, Bed, Cotton, White, Fitted Style
MIL-T-44047	Trousers, Camouflage Pattern; Combat
MIL-L-44142	Laundry Unit, Trailer Mounted

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-130	Identification Marking of US Military Property
MIL-STD-195	Marking of Connections for Electrical Assemblies

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

6-1-8771	- Dryer, Diesel Fired, M-85 Laundry
6-1-8774	- Dryer, Diesel Fired, M-85 Laundry Drawing List
6-1-9374	- Finish Requirements, CARC Paint

(Copies of documents required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.1.2 Other Government documents. The following other Government documents form a part of this document to the extent specified herein. Unless otherwise specified. the issues shall be those in effect on the date of solicitation.

OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

29 CFR 1910.264" - Laundry Machinery and Operations

(Copies may be obtained from the superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

2.2 Other publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issues of the DODISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS shall be the issues of the nongovernment documents which are current on the date of the solicitation.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA No. 70 - National Electrical Code

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02169.)

UNDERWRITERS LABORATORIES, INC. (UL) STANDARDS

(Application for copies should be addressed to the Underwriters Laboratories, Inc., 333 Pfingsten Road, Northbrook, IL 60062,)

AMERICAN WELDING SOCIETY (AWS)

Standard Qualifications of the American Welding Society

(Application for copies should be addressed to the American Welding Society, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Welding Qualifications of the American Society of Mechanical Engineers

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

(Technical society and technical association documents are generally available for reference from libraries, They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document shall take precedence. Nothing in this document, however, shall supersede applicable laws and regulations unless a specific exemption has been made.

3. REQUIREMENTS

3.1 First article. When specified in the contract or purchase order, a sample shall be subjected to first article inspection (see 4.3, 6.2, 6.3 and 6.3.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

3.2 Codes and standards. The tumblers shall comply with the applicable requirements of NFPA 70, UL and OSHA 29 CFR 1910.264. Satisfactory evidence that these requirements have been met shall be submitted to the contracting officer or his authorized representative prior to the start of production (see 4*5)*

3,3 Materials and components. Materials and components shall be as specified herein and on the applicable drawings. Materials and components not definitely specified shall be of the quality normally used by the manufacturer provided the completed item complies with all provisions of this document(see 6.4).

3.4 Alternate components. Components offered as equivalent to components specified herein and on the referenced drawings as a specific manufacturer's part number or equal shall be functionally equal with the manufacturer's part number identified. The incorporation of such a component in the design of the specified end product shall not require modification to any components, unless such modification is specifically approved by the contracting officer. Prior to commencing production, the contractor shall submit for the contracting officer's approval, a list identifying each alternate component, together with proof that each listed component complies with requirements specified above. The contracting officer, at his option, may require a physical sample of the proposed substitution. Approval of the submitted listing, together with necessary supporting data does not relieve the contractor of the responsibility that these components perform in accordance with specified requirements when incorporated into the end product.

3.5 Design and construction. The design and construction of the drying tumbler shall be as specified herein and as shown on Drawing 6-1-8771. Wiring specified herein and all wiring not delineated on the applicable detail drawings shall be done in accordance with NFPA 70. All wires or wiring shall be identified in accordance with the applicable wiring diagrams and marked in accordance with MIL-STD-195. Unless otherwise specified on the detail drawings, all wiring connections shall be soldered, or have staked connections, The solder shall conform to type R of QQ-S-571 and the tape shall conform to HH-I-553. The polarity of the wiring connections in the installation of the equipment shall be such that the electric motors operate in the proper direction when tested as specified in 4.6.1. All motors shall have windings impregnated to resist moisture. Unless otherwise specified (see 6.2), electrical components of equipment shall be moisture and fungus-resistant treated with materials conforming to, and applied as specified in MIL-T-152. Each item or subassembly shall be treated and painted in accordance with Drawing 6-1-9374 as specified on the applicable item drawing. "

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

3.6 Performance.

3.6.1 Endurance. The drying tumbler shall operate for 20 hours when tested as specified in 4.6.1. There shall be no damage to any component throughout the test and all electrical and mechanical components shall function properly, There shall be no evidence of the following conditions during the test:

a. Improper interrelationship of components.
b. Improper sequence of operational control devices.
c. Overheated bearings.
d. Structural failures,
e. Improper fit, tightness or alignment of components.
f. Improper cycle time.
g. Improper operation of controls.
h. Excessive vibration,
i. Excessive noise.

3.6.2 Drying of sheets, blankets and trousers. The drying tumbler shall dry cotton sheets (MIL-S-36868), wool blankets (type I or 11 of MIL-B-844) and trousers (MIL-T-44047) when tested as specified in 4.6.2. Dry for cotton and wool shall be defined as not more than 5 percent moisture content or when normal dry weight is increased by not more than 5 percent. Dry for trousers shall be defined as not more than 7 percent moisture content. When tested as specified in 4.6.2, the final drying weights of the materials shall be as follows:

a. Blankets 31.5 pounds
b. Sheets 31.5 pounds
c. Trousers 32.1 pounds

3.6.3 Door switch. The door switch shall prevent operation of the burner assembly and tumbler drive motor when tested as specified in 4.6.3 and 4.6.4,

3.6.4 Post purge control. The post purge control shall cause excess combustion by products to be exhausted from the burner chamber and flexible metal exhaust hose when tested as specified in 4.6.4 and 4.6.5.

3.6.5 High limit control. The high limit control shall be factory preset at 275°F and shall be normally closed and shall open on temperature rise. The control shall deactivate the burner when tested as specified in 4.6.6.

3.6.6 Operating control. The operating control shall allow the exhaust air temperature to be within ± 10°F for the 135° and 200° temperature settings and ± 15°F for the 2500 temperature setting when tested as specified in 4.6.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

3,6.7 Flame safeguard control. The flame safeguard control shall be capable of operating in ambient temperatures from -40°F to 125±F. The flame pickup scanner shall be capable of operating in ambient temperatures from -40°F to 212°F. The control shall provide an initial startup flame failure lockout as specified in 3.6.7.1 and a firing period flame failure lockout as specified in 3.6,7.2,

3.6.7.1 Flame failure, initial start safety lockout. When tested as specified in 4.6.8 the flame safeguard control system shall operate in sequence as follows (± 2 seconds):

a. Provide a 7 second purge.

b. Provide a 10 second trial for ignition. No flame will be picked up by the sensor and the fuel solenoid valve and ignition transformer shall be de-energized by the safeguard control at the end of this 10 second period (lockout).

c. The blower shall continue to operate and purge the system for 60 (± 5) seconds after lockout occurs.

d. An alarm signal shall activate no more than 90 seconds after start-up,

3.6,7.2 Flame failure, firing period safety lockout. When tested as specified in 4.6.9 the flame safeguard control system shall operate in sequence as follows (± 2 seconds):

a. Provide a 4 second response time to de-energize the fuel solenoid valve after flame failure.

b. Provide a 10 second purge cycle.

c. Provide a 10 second trial for ignition (activation of fuel solenoid and ignition spark). No flame will be picked up by the sensor and the fuel solenoid and ignition transformer shall be de-energized by the safeguard control at the end of this 10 second period (lockout),

d. The blower shall continue to operate and purge the system for 60 (± 5) seconds after lockout occurs.

e. An alarm signal shall activate no more than 90 seconds after manual fuel valve is turned off.

3.6.8 Signal flame. The flame control shall not be effected by the ignition spark and shall have a failure response time of less than 6 seconds, when tested as specified in 4.6.10,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

3.6.9 Signal device. An audible signal device and visible warning light shall activate when tested as specified in 4.6.11.

3.7 Marking. Marking for identification shall be in accordance with MIL-STD-130.

3.8 Workmanship, The units shall be free from fractures, splits, punctures, tears, dents, creases, bows, miscasts, deteriorations or malformations. There shall be no sharp edges, burrs or slivers, The finish shall be free of blisters, orange peel, color separation, chipped areas or areas of no film. The finish shall be free from smudges, poor touch up, scale, scratches, stain, overspray, sag, imprint or embedded foreign matter, Threaded fasteners shall not be broken, stripped or loose. Holes for rivets shall be accurately punched or drilled and any burrs that would prevent proper seating of the rivet shall be removed. Rivets shall completely fill the holes, with full size heads neatly finished and in full contact with the surface of the riveted members and shall not be loose.

3.8.1 Welding. The surfaces of parts to be welded shall be free from oxide, scale, paint, grease, and other foreign matter. Welds shall be continuous, sound smooth, and free from porosity, cracks, incomplete fusion, and deformation of material. All scale and flux deposits (when flux is used) shall be removed from the finished welds, and rough edges and projections shall be dressed smooth.

3.8.2 Electrical wiring. Wiring shall not be cut, abraded, or have excessive insulation stripped, and shall be properly and tightly joined at terminals. Wiring shall have adequate slack to provide strain relief.

3.8.3 Welders. Before assigning any welder to work, the contractor shall provide the contracting officer, or his authorized representative, with the names of welders to be employed in the work, together with certification that each of these welders has passed a qualification test as prescribed by either of the following listed codes for the type of welding operation to be performed, and that such qualification is effective as defined by that particular code as follows:

a. Standard Qualification Procedure of the American Welding Society.
b. Welding Qualification of the American Society of Mechanical Engineers,

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements .

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this document shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the document shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for assuring that all specified dimensions have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point, or at all points ion the manufacturing process necessary to assure compliance with all dimensional requirements.

4.1.3 Certificates of compliance. When certificates of compliance are submitted, the Government reserves the right to inspect such items to determine the validity of the certification.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

4.3 First article inspection. When a first article is required (see 3.1), it shall be examined for the defects specified in table I and 4.4.3 and tested as specified in 4.6.1 thru 4.6.11 and, when required (see 6.3.1), the road and terrain and rail impact tests as specified in MIL-L-44142. The presence of any defect or failure to pass any test shall be cause for rejection of the first article.

4,4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this document or applicable purchase document.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

4.4.1,1 In-process inspection, Examination of the surface preparation prior to welding shall be made to determine compliance with 3.8.1. Examination of surface preparation, pretreatment and priming prior to each succeeding phase and top coating shall be made to determine compliance with Drawing 6-1-9374 and MIL-T-704. Whenever nonconformance is noted, correction shall be made to the applicable process and all affected items processed.

4.4.2 End item visual examination, The end items shall be examined for the defects listed in table I. The lot size shall be expressed in units of drying tumblers. The sample unit shall be one drying tumbler. The inspection level shall be II and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 2.5 for major defects and 6.5 for total (major and minor combined) defects.

TABLE I. End item visual defects

Examine	Defect	Classification Major	Minor
Finish	Finish not as specified	X	
	Blistered, peeled, chipped, or area of no film		X
	Poor touch-up, orange peel, color separation, smudge, scale, scratched, stained, overspray, sag, imprint, or foreign matter imbedded		X
Design, construction and workmanship applicable to all components and assemblies	Any component or part missing or not specified type or size	X	
	Any component that does not function, malfunctions, or is misplaced to the degree that it does not serve its intended purpose	X	
	Not fabricated as specified by the document or drawing	X	
	Not clean (evidence of oil, grease, or dirt)		X
	Sharp edge or burr		X
	Puncture, fracture, or malformed	X	
	Design detail deviating from document or drawing requirements	X	
	Evidence of scale, rust, discoloration, or deposit of any foreign matter		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor
Design, construction and workmanship applicable to all components and assemblies (cont'd)	Finish omitted or not as specified:		
	a. On brass or aluminum components		X
	b. On steel components	X	
	Area of partial or no finish		X
Riveting	Mating surfaces of riveted components not drawn up tightly	*	
	Rivet head not in contact with its mating surface	*	
	Rivet loose - not properly set	*	
	Roll of a rivet contains more than one split		X
	Portion of a rivet is set or rolled on itself in lieu of being set or rolled on the mating surface of component	X	
Welding	Missing, incomplete, cracked, fractured, or not fused	X	
	Undercut, not smooth and uniform, or scale or flux deposits not removed		X
Soldering (when applicable)	Missing, not adherent, or incomplete		X
	Not clean (flux residue not removed, pinholes in solder)		X
Bolts, nuts, screws, studs, and other types of threaded fasteners	Broken, stripped, fractured, or not tight		X
Electrical assembly	Wiring cut, abraded, or not properly installed or joined	X	
	Adequate slack not provided for wiring to relieve strain		X
Marking	Missing; incorrect; incomplete; illegible; of improper size, location, sequence, or method of application	X	

NOTE: Defects designated by an asterisk (*) shall be scored as "major" when seriously affecting serviceability or appearance and "minor" when affecting serviceability or appearance but not seriously.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

4.4.3 End item dimensional examination. The end item shall be examined for compliance with dimensions specified. The lot size shall be expressed in units of drying tumblers. Any dimension that is not within the specified tolerance shall be classified as a defect. The sample unit shall be one drying unit. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units shall be 6.5.

4,4.4 End item testing. Each production end item shall be tested for the characteristics listed in table II. Failure of any test shall be cause for rejection of the end item involved.

TABLE II. Performance tests

Characteristic	Requirement paragraph	Test method
Endurance	3.6.1	4.6.1
Drying of sheets, blankets and trousers	3.6.2	4.6.2
Door switch	3.6.3	4.6.3 and 4.6.4
Post purge control	3.6.4	4.6.5
High limit control	3.6.5	4.6.6
Operating control	3.6.6	4.6.7
Initial start lockout	3.6.7.1	4.6.8
Firing period lockout	3.6.7.2	4.6.9
Signal flame control	3.6.8	4.6.10
Signal device	3.6.9	4.6.11

4.4.5 Packaging examination. An examination shall be made to determine that preservation, packaging, and marking comply with the requirements of MIL-L-3153.

4.5 Code and standard compliance. Certifications, certified 'test reports, or listing marks for standards submitted in accordance with 3.2 shall be examined and validated as proof of compliance. Prior to Government approval of first shipment, the contractor shall submit to the contracting officer or his authorized representative for approval, certification that the drying tumblers he proposes to furnish under this document meet the applicable requirements of NFPA 70, and UL and OSHA 29 CFR 1910.264 as follows:

4.5,1 NFPA. Acceptable evidence of meeting the requirements of NFPA shall be the manufacturer's certified statement that the tumbler is wired for use in non-hazardous locations in accordance with NFPA Standard 70.

4.5.2 UL. Acceptable evidence of meeting the requirements of UL shall be the UL listing mark, or a certified test report from a recognized independent testing laboratory, acceptable to the Government indicating the the tumbler wiring, fittings and conduit conform to applicable UL requirements as specified on the applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

4.5.3 OSHA. Acceptable evidence of meeting the requirements of OSHA shall be a certificate of compliance certifying that the drying tumblers being furnished under this document conform to the applicable requirements for laundry equipment 29 CFR 1910.264 of OSHA Standard. The Government reserves the right to check test such tumblers to determine the validity of the certification,

4.6 Methods of inspection. Commercial power source and No. 2 diesel fuel shall be used for the applicable tests.

4.6.1 Endurance test. The drying tumbler motors shall be check-tested for proper motor rotation. Motors with improper rotation shall be corrected, Each dryer shall then be loaded and operated (see table 111) at a rate of four drying cycles per hour. Any nonconformance with the requirements of 3.6.1 shall constitute failure of this test.

TABLE III. Endurance test data

Material"	Dry weight (pounds)	Drying temperature (O°F + 10F)	Number of drying cycles	Water retention (percent)	Total weight (pounds)
Trousers	30	135	80 (13 minutes each)	25	37.5

4,6.2 Drying test. Each drying tumbler shall be loaded and operated (see table IV) at a rate of five drying cycles for each material. Any nonconformance with the requirements of 3.6.2 on 80 percent of the cycles shall constitute failure of this test,

TABLE IV. Drying test data

Material	Dry weight (pounds)	Drying temperature (0°F ± 10F)	Water retention (percent)	Total, weight (pounds)	Drying time (minutes)
Trouser	30	135	25	37.5	13
Sheets	30	250	25	37.5	10
Blankets	30	200	25	37.5	13

4.6.3 Door switch test (activation prevention), With the door open push the start switch. The burner shall not turn on and the tumbler shall not be rotating. Any nonconformance with the requirements of 3.6.3 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

4,6.4 Door blower switch test (deactivation), With the door closed set the timer to 10 minutes and start the drying cycle. After three minutes of operation open the door. The burner shall deactivate and the tumbler shall stop rotating, but the burner exhaust blower shall continue to operate for an additional 60 seconds. Any nonconformance with the requirements of 3,6.3 or 3.6,4 shall constitute failure of this test. NOTE: Purge control relay may require adjustment to pass requirements.

4.6.5 Post-purge control test. With the door closed set the timer to 3 minutes and start the drying cycle, At the end of the cycle the burner shall deactivate and the end of cycle signal shall sound. Press the stop button, The tumbler shall stop rotating but the burner exhaust blower shall continue to operate for an additional 60 seconds (± 5 seconds). Any nonconformance with the requirements of 3.6.4 shall constitute-failure of this test.

4.6.6 High limit control test. The operating thermostat shall be electrically bypassed. The dryer shall be activated and operated. At 275° ± 5°F the burner shall deactivate but the burner exhaust motor shall continue to operate for an additional 60 seconds. Any nonconformance with the requirements of 3.6.5 shall constitute failure of this test.

4.6.7 Operating control test, Activate the dryer unit for 15 minutes. Set the operating control at 135°F. Within 5 to 10 minutes, the required temperature shall be reached and the burner shall shut down. Read the temperature gauge located in the hot air exhaust piping. Repeat the above procedure for 200°F and 250°F. Any nonconformance with the requirements of 3.6.6 shall constitute failure of this test.

4.6.8 Flame failure, initial start lockout test. The fuel valve shall be manually closed and the dryer shall be started and tested for initial flame lockout. Any nonconformance with the lockout time or sequence specified in 3.6.7.1 shall constitute failure of this test,

4,6.9 Firing period lockout test. The dryer shall be started and operated for more than 2 minutes. The manual fuel valve shall be closed and the unit shall be tested for flame failure during the firing period. Any nonconformance with the lockout times or sequence specified in 3.6.7.2 shall constitute failure of this test,

4.6,10 Flame, signal test. An ac/dc multimeter with a 20,000 elm/volt dc rating shall be connected to the test jacks of the flame safeguard control, When the flame is detected a steady reading of 5 to 6 volts dc shall be obtained. The dryer shall be started and operated for more than 2 minutes, The manual fuel valve shall then be closed. The time from when the flame is extinguished until the reading is O volts shall not be more than 6 seconds. When the flame is extinguished and the ignition spark is on for ignition retrial the reading shall be O volts. Any nonconformance with the control requirements of 3.6.8 shall constitute failure of this test,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

4.6.11 Signal device test. Press the start button when the flame safeguard is activated (safeguard control has not been manually reset after lockout). Any nonconformance with the requirements of 3.6.9 shall constitute failure of this test.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial as specified (see 6.2), in accordance with the applicable requirements of MIL-L-3153.

5.2 Packing. Packing shall be level A, B or Commercial as specified (see 6.2), in accordance with the applicable requirements of MIL-L-3153.

5.3 Marking. Markings shall be in accordance with MIL-L-3153.

6. NOTES

6.1 Intended use. The drying tumbler is to provide laundry drying service for the troops and hospitals in the field.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number and date of this document.
b. When a first article is required (see 3,1, 4.3, 6.3 and 6.3.1).
c. When moisture and fungus-resistant treatment is not required (see 3.5).
d. Selection of applicable levels of preservation and packing (see 5.1 and 5.2).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article shall be a preproduction sample. The contracting officer shall specify the appropriate type of first article and the number of units to be furnished. The contracting officer shall include specific instructions in all acquisition documents regarding arrangements for selection, inspection, of the first article.

6.3.1 Modified first article testing. When the dryer is procured as part of a contract for fabrication of the Army Trailer Mounted Laundry per MIL-L-44142, the first article dryer will be subjected to the road and terrain and rail impact tests as specified in MIL-L-44142 as part of the first article test for the Army Trailer Mounted Laundry.

6.4 Recycled material. “It is encouraged that recycled material be used when practical as long as it meets the requirements of the document (see 3.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

6.5 Subject term (key word) listing.

Drying tumbler
Laundry

6.6 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:

Army - GL

Preparing activity:

Army - GL

Project No. 3510-A295

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T00:11Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

US Army Natick RD& Engin. Center
ATTN: STRNC-ES
Natick, MA 01760-5014

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick RD& Engineering Center
ATTN: STRNC-ES
Natick, MA 01760-5014

Source: https://assist.dla.mil -- Downloaded: 202610-22T00:11Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-D-44144A (GL)	Drying Tumbler, Laundry

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*:

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

Source: https://assist.dla.mil -- Downloaded: 202610-22T00:11Z
Check the source to verify that this is the current version before use.