MIL-F-38456A(USAF)
28 June 1982
Superseding
MIL-F-38456(USAF)
17 Feb 66

MILITARY SPECIFICATION
FOOD CONTAINER, INSULATED

This specification is approved for use by the Department of the Air Force, and is available for use by all Departments and Agencies of the Department of Defense

1. SCOPE.

1.1 Scope. This specification covers the requirements for food containers to be utilized for domestic and overseas air transporation of fresh and frozen foods.

CNU-39B	Full Size
CNU-38B	Half Size
CNU-37B	Quarter Size

2. APPICABLE DOCUMENTS

2.1 Government douments.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue in the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

Federal

L-P-378	Plastic Film (Polyethylene Thin Gage)
L-S-300	Sheeting and Tape, Reflective; Nonexposed Lens Adhesive Backing.

Military

MIL-P-514	Plates, Identification, Transporation - Data and Blank.
MIL-B-26195	Boxes, Wood-Cleated, Skidded, Load-Bearing Base.
MIL-P-27443	Pallet, Cargo Aircraft, Type HCU-6/E, HCU-12/E and HCU-10/C.

STANDARDS

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: HQ AFLC CASO/LODSA, Federal Center, Battle Creek, MI 49016 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 7330

Source: https://assist.dla.mil -- Downloaded: 202610-21T12:39Z
Check the source to verify that this is the current version before use.

Federal

FED-STD-101	Preservation, Packaging Materials, Test Procedures.
FED-STD-595	Colors.

Military

MIL-STD-100	Engineer Drawing Practices.
MIL-STD-129	Marking for Shipment and Storage.
MIL-STD-143	Specifications and Standards Order of Precedent for Selection of Finishes, Protective and Codes for Finishing Schemes for Ground and Ground Support Equipment.
MIL-STD-808	Environmental Test Methods for Aerospace and Ground Equipment.
MIL-STD-810	Environmental Test Methods.
MIL-STD-889	Dissimilar Metals.

(Copies of documents required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

2.1.2 Other Government documents, drawings, and publications. The following other Government documents form a part of this specification to the extent specified herein.

American Society of Testing Materials Standards

ASTM C-177-63	Standard Method of Test for Thermal Conductivity of Materials by Means of the Guarded Hot Plate.
ASTM-D-1692-59T	Tentative Method of Test for Flammability of Plastics, Foams, and Sheeting.

(Copies of ASTM documents may be obtained from the American Society for Testing Materials, 1916 Race Street, Philadelphia, Pa, 19103).

Joint Committee on Food Equipment Standards.

National Sanitation Foundation Standard No. 1.

National Sanitation Foundation Standard No. 2.

(Application for copies should be addressed to the Joint Committee on Food Equipment, Ann Arbor, MI 48106.)

2.1.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 202610-21T12:39Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS.

3.1 First Article. This specification provides for first article inspection.

3.2 Selection of Specification and Standards. Specifications and standards for necessary commodities and services not specified herein shall be selected in accordance with MIL-STD-143.

3.3 Materials. Materials used in the construction of the food containers shall be the lightest weight possible and consistent with all the requirements specified herein. All parts shall be fabricated of materials which are not susceptible to damage of any kind from exposure to extremes of temperature and humidity as well as any other environmental conditions specified herein. Materials that can impart flavor or odor to food or cause any toxic conditions shall not be used. Materials used shall be insect proof and have minimum hydroscopic tendencies. Materials not specified herein or on drawings shall be the same as used on the manufacturer's standard product.

3.3.1 Reclaimed Materials. The food containers shall contain reclaimed materials to the maximum extent possible without jeopardizing its intended use and performance. The reclaimed materials shall have been processed, remanufactured or recycled in a manner which restores them to the same chemical composition and physical properties as the materials originally selected for use on the food container. Reclaimed materials shall include iron, steel, copper, brass, aluminum, fiber products, platie, elastomers that have been collected from discarded solid, liquid, semi-solid, or gaseous waste such as garbage, refuse, or sludge.

3.3.2 Fungus-proof materials. Materials that are nutrients for fungi shall not be used where it is practical to avoid them. Where used, materials shall be treted with a suitable fungicial agent. The following materials shall not be used:

a. Cellulose regenerated.
b. Cotton.
c. Cork.
d. Felt, hair or wool.
e. Jute.
f. Leather.
g. Linen.
h. Paper, paperboard, cardboard, organic fiberboard, vulcanized fiberboard, et cetera.
i. Thermosetting materials using cotton, linen or wood flour as a filler or base.

3.3.3 Metals. Metals shall be corrosion resistant or suitably heated to resist corrosion due to fuels, salt spray, or atmospheric conditions likely to be met in storage or normal service. Cadmium and magnesium and alloys thereof shall not be used.

3.3.3.1 Dissimilar metals. Unless suitably protected against electrolytic corrosion by metal plating or spraying, dissimilar metals shall not be used in intimate contact with each other. Dissimilar metals are defined in MIL-STD-889.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

3.3.4 Nonmetal exterior surfaces. Nonmetal exterior surfaces shall be primed with epoxy, urethane or polyester reinforced with fiberglass as necessary. The finish coat shall be of the appropriate epoxy, urethane or polyester composition as recommended by the manufacturer and pigmented to the required finish-coat color.

3.3.5 Sanitation. The containers shall conform to the requirements of the National Sanitation Foundation Standards No. 1 and No. 2.

3.4 Design and construction. The container shall be so designed and constructed that no parts will work loose in service. The food container shall be built to withstand shock and environmental conditions specified herein and to withstand conditions incident to domestic and overseas shipment by air transportation along with the associated handling and storage.

3.4.1 The container shall be of sandwich design and constructed of light-weight flame-retardant materials. The core material shall completely fill all voids within the skins not occupied by structural members or by other provisions specified herein. The weight carrying capacity of each container shall be a minimum of 50 pounds per cubic foot of internal volume carrying capacity. The containers shall be designed and constructed as an integral unit which shall not require assembly or attachment of separate parts during usage.

3.4.2 Capacity. The containers shall be designed to provide maximum usable cube. The usable interior volume shall be a minimum of 60 percent of the overall volume within the dimensions specified in 3.11 which shall include the allowance at the bottom for forklift entries.

3.4.3 Forklift entry. Forklift entry openings, which shall be a minimum of 3 1/2 inches high, shall be provided and shall be included in the overall height of the containers. The CNU-38/B and CNU-37/B containers shall permit two way entry and the CNU-39/B shall have four-way entry. Limiting dimensions shall be in accordance with figures 1, 2, and 3.

3.4.4 Stacking. The containers shall be so designed and constructed that when used in any combination of sizes, one layer of containers may be stacked on top of another layer of containers. (see 4.6.16).

3.4.5 Container interior. The interior of the container shall be water-proof, and shall have minimum water transmission and water absorption, and shall not crack, crumble or break. The cover, sides and bottom shall have plain surfaces with external projections not exceeding one-sixteenth of an inch for fastening and joining. Inside seams shall be sealed with a vulcanizing flexible sealant, care shall be taken so that there are no crevices. The seams shall have a minimum of one-eight of an inch radius fillet. The container and sealant shall withstand repeated steam cleanings without damage.

3.4.6 Maintainability. The containers shall have a minimum number of parts consistent with reliability. Maintenance including repairs on shattered or punctured sections, shall be accomplished with tools and equipment normally available commercially by operating personnel having a minimum of training.

Source: https://assist.dla.mil -- Downloaded: 202610-21T12:39Z
Check the source to verify that this is the current version before use.

3.4.7 Reliability. Containers shall have a minimum service life of 200 usages. A round trip of 8,000 miles, including the associated packing, unpacking and handling at each end of the trip and two intermediate stops, shall be considered on usage.

3.5 Performance. The containers shall be capable of withstanding the following:

a. Temperatures ranging from - 65°F to 125°F.

b. Fungus as encountered in tropical climates.

c. Exposure to salt sea atmosphere.

3.5.1 Moisture resistance. Container walls shall withstand continued exposure to moisture and humidity during service operations without serious effect.

3.5.2 Thermal conductivity. With a 100°F - temperature differential between the inside and outside of the containers, the total maximum thermal energy passing through the containers for a 20 hour period shall be 13,000 BTU for the CNU-39/B container, 9,500 BTU for the CNU-38/B container, and 9,000 BTU for the CNU-37/B container.

3.5.3 Thermal shock. There shall be no separation between any assembled parts and materials as a result of rapid temperature changes. The container shall be operative at all temperature extremes.

3.5.4 Impact resistance. The container shall not be damaged when a 7/8 inch diameter dart weighing 1,300 grams (2.86 pounds) is dropped on it from a height of 24 inches.

3.5.5 Forklift handling. When loaded to capacity, the container shall withstand normal handling by a 15,000 pound capacity, or similar, forklift truck without structural damage or component damage.

3.5.6 Structural strength. The container shall have sufficient strength to withstand shock and vibration as encountered during shipment.

3.6 Part numbering of individual parts. The parts having the same manufacturer's part number shall be functionally and dimensionally interchangeable. The drawing number requirements of MIL-STD-100 shall govern the manufacturer's part numbers and changes thereto.

3.7 Components. All components necessary to provide complete and efficient containers for use as outlined herein shall be furnished even though such components may not be individually specified in detail herein. The components shall conform to the best current engineering practices with regard to design, structural strength, reliability, maintainability, weight requirements, quality of materials, and workmanship.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.




Figure 1. CNU-37/B Container Forklift Entry Limiting Dimensions

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.






Figure 2. CNU-38/B Container Forklift Entry Limiting Dimensions

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.



SYM ABOUT Q



BOTTOM VIEW

Figure 3. CNU-39/B Container Forklift Entry Limiting Dimensions

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

3.7.1 Cover. The cover shall be easily lifted for loading and unloading contents and shall be comprised of the entire upper surface of the container. Closure fastenings shall be such that only a small force, easily applied by hand without the use of tools, will be required to open and close the container. The assembled and closed container shall meet the requirements specified herein without the use of separately applied sealing components or materials. The cover assembly shall be fitted with strips having indented hand grips for opening and closing.

3.7.1.1 Hinges. The hinges shall be of a continuous type across the full length of the container top. The hinges shall not extend beyond the specified dimensions of the container.

3.7.1.2 Latches. Latches shall be provided to secure the cover. The cover latch and hinges shall not extend beyond the specified dimensions of the container. Provisions shall be made to accommodate a pad lock and security seal.

3.7.1.3 Brackets. The hinged cover shall be provided with folding, metal support brackets which shall be capable of maintaining a 90 degree to 105 degree open position.

3.7.2 Gaskets. Gaskets shall be fabricated from materials that will withstand temperatures ranging from -65°F to +160°F and shall assure an adequate seal between the cover and container body. The gaskets shall be of such configuration and shall be so attached that no foreign matter can get under the edge.

3.7.3 Handles. The CNU-39/B and CNU-38/B containers shall be equipped with four handles and the CNU-37/B container shall be equipped with two handles. The handles shall be readily accessible and shall be so located that containers can be conveniently moved by a man of average height. When not in use, the handles shall not project beyond the specified dimensions of the container. Each handle shall be capable of a sustaining force of 200 pounds.

3.7.4 Thermometers. A thermometer shall be mounted in one of the inside corner areas of the container. It shall have a calibration range of -50°F to +125°F and shall be accurate within ± 3°F. The face shall be recessed a minimum of 1/4 inch into the container surface and shall be readable from outside the closed container.

3.8 Conveyor handling. The containers shall accommodate generally accepted materials handling procedures without damage. When handled on a 463L warehouse-loader aircraft conveyor system, the container shall be conveyed on 463L aircraft cargo pallets conforming to MIL-P-27443.

3.9 Finish. The containers shall be finished in accordance with MIL-STD-808 unless a conflict exists with the requirements of this specification, in which case this specification, shall govern. To provide maximum reflectance, the color shall be gloss white ranging between Color No. 17875 and No. 17886 of FED-STD-595.

3.10 Marking.

Source: https://assist.dla.mil -- Downloaded: 202610-21T12:39Z
Check the source to verify that this is the current version before use.

3.10.1 Identification of product. Containers shall be marked for identification in accordance with MIL-STD-130. The following information shall be embosed on a corrosion-resistant plate conforming to MIL-P-514.

Tare weight.
Weight capacity.
Volume capacity.
Contract number.
National stock number.

3.10.2 463L Marking. Containers shall be marked with 463L in 1, 2, 3, or 4 inch size block-type numerals and letters. The sizes selected shall be the largest practicable, for the space availabie, consistent with good appearance and visibility. The marking shall be legible, in a conspicuous location and shall be so placed that a casual observer will not confuse the 463L marking with any other identification.

3.10.3 Handle. A decal, marked in red with approximately 1-inch block lettering, shall be placed underneath each handle and shall read as follows:

HANDLE FOR HAND LIFTING EMPTY CONTAINER ONLY.

3.10.4 Use and care instructions. A permanently attached waterproof label or decal containing the following instructions for functional operation shall be located on the outside of the container wall convenient to the thermometer.

Operational Instructions.

Container stacking maximum: Two-level loaded
Inspect after each usage to assure cleanliness
See T.O _____*_____
*To be inserted by manufacturer.

FOOD STORAGE LIMITATIONS

Fresh Food	Lower Limit °F	Upper Limit °F
Apples	30	42
Apricots	32	45
Bananas	55	72
Beans (late)	31	42
Beets	32	50
Butter	32	40
Cabbage (late)	33	45
Carrots	32	45
Cauliflower	32	45
Cheese (American)	32	45
Cherries	28	40
Corn (Sweet)	31	45
Eggs (Shell)	29	45
Ice Cream		10
Lamb	30	42

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

Lettuce	32	45
Lima Beans	33	45
Milk (Fluid, Whole, Grade A Pasturized)	33	45
Oranges	30	50
Peaches	31	50
Plums	30	45
Pork	30	40
Potatoes	36	60
Poultry	28	32
Spinach	32	50
Strawberries	41	45
Tomatoes	40	70

Frozen foods should be maintained at 0°F or below.

NOTE: Average rise or fall of 10°F in a 20-hour period with a differential temperature of 100°F.

3.10.5 Reflectorized adhesive sheeting. Reflectorized adhesive sheeting shall be in accordance with L-S-300, type 1, class 1, (ready cut letters and numberals are available). The color code specified in accordance with MIL-STD-808 shall be used.

3.10.6 Stenciling. Stenciling shall be in accordance with MIL-STD-808.

3.11 Size and weight. The weight and exterior dimensions, including forklift entries, shall be as follows. Dimension tolerance shall be +0 - 1/4 inch.

Type	Length (Inches)	Width (inches)	Height (Inches)	Max. Weight Pounds)
CNU-39/B	82	50	45-1/2	335
CNU-38/B	50	41	45-1/2	180
CNU-37/B	41	25	45-1/2	118

3.12 Workmanship. Workmanship shall be of the highest quality to insure proper functioning under any condition to which the container may be subjected. Unsatisfactory workmanship such as loose, cocked or inadequately headed rivits; rough, loose, malformed, misaligned or improperly fabricated fittings; or sharp edges, burrs or other protrusions will not be acceptable.

4. QUALITY ASSURANCE PROVISIONS.

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections where such inspections are deemed necessary to assure that supplies and services conform to the prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 202610-21T12:39Z
Check the source to verify that this is the current version before use.

4.2 Classification of tests. Inspection and testing of containers shall be classified as follows:

a. First article inspection.

b. Quality conformance inspection.

4.3 Test conditions.

4.3.1 Apparatus. As far as practicable, laboratory precision type apparatus shall be used for testing containers selected for inspection and testing. Apparatus shall be calibrated against National Bureau of Standards approved standards to assure accuracy.

4.3.2 RE-test. Disapproval of any container due to configuration, or components, other than minor changes or corrections during testing, shall be cause for a repeat of that particular test. Changes in design, materials, or manufacturing methods prior to the contracting officer's approval, shall be cause for the disapproval and rejection of all containers.

4.4 First article inspection.

4.4.1 First article inspection samples. First article inspection samples shall consist of one container of each size, identified with the manufacturer's part number, and any other pertinent information deemed necessary. The containers shall be selected at random and shall be representative of the production requirements, in accordance with the contract or workorder.

4.4.2 First article inspection. First article inspection shall consist of the examination of the container to determine compliance with the requirements specified herein with respect to materials, configuration, finishs, clearances, completeness, and dimensional accuracy. (see 3.1).

4.4.3 First article approval. When first article approval is required under 3.1, first article inspection shall be performed. Unless otherwise specified (see 6.2), first article inspection shall comprise the examination in 4.4 and all tests in 4.5. Failure of the item to pass any examination or test shall be cause for disapproval of the first article.

4.5 Quality conformance inspection. Quality conformance inspection shall consist of the examination in 4.4.2, the tests in 4.5.2 and the inspection of the preparation for delivery referenced in paragraph 4.6. Failure of the item to pass any examination, test or inspection shall be cause for rejection.

4.5.1 Non-destructive and destructive tests. Non-destructive and destructive tests shall be in accordance with the following:

a. Non-destructive tests.

1.	Examination	(4.4.2)
2.	Thermal conductivity	(4.5.2.1)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

3.	Steam cleaning	(4.5.2.2)
4.	Handle strength	(4.5.2.3)
5.	Forklift handling	(4.5.2.4)
6.	Stacking	(4.5.2.5)
7.	Structural strength	(4.5.2.6)
8.	Salt spray	(4.5.2.7)
9.	Reliability	(4.5.2.8)

b. Destructive tests.

1.	Fire resistance	(4.5.3.1)
2.	Impact resistance	(4.5.3.2)
3.	High and low temperature	(4.5.3.3)
4.	Gasket	(4.5.3.3.3)
5.	Fungus resistance	(4.5.3.4)
6.	Moisture and water absorption	(4.5.3.5.1)
7.	Thermal shock	(4.5.3.6)

4.5.2 Nondestructive tests.

4.5.2.1 Thermal conductivity tests. An empty container, closed and sealed identical in manner to which it is to be used under normal shipment conditions, shall be used for the thermal conductivity test. (i.e. additional gaskets, sealants or caulking as insulation are prohibited). Openings for instrumentation leads and conduits may be packed with suitable insulation, however, these openings shall not exceed the lead or conduit cross-sectional dimensions by more than 1/2 inch. The container shall be subjected to a temperature differential of 100°F between the inside and outside of the container for a minimum of 20 hours. During this period, temperatures inside and outside the container shall be continuously recorded and controlled to ±2°F. Either the inside or the outside temperature shall be 0°F. The required energy to maintain temperature control on the warm side of the container shall be continuously recorded. Air inside the container shall be circulated by a mechanical method and the inside temperature measured by thermocouples, located from at least ten different areas, to provide representative readings including corners, throughout the container. Thermal energy transfer shall not exceed the values specified in 3.5.2.

4.5.2.2 Steam cleaning. An empty container turned 90° and resting on either side shall be subjected to saturated and steam at 80 p.s.i for a period of 10 minutes by means of a 1/2 inch standard pipe steam lance. The lance tip shall not be more than 6 inches from the surface of the area being cleaned, and moved in a constantly moving 12 inch diameter pattern covering all inside surfaces of the container. Evidence of peeling delamination, cracking, blistering, or leaking shall be cause for rejection.

4.5.2.3 Handle strength. 4200 pound static tensile load shall be applied to all handles with direction of loading perpendicular to the sidewall of the container and then applied with the direction of loading upward at an angle of 30° to the sidewall. Permanent deformation of the handle or attaching media shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

4.4.2.4 Forklift handling. The forklift handling test shall be in accordance with Federal Test Method Standard 101, Method 236. The CNU-39/B container shall be loaded with 5000 pounds, the CNU-38/B container with 2500 pounds, and the CNU-37/B container with 1,250 pounds. No limit shall be imposed on the height at which the container must be carried.

4.5.2.5 Stacking. A closed empty container shall be placed on a level floor. A container of the same size and loaded as specified in 4.4.2.4, as applicable, shall be placed on top of the empty container for a continuous period of 1/2 hour. No shielding or protective layers or devices shall be used between the two containers. Any evidence of collapse, deformation, cracks or other structural deficiencies shall be cause for rejection.

4.5.2.6 Structural strength. The containers shall be loaded as specified in 4.4.2.4, as applicable, and subjected to a structural strength test in accordance with Federal Test Method Standard 101, method 211 or 212, and method 213 or 214. Any evidence of cracking, permanent deformation, separation of joints or other structural deficiencies shall be cause for rejection.

4.5.2.7 Salt fog. All metal hardware shall be subjected to a salt fog test in accordance with MIL-STD-810, Method 509.

4.5.2.8 Reliability. Satisfactory completion of all non-destructive tests will demonstrate compliance with the reliability requirements specified in 3.4.7.

4.5.3 Destructive tests.

4.5.3.1 Fire resistance. Test samples shall be cut from the sandwich panels used to construct the container walls. These test samples shall be subjected to fire resistance test in accordance with ASTM Standard D-1692-59T. Materials that burn (as defined in referenced standard) shall be rejected.

4.5.3.2 Impact resistance. Two test samples, size 6 inches by 6 inches minimum, shall be cut from the sandwich panels used to construct the container walls and fastened down for impact resistance testing. A 7/8 inch diameter round nosed dart weighing 1,300 grams (2.86 pounds) shall be dropped on the samples from a height of 24 inches. Evidence of surface deformance, cracks, or surface indention greater than 1/16 inch at the point of contact shall be cause for rejection.

4.5.3.3 High and low temperature tests.

4.5.3.3.1 High temperature. The container shall be subjected to a high temperature test in accordance with MIL-STD-810, Method 501.

4.5.3.3.2 Low temperature. The container shall be subjected to a low temperature test in accordance with MIL-STD-810, Method 502, at -65°F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

4.5.3.3.3 Gasket. Two samples of gasket approximately 6 inches long shall be subjected to a temperature of -65°F for a period of one hour. While at this temperature the samples ahll be sharply bent to 90° between the thumbs and forefingers. Evidence of cracking or brittleness shall be cause for rejection. The two samples shall then be exposed to a temperature of 160°F for one hour. The surfaces shall be examined and shall be dry. Evidence of stickiness or tackiness to the touch shall be cause for rejection.

4.5.3.4 Fungus resistance. The containers shall be subjected to a fungus resistance test in accordance with Federal Test Method Standard, Method 233.

4.5.3.5 Moisture and water absorption. The amount of moisture and water absorbed during the thermal conductivity test shall be determined in accordance with the following formula and shall be expressed as a percentage of the weight of the dry container. An excess of 2 percent increase in weight shall be cause for rejection.

$$\frac{\text{Weight after test - Initial weight}}{\text{Initial weight}} \times 100 = \text{Percent increase in weight}$$

4.5.3.5.1 Moisture and water absorption test. Two samples size 12 inches by 12 inches minimum, shall be cut from the sandwich panels used to construct the containers and suspended in an atmosphere of 95 ± 5 percent relative humidity at 125 ± 5°F for 10 days. Visible evidence of corrosion, deterioration, delamination, or swelling greater than 10 percent of the original dimensions shall be cause for rejection. Samples of insulation, 4 inches by 4 inches by one inch in size shall be cut from the samples and within 30 minutes shall be subjected to the thermal conductivity test with instrumentation configured and calibrated in accordance with ASTM C-177-63. The K factor for any sample shall not exceed 2.0.

4.5.3.6 Thermal shock. Two samples, size 12 inches by 12 inches minimum shall be cut from the sandwich panels used to construct the container walls. These samples shall be exposed alternately for one hour to minus 50°F and the 70°F for consecutive cycles. Evidence of delamination, deformation or cracking shall be cause for rejection.

4.6 Inspection of packaging for delivery. Packaging shall be inspected to determine compliance with the requirements of Section 5.

5 PACKAGING

5.1 Preservation and packaging. All levels of preservation and packaging shall be as specified in 5.1.1.

5.1.1 Container preparation. The lid of each container shall be secured in a closed position with closing devices forming a part of the container. The container shall be covered with a shroud of polyethylene film, approximately 0.0060 inch thick, complying with any type, grade, or finish of L-P-378.

5.2 Packing.

5.2.1 Level A. The shrouded container shall be enclosed in a wood-cleated, skidded, load-bearing-base type box constructed in a compact manner and conforming to Type I, Style A, Class 2 of MIL-B-26195.

Source: https://assist.dla.mil -- Downloaded: 202610-21T12:39Z
Check the source to verify that this is the current version before use.

5.2.5 Level B. The shrouded container shall be enclosed in a wood-cleated, skidded, loaded-bearing-base type box constructed to fit the contents in a compact manner and conforming to Type II, Style B, Class 1 of MIL-B-26195.

5.2.3 Level C. Containers shall be packed in a manner to ensure carrier acceptance and safe delivery at destination. Containers shall be in accordance with the rules or regulations of carriers applicable to the mode of transportation.

5.3 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES.

6.1 Intended use. The containers covered by this specification are intended for use in air cargo transportation of fresh and frozen foods between air terminals and staging areas. It is intended that the containers be palletized on U.S. Air Force 463L system pallets, tied down with 463L system nets, and that they be compatible with overall 463L system operations in world wide climatic environments.

6.2 Ordering data. Purchasers should specify their requirements in procurements, in accordance with the following:

a. Title, number, and date of the specification.

b. Type of container required (see 1.2 and 3.11).

c. If first article is required (see 3.1).

d. First article inspection, if different (see 4.4.3).

e. Quality conformance inspection, if different (see 4.5)

f. When Palletizing is required (see 5.2 and 6.1).

Custodian:

Air Force - 99

Preparing Activity:

Air Force - 99

Project Number:

7330-F516

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE AIR FORCE

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 73236 WASHINGTON D C

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE AIR FORCE

HQ AFLC CASO/LODSH
Federal Center
Battle Creek, MI 49016

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS. The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE
MIL-F-38456A Food Container, Insulated

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A
☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?
[ ] YES [ ] NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

S/N 0102-014-1802

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T12:39Z
Check the source to verify that this is the current version before use.