MIL-C-62500(AT)
11 September 1985
SUPERSEDING
(see 6.9)

MILITARY SPECIFICATION

CARRIER, ELECTRONIC WARFARE SYSTEM, FULL-TRACKED: M1015A1

This specification is approved for use by US Army Tank-Automotive Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a full-tracked, unarmored, non-amphibious, diesel powered vehicle. This vehicle consists of a full-tracked cargo carrier modified for use as a cross country carrier for shelter-housed electronic warfare (EW) systems.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified, the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Tank-Automotive Command, ATTN: AMSTA-GSS, Warren, MI 48397-5000, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document, or by letter.

FSC 2350

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS
FEDERAL

VV-F-800	- Fuel Oil, Diesel.

MILITARY

MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-C-46168	- Coating, Aliphatic Polyurethane, Chemical Agent Resistant.
MIL-E-52798	- Enamel, Alkyd, Camouflage.
MIL-E-52835	- Enamel, Modified Alkyd, Camouflage, Lusterless.
MIL-T-62099	- Transmission, Hydraulic, Modified Automatic TX-100-1.
MIL-E-62140	- Engine Diesel: 6 Cylinder, V-type, 210 Hp.

STANDARDS
MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-193	- Painting Procedures, Tactical Vehicles (Tracked and Wheeled).
MIL-STD-210	- Climate Extremes for Military Equipment.
MIL-STD-461	- Electromagnetic Interference Characteristics, Requirements for Equipment.
MIL-STD-462	- Electromagnetic Interference Characteristics, Measurement of.
MIL-STD-642	- Identification Marking of Combat and Tactical Transport Vehicles.
MIL-STD-1275	- Electrical Circuit, 28 Volt DC Transient Characteristics for Military Vehicles.
MIL-STD-1474	- Noise Limits for Army Materiel.
MIL-STD-45662	- Calibration Systems Requirements.

2.1.2 Other Government documents, drawings, and publications. The following documents, drawings, and publications form a part of this specification to the extent specified herein.

DRAWINGS
ARMY

5051440	- Carrier, Tracked, SIGINT/EW, M1015A1.
8750029	- Carrier, Cargo, M548A1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

2.1.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 First article. Unless otherwise specified (see 6.2), the contractor shall furnish vehicles which shall be subjected to first article inspection (see 4.4). First article inspection samples, properly marked with identifying information shall be representative of the unit to be furnished to the Government. All subsequent vehicles delivered to the Government shall conform to these samples in all of their pertinent physical and performance attributes.

3.2 Materials. Materials shall be as specified herein and in referenced specifications, standards, and drawings. Material shall be free from defects which adversely affect performance or serviceability of the finished product (see 4.8.1 and 6.7).

3.2.1 Ozone resistance. When rubber components are required to be ozone resistant, the degree of resistance shall be as specified in applicable specifications or drawings (see 4.8.1).

3.3 Design and construction. Vehicles, components, subassemblies and assemblies shall be manufactured and assembled into a complete vehicle in accordance with the following drawings, as applicable, specifications and documents. Vehicles shall meet all requirements specified herein and be of a quality that assures a vehicle free from defects that would compromise, limit, or reduce its performance (see 4.8.1).

Modified EW model	Army modification drawing	Unmodified cargo carrier model	Unmodified Army cargo carrier drawing
M1015A1	5051440	M548A1	8750029

3.3.1 Qualified products. The contractor shall be responsible for using parts and assemblies from Qualified Products Lists (QPLs) whenever available. Contractor's inspection records shall specifically list all QPL items by number and date of the QPL, name of supplier and part or drawing number(s). When parts and assemblies are approved as qualified products, but not yet listed on the QPL, the contractor shall list the products by number and date of the approved document and name of supplier(s) (see 4.8.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.3.2 Break-in run. The vehicle shall be subjected to a break-in run. The break-in run will include preliminary checks of suspension, controls, power pack, and provide wear-in for final adjustments. A combat-loaded condition is not required. When specified (see 6.2), the break-in run shall be simulated. Prior to the break-in run will involve the following activities and conditions (see 4.8.1):

a. Preparation. Prior to the break-in run, except for equipment and component installations and servicing performed by the contractor as a final processing of the vehicle for acceptance, the vehicle shall be completely assembled and all adjustments completed. The vehicle, including all applicable components requiring lubrication, shall be lubricated in accordance with production lubrication chart. The vehicle shall be serviced with fuel conforming to applicable seasonal grades of VV-F-800.

b. Oil pressure and temperature. Prior to the start of the break-in run, the engine shall be operated at 600 to 800 revolutions per minute (rpm) until lubricating oil is at operating pressure and temperature. If at any time during break-in run the engine has been stopped for at least 15 minutes, the engine shall again be operated, as above, before continuing break-in run. Proper oil pressure and temperature shall be maintained in the engine, transmission, transfer unit speed increaser, and controlled differential during operation.

3.3.2.1 Break-in procedure. Each vehicle shall be operated for distances specified in table I, on smooth, level, hard-surfaced roads. The vehicle shall be operated over the undulating section of road (see figure 1) twice in each direction at speeds between 5 and 10 miles per hour (mph) during division "a", and between 11 and 14.5 mph during division "b" (see 4.8.1).

TABLE I. Speeds and distances for break-in run.

Division of run	Speed - mph	Distance - miles
a	0 to 10	5
b	11 to 20	5
c	21 to 30	10
d	31 to maximum governed	10

3.3.2.2 Reverse operation. After each division of the break-in run, the vehicle shall be stopped, the engine allowed to idle for not less than one minute, and the vehicle driven in reverse for a distance of not less than 50 feet (see 4.8.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

(see 6.2). In addition, an air operated horn shall be provided

3.3.2.3 Simulated break-in run. When specified (see 6.2), a simulated break-in run (see table II) maybe performed on the Army Skid Type Dynamometer in lieu of the run specified in 3.3.2 1. The final 10 miles of the total break-in run shall be on smooth, level, hard-surfaced roads, except for the undulating portion of the road conforming to figure 1. The undulating portion of the test shall be accomplished twice in each direction, at speeds between 5 and 10 mph during division "e" and between 11 and 14.5 mph during division "f" (see table II). After completion of division "b" and "d", the vehicle shall be operated in reverse as specified in 3.3.2.2 (see 4.8.1).

TABLE II. Simulated break-in run.

Division of run	Speed (mph)	Miles of test	Test conditions
a	0 to 10	5	Dynamometer
b	11 to 20	5	Dynamometer
c	21 to 30	5	Dynamometer
d	31 to maximum governed	5	Dynamometer
e	21 to 30	5	Track (road)
f	31 to maximum governed	5	Track (road)

3.3.2.4 Condition after break-in run. After completion of the break-in run, there shall be no indication of damaged components, maladjustment or loss of original adjustment that may cause faulty vehicle operation subsequent to Government acceptance. The differential oil filter element shall be removed cleaned and reinstalled upon completion of the break-in run (see 4.8.1).

3.3.3 Special kits. When specified (see 6.2), special kits shall be provided. Special kits when installed, shall fit properly without interference or misalinement and meet applicable environmental and performance requirements specified herein (see 4.8.1).

3.3.3.1 Cab personnel heater kit (primary). When installed, the (primary) cab personnel heater kit shall provide heat for personnel and windshield defrosting in ambient temperatures down to minus 25 degrees Fahrenheit (°F) (see 4.8.1).

3.3.3.2 Cab personnel heater kit (secondary). When installed the (secondary) cab personnel heater kit shall supplement the (primary) cab personnel heater and insure heat for personnel and windshield defrosting during operations in ambient temperatures from minus 25°F to minus 65°F. The insulated hard top cab cover shall resist the entrance of water, dust and snow (see 4.8.1).

3.3.3.3 Engine coolant heater kit. When installed, the engine coolant heater kit shall assure engine starting and operation in ambient air temperatures from minus 25°F to minus 65°F. The engine coolant heater shall be capable of operating for a minimum of 12 hours on battery power alone without discharging the battery to a level that would preclude satisfactory starting of the engine (see 4.8.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.3.4 Air brake. The air brakes shall be installed and shall be compatible in operation with trailers equipped with air brakes. Test mileage apportioned to first article vehicles equipped with air brakes shall include 200 miles with a towed load of approximately 12 000 pounds (lb) in the hard-surfaced road mode and in the cross country mode (see 3.5.1 and 4.8.1).

3.4 Physical characteristics.

3.4.1 Bearing seals. The bearing seals shall prevent the entrance of foreign matter into the bearings exposed to contamination during fording, or operating in mud, sand or snow. Bearing seals shall restrict the leaking of lubricants from the bearings (see 4.8.3.1).

3.4.2 Doors, windows and covers. All doors, windows and covers shall conform to applicable drawings. When installed, they shall fit and be water, dust and snow resistant, and function without interference or misalinement (see 4.8.3.2).

3.4.3 Engine. The engine shall conform to MIL-E-62140 and shall operate throughout all speed ranges without evidence of cooling system, lubricant, or fuel leakage (see 4.8.3.3).

3.4.3.1 Engine air induction system. The air induction system, as installed, shall prevent entrance of foreign matter in conformance with applicable drawings (see 4.8.3.3.1).

3.4.4 Exhaust systems. The engine exhaust system, as installed, and the personnel heater exhaust system, when installed, shall not permit concentration of toxic fumes in the driver and crew compartments to exceed 50 parts per million (ppm) for carbon monoxide (CO) or 5 ppm for oxides of nitrogen (NO) (see 4.8.3.4).

3.4.5 Fuel system, grades and slopes. The fuel system shall maintain a continuous supply of fuel to the engine when ascending and descending 60 percent grades in forward and reverse gear, and when the vehicle is being operated left side or right side up on 30 percent side slopes (see 4.8.3.5).

3.4.5.1 Fuel tank. Provision shall be made to assure the internal cleanliness of the fuel tank prior to initial fueling of the vehicle. The fuel tank shall be capable of receiving 50 gallons of fuel per minute (see 4.8.3.5.1).

3.4.5.2 Fuel lines. The fuel lines and connections shall be internally clean prior to initial fueling and servicing of the vehicle. All fuel lines, connections, and tanks shall be free of leaks (see 4.8.3.5.2).

3.4.5.3 Rack linkage. With the rack linkage installed in accordance with applicable drawings, and with the accelerator pushed against the stop, the rack shall be at full open position (see 4.8.3.5.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.4.6 Transmission, transfer gearcase, speed increaser, and control differential. The transmission shall conform to MIL-T-62099. When installed in the vehicle, the transmission, transfer gearcase, speed increaser, and controlled differential shall operate throughout all gear ranges without evidence of leakage (see 4.8.3.6).

3.4.7 Electrical system.

3.4.7.1 EW generator governor. After not less than 20 minutes of operation with the headlights on the regulator control shall be observed. The EW generator governor shall be operated at 4000 ± 100 rpm with an output of 50 ± 5 amperes (A), and the voltage regulator rheostat adjusted to provide 28 volts (V) direct current (dc) at the vehicle batteries. Voltage at the vehicle batteries shall not increase more than 0.5 V dc when the load is removed (see 4.8.3.7.1).

3.4.7.1.1 EW generator governor frequency variation. The EW generator governor system, at any constant load between no-load and full-load, shall maintain the EW generator unit frequency constant within ± 1 hertz (Hz). There shall be no sustained periodic frequency oscillations, even within the ± 1 Hz variation at constant load (see 4.8.3.7.1).

3.4.7.1.2 EW generator governor frequency drift. The EW generator governor system shall not permit the EW generator unit frequency to change more than 3 Hz for an ambient temperature change of 60°F, within the specified temperature range, at any constant load condition from no-load to full-load. The EW governor system shall not permit the frequency to change more than 3 Hz during warm-up and stabilization for any load condition from no-load to full-load for any environmental condition specified herein (see 4.8.3.7.1).

3.4.7.2 Lights. The internal and external lights specified on applicable drawings shall operate, and all electrical contacts and connections shall maintain positive contact, under all vehicle operating conditions (see 4.8.3.7.2).

3.4.7.3 Communication and electrical circuits. The communication and electrical circuits shall maintain continuity from end to end, without shorts from pin to pin, or from pin to connector shell (see 4.8.3.7.3).

3.4.7.4 System voltage characteristics. The electrical system voltage characteristics shall fall within the limits for transient and steady state voltage requirements specified in MIL-STD-1275 (see 4.8.3.7.4).

3.4.7.5 Heaters. The personnel heaters shall start and operate satisfactorily on 20 V dc, using diesel fuel conforming to VV-F-800 (see 4.8.3.7.5).

3.4.8 Controls. All electrical, mechanical and hydraulic controls shall operate without malfunction throughout all ranges of operation under all vehicle operating conditions (see 4.8.3.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.4.9 Adjustment mechanisms. All adjustment mechanisms shall function properly and maintain adjustment within required settings during all vehicle operating conditions (see 4.8.3.9).

3.4.10 Stowed material. All interior and exterior basic issue items (BII) shall be stowed (combat loaded) on the vehicle, in spaces provided, to assure that items will not interfere with operation of the vehicle and components (see 4.8.3.10).

3.4.11 EW generator system.

3.4.11.1 EW generator input power. The 60 kilowatt (kW), 400 Hz engine-drive EW generator system shall be operable only when 22 to 30 V dc is supplied from the vehicle battery (see 4.8.3.11.1).

3.4.11.2 EW generator output voltage. The EW generator output voltage shall be 120/208 V alternating current (ac), three phase wye connected. The voltage shall be adjustable over a minimum range of 120/208 V ac plus and minus 5 percent. Voltage regulation shall be within ± 2 percent from no load to full load and back to no load. Upon application or removal of the rated load the voltage change shall be not greater than 15 percent and the recovery time shall be less than 0.7 second (see 4.8.3.11.1).

3.4.11.3 EW generator output frequency. The EW generator output frequency shall be 400 Hz adjustable over a minimum range of plus and minus 10 Hz. Frequency regulation shall be within ± 2 percent from no load to full load and back to no load. Upon application or removal of the rated load the frequency change shall be not greater than 2 percent and the recovery time to within ± 1 percent shall be less than 1.5 seconds (see 4.8.3.11.1).

3.4.11.4 EW generator fault conditions.

3.4.11.4.1 Engine stop faults. Any of the following abnormal conditions shall stop the vehicle engine (see 4.8.3.11.2):

a. Emergency stop circuit actuation.
b. Engine coolant overtemperature.
c. Low engine oil pressure.
d. Low gearbox oil pressure.
e. Low actuator fluid pressure.
f. Engine overspeed.

3.4.11.4.2 Generator off faults. Any of the following abnormal conditions shall switch off the EW generator and return the engine to idle (see 4.8.3.11.2):

a. Engine underspeed below 1980 rpm while the generator is on.
b. Output voltage greater than 132/229 V ac.
c. Ouptut current greater than 200 or 800 A (depending upon the output cable connection selected).
d. Neutral gear not selected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.4.11.4.3 Shelter power off fault. Any of the following conditions shall disconnect the output power from its load, but shall leave the EW generator set on and shall leave the vehicle engine operating at speed (see 4.8.3.11.2):

a. Output frequency greater than 420 Hz.
b. Output frequency less than 380 Hz.
c. Output voltage less than 102/177 V ac.
d. Output voltage less than 72/125 V ac.

3.4.11.5 EW generator controls.

3.4.11.5.1 GENERATOR ON switch. The GENERATOR ON switch shall engage the clutch connecting the generator to the engine, and shall raise the engine from idle to normal operating speed (see 4.8.3.11.3).

3.4.11.5.2 GENERATOR OFF switch. The GENERATOR OFF switch shall disengage the clutch connecting the generator to the engine, and shall return the engine to idle (see 4.8.3.11.3).

3.4.11.5.3 SHELTER ON switch. The SHELTER ON switch shall connect the EW generator to the load (see 4.8.3.11.3).

3.4.11.5.4 SHELTER OFF switch. The SHELTER OFF switch shall disconnect the EW generator from the load (see 4.8.3.11.3).

3.4.11.5.5 EMERGENCY STOP switch. The EMERGENCY STOP switch shall disengage the generator from the engine, and shall stop the engine. The red switch background shall be lighted at full brilliance at all times that battery power is applied to the EW generator (see 4.8.3.11.3).

3.4.11.5.6 LAMP TEST switch. The LAMP TEST switch shall light all of the control panel lamps (see 4.8.3.11.3).

3.4.11.5.7 FAULT RESET switch. The background of the FAULT RESET switch shall light red whenever any fault condition occurs. The FAULT RESET switch shall reset the fault indications and shall return the EW generator system to the off condition (see 4.8.3.11.3).

3.4.11.5.8 PRESS TO BYPASS switch. The PRESS TO BYPASS switch shall cause the red switch background to flash and to display the PROTECTOR BYPASSED legend. The PRESS TO BYPASS switch shall allow actuation of the GENERATOR ON and SHELTER ON switches to operate the EW generator and connect the load. Actuation of the PRESS TO BYPASS switch shall permit all of the faults specified by the 3.4.11.4 to be overridden except for the following (see 4.8.3.11.3):

a. Emergency stop.
b. Engine overspeed.
c. Output current high.
d. Output voltage under 72/125 V ac.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.4.11.5.9 METER FUNCTION switch. Selection of the appropriate position of the METER FUNCTION switch shall allow the VOLTS/AMPS meter to read the line-to-line voltage, line-to-neutral voltage, or line current for any phase (see 4.8.3.11.3).

3.4.11.5.10 PANEL LAMPS control. The adjustment of the PANEL LAMPS control shall set the intensity of the panel lamps and all indicators except for the EMERGENCY STOP, PRESS TO BYPASS, and PROTECTOR BYPASSED indicators (see 4.8.3.11.3).

3.4.11.5.11 VOLTAGE ADJUST control. The VOLTAGE ADJUST control shall provide adjustment of the output voltage over the range specified by 3.4.11.2 (see 4.8.3.11.3).

3.4.11.6 Control panel indicators and displays.

3.4.11.6.1 Elapsed time indicator. The elapsed time indicator shall run while the GENERATOR ON switch is engaged and shall display the elapsed hours that prime voltage has been available (see 4.8.3.11.4).

3.4.11.6.2 Frequency meter. The frequency meter shall display the output voltage frequency of the EW generator. The frequency meter range shall be 360 to 440 Hz (see 4.8.3.11.4).

3.4.11.6.3 Wattmeter. The wattmeter shall display the power delivered by the EW generator. The wattmeter range shall be 0 to 90 kilowatts (see 4.8.3.11.4).

3.4.11.6.4 Voltage and amperage meter. The voltage and amperage meter shall have a range of 0 to 250 V and A and shall display the following readings (see 4.8.3.11.4):

a. Voltage

1. Line A to neutral
2. Line B to neutral
3. Line C to neutral
4. Line A to B
5. Line A to C
6. Line B to C

b. Amperage

1. Line A
2. Line B
3. Line C

3.4.11.6.5 Fault protection indicator lamps. The fault protection indicator lamps shall indicate the presence of each fault specified by 3.4.11.4 (see 4.8.3.11.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

and two on the curbside (see figure 1).

3.4.12 Ground rod driver.

3.4.12.1 Ground rod driver input power. The ground rod driver shall operate without degradation of the performance of the characteristics specified herein while connected to vehicle power (see 4.8.3.11.5):

3.4.12.2 Ground rod driver hammer. The ground rod driver hammer when mounted on the vehicle, shall be capable of driving, within 1 minute, a 5-foot long, 0.75-inch diameter, ground rod into clay, sand or gravel (see 4.8.3.11.5).

3.4.12.3 Ground rod driver brake. The ground rod driver hoist shall be capable of preventing a runaway condition caused by the hammer carriage dropping when the hoist is left unattended (see 4.8.3.11.5).

3.4.13 EW shelter mechanical interface. The shelter mechanical interface components shall accept and secure an applicable EW shelter and its subsystems without interference with existing equipment and controls. The shelter mechanical interface components shall withstand the following dynamic loads (see 4.8.3.11.6):

a. Shelter side stop block: 25 000 lb in a side-to-side direction.
b. Shelter-vehicle adapter: 14 800 lb downward.
c. Forward stop block: 20 000 lb forward.
d. Shelter tie-down eye: 14 800 lb upward, forward and rearward.
e. Rearward stop bracket: 40 000 pounds rearward.

3.5 Performance. A complete vehicle, loaded with rated payload, serviced, and equipped for existing climatic conditions, shall operate as specified herein without special equipment. Performance shall be demonstrated on smooth, level, hard-surfaced roads free of loose material, except that a section of road shall be as shown in figure 1 (see 4.8.4).

3.5.1 5000 mile operation profile. The vehicle test mileage for the 5000 mile operation profile shall be apportioned as follows and meet the operational requirements specified in 3.5.1.1 through 3.5.1.3. The operation profile shall include the hours of EW generator operation and ground rod drive operations (see 4.8.4.1):

a. 20 percent hard-surfaced roads.
b. 40 percent secondary roads.
c. 40 percent cross country.

NOTE: Mileage during operation on hard-surfaced roads and cross country shall include 200 miles in each mode towing a 12 000 lb gross vehicle weight (GVW) wheeled trailer.

3.5.1.1 Reliability. The vehicle reliability shall be not less than 750 mean miles between failure (MMBF) during the first 5000 miles, when operated in accordance with the operational profile. For calculating MMBF, the definition in the M113 family 50 mile mission failure scoring criteria shall be used (see 4.8.4.1.1 and 6.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.5.1.2 Durability. The vehicle with rated payload shall have a 50 percent probability of completing the first 5000 test miles without replacement, rebuild, or major overhaul of the engine, transmission, transfer gear unit, speed increaser, EW generator, differential steer unit, or final drives, and without repair or rebuild of the hull, when operated in accordance with the operational profile (see 4.8.4.1.2).

3.5.1.3 Maintainability. The total maintenance, excluding driver and crew checks and services, shall not exceed 175 manhours during 5000 miles of operation in accordance with the operation profile. This equates to a Maintenance Ratio (MR) of 0.35 at 10 operational miles, equivalent to one operational hour. The scheduled maintenance interval shall be three months or 750 miles, whichever comes first (see 4.8.4.1.3).

3.5.2 Cooling systems.

3.5.2.1 Engine cooling. With the vehicle operating in an ambient temperature of 125°F, the engine cooling system shall maintain engine coolant at not more than 230°F, measured at a point in the engine outlet to the radiator. The radiator pressure cap shall relieve between 13 and 18 psi (see 4.8.4.2).

3.5.2.2 Transmission, lubricant cooling. With the vehicle operating in an ambient temperature of 125°F, the transmission lubricant cooling system shall maintain lubricant temperature at not more than 325°F, measured out of the transmission to cooler, except at torque converter speed ratios less than 4 to 10 (see 4.8.4.2).

3.5.2.3 Differential oil cooler. With the vehicle operating in an ambient temperature of 125°F, the differential lubricant cooler shall maintain lubricant temperature below 300°F, measured out of the differential into cooler (see 4.8.4.2).

3.5.3 Bilge pumps. The bilge pump(s), installed in accordance with applicable drawings, shall remove water from the vehicle at a minimum rate of 35 gallons per minute (gpm) each with a discharge head of 4 1/2 feet, and with the pump motor operating on 27.5 V dc impressed at the motor (see 4.8.4.3).

3.5.4 Speeds and vehicle control. The vehicle shall sustain speeds up to 30 mph, and a maximum speed of 36 mph without a towed load after 400 miles of operation, without damage to power plant or suspension system. The vehicle shall sustain speeds up to 26 mph, and a maximum speed of 30 mph with a 6 ton towed load after 400 miles of operation, without damage to power plant or suspension system. With the vehicle traveling between 15 mph and maximum speed, drift shall not exceed three feet in 100 feet without corrective effort by the driver (see 4.8.4.4).

3.5.5 Acceleration. With the vehicle initially at a standstill, the transmission in 1-3 range, the vehicle shall accelerate from 0 to 20 mph in not more than 18 seconds (see 4.8.4.5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.5.17 Emergency reflective triangles. Three emergency reflec

3.5.6 Engine starting on grades and slopes. With the vehicle parked in the following positions, the engine shall be capable of restarting within one minute after being stopped for not less than one minute after being operated for not less than two minutes under no load between 750 and 1000 rpm (see 4.8.4.6):

a. Headed upgrade on 60 percent grade.
b. Headed downgrade on 60 percent grade.
c. Left side up on 30 percent slope.
d. Right side up on 30 percent slope.

3.5.7 Braking.

3.5.7.1 Stopping and vehicle control. The vehicle shall stop within a distance of 40 feet from point of service brake application when traveling at a speed of 20 mph on smooth, level, hard-surfaced roads free of loose material. Drift shall not exceed three feet in stopping distance. During stopping, the vehicle being under driver's individual control, steering action is permitted (see 4.8.4.7.1).

3.5.7.2 Holding. With brakes locked for parking and with the transmission in neutral, the vehicle shall hold stationary when parked on a 60 percent longitudinal grade. For this operation the vehicle shall be loaded with rated payload or towing a trailer (see 4.8.4.7.2).

3.5.8 Turning. The vehicle, on smooth, level, hard-surfaced road or track, with differential steer, shall make continuous, full 360 degrees turns to right and to left, with rear point of outer edge of the vehicle at all times in contact with or within a 50 foot diameter circle. When in pivot steer, the vehicle shall pivot within a 28 foot diameter circle. The applied effort to the steering lever shall not exceed 100 lb to pivot the vehicle (see 4.8.4.8).

3.5.9 Shallow water fording. The vehicle shall ford shallow, hard-bottom salt or fresh water channels up to a depth of 40 inches. Leakage of water into the hull shall not exceed 3 quarts per minute (see 4.8.4.9).

3.5.10 Trench crossing. The vehicle, without a ground rod driver installed, shall cross trenches up to 36 inches in depth, and up to 66 inches in width, without damage to the vehicle (see 4.8.4.10).

3.5.11 Vertical obstacles. The vehicle, operating at low speeds in forward gear, shall cross vertical obstacles (wall) up to 24 inches in height and, in reverse gear, obstacles up to 14 inches in height without damage to the vehicle (see 4.8.4.11).

3.5.12 Grade and slope operation. The vehicle shall ascend 60 percent grades in forward and reverse gear, from a standstill position on the grade, without stalling or damage to power plant or power train. The vehicle shall operate without malfunction or damage on 30 percent side slopes, with the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

right and then the left side of the vehicle up-slope. Proper oil pressure and temperature shall be maintained in the engine, transmission, transfer gear unit, and controlled differential during all grade and sloper operation. Oil pressure observation shall be made with engine operating at 600 to 800 rpm (see 4.8.4.12).

3.5.13 Suspension. The vehicle suspension shall operate over a minimum of three 6x6 inch obstacles, spaced 30 feet apart, at a speed of 18 to 22 mph, without bottoming out the track drive sprockets, roadarm bump stops, or idler wheels, with either side or both tracks, engaging the obstacles (see 4.8.4.13).

3.5.14 Winch system. The winch system shall withstand an increasing load with a 11 to 12 foot cable (total length), including three to four wraps of cable on a bare drum. The load shall be gradually increased until the shear pin fails or the load reaches 24 000 lb. The load must exceed 14 000 lb. Failure load shall be recorded (see 4.8.4.14).

3.5.14.1 Winch operation. Starting with the fifth to tenth wrap on a bare drum, tension shall be applied to provide even distribution of the cable until the cable has been completely reeled in (see 4.8.4.14).

3.5.14.2 Winch structural integrity. The winch system structural integrity shall be verified by pulling the winch cable with a 20 000 lb load. During the test, the engine power takeoff shall be disengaged. Three to six wraps of cable shall be wrapped on the bare drum. The rope length is optional (see 4.8.4.14).

3.5.14.3 Winch controls. The cab-mounted controls shall engage the power takeoff drive for operation of the winch. The manually operated device furnished shall permit free spooling of the winch drum (see 4.8.4.14).

3.6 Environmental conditions. The complete vehicle shall operate in ambient air temperatures of plus 125°F to minus 25°F without winterization equipment and with special equipment installed, down to minus 65°F. The complete vehicle, when in storage, shall withstand climatic extremes as specified in MIL-STD-210 without deterioration that may cause failure of any component part of the vehicle (see 4.9).

3.7 Electromagnetic interference suppression. The vehicle, when operating, shall meet the requirements for electromagnetic interference and electromagnetic compatibility (EMI/EMC) suppression in accordance with class A3 and class C1 of MIL-STD-461 (see 4.10).

3.8 Fire extinguisher. The fixed fire extinguisher system, when installed in accordance with applicable drawings, shall be readily accessible for servicing and operation internally and externally. Maximum effort for externally discharging system shall not exceed value specified on applicable drawing (see 4.11).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

3.9 Noise level. With a sound level meter located four inches forward of the engine compartment left bulkhead, and 12 inches below the inside surface of the top plate, and the vehicle traveling at 30 mph in a 1-3 gear range on a hard-surfaced straight rod with all doors, hatches and windows closed, the sound level shall not exceed 119 decibels as measured by an a-weighting network [dB(A)] (see 4.12).

3.9.1 Noise hazard caution sign. The vehicle driver and passenger compartments shall be posted as noise hazardous areas as specified in MIL-STD-1474 (see 4.12.1).

3.10 Painting, marking and data plates.

3.10.1 Painting. The interior of the vehicle and component assemblies and parts which require painting shall be prepared and painted in accordance with MIL-STD-193, MIL-E-52798 or MIL-E-52835. Color shall be 383 green. The exterior of the vehicle shall be painted using chemical agent resistive coating (CARC) conforming to MIL-C-46168. Application of CARC shall be as directed by the procuring activity (see 4.13 and 6.2).

3.10.2 Marking. The vehicle marking shall be in accordance with MIL-STD-642. Parts and components shall be marked in accordance with MIl-STD-130 (see 4.13).

3.10.3 Name, shipping and service data plates. Plates shall meet the requirements of MIL-P-514, or applicable drawings (see 4.13).

3.11 Workmanship. Workmanship shall be of such quality as to assure that the vehicle and its components are free of defects that compromise, limit or reduce capability in the performance of its intendend use. In addition to general appearance, the defects listed in table V shall be considered to be cause for failure (see 4.14).

3.11.1 Welding repairs. Welding repairs of any kind shall be made only when, and to the extent, specifically authorized by the procuring activity (see 4.14.1 and 6.2).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order (see 6.2), the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform or witness any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

shall be subjected to a water spray test. The water spray test shall be

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Inspection equipment. Unless otherwise specified in the contract (see 6.2), the contractor is responsible for the provision and maintenance of all inspection equipment necessary to assure that supplies and services conform to contract requirements. Inspection equipment must be capable of repetitive measurements to an accuracy of 10 percent of the measurement tolerance. Calibration of inspection equipment shall be in accordance with MIL-STD-4662.

4.1.3 Government verification. All quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of (a) surveillance of the operation to determine that practices, methods, and procedures of the written quality assurance system plan are being properly applied, and (b) Government product inspection to measure the quality of the product offered for acceptance. Deviation from the prescribed or agreed upon procedure, or instances of poor practices which might have an adverse effect upon quality of the product, will immediately be called to the attention of the contractor. Failure of the contractor to promptly correct deficiencies shall be cause for suspension of acceptance until corrective action has been made, or until the conformance of the product to prescribed criteria has been demonstrated.

4.1.4 Qualified products. When a part or component is specified to conform to a specification having a Qualified Products List (QPL), the contractor shall make available to the Government documentation of item acquisition from such QPL. The documentation shall include the QPL date and identification of the supplier, purchase order, and quantity.

4.1.5 Quality assurance provisions. In the conduct of inspection, the contractor shall adhere to Quality Assurance Provisions (QAP) and General Quality Assurance Provision (STA Form 458) as applicable and as required by the documents forming part of this specification.

4.1.6 Certification. Where certification (see 4.8.1) is required to verify material or component conformance to a specification, the contractor shall furnish such certification along with documented test results and performance and analytical data, as applicable.

4.2 Classification of inspection:

a. First article inspection (see 4.3).
   1. First production vehicle inspection (FPVI) (see 4.3.1).
   2. Initial production test (IPT) (see 4.3.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

b. Quality conformance inspections (QCI) (see 4.4).
c. Control tests (see 4.5).
d. Comparison tests (see 4.6).

4.4 First article inspection. First article inspections shall be performed on the first production vehicle and on no less than two vehicles, randomly selected from vehicles that the contractor considers are representative of production parameters, which shall be designated as initial production vehicles. Approval of the first article samples shall not relieve the contractor of the obligation to supply vehicles that are fully representative of those inspected as a first article sample. Any changes or deviation of the production units from the first article sample shall be subject to the approval of the contracting officer.

4.3.1 FPVI.

4.3.1.1 In-process inspection. The first production vehicle shall be inspected during fabrication to determine conformance of materials and workmanship to specified requirements. These inspections shall preceed application of primer and paint. Processing and welding procedures, the quality system, inspection records, calibration procedures, radiographic procedures welder certifications shall be reviewed and evaluated.

4.3.1.2 Completed vehicle inspections.

4.3.1.2.1 Contractor inspection. The contractor shall subject the vehicle to a road test and the FPVI specified in table III. The road test shall

4.3.1.2.2 Preliminary inspection. The responsible Government inspection element shall conduct the FPVI specified in table III to the extent that acceptability of the vehicle is verified.

4.3.1.2.3 Provisional inspection. The Government procuring activity shall perform the FPVI specified in table III to the degree required to justify approval of the vehicle.

4.3.1.2.4 Vehicle disposition. After completion of inspection, the first production vehicle shall remain at the manufacturing facility, as a production sample, and be the last vehicle of its type shipped on the contract. The vehicle(s) may be released sooner at the discretion of the contracting officer. The contractor shall service and maintain the vehicle(s) during this period in accordance with applicable documents for care and preservation while in storage. All configuration changes taking place after the first production inspection, shall be made to the first production vehicle(s) so that the vehicle(s) will be representative of the current configuration throughout the life of the contract. No configuration changes may be implemented on production vehicles after Government conditional acceptance of the first production vehicle (applicable vehicle type) without written authorization from the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

TABLE III. Classification of inspections.

Title	Requirements	Inspection	First article		1/ QCI	1/ Control	1/ Comparison
			1/ FPVI	2/ IPT			
Material, design and construction	3.2 thru 3.3.1	4.8.1	X				
Defects (see table V)	3.3 thru 3.11.1	4.8.2	X	X	X		
Break-in run	3.3.2	4.8.1	X	X	X		
Break-in procedure	3.3.2.1	4.8.1	X	X	X		
Reverse operation	3.3.2.2	4.8.1	X	X	X		
Simulated break-in run	3.3.2.3	4.8.1	X	X	X		
Conditions after break-in run	3.3.2.4	4.8.1	X	X	X		
Special kits	3.3.3	4.8.1	X	X	X		
Cab personnel heater (primary)	3.3.3.1	4.8.1	X	X	X		
Cab personnel heater (secondary)	3.3.3.2	4.8.1	X	X	X		
Engine coolant heater	3.3.3.3	4.8.1	X	X	X		
Air brake	3.3.4	4.8.1	X	X	X	X	X
Bearing seals	3.4.1	4.8.3.1	X	X	X		X
Doors, windows and covers	3.4.2	4.8.3.2	X	X		X	
Engine	3.4.3	4.8.3.3	X	X			X
Engine air induction system	3.4.3.1	4.8.3.3.1	X	X			
Exhaust systems	3.4.4	4.8.3.4	X	X		X	X
Fuel system, grades and slopes	3.4.5	4.8.3.5	X	X	X		X
Fuel tank	3.4.5.1	4.8.3.5.1	X	X	X		X
Fuel lines	3.4.5.2	4.8.3.5.2	X	X	X		X
Rack linkage	3.4.5.3	4.8.3.5.3	X		X	X	
Transmission, transfer gear case, speed and increaser, control differential	3.4.6	4.8.3.6	X	X	X		
EW generator governor	3.4.7.1	4.8.3.7.1	X	X	X		X
EW generator governor frequency variation	3.4.7.1.1	4.8.3.7.1	X	X	X		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

TABLE III. Classification of inspections - Continued.

Title	Requirements	Inspection	First article		1/ QCI	1/ Control	1/ Comparison
			1/ FPVI	2/ IPT			
EW generator governor frequency drift	3.4.7.1.2	4.8.3.7.1	X	X	X		X
Lights	3.4.7.2	4.8.3.7.2	X	X	X		X
Communication and electrical circuits	3.4.7.3	4.8.3.7.3	X	X	X		X
System voltage characteristics	3.4.7.4	4.8.3.7.4	X	X			
Heaters	3.4.7.5	4.8.3.7.5	X	X	X		X
Controls	3.4.8	4.8.3.8	X	X	X		
Adjustment mechanisms	3.4.9	4.8.3.9	X	X	X		X
Stowed material	3.4.10	4.8.3.10	X	X		X	
EW generator input power	3.4.11.1	4.8.3.11.1	X	X	X		X
EW generator output voltage	3.4.11.2	4.8.3.11.1	X	X	X		X
EW generator output frequency	3.4.11.3	4.8.3.11.1	X	X	X		X
EW generator fault conditions	3.4.11.4	4.8.3.11.2	X	X	X		X
Engine stop faults	3.4.11.4.1	4.8.3.11.2	X	X	X		X
Generator off faults	3.4.11.4.2	4.8.3.11.2	X	X	X		X
Shelter power off fault	3.4.11.4.3	4.8.3.11.2	X	X	X		X
EW generator controls	3.4.11.5	4.8.3.11.3	X	X	X		X
GENERATOR ON switch	3.4.11.5.1	4.8.3.11.3	X	X	X		X
GENERATOR OFF switch	3.4.11.5.2	4.8.3.11.3	X	X	X		X
SHELTER ON switch	3.4.11.5.3	4.8.3.11.3	X	X	X		X
SHELTER OFF switch	3.4.11.5.4	4.8.3.11.3	X	X	X		X
EMERGENCY STOP switch	3.4.11.5.5	4.8.3.11.3	X	X	X		X
LAMP TEST switch	3.4.11.5.6	4.8.3.11.3	X	X	X		X
FAULT TEST switch	3.4.11.5.7	4.8.3.11.3	X	X	X		X
PRESS TO BYPASS switch	3.4.11.5.8	4.8.3.11.3	X	X	X		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

TABLE III. Classification of inspections - Continued.

Title	Requirements	Inspection	First article		1/ QCI	1/ Control	1/ Comparison
			1/ FPVI	2/ IPT			
METER FUNCTION switch	3.4.11.5.9	4.8.3.11.3	X	X	X		X
PANEL LAMPS control	3.4.11.5.10	4.8.3.11.3	X	X	X		X
VOLTAGE ADJUST control	3.4.11.5.11	4.8.3.11.3	X	X	X		X
FREQUENCY ADJUST control	3.4.11.5.12	4.8.3.11.3	X	X	X		X
Control panel indicators and displays	3.4.11.6	4.8.3.11.4	X	X	X		X
Elapsed time indicator	3.4.11.6.1	4.8.3.11.4	X	X	X		X
Frequency meter	3.4.11.6.2	4.8.3.11.4	X	X	X		X
Wattmeter	3.4.11.6.3	4.8.3.11.4	X	X	X		X
Voltage and amperage meter	3.4.11.6.4	4.8.3.11.4	X	X	X		X
Fault protection indicator lamps	3.4.11.6.5	4.8.3.11.4	X	X	X		X
Ground rod driver	3.4.12	4.8.3.11.5					
Ground rod driver input power	3.4.12.1	4.8.3.11.5	X	X	X		X
Ground rod driver hammer	3.4.12.2	4.8.3.11.5	X	X	X		X
Ground rod driver brake	3.4.12.5	4.8.3.11.5	X	X	X		X
EW shelter mechanical interface	3.4.13	4.8.3.11.6	X	X	X		X
Performance	3.5	4.8.4	X	X	X	X	
5000 mile operational profile	3.5.1	4.8.4.1	X	X	X		X
Reliability	3.5.1.1	4.8.4.1.1	X	X	X		X
Durability	3.5.1.2	4.8.4.1.2	X	X	X		X
Maintainability	3.5.1.3	4.8.4.1.3	X	X	X		X
Cooling systems	3.5.2	4.8.4.2					
Engine cooling	3.5.2.1	4.8.4.2	X	X	X		X
Bilge pumps	3.5.3	4.8.4.3	X	X		X	X
Speeds, and vehicle control	3.5.4	4.8.4.4	X	X	X		X
Acceleration	3.5.5	4.8.4.5	X	X	X		X
Engine starting on grades and slopes	3.5.6	4.8.4.6	X	X	X		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

TABLE III. Classification of inspections - Continued.

Title	Requirements	Inspection	First article 1/ FPVI	First article 2/ IPT	1/ QCI	1/ Control	1/ Comparison
Stopping and vehicle control	3.5.7.1	4.8.4.7.1	X	X	X	X	X
Holding	3.5.7.2	4.8.4.7.2	X	X	X	X	X
Turning	3.5.8	4.8.4.8	X	X	X	X	X
Shallow water fording	3.5.9	4.8.4.9	X	X	X		X
Trench crossing	3.5.10	4.8.4.10	X	X			X
Vertical obstacles	3.5.11	4.8.4.11	X	X			X
Grade and slope operation	3.5.12	4.8.4.12	X	X	X		X
Suspension	3.5.13	4.8.4.13	X	X	X		X
Winch system	3.5.14	4.8.4.14	X	X	X		X
Winch operation	3.5.14.1	4.8.4.14	X	X	X		X
Winch structural integrity	3.5.14.2	4.8.4.14	X	X		X	
Winch controls	3.5.14.3	4.8.4.14	X	X		X	
Environmental conditions	3.6	4.9	X	X		X	X
Electromagnetic interference suppression	3.7	4.10	X	X		X	X
Fire extinguisher	3.8	4.11	X	X		X	
Noise level	3.9	4.12	X	X		X	
Noise hazard caution sign	3.9.1	4.12.1	X	X			X
Painting, marking and data plates	3.10	4.13	X	X	X		X
Painting	3.10.1	4.13	X	X	X		X
Marking	3.10.2	4.13	X	X	X		X
Name, shipping and service data plates	3.10.3	4.13	X	X	X		X
Workmanship	3.11	4.14	X	X	X		X
Welding repairs	3.11.1	4.14.1	X	X	X		X
Preservation, packaging and vehicle processing	Section 5	4.15	X	X	X		X

1/ At place of manufacture
2/ At Government proving ground

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

4.3.2 IPT.

4.3.2.1 Contractor inspection. The contractor shall inspect the initial production test vehicle(s) in accordance with 4.4.

4.3.2.2 Government inspection. The Government shall perform the IPT specified in table III and a 5000- mile test according to the scenario as specified in table IV.

TABLE IV. 5000 mile IPT combat loaded (Government proving ground).

Course	Mileage and speeds
1/ Hard-surfaced roads	1000 miles at varying speeds up to maximum
Gravel and dirt roads	2000 miles at varying speeds up to maximum
Level cross country	1000 miles at varying speeds up to maximum
1/ Hilly cross country	1000 miles at varying speeds up to maximum
Shallow water	One (1) hour minimum at varying speeds up to maximum

1/ Hard-surfaced road and hilly cross country mileage includes 200 miles each with towed load.

4.3.3 Deficiencies. Unresolved failures or deficiencies during, or as a result of, first article inspection shall be cause for rejection of the vehicles until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiency. Any deficiency found during, or as a result of the IPT shall be evidence that all vehicles already accepted prior to completion of the IPT are similarly deficient unless contrary evidence satisfactory to the contracting officer is furnishd by the contractor. Such deficiencies on all vehicles shall be corrected by the contractor.

4.4 QCI. QCI shall be performed in the following sequence and utilizing an approved Final Inspection Record (FIR).

a. Examination for the defects specified in table III and classified in table V.
b. A 8-mile road test in accordance with 4.4.4.
c. QCI specified in table III.

4.4.1 One hundred percent. Each vehicle shall be subjected to the QCI specified in 4.4.

4.4.2 Acceptable quality level. When authorized by the Government contracting authority, one hundred percent QCI (see 4.4.2.1) shall be waived. Thereafter, samples shall be selected in accordance with 4.4.2.1.2 and shall be inspected to determine conformance to the following acceptable quality levels (AQL).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

Classification	AQL
Major	25
Minor	150

4.4.2.1 Sampling.

4.4.2.1.1 Lot formation. An inspection lot shall consist of all the vehicles of one type and part number, from an identifiable production perio, from one manufacturer, submitted at one time for acceptance.

4.4.2.1.2 Sampling for examination. When sampling is authorized for QCI (see 4.4.2) samples shall be selected in accordance with general inspection level II of MIL-STD-105. Before sampling may be initiated, the contractor shall examine at least 20 consecutively produced vehicles. The examination shall establish that the process average percent defective, as defined in MIL-STD-105, is not greater than the specified AQL.

TABLE V. Classification of defects.

Category	Defect	Method of examination
Major	AQL 25 Defects/100 Units	
101	Bearing seals, malfunction, damage, improper fit, leaks (see 3.4.1).	Visual and functional
102	Doors, windows and covers, improper fit, malfunction, damage (see 3.4.2).	Visual and functional
103	Engine, malfunction, leaks, improper mounting (see 3.4.3).	Visual and functional
104	Fuel system components, malfunction, leaks (see 3.4.5). 1/	Visual and functional
105	Transmission, malfunction, leaks, improper mounting (see 3.4.6).	Visual and functional
106	Transfer gear, speed increaser, differential steer and final drive, malfunction leaks (see 3.4.6).	Visual and functional
107	Electrical system components and circuits, communication system malfunction (see 3.4.7). 2/	Visual and functional
108	Controls; malfunction, clearance improper (see 3.4.8).	Visual and functional
109	Adjustment mechanisms, malfunction, clearance improper (see 3.4.9).	Visual and functional
110	Stowed material, malfunction, damage (see 3.4.10).	Visual and functional
111	EW generator system, malfunction (see 3.4.11).	Visual and functional
112	EW shelter mechanical interface, improper fit, malfunction, damage (see 3.4.13).	Visual and functional
113	Ground rod driver, malfunction, damage, improper installation (see 3.4.12).	Visual and functional
114	Cooling systems, components, malfunction, leaks, damage (see 3.5.2).	Visual and functional
115	Bilge pumps, malfunction, damage (see 3.5.3).	Functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

TABLE V. Classification of defects - Continued.

Category	Defect	Method of examination
116	Suspension system, components and adjustments damage, leaks, improper clearance, misalinement (see 3.5.13).	Visual and functional
117	Tracks, damage, pad separation (see 3.5.13).	Visual and functional
118	Track drive sprockets and driveshafts, damage, clearance improper (see 3.5.13).	Visual, functional, and SIE 3/
119	Fire extinguisher system control, seals missing, component damage (see 3.8).	Visual
120	Hull, structural and welding defects (see 3.11).	Visual and functional
Minor	AQL 150 Defects/100 Units	
201	Bearing seals, improper assembly or installation (see 3.4.1).	Visual and functional
202	Doors, windows and covers, improper assembly or installation (see 3.4.2).	Visual and functional
203	Engine, improper component assembly (see 3.4.3).	Visual and functional
204	Fuel system components, improper line clearance, assembly or installation (see 3.4.5). 2/	Visual and functional
205	Transmission, improper component assembly or installation (see 3.4.6).	Visual and functional
206	Transfer gear, speed increaser, differential steer and final drive units, improper component assembly or installation (see 3.4.6).	Visual and functional
207	Electrical, system components and circuits, communication system, improper assembly or installation (see 3.4.7).	Visual and functional
208	Controls, improper assembly or installation (see 3.4.8).	Visual, functional, and SIE 3/
209	Adjustment mechanisms, improper assembly or installation (see 3.4.9).	Visual and functional
210	Cooling system components, improper assembly or installation (see 3.5.2).	Visual and functional
211	Bilge pumps, improper assembly or installation (see 3.5.3).	Functional
212	Suspension, system components and adjustments improper installation or assembly, bolt or nut torque (see 3.5.13).	Visual, functional, and SIE
213	Tracks, tension, installation or assembly improper, including bolt torque, damage (see 3.5.13).	Visual, functional, and SIE
214	Track drive sprockets and drive shafts, improper assembly, installation or bolt torque (see 3.5.13).	Visual, functional, and SIE

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

TABLE V. Classification of defects - Continued.

Category	Defect	Method of examination
215	Fire extinguisher system control, data card incomplete, improper installation, coding or protection (see 3.8).	Visual
216	Caution signs improper installation, size or location (see 3.9.1).	Visual
217	Paint, application or color improper (see 3.10.1).	Visual
218	Marking data and instruction plates, missing, improper location or size, defective (see 3.10.2 and 3.10.3).	Visual
219	Workmanship, improper fit, appearance, installation, adhesion, adjustment, assembly or weldment (see 3.11 and 3.11.1).	Visual and functional

1/ Fuel leaks constitute a special defect and will result in total inspection of the lot for this defect.
2/ Filament failures are not to be classified as major or minor defects.
3/ SIE = Standard Inspection Equipment.

4.4.3 Defects. The following rules shall be applied to the counting of defects.

4.4.3.1 Unclassified defects. All defects that have no effect on function, safety, interchangeability or life, but are considered departures from good workmanship will be noted in writing. Workmanship deficiencies falling within this category and recurring in five consecutive lots, or ten lots or more within a thirty-day period, will be added to the minor defects classification with no increase in AQLs.

4.4.3.2 Recurring major deficiencies. A major deficiency is recurring when the same defect occurs more than once in the same sample, or when the defect occurs in two successive samples. A major defect may be considered recurring when the historical inspection records ("P" chart or approved equivalent) reflect such a condition. Recurring major deficiencies shall be cause for the entire lot or lots to be inspected for the recurring deficiencies. The deficiencies shall be corrected by the contractor when found.

4.4.3.3 Recurring minor deficiencies. A minor deficiency is recurring if it occurs more than twice in the same sample, or when the defect occurs in four successive samples. Recurring minor deficiencies shall be cause for the entire lot or lots to be inspected for the recurring deficiencies and correction shall be accomplished prior to acceptance.

4.4.4 Road test. A road test for each vehicle without payload, shall be conducted for a distance of eight miles or more by the contractor. The vehicle shall be completely assembled and serviced. It shall be subjected to tests specified to be performed at the place of manufacture in table III.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

Performance of the vehicles shall be demonstrated on smooth, relatively level hard surfaced roads, and shall meet all the requirements specified herein. After the tests, the vehicle shall be examined for evidence of fuel or lubricant leakage, or other deficiencies.

4.5 Control tests. One of the first 10 vehicles produced, and thereafter one per month, shall be selected for control testing after a break-in run. The vehicle shall be loaded to full combat weight and operated for a distance of 50 miles over relatively smooth, hard-surfaced roads. During and subsequent to the test, as appropriate, the vehicle shall meet the requirements specified for control tests in table III.

4.6 Comparison test. The Government may randomly select vehicles at anytime during the contract period and subject them to Government proving ground testing. Vehicles shall be examined for the defects listed in table V and tested in accordance with table III, including a 2000 mile test for reliability, maintainability, and durability in accordance with table VI. Vehicles shall be combat loaded with all BII stowed in their allotted space to conform to 3.4.10. Samples shall not include any vehicles previously tested.

TABLE VI. 2000 mile comparison test, combat loaded (Government proving ground)

Course	Mileage and speed
1/ Hard-surfaced or gravel	200 miles at varying speeds up to maximum
Shallow water	One (1) hour minimum at varying speeds up to maximum

1/ Hard-surfaced road and hilly cross country mileage includes 100 miles each with towed load.

4.7 Failure. Failure of any vehicle to pass any of the specified inspections or failure to meet inspection AQL levels, as applicable, shall be cause for the Government to refuse acceptance of the production quantity represented, until action taken by the contractor to correct defects and prevent recurrence has been approved by the Government.

4.8 Methods of inspection.

4.8.1 Materials and construction. Conformance to 3.2 through 3.3.4, shall be determined by inspection of contractor records providing proof or certification that design, construction, processing, and materials conform to requirements. Applicable records shall include drawings, specifications, design data, receiving inspection records, processing and quality control standards, vendor catalogs and certifications, industry standards, test reports, and rating data.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

4.8.2 Defects. Conformance shall be determined by examination of the characteristics for defects listed in table V. Examination shall be visual, tactile, or by measurement with standard inspection equipment.

4.8.3 Physical characteristics.

4.8.3.1 Bearing seals. To determine conformance to 3.4.1, the vehicle shall be operated in the environments and conditions specified. Bearing and seals shall subsequently be examined for lubricant leakage and lubricant contamination.

4.8.3.2 Doors, windows and covers. To determine conformance to 3.4.2, all doors, windows and covers shall be operated and examined for functional requirements.

4.8.3.3 Engine. To determine conformance to 3.4.3, the engine shall be operated throughout all speed ranges, and examined for proper installation and absence of leakage of lubricants, fuel and coolants. Prior to assembly and installation, all coolant, lubricant, and fuel lines shall be examined to insure internal cleanliness.

4.8.3.3.1 Engine air induction systems. To determine conformance to 3.4.3.1, the engine air induction system shall be examined for proper installation and absence of leaks.

4.8.3.4 Exhaust systems. To determine conformance to 3.4.4, the exhaust system shall be examined for proper installation and absence of leaks. Toxic fume levels measured in the driver and crew compartment shall not exceed specified values. For the test, the vehicle shall be sealed, the engine operated at 900 to 1000 rpm and the personnel heater, if installed, operated at high heat, for a period of not less than 30 minutes.

CAUTION: When conducting these tests, safety precautions shall be exercised (see 6.3.1).

4.8.3.5 Fuel system grades and slopes. With the vehicle operating on specified grades and slopes, the vehicle engine and fuel system shall be observed to determine conformance to 3.4.5.

4.8.3.5.1 Fuel tank. To determine conformance to 3.4.5.1, the fuel tank shall be examined for cleanliness. The fuel tank(s) filled to capacity, and all fuel lines and connections, shall be examined for leakage before and after the testing specified in 4.4.4.

4.8.3.5.2 Fuel lines. To determine conformance to 3.4.5.2, the fuel lines shall be examined for leaks at all connections and sealed items before and after a road test on smooth, level, hard-surfaced road.

4.8.3.5.3 Rack linkage. To determine conformance to 3.4.5.3, the accelerator pedal shall be operated to full throttle, and the rack examined to assure that full open position has been reached when pedal is in contact with stop.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

4.8.3.6 Transmission, transfer gearcase, speed increaser, and control differential. To determine conformance to 3.4.6, the transmission and control differential shall be operated throughout all gear ranges, and examined for proper installation and absence of leaks.

4.8.3.7 Electrical systems.

4.8.3.7.1 EW generator governor. To determine conformance to 3.4.7.1 through 3.4.7.1.2 with the EW generator governor operating as specified, voltage and frequency measurements shall be made under the specified load conditions. Conformance with 3.4.7.1 shall be determined immediately after the road test.

4.8.3.7.2 Lights. All lights shall be operated during and after break-in run throughout all stages of operation, and observed to determine conformance to 3.4.7.2.

4.8.3.7.3 Communication and electrical circuits. To determine conformance to 3.4.7.3, electrical circuits supplying current to vehicle equipment shall be tested at all points to assure continuity throughout the circuits. Previously tested circuits shall be functionally tested after installation.

4.8.3.7.4 System voltage characteristics. System voltage characteristics shall be evaluated as specified in MIL-STD-1275 to determine conformance to 3.4.7.4.

4.8.3.7.5 Heaters. To determine conformance to 3.4.7.5, verify that the personnel and cargo area heaters start and operate satisfactorily when 20 V dc is applied at the appropriate connectors.

4.8.3.8 Controls. All controls shall be operated as specified and observed to determine conformance to 3.4.8.

4.8.3.9 Adjustment mechanisms. To determine conformance to 3.4.9, all adjustment mechanisms shall be observed during operation, examined for proper adjustment, and adjusted if required.

4.8.3.10 Stowed material. To determine conformance to 3.4.10, all manufacturer and depot installed BII shall be stowed (combat loaded) on the vehicle. All interior and exterior items shall fit in the spaces provided. The material shall be removed after the test. The BII shall be of the latest configuration available to the contractor. The contractor shall be permitted to unpackage and repackage equipment used for test (for domestic shipment only).

4.8.3.11 EW generator system.

4.8.3.11.1 EW generator input power, output voltage, and output frequency. To determine conformance to 3.4.11.1 through 3.4.11.3, with the EW generator operating as specified, the input power, output voltage, and output frequency shall be measured over the ranges and at the limits specified therein (see 6.3.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

Yearbook.

4.8.3.11.2 EW generator fault conditions. To determine conformance to 3.4.11.4.1 through 3.4.11.4.3, with the EW generator operating as specified, the fault conditions shall be simulated and the specified system response verified.

4.8.3.11.3 EW generator controls. To determine conformance to 3.4.11.5.1 through 3.4.11.5.11, with the EW generator operating as specified, the EW generator controls shall be operated and the specified system response verified.

4.8.3.11.4 Control panel indicators and displays. To determine conformance to 3.4.11.6.1 through 3.4.11.6.5, with the EW generator operating as specified, the control panel indicators and displays shall be examined and the proper indications verified.

4.8.3.11.5 Ground rod driver. To determine conformance to 3.4.12.1 through 3.4.12.3, the ground rod driver shall be operated and examined for proper installation.

4.8.3.11.6 EW shelter mechanical interface. To determine conformance to 3.4.13, the shelter mechanical interface components shall be tested and examined for proper installation.

4.8.4 Performance. To determine conformance to 3.5, unless otherwise specified herein, testing shall be performed on smooth, hard, flat, level surfaces free of loose material.

4.8.4.1 5000 mile operational profile. To determine conformance to 3.5.1, the 5000 mile operational profile shall be performed as specified in table IV.

4.8.4.1.1 Reliability. To determine conformance to 3.5.1.1, a point estimate value equal to or greater than 750 miles shall be demonstrated during test. The point estimate value will be computed by dividing the total cumulative test mileage of all the test vehicles by the total cumulative chargeable failures experienced on these vehicles.

4.8.4.1.2 Durability. Conformance to 3.5.1.2 shall be verified during test at or above a 50 percent confidence level. The durability requirement will be calculated using a binominal approach requiring a minimum test vehicle sample of two vehicles.

4.8.4.1.3 Maintainability. To determine conformance to 3.5.1.3, a MR equal to or less than that specified, must be demonstrated during test. The MR will be based upon the total cumulative maintenance manhours with the exceptions of human induced errors and driver or crew checks and services.

4.8.4.2 Cooling systems. To determine conformance to 3.5.2.1 through 3.5.2.3, the vehicle shall be operated at specified ambient temperatures and cooling system temperatures measured during and after the test. The radiator pressure cap shall be pressure tested and shall relieve the operating pressure within the specified range.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

4.8.4.3 Bilge pumps. To determine conformance to 3.5.3, the vehicle shall have sufficient water in the hull to measure the bilge pumps operation. The rate of water removal, discharge head and the pump motor voltage shall be measured.

4.8.4.4 Speeds and vehicle control. To determine conformance to 3.5.4, the vehicle shall be driven at speeds from 2 to 3 mph for not less than five minutes and at specified speeds thereafter and performance observed.

4.8.4.5 Acceleration. To determine conformance to 3.5.5, the vehicle shall be operated as specified, and the acceleration measured.

4.8.4.6 Engine starting on grades and slopes. To determine conformance to 3.5.6, the vehicle shall be driven up a 60 percent grade. After the vehicle has been standing on the grade for not less than two minutes, with the engine operating under no load, between 750 and 1000 rpm, the engine shall be stopped for not less than two minutes and restarted within the specified time. The vehicle shall then be operated on 30 percent side slopes and the engine stopped for not less than two minutes and restarted within the specified time.

4.8.4.7 Braking.

4.8.4.7.1 Stopping and vehicle control. To determine conformance to 3.5.7.1, the vehicle shall be driven at the specified speed and stopped. Three stops shall be made and the results shall be averaged to determine acceptance.

4.8.4.7.2 Holding. To determine conformance to 3.5.7.2, the vehicle shall be driven up the specified grade, brakes applied and the vehicle observed for movement. Then, with brakes locked for parking, the vehicle shall again be observed for movement. During this test the vehicle shall be combat loaded, or with a simulated load of equal weight placed in a position that will not restrict the flow of engine air (intake or exhaust).

4.8.4.8 Turning. To determine conformance to 3.5.8, the vehicle shall be operated as specified, turned to the right and left in full 360 degree turns and performance observed.

4.8.4.9 Shallow water fording. To determine conformance to 3.5.9, the vehicle shall be driven into water of specified depth without special equipment. Water accumulation shall not exceed specified amount after 15 minutes of test.

4.8.4.10 Trench crossing. To determine conformance to 3.5.10, the vehicle, without ground rod driver installed, shall be operated over trenches of specified depth and width.

4.8.4.11 Vertical obstacles. To determine conformance to 3.5.11, the vehicle shall be operated over vertical obstacles of specified height.

4.8.4.12 Grade and slope operation. To determine conformance to 3.5.12, the vehicle shall be operated as specified on grades and slopes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

4.8.4.13 Suspension. To determine conformance to 3.5.13, the vehicle, operating at a speed of 18 to 22 mph, shall cross specified obstacles without bottoming out.

4.8.4.14 Winch system. To determine conformance to 3.5.14 through 3.5.14.3, the winch shall be operated as specified and performance observed.

4.9 Environmental conditions. To determine conformance to 3.6, the vehicle shall be stored and operated at the temperatures specified.

4.10 Electromagnetic interference suppression. To determine conformance to 3.7, the vehicle shall be tested as specified in MIL-STD-462.

4.11 Fire extinguisher. To determine conformance to 3.8, the fire extinguisher system shall be examined and functionally tested (see 6.3.2).

4.12 Noise level. To determine conformance to 3.9, the vehicle noise level measured at the location indicated shall not be more than the specified dB, when measured with a sound level meter which meets the requirements of MIL-STD-1474.

4.12.1 Noise hazard caution sign. To determine conformance to 3.9.1, the driver and passenger compartments shall be examined for signs indicating noise hazard.

4.13 Painting, marking and data plates. To determine conformance to 3.10.1, 3.10.2 and 3.10.3, the vehicle shall be visually examined to verify the painting, marking and data plate requirements.

4.14 Workmanship. The vehicle shall be examined to determine conformance to 3.11.

4.14.1 Welding repairs. To determine conformance to 3.11.1, all welding repairs and burning operations shall be examined to determine that slag has been removed and approved procedures have been followed.

4.15 Preservation, packaging, and vehicle processing inspection. Material and equipment shall be inspected, prior to shipment, to determine conformance to Section 5 of this specification. Sampling shall be as specified in applicable packaging specification referenced therein.

5. PACKAGING

5.1 Preparation for delivery. Preparation for delivery and storage shall be as directed by the procuring activity.

6. NOTES

6.1 Intended use. The M1015A1 carriers are to be used to transport, and to provide prime operating power for, SIGINT/Electronic Warfare systems.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Model of carrier, drawing title, number and date (see 2.1.2).
c. If first article samples are required (see 3.1).
d. If simulated break-in run is authorized (see 3.3.2.3).
e. If special kits are required (see 3.3.3).
f. Instructions for CARC application (see 3.10.1).
g. If welding repairs are authorized, and extent allowed (see 3.11.1).
h. If responsibility for inspection shall be other than as specified (see 4.1).
i. If responsibility for inspection equipment shall be other than as specified (see 4.1.2).
j. Applicable levels of preservation, packaging, packing, and marking (see 5.1).

6.3 Safety precautions.

6.3.1 Carbon monoxide. Carbon monoxide is a colorless, odorless, deadly poisonous gas which, when breathed, deprives the body of oxygen and causes suffocation. Exposure to air contaminated with carbon monoxide produces symptoms of flushed complexion, headache, dizziness, dimness of vision, nausea, apparent drowsiness, loss of muscular control. If exposure symptoms are evident, remove affected personnel from the area and treat as follows: expose to fresh air; keep warm; do not permit physical exercise; if necessary, administer artificial respiration (see 4.8.3.4).

6.3.2 Fire extinguisher. Caution should be exercised in handling carbon dioxide fire extinguisher cylinders. They should not be dropped, permitted to strike each other, or be handled roughly. Extreme care should be exercised during reinstallation to avoid tripping fire extinguisher control system since physical injury is highly probable (see 4.11).

6.3.3 EW generator high voltage. Extreme caution shall be used when operating the EW generator to avoid contact with high voltage (see 4.8.3.11.1).

6.4 Process average. Sampling may be initiated if the process average value for the first twenty vehicles inspected is less than the AQL specified in the classification of defects for major and minor defects. If the computed process average exceeds the specified AQL, 100 percent inspection shall be performed and continued until such time that the process average for twenty consecutive vehicles is less than the specified AQL.

6.5 Leakage definitions. The following definitions shall be used with the classification of defects for leaks:

a. Weep - Any evidence of fluid beyond the seal.
b. Seep - Any evidence of fluid beyond the seal that does not result in the formation of a droplet.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

c. Droplet - Any evidence of fluid beyond the seal that results in the formation of a droplet.
d. Drip - Any evidence of fluid beyond the seal where the droplet forms and falls.

6.6 International standardization agreement. Certain provisions (see 3.5.9) of this specification are the subject of international standardization agreements NATO STANAG 2805-A (Edition 3), and ABCA-ARMY-STD-151. When amendment, revision or cancellation of this specification is proposed which will affect or violate the international agreement concerned, the preparing activity will take appropriate reconciliation action through international standardization channels, including departmental standardization offices, if required.

6.7 Recycled materials. The use of recycled materials which meet the requirements of the applicable material specifications without jeopardizing the intended use of the item shall be encouraged (see 3.2).

6.8 Mission failure scoring criteria. M113 Family Vehicles Failure Definition and Scoring Criteria may be obtained from the US Army Tank-Automotive Command, Warren, MI 48397-5000, ATTN: AMSTA-QRA.

6.9 Supersession data. This military specification supersedes Western Division, GTE Government Systems Corporation (FSCM 07397), specification draft, dated 26 April 1985.

Custodian:
Army - AT

Preparing activity:
Army - AT

(Project No. 2350-A326)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.




FIGURE 1. Profile of test track (artificial pump).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Tank-Automotive Command
ATTN: AMSTA-GSS
Warren, MI 48080

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*:

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

DD FORM 82 MAR 1426

PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:24Z
Check the source to verify that this is the current version before use.