MIL-S-48893 (AR)
7 July 1977
SUPERSEDING
See Section 6

MILITARY SPECIFICATION

SHIPPING AND STORAGE CONTAINER: XM543E1

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of container entitled Shipping and Storage Container: XM543E1 which is used with the Sprint warhead.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-M-50508 - Mounts, Resilient
MIL-M-6866 - Inspection, Penetrant Method of
MIL-W-22248 - Weldments, Aluminum and Aluminum Alloy
MIL-T-5021 - Tests, Aircraft Welding Operator's Certification

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-1261 - Welding Procedures for Constructional Steels.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components.

Beneficial comments (recommendations, additions, deletions), and any pertinent data which may be of use in improving this document, should be addressed to: Commander, US Army Armament Research and Development Command, ATTN: DRDAR-QAN-Q, Dover, New Jersey 07801, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426), appearing at the end of this document, or by letter.

FSC 1410R

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

DRAWINGS

ORDNANCE CORPS

8859012	- Finishing Requirements for Ferrous Metal Containers.
9243645	- Ground Cable Assembly.
9257235	- Shipping and Storage Container: XM543E1.
9257236	- Cover Assembly.
9257237	- Base Assembly.
9268965	- Frame Assembly.
9268966	- Sandwich Mounting, Bonded.
EL-9243645	- Equipment List.
EL-9257235	- Equipment List.
EL-9257236	- Equipment List.
EL-9257237	- Equipment List.
EL-9268965	- Equipment List.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The container shall comply with all requirements specified on the drawing (dwg) 9257235, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. The contractor shall assign serial numbers as required by drawings. The contractor may select any number which complies with the drawing requirement. These numbers shall not be duplicated.

3.5 Performance. The container and its frame assembly shall support, without damage, and permit the installation and removal of an adaption kit (AK) sub-assembly with associated cables and hardware or an approved test load. The test load shall be identical to the AK in configuration, center of gravity (cg), weight and possess all features needed for mounting to the frame assembly. The container shall be loaded in the manner described in 4.4.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

3.6 Physical characteristics. The container shall withstand the handling operations described below. The physical tests shall be performed as described in 4.4.2. Upon completion of the test the container should not exhibit any physical damage to the shock mitigating assembly, and the approved test load shall remain in place and not create a hazard. Bending and distortion shall be permitted providing container complies with 3.7.

3.6.1 Stacking. The container shall support a load equivalent in weight to five loaded containers for a minimum of 15 minutes.

3.6.2 Drop test. The container shall be positioned and dropped from a height of 24 inches in all attitudes.

3.6.3 Transportation vibration. The container shall be subjected to the vibratory parameters specified in Table I along its 3 mutually perpendicular axis.

Table I

Vibration Schedule, Three Axis Testing

Frequency Hertz (Hz)	Amplitude	Bi-Directional Time (minutes)	Number of Sweeps
5.5-13-5.5	0.30" (double amplitude) (da)	7.7	2
13-17-13	1.5g	2.0	2
17-25-17	0.1" da	3.1	2
25-37-25	2.5g	3.1	2
37-52-37	0.036" da	2.6	2

Sweep rate 0.15 oct/min.

3.7 Seal integrity. The sealed container with or without the test load shall withstand an internal pressure of 3+0.5 pound per square inch gauge (psig) maintained for 30 minutes minimum (min). The leakage rate shall not exceed 0.01 psig. Testing shall be as described in 4.4.3.

3.8 Design and construction.

3.8.1 Material, process, and unit of product. Materials, processes, and units of product (see 6.2) shall conform to the requirements specified in the contract, drawings and specifications. The contractor shall have objective quality evidence (see 6.2) available to the Government substantiating that inspections (see 6.2) to determine conformance have been performed and regulated as prescribed in the contractor's quality control (see 6.2) system. The contractor shall offer, to the Government, only those units that have conformed.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.

3.8.2 Weldments. Weldments shall be reasonably smooth and free of craters. They shall exhibit characteristics of fusion penetration and soundness of weld deposit representative of good welding practice. They shall be free of irregularities which indicate lack of good practice on the part of the operator. All welding fluxes, scale, weld spatter, acids or basic solutions shall be removed prior to application of any finish coat.

3.8.3 Units of product. Listed units, assembled into the container shall have conformed with designated specifications. Objective quality evidence, substantiating conformance, shall be made available to the Government Representative before units are assembled into container or used in connection with the container.

Unit of Product	Drawing	Specification
Sandwich Mounting; Bonded	9268966	MIL-M-50508

3.9 Welder. Only welder(s) certified as prescribed in MIL-T-5021 is (are) authorized to make weldments.

3.10 Welding. Welding shall be in accordance with MIL-W-22248 or MIL-STD-1261 as applicable (see 4.4.4).

3.11 Penetrant. (Before protective finish is applied). Penetrant inspection shall be in accordance with MIL-I-6866, Type 11 (see 4.4.5).

3.12 Circuit resistance (Ground cable). The circuit resistance of the ground cable shall not exceed 0.025 ohms when tested as specified in 4.4.6.

3.13 Workmanship.

3.13.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.13.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.13.3 Burrs. Parts shall be free from burrs.

3.13.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.13.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.

inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 1 complete assembly (see dwg 9257235) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table II. Tests shall be conducted in order specified in Table II.

Table II

First article inspection and tests

Inspection or Test	Dest	Non-Dest
1. Classification of Characteristics/ Defects (see 4.3.2.1)		X
2. Circuit resistance (see 3.12)		X
3. Performance (see 3.5)		X
4. Physical characteristics (see 3.6)		X
5. Welding (see 3.10)		X
6. Penetrant (see 3.11)		X
7. Seal integrity (see 3.7)		X

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor defects/characteristics table (see Table III and Table IV), and inspected for all defects/characteristics in the applicable classification. Any defects/characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of defects/characteristics in each classification need not be followed as long as all defects/characteristics inspections are performed.

Table III
Major Defects/Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

Table IV
Minor Defects/Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-9	all	14-16	12	28-33	16	77-121	20
10	9	17-18	13	34-41	17	122-273	21
11	10	19-22	14	42-54	18	over 273	22
12-13	11	23-27	15	55-76	19		

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.2.1 Classification of defects/characteristics (see 3.2). Critical, major and minor defects/characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1 Ground cable assembly (see dwg 9243645).

Categories	Defects/Characteristics	Methods of Inspection
Critical:	None defined.	
Major:		
101.	Pin not peened over (see note on dwg) (2 places)	Visual
102.	Wire braid damaged	Visual
103.	Cable overall length incorrect	Gage
104.	Cable terminal or fittings incorrect	Visual
Minor:		
201.	Marking missing, improper, misplaced or illegible	Visual

4.3.2.1.2 Shipping and storage container XM543E1 (see dwg 9257235) cover removed.

Categories	Defects/Characteristics	Methods of Inspection
Critical:	None defined.	
Major:		
101.	Sandwich mounts (8) improperly installed, assembled, or loose, missing, damaged improper	Manual/Visual
102.	Components improperly assembled, installed or missing, loose, damaged, improper, misplaced	Manual/Visual
103.	Insufficient torque applied to nuts (8) attaching mounts to cradle assembly	Gage
104.	Latch (12) engage and disengage smoothly	Manual
105.	Protective finish damaged exposing base metal or is improper	Visual
106.	Marking missing, illegible, or is improper	Visual
107.	Identification plate missing or is improperly positioned	Visual
108.	Nuts (2) improperly torqued	Gage
109.	Serialization missing or improper (see 3.4)	Visual

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:43Z
Check the source to verify that this is the currentversion before use.

Major: (Cont).

110. Objective evidence relative to material missing or improper (see 3.1).....Visual

Minor:

201. Evidence of poor workmanship (see 3.13).....Visual

4.3.2.1.3 Cover assembly (see dwg 9257236).

Categories	Defects/Characteristics	Methods of Inspection
Critical:	None defined.	
Major:		
	101. Incorrect length at parting (2 places)	Gage
	102. Incorrect height all around	Gage
	103. Weldment not in conformance to MIL-W-22248	Visual
	104. Evidence of poor workmanship (see 3.13)	Visual
	105. Incorrect height from parting edge to latch gripping surface (see Detail "C") all around	Gage
Minor:	None defined.	

4.3.2.1.4 Base assembly (see dwg 9257237).

Categories	Defects/Characteristics	Methods of Inspection
Critical:	None defined.	
Major:		
	101. Incorrect position of latches (12)	Gage
	102. Incorrect height	Gage
	103. Incorrect length (2 places)	Gage
	104. Incorrect location of holes (4 places)	Gage
	105. Weldment not in conformance to MIL-W-22248	Visual
	106. Evidence of poor workmanship (see 3.13)	Visual
Minor:	None defined.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.2.1.5 Frame assembly (see dwg 9268965).

Categories	Defects/Characteristics	Methods of Inspection
Critical:	None defined.	
Major:		
101.	Length of cross members incorrect	Gage
102.	Location of cross members incorrect	Gage
103.	Welds not in conformance with MIL-STD-1261	Visual
104.	Position of hex head cap screws incorrect (2 places)	Gage
105.	Pitch diameter of threaded holes incorrect (max) (8 places)	Gage
106.	Minor diameter of threaded holes incorrect (min) (8 places)	Gage
107.	Location of threaded holes incorrect (8 places)	Gage
108.	Incorrect depth of c'bore or countersink	Gage
109.	Outside dimensions of basket incorrect	Gage
110.	Location of basket incorrect	Gage
111.	Flatness of datum -A- incorrect	Gage
112.	Location of stop plates incorrect (4 places)	Gage
113.	Components improperly assembled, damaged, missing, improper or loose	Manual/Visual
114.	Objective evidence that finish complies with dwg 8859012 missing (see 3.8.1)	Visual
115.	Evidence of poor workmanship (see 3.13)	Visual
Minor:	None defined.	

4.3.2.1.6 Sandwich mounting, bonded (see dwg 9268966).

Categories	Defects/Characteristics	Methods of Inspection
Critical:	None defined.	
Major:		
101.	Objective quality evidence that mounts conform to specification, missing, improper or incomplete (see note on dwg)	Visual
102.	Marking missing, improper, misplaced or illegible (see note on dwg)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

Major: (Cont.).

103. Mount damaged (VIZ: crack, split, gouge, rupture, etc.).....Visual
104. Mount older than 18 months (see note on dwg).....Visual

Minor: None defined.

4.3.2.1.7 Preparation for delivery (see 5).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Preservation, packing, and packaging not in accordance with MIL-STD-1169	Visual
	102. Marking not in accordance with MIL-STD-1169	Visual
Minor:		
	201. Evidence of poor workmanship (see 3.13)	Visual

4.3.3 Testing. All tests shall be performed. Tests need not be performed in the order specified below:

Test	Test Classification
a. Circuit resistance	Major
b. Performance	Major
c. Welding	Major
d. Penetrant	Major
e. Seal integrity	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Performance, circuit resistance and seal integrity. Each container shall be tested in accordance with 4.4.1, 4.4.3 and 4.4.6. If any item fails to comply with 3.5, 3.7 and 3.12 the item shall be rejected and removed from the lot.

4.3.3.2 Welding, and penetrant. A sample shall be selected at random in accordance with Table III. The sample shall be tested in accordance with 4.4.4 and 4.4.5. If any item fails to comply with 3.10 and 3.11, the lot shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major defects/characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see ELs-9243645, 9257235, 9257236, 9257237, and 9268965). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor defects/characteristics and tests. Acceptance inspection equipment for minor defects/characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Performance testing. The adaption kit subassembly or approved test load shall be lowered onto the frame assembly in the proper orientation so that the grounding plug hole is toward the left side of container (from front looking toward the rear of container). This position allows the bracket assembly to extend to the left front over the subassembly without interference. The subassembly shall fit firmly in place without rocking on the frame assembly. The retaining plate assembly and the bracket assembly shall be placed in sequence over the subassembly and shall fit loosely without excessive rocking. Secure subassembly, retaining plate assembly, and bracket assembly with washers, lock washers and nuts torqued to 20±5 inch-pounds. The cover shall be placed on the container in proper orientation and secured by swinging latches into position and turning clockwise 180°. Thereafter, the container shall conform to the requirements of 3.7 when tested as described in 4.4.3. This test (seal) may be performed without the approved test load and at final assembly prior to delivery.

4.4.2 Physical characteristics. The loaded and sealed container shall be tested (at ambient temperature) as described below. Prior to and after testing, the container shall be tested and conform to requirements of 3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.4.2.1 Stacking. A load equal to five times the gross (loaded) weight of the container shall be applied to the top of the container shall be applied to the top of the container in a manner simulating the effect of a similar container being stacked on the container supporting the load.

4.4.2.2 Drop test. The container shall be positioned; raised off the floor to a height of 24 ± 1/2 inches and dropped free fall, as described below:

4.4.2.2.1 Flat drop. The container shall be raised off the floor and dropped so that it lands flatly onto a concrete or equally hard flat surface. This test shall be performed once on the top, bottom and any side for a total of three drops.

4.4.2.2.2 Corner drop. The container shall be raised off the floor and dropped onto a concrete or equally hard flat surface. The test shall be performed once each on diagonally opposed corners for a total of two drops.

4.4.2.3 Transportation vibration. The container, mounted onto a fixture capable of being oriented to vibrate the container in the three mutually perpendicular axes shall be secured to an approved vibration device, and tested to requirements in 3.6.3.

4.4.3 Seal integrity. The container shall be pressurized through the pressure relief port or other suitable opening to 3 ± 0.5 psig with a gas that is non-corrosive to metallic, and non-metallic material. The specified pressure shall be maintained for 30 minutes minimum. After the 30 minutes have elapsed, the pressure drop in the manometer column shall not be greater than 0.01 psig. An approved "U" shaped tube manometer with increments graduated to allow visual detection in pressure, and filled with merian No. 3 oil shall be used for this test. After testing, the pressure shall be released and the container and test load or adaption kit shall be examined for damage (see 6.4). Pressure relief valve is to be replaced and properly torqued. Other test methods, equal to or superior in sensitivity to the test described may be used, after approval is granted by the procuring activity.

4.4.4 Welding. Acceptability criteria for weldments are specified in MIL-W-22248, or MIL-STD-1261 as applicable, using the penetrant inspection method. Weldments found unacceptable, shall not be removed unless the repair method is approved by the procuring activity (see 6.3) ATTN: SARPA-QA-N-Q.

4.4.5 Penetrant. Penetrant inspection shall be in accordance with MIL-I-6866, Type II Method. However, discontinuities, if any, cannot be removed, unless removal method is approved by the procuring activity.

4.4.6 Circuit resistance. The circuit resistance of the ground cable shall be measured with approved measuring equipment.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The container shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(PA).

5.1.2 Level C. The container shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(PA).

5.2 Packing.

5.2.1 Levels A and C. The container shall be packed in accordance with the applicable instructions contained in MIL-STD-1169(PA).

5.3 Marking. Marking shall be in accordance with MIL-STD-1169(PA).

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.

b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 when required on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, US Army Armament Research and Development Command, ATTN: DRDAR-QAN-I, Dover, New Jersey 07801.

6.4 Damage. A defect that is detectable by visual examination and listed under the following categories:

(1) Internal, VIZ: Illegible marking, damage in finish exposing base metal; loose component; broken or permanently set structural member; distorted, split crack in mount; or separation of mount from mounting plate.

(2) External, VIZ: Illegible marking, damage in finish, exposing base metal; loose component; broken or permanently set structural member; puncture in shell or separation of weldment; crack; tear; damage in gasket.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description PA-PD-2237A dated 24 June 1974.

Custodian:
Army - AR

Preparing activity:
Army - AR

Project No. NUOR-A065

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426

REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Armament R&D Command
ATTN: DRDAR-QAN-Q
Dover, NJ 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:43Z
Check the source to verify that this is the current version before use.