24 January 1972
Superseding
MIL-T-55655(EL)
4 February 1969

MILITARY SPECIFICATION
TEST FACILITIES KIT MK-980( )/PPS-5

1. SCOPE

1.1 Scope.- This specification covers the requirements for a portable, self contained test set for maintenance support of Radar Set AN/PPS-5( ).

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

NN-P-71	Pallet, Materials Handling, Wood
QQ-S-781	Steel, Strapping Flat
PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated-Plywood
PPP-B-621	Box, Wood, Nailed and Lock Corner
PPP-B-636	Box, Fiberboard
PPP-B-640	Box, Fiberboard, Corrugated, Triple-Wall
PPP-F-320	Fiberboard, Corrugated and Solid, Sheet Stock (Container Grade) and Cut Shapes
PPP-S-760	Strapping, Non-Metallic
PPP-T-76	Tape, Pressure-Sensitive Adhesive Paper, Water Resistant (for carton sealing)
PPP-T-97	Tape, Pressure-Sensitive Adhesive, Filament Reinforced

MILITARY

MIL-P-116	Preservation, Methods of
MIL-T-152	Treatment, Moisture and Fungus-Resistant
MIL-V-173	Varnish, Moisture and Fungus Resistant
MIL-C-3885	Cable Assemblies and Cord Assemblies
MIL-T-7928	Terminals, Lug and Splice, Crimp-Style, Copper
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Signal Equipment
MIL-R-55348(EL)	Radar Set AN/PPS-5( )

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipping and Storage
MIL-STD-147	Palletized and Containerized Unit Loads 40 inch x 48 inch pallets, skids, runners, or pallet type base
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects
MIL-STD-454	Standard General Requirements for Electrical Equipment
MIL-STD-461	Electromagnetic Interference Characteristics Requirements for Equipment
MIL-STD-462	Electromagnetic Interference Characteristics Measurement of
MS90577	Adapter, Connector, Series Uhf to Series BNC, UG-273/U

DRAWINGS

ELECTRONICS COMMAND

DL-SM-A-610197	Test Facilities Kit MK-980( )/PPS-5
SC-B-61578	Grounding to Chassis
SC-A-46691	RF Cable Assembly Tests

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies).

3. REQUIREMENTS

3.1 Definition.- Test Facilities Kit MK-980( )/PPS-5 is a portable unit, contained in a lightweight, fiberglass case. It provides independent circuits for testing Radar Set AN/PPS-5( ) components. Power converter units of the radar set are part of the MK-980( )/PPS-5 and provide the necessary voltage for energizing removed components of the radar set during bench tests. Test jacks on the test panel provide access to circuit test points. Associated cables and connectors of the MK-980( )/PPS-5 provide for interconnection to the radar set or to components under test. The test facilities kit operates from 115 VAC, 50 to 1,000 Hz or from a 6 VDC source.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

3.2 First Article.- The contractor shall furnish first articles for approval, if required by the invitation for bids and the contract. (See 4.3 and 6.1e(1).

3.3 Physical construction.- Physical construction shall be in accordance with the following:

DL-SM-A-610197	Test Facilities Kit MK-980( )/PPS-5
MS 90577	Adapter, Connector, Series Uhf to Series BNC, UG-273/U
MIL-R-55348(EL)	Radar Set AN/PPS-5( ) (Converter Assemblies, Radar and Remote)

3.4 Parts, materials and processes.- (See 4.4)

3.4.1 Cable assemblies and leads, electrical.- Cable assemblies and leads shall be constructed in accordance with the applicable drawings and shall meet all the requirements of the following documents: (See 4.4)

Specification	MIL-C-3885 (audio & power)
Drawing	SC-A-46691 (rf)

3.4.2 Cleaning.- In addition to Requirement 9 of MIL-STD-454, the following shall apply:

After assembly, units shall be cleaned thoroughly and shall be free from particles of solder, flux, and other foreign material. In addition, when necessary, such cleaning shall also be performed before final assembly of units.

3.4.3 Finish.- The equipment shall be finished in accordance with Specification MIL-F-14072 and the equipment drawings. (See 4.4)

3.4.4 Marking.- Marking shall be in accordance with Requirement 67 of MIL-STD-454, and MIL-M-13231 for front panel marking. (See 4.4)

3.4.4.1 Serial Number.- Each Test Facilities Kit and each Test Panel shall be serial numbered.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

3.4.5 Connections.- Bared ends of wire leads to be terminated in solder-type terminal lugs shall be tinned, silver-plated, or lead-alloy coated. Electrical connections shall not be made by clamping between a metallic and a nonmetallic material. Welded electrical connections shall not be used where it may be necessary to disconnect and reconnect the circuit during servicing. Fraying of textile ends of wires shall be prevented mechanically or by application of varnish conforming to MIL-V-173, in accordance with MIL-T-152. No varnish, lacquer, inspection paint, or other coating shall be applied to completed electrical connections, except that these connections need not be masked during overall treatment with transparent protective coating materials.

3.4.6 Grounding.- Ground connection to shields and to other mechanical parts, except the chassis or frame, shall not be made to complete electrical circuits but only to eliminate high potential ac points. Intermediate-frequency transformers, however, may be grounded through their cases if other means of grounding are impracticable. Grounding to chassis shall conform to Drawing SC-B-61578.

3.4.7 Wiring.- Wiring shall be in accordance with Requirement 20 of MIL-STD-454 and the following:

a. Wires shall not be bent sharply where they enter insulation material.

b. Insulating sleeving.- Insulating sleeving shall not be used unless specified for a particular application or specifically approved by the contracting officer. Twine or tape shall not be used for securing wire and cable.

NOTE: When shielding on wire or cable is unprotected by an outer insulation, adequate support is necessary to prevent the shielding from coming in contact with exposed terminals or conductors.

3.4.8 In addition to the above, the following requirements of Specification MIL-STD-454 shall also apply:

a. Fungus-Inert materials, Requirement 4.

b. Soldering, per Requirement 5.

c. Insulating Materials, Electrical, per Requirement 11.

d. Fastener, Hardware, per Requirement 12.

e. Structural Welding, per Requirement 13.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

f. Printed Wiring, per Requirement 17.

h. Derating of Electronic Parts and Materials, per Requirement 18.

i. Terminals (Terminal Boards and Strips), per Requirement 19.

j. Castings, per Requirement 21.

k. Adhesives, per Requirement 23.

l. Fibrous Material, Organic, per Requirement 44.

m. Indicator Lights, per Requirement 50.

n. Brazing, per Requirement 59.

3.4.9 Sampling for inspection of solderless-terminal-lug connections.- Five specimens of each combination of wire and terminal shall be prepared each week for inspection. A specimen is a one (1) foot length of wire on which a terminal lug has been applied, using the same tools and procedures used in crimping the terminal lugs in production. (See 4.5.3.2)

3.5 Interchangeability.- Like units, assemblies, subassemblies, and replaceable parts shall conform to Requirement 7 of MIL-STD-454. (See 4.7)

3.6 Electromagnetic Compatibility.- Panel, Test, Electrical SB-3004( )/PPS-5 shall meet the emission and susceptibility requirements of MIL-STD-461A, Change Notice 4 (EL). The following requirements of that standard apply: (See 4.10)

CE02 Limits relaxed by 20 db in frequency range 13 KHz to 26 KHz.

CE04 Limits relaxed by 5 db in frequency range 145 KHz to 180 KHz.

RE02 Limits relaxed by 8 db in frequency range 19 KHz to 50 KHz.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

3.7 Service conditions.- Service condition requirements shall be as follows, for Case CY-6208( )/PPS-5, Panel, Test, Electrical SB-3004( )/PPS-5, and Pouch Accessory Kit. Table I indicates the specific conditions applicable to the individual units. (See 4.9)

TABLE I - SERVICE CONDITIONS

Requirement	Panel, Test Electrical SB-3004( )/PPS-5	Case CY-6208( )/PPS-5	Pouch Accessory Kit
Temperature			
Low	X	X	X
High	X	X	X
Humidity	X	X	X
Vibration	X		
Altitude	X	X	
Leakage (Immersion)		X	
Shock	X	X	
Drop		X	
Air Seal Test		X	
Fungus	X	X	X

3.7.1 Temperature/Altitude.- When tested as specified in 4.9.1, the Temperature/Altitude limits shall be: (These tests are to be performed simultaneously)

Temperature Extremes	0° C	to	71° C	operating
	-62° C	to	85° C	non-operating
Altitude Extremes	0 Ft.	to	10,000 Ft.	operating
	0 Ft.	to	50,000 Ft.	non-operating

3.7.2 Vibration.- The unit shall not suffer damage or fail to provide specified performance when subjected to continuous vibration along each of the three mutually perpendicular axes within the frequency range and amplitude as follows: (See 4.9.2)

Frequency range	Double amplitude
5 to 15	0.06 inch
15 to 25	0.04 inch
25 to 55	0.02 inch

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

3.8 Pre-conditioning Bounce.- Each Panel, Test Electrical SB-3004( ) /PPS-5 shall meet the requirements herein without subsequent processing after subjection to the bounce preconditioning procedure of 4.6.

3.9 Equipment performance.- The equipment shall meet the requirements specified in the following documents:

SM-C-600901	Attenuator, Fixed CN-1175/PPS-5
SM-B-601529	Power Supply, Test Specification
SM-A-686842	Front Panel Assembly, Test Specification
MIL-R-55348(EL)	Radar Set AN/PPS-5( ) (Converter Assembly, Radar) and (Converter Assembly, Remote)

NOTE: In addition to the above, all cable assemblies and leads, electrical, shall meet the requirements of 3.4.1.

3.10 Technical literature, tools, and running spare parts.- Technical literature, tools, and running spare parts shall be furnished if specified in the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order. (See 6.1h and i)

3.11 Workmanship.- The workmanship requirements of MIL-STD-454, Requirement 9, and the applicable portions of the following paragraphs shall apply:

Cleaning	3.4.2
Marking	3.4.4
Finish	3.4.3
Connections	3.4.5
Grounding to Chassis	3.4.6
Wiring	3.4.7
Other Requirements of MIL-STD-454	3.4.8

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

4.1.1 Contractor product assurance.- The contractor shall provide and maintain a means of determining product conformance in accordance with the requirements specified herein or elsewhere in the contract. The Government, at its option, may perform any evaluation deemed necessary to assure the adequacy of the means employed and the effectiveness of the contractor's product assurance methods and systems.

4.1.2 Government verification.- All quality assurance operations required of the contractor shall be subject to Government verification at scheduled or unscheduled intervals. Verification will consist of the following:

a. Surveillance of the contractor's operations to determine that practices, methods, and procedures of the contractor's product assurance system are being applied and are, in fact, accomplishing the objectives of total compliance of the product with the requirements of this specification.

b. Government product inspections to determine compliance of the product with the specification requirements.

4.1.3 Accommodation and assistance.- The Government quality assurance representative shall have the right of access to any area of the contractor's or his subcontractor's premises where any part of the work is being performed. The Government quality assurance representative shall be afforded unrestricted opportunity to verify conformance of the product with specification requirements. The contractor shall make his inspection equipment available for use by the Government quality assurance representative for verification purposes. The contractor's personnel shall be made available for operation of such inspection equipment as required.

4.2 Classification of inspection.- Inspection shall be classified as follows:

a. First Article inspection (does not include preparation for delivery). (See 4.3)

b. Inspection covered by subsidiary documents. (See 4.4)

c. Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5)

(2) Quality conformance inspection of preparation for delivery. (See 4.12)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

4.3 First Article inspection.- This inspection shall consist of the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified in Group A, Group B, and Group C. Environmental and stress inspections shall be performed in the order shown in Table II according to the number of samples specified in the contract or order.

TABLE II - FIRST ARTICLE/GROUP C INSPECTION, ORDER OF TESTING

Inspection (Note 1)	Test Para.	Number of samples					
		One	Two		Three		
			Unit 1	Unit 2	Unit 1	Unit 2	Unit 3
Non-damaging (Note 2)							
Preconditioning Bounce	4.6	1	1	1	1	1	1
Temperature (Low, High)	4.9	3	2		2		
Altitude (elevation)							
Leakage (immersion)	4.9	2 & 10		2 & 6		2 & 5	
Potentially Damaging							
Humidity (Moisture-Resistance) (Note 3)	4.9	4	4			3	
Shock (Ballistic) (Panel Assembly only)	4.9	5	3		4		
Shock (Ballistic) (Case only, with dummy load)	4.9	6		3		4	
Shock, Drop (Case only, with dummy load)	4.9	7		4			2
Fungus (Note 3)	4.9	8		5	3		
Vibration	4.9.2	9	5				3

NOTE 1: Other First Article inspection may precede, follow, or be interspersed between the non-damaging tests.

NOTE 2: Except for Preconditioning Bounce, the order of non-damaging tests and the choice of which units are subjected to the non-damaging tests may be varied if convenient.

NOTE 3: The equipment shall be thoroughly washed, cleaned, dried, and refurbished, if necessary, before proceeding with subsequent tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

4.4 Inspection covered by subsidiary documents.- The following shall be inspected under the applicable subsidiary documents as part of the inspection of equipment before preparation for delivery:

Item	Where required
Parts, materials and processess	3.4
Cable Assemblies and Leads, Electrical	3.4.1
Finish, protective	3.4.3
Marking	3.4.4
Converter Assembly, Radar	3.9
Converter Assembly, Remote	3.9

4.5 Quality conformance inspection of equipment before preparation for delivery.- Every equipment shall be subjected to the preconditioning bounce procedure of 3.8 prior to conformance inspection. The contractor shall perform the inspection specified in 4.4 and 4.5.1 through 4.5.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. Failure to meet any requirement as a result of this preconditioning shall be classified as a defect and recorded as such. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records as an element of Government verification. (See 4.1.2 and 6.4)

4.5.1 Group A inspection.- Equipment shall be assembled into discrete lots for quality conformance inspection, utilizing the criteria of MIL-STD-105 for determination of lot composition. Unless otherwise specified, the lot size shall be determined from Table IIIA as related to production rates necessary to meet delivery schedules of the contract. The lot size shall be adjusted throughout the life of the contract as necessary to provide for changes in contract delivery schedules and production rates. Each unit of each lot of equipment shall be inspected for conformance to all the examinations and tests required by Table IIIB. The quality conformance of each lot shall then be subjected to an audit, utilizing the procedures of MIL-STD-105, under the general inspection levels and Acceptable Quality Level (AQL) indicated in Table IIIB. Group A inspection shall be performed in any order satisfactory to the Government, except that the air-seal test shall be last. (See SM-A-686846)

TABLE IIIA - LOT INFORMATION

Production Rate	Size of Lot
500 or more per month	One week's production
51 to 499 per month	Two week's production
1 to 50 per month	One month's production

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

TABLE IIIB - GROUP A INSPECTION

INSPECTION OR TEST	REQ. PARA.	INSPEC. PARA.	AQL MAJOR	AQL MINOR
Visual and Mechanical	3.11	4.11	1.5%	6.5%
Panel, Test, Electrical SB-3004( )/PPS-5	3.11	4.11	1.0%	4.0%
Case, Test Facilities Kit CY-6208( )/PPS-5	3.11	4.11	1.0%	4.0%
Attenuator, Fixed, CN-1175( )/PPS-5	3.11	4.11	1.0%	4.0%
Ancillary Items	3.11	4.11	1.0%	4.0%
Operational and Electrical				
Ground circuits	3.9	4.8	1.0% for the Group *	
Continuity	3.9	4.8		
Test Points	3.9	4.8		
Hipot Tests	3.9	4.8		
-6 VDC Switch	3.9	4.8		
Ground Switch	3.9	4.8		
Voltage Ckt Resistance	3.9	4.8		
Special Resistance Checks	3.9	4.8		
Test Point Resistance Checks	3.9	4.8		
Operational Tests	3.9	4.8		
-6 VDC Input	3.9	4.8	1.0% for the Group *	
AC Input	3.9	4.8		
Performance	3.9	4.8		
Power Supply	3.9	4.8	1.0% *	
Attenuator CN-1175( )/PPS-5	3.9	4.8	1.0% *	

*All defects are considered to be major.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

4.5.2 Group B inspection.- This inspection, including sampling, shall conform to Table IV and to procedures for special inspection levels of MIL-STD-105. Group B inspection shall normally be performed on production lots of product that have passed Group A inspection. (See 4.5.1 for lot formation).

4.5.2.1 Group B sampling plans.- The Group B sampling plans, for the AQL's listed in Table IV, shall be inspection level S-4.

TABLE IV - GROUP B INSPECTION

Inspection or Test	Req. Para.	Insp. Para.	AQL
Interchangeability	3.5	4.7	6.5%

4.5.3 Group C inspection.- This inspection shall consist of the tests specified in Table II and shall be performed on sample units that have been subjected to and met Group A and Group B inspection. Sample units shall be selected in accordance with paragraph 4.5.3.1.

4.5.3.1 Sampling for inspection.- One (1) sample unit shall be selected at random for all inspections in Table II from every fifty (50) or fraction thereof produced. The first samples selected shall be at the start of the contract from the first quality conformance inspection production lot. (See 4.5.3)

4.5.3.2 Crimping of solderless terminal lugs.- Crimping of solderless terminal lugs shall be so accomplished that the connections will meet the resistance (voltage drop) and tensile strength requirements and tests of MIL-T-7928. (See 3.4.9)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

4.5.3.3 Noncompliance.- All quality conformance inspection shall be halted, including Group A and Group B inspections, upon the occurrence of any Group C failure. The contractor shall immediately report in writing each Group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on the processes and materials, as applicable, and on all units of production which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded throught the Government Procurement Quality Assurance Representative to the responsible technical activity designated in the contract. After corrective action has been taken, additional sample units shall be subjected to Group C inspection (all inspections, or the inspections which the sample failed, at the option of the technical activity) and Groups A and B inspections may be reinstituted. However, final acceptance and shipment will be withheld until Group C reinspection results have shown that the corrective action was effective and approved by the technical activity. (See Delivery and Conditional Acceptance of Contract Items Subject to Group C Inspection provisions in the contract).

4.5.4 Reinspection of conforming Group B and Group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed both Group B and Group C inspection may be accepted on contract or order provided all damage is repaired and the sample units are resubjected to and pass Group A inspection.

4.6 Preconditioning Bounce.- Test Facilities Kit MK-980( )/PPS-5 with cover removed shall be placed in its normal operating position on the table of the Package Tester, Type 1000-3C, as made by the L.A.B Corporation, Skaneatales, New York, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32 inch thick strip of material under one corner or edge of the unit to a distance of 3 inches as the unit bounces. The unit shall be subjected to this preconditioning for one minute. After bounce preconditioning, the unit shall not be repaired, alined, cleaned, or otherwise changed prior to subjection to inspection.

4.7 Inspection for dimensional interchangeability.- In addition to Requirement 7 of MIL-STD-454 the demensions listed below shall be gaged or measured to determine conformance to the physical interchangeability requirements of 3.5. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

a. External and internal dimensions of cases, covers, and insertable assemblies, when such dimensions affect mating of parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

b. Dimensions of cavities, when such dimensions affect insertion of items.

c. Location of hinges and fasteners on separable parts or assemblies which must mate, such as cases, covers, and mountings.

d. Location of connectors, locking pins, fasteners, slides, and mountings which receive mating parts of plug-in assemblies and major units; and location of the mating parts on the plug-in assembly or major unit.

e. Size and form of special threads.

4.8 Equipment performance tests.- The equipment shall be tested in accordance with the following procedures, to determine compliance with 3.9:

SM-A-686705 Test Procedure for Test Facilities Kit Assembly SM-D-686400 and SM-D-686401

4.9 Service condition tests.- Service condition tests shall be conducted as specified in SM-A-686846.

4.9.1 Temperature/Altitude tests.- The temperature/altitude test shall be performed as specified in Table V.

4.9.2 Vibration.- A resonance survey shall be performed in each of the three axis over the frequency and amplitude range specified in para. 3.7.2 at a rate of one complete excursion in approximately 15 minutes. The test shall continue for a period of three hours in each axes for a total of nine hours.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

TABLE V - TEMPERATURE/ALTITUDE PROCEDURES (CHAMBER CONDITIONS)

STEPS	1	2	3	4	5	6	7	8	9
a	-62°C, Atm. pressure for 2 hrs (Non-operational)	0°C, 10,000 ft; to temp stabilization. (Non-operating)	0°C, Atm. pressure (Non-operating)	0°C, Atm. pressure (Non-operating)	85°C, Atm. pressure Till stabilized (Non-operating)	55°C, Atm. pressure Till stabilized (Non-operating)	71°C, Atm. pressure Till stabilized (non-operating)	85°C, 50,000 ft. 4 hours (Non-operating)	Room Ambient
b	Examine visually for deterioration	Operate at 103 VAC 60 Hz	Operate at 127 VAC, 60 Hz	Open door to permit formation of ice, close door	Maintain for 16 Hrs.	Operate at 127 VAC, 60 Hz for 4 Hrs	Operate at 127 VAC, 60 Hz 20 min. ON 15 min. OFF	Return chamber to Atm. pressure	Check operation of case relief valve. Record.
c	Record findings	Switch equip. ON and OFF several times.	Reduce pressure to 10,000 Ft.	Turn equip. ON and OFF three times		Record thermo couple readings every 30 min.	Record data per equip. indicators		After temp. stabilization conduct complete operating tests.
d		Record data per equip. indicators	Record data per equip. indicators	Record data per equip. indicators		Record data per equip. indicators	Repeat 20 min. ON 15 min. OFF for a total of 4 times		Record data.
e							Each 10 min. record thermo-couple readings		

PROCEDURES

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

4.10 Electromagnetic Compatibility Tests.- The equipment shall be tested for compliance with the requirements of 3.6 using the approved test methods of MIL-STD-462, Notice 3.

4.11 Visual and Mechanical Inspection.- The equipment shall be examined for the defects listed in MIL-STD-252.

4.12 Quality conformance inspection of preparation for delivery.- Preparation for delivery shall be inspected in accordance with specification MIL-P-116 to determine conformance to the requirements of Section 5.

5. PREPARATION FOR DELIVERY.

5.1 Preservation and packaging.- Preservation and packaging shall be Level A or C as specified (See 6.1.c).

5.1.1 Level A.-

5.1.1.1 Cleaning.- MK-980( )/PPS-5 shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying.- MK-980( )/PPS-5 shall be dried in accordance with the applicable procedure of MIL-P-116.

5.1.1.3 Preservation application.- None required.

5.1.1.4 Unit packaging.- Unit packaging shall be in accordance with the methods prescribed in MIL-P-116, as specified herein.

5.1.1.4.1 Technical literature.- Each technical literature shall be packaged method 1C-1.

5.1.1.4.2 MK-980( )/PPS-5.- Each test facilities kit shall be packaged Method III as follows: Place the accessories in the pouch. Secure the fastenings of the pouch. Place the accessories and the technical literature, packaged as in 5.1.1.4.1, in the top half of the case. Secure the cover plate. Place the top half of the case on the bottom half and secure all fastenings. Cushion the case on all surfaces with cells or pads or both fabricated of fiberboard conforming to PPP-F-320, W6c, weather resistant designed and fabricated to protect all projections and absorb the shock of impact in handling and transit. Place the cushioned case within a close-fitting fiberboard box conforming to PPP-B-636, W5c, weather resistant. Box closure shall be as specified in the appendix of the specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

5.1.2 Level C.- MK-980( )/PPS-5 shall be preserved and packaged in a manner that will afford adequate protection against corrosion, physical and environmental damage during shipment, handling and limited intransit storage.

5.2 Packing.- Packing shall be level A, B, or C as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents.

5.2.1 Level A.-

5.2.1.1 Palletized load.- A quantity of MK-980( )/PPS-5, packaged as specified in 5.1, shall be placed on a pallet, load type I, conforming to MIL-STD-147 except that the pallet shall be softwood conforming to NN-P-71, type IV, size 2. A fiberboard cap shall be employed over the load having two sides extending down the stacked load at least 12 inches to accommodate marking requirements. The cap shall be fabricated of fiberboard conforming to PPP-F-320, class weather-resistant, W5s or V3c. The load shall be "bonded" to the pallet by strapping.

5.2.1.2 Less than palletized load.- When quantities per destination are less than a pallet load, the item packaged as specified in 5.1, shall be waterproofed, with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. A quantity of the waterproofed containers shall be packed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, type I, class B.

5.2.2 Level B.-

5.2.2.1 Palletized load.- A quantity of MK-980( )/PPS-5, packaged as specified in 5.1, shall be palletized as specified in 5.2.1.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

5.2.2.2 Less than palletized load.- When quantities per destination are less than a pallet load, a quantity of MK-980( )/PPS-5, packaged as specified in 5.1, shall be packed within a close-fitting fiberboard box conforming to PPP-B-640, class 2, style E, or PPP-B-636, type CF, class weather-resistant, variety DW. The gross weight of boxes conforming to PPP-B-640 shall not exceed 250 pounds. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, containers will be pallet-mounted on pallets conforming to NN-P-71, type IV. Closure shall be in accordance with the appendix of the applicable box specification. Reinforcing shall be by pressure-sensitive filament tape banding or nonmetallic strapping conforming to PPP-T-97, type IV and PPP-S-760, type II, respectively; selection of the material and application shall be in accordance with the appendix of the applicable box specification.

5.2.3 Level C.-

5.2.3.1 Palletized load.- A quantity of MK-980( )/PPS-5, packaged as specified in 5.1, shall be palletized as specified in 5.2.1.1 except that the fiberboard caps shall be class domestic.

5.2.3.2 Less than palletized load.- When quantities per destination are less than a pallet load, a quantity of MK-980( )/PPS-5, packaged as specified in 5.1, shall be packed as specified in 5.2.2.2 except that the fiberboard boxes shall conform to PPP-B-640 and PPP-B-636, class 1 and class domestic, respectively, and reinforcing shall not be required for boxes conforming to PPP-B-636.

5.3 Marking.- In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Ordering Data.- Procurement documents should specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Type required.

c. Levels of preservation and packaging and packing (See Section 5).

d. When rough handling and functional tests are required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

e. The specific paragraphs of Section 5 which are applicable to the particular procurement.

f. First Article Inspection:

(1) Two sample units of each item cited in Section 1 are generally required so that lengthy environmental tests can be completed on one sample unit while complete performance measurements can be made on the second sample unit. (See 3.2)

(2) Preproduction pack(s) as follows:

Makeup of pack(s).

Number of each kind of pack to be submitted.

Inspection to be performed thereon.

g. Marking and shipping of samples.

h. Place of final inspection.

i. Technical literature required. (See 3.10)

j. Quantity of tools and running spare parts required. (See 3.10)

6.2 Group C Inspection.- Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action. (See 4.5.3.3)

6.3 Nomenclature.- The parentheses in the nomenclature will be detailed or replaced by a letter identifying the particular design; for example: MK-98(N/PPS-5. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

6.4 Verification Inspection.- Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL-PP-ED
Fort Monmouth, New Jersey 07703

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION MIL-T-55655A(EL) TEST FACILITIES KIT MK-980( )/PPS-5

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

[ ] DIRECT GOVERNMENT CONTRACT [ ] SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

[ ] YES [ ] NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

ESC-FM 1068-68

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:49Z
Check the source to verify that this is the current version before use.