MILITARY SPECIFICATION

WARHEAD SECTION, TRAINING: M138E6

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of Warhead Section, Training: M138E6.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1460	- Soldering of Electrical Connections and Printed Wiring Assemblies, Procedure For.

DRAWINGS

ORDNANCE CORPS

8862925	- Warhead Section, Training: M138E6.
8882046	- Shipping and Storage Container M481E1 for Adaption Kits and Warhead Sections Packing and Marking.
EL-8869273	- Equipment Lists.

FSC: 1115

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The M138E6 training warhead section shall comply with all requirements specified on the drawing (dwg) 8862925, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. The contractor shall assign serial numbers as required by drawings. The contractor may select any number which complies with the drawing requirement. These numbers shall not be duplicated.

3.5 Circuit resistance and continuity. The continuity and resistance for the rotary switch, latching relay and the continuity loops shall be as specified in 3.5.1, 3.5.2, and 3.5.3.

3.5.1 Rotary switch circuit resistance. The resistance between terminals listed in Table I shall not exceed the specified values when tested as specified in 4.4.1.

Table I

Rotary Switch Position Number	P919 Connector Pins	Maximum Resistance (Ohms)
1	From 70 to 54	3K ±0.2%
2	From 70 to 43	3K ±0.2%
3	From 70 to 43	5K ±0.2%
4	From 70 to 43	7K ±0.2%
5	From 70 to 43	9K ±0.2%
6	From 70 to 43	11K ±0.2%

3.5.2 Latching relay circuit resistance. The resistance of the latch and unlatch relay positions shall be as specified below.

3.5.2.1 Latch position. The resistance between terminals 43 to 62 shall be 5K ±0.2% ohms when tested as specified in 4.4.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.5.2.2 Unlatch position. The resistance between terminals 43 to 62 shall be 7K ±0.2% ohms when tested as specified in 4.4.2.1.

3.5.3 Continuity loop resistance. The resistance between terminals listed in Table II shall not exceed the specified values when tested as specified in 4.4.3.

Table II

Connector Pins	Maximum Resistance (Ohms)
From P919-71 to P919-10	0.2
From P919-72 to J2-U	0.2
From J2-S to P919-71	0.2
From W106LP2-E to W106LP2-L	0.2
From W106LP2-E to W106LP2-G	0.2
From W106P2-L to W106LP2-G	0.2

3.6 Insulation resistance. The insulation resistance between the pins designated in Table III shall be 20 megohms minimum when tested at 500 ±50 VDC as specified in 4.4.4, current shall be limited to 5 milliamperes, unused terminals shall be connected together and tested as one terminal. The panel of each assembly shall be at test fixture ground.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Table III

P919 Connector Pins

From	To
56	53, 27, 40, 1, 8, 14, 21, 54, 43, 62, 70, 71, 10, 16, 23, 52, 72, U, S.
52	53, 27, 40, 1, 8, 14, 21, 31, 54, 43, 64, 62, 70, 71, 10, 16, 56, 72, U, S.
16	53, 27, 40, 1, 8, 14, 21, 31, 54, 43, 62, 63, 64, 70, 71, 10, 23, 52, 56, 72, U, S.
10	53, 27, 40, 1, 8, 14, 21, 31, 54, 43, 62, 63, 64, 70, 16, 23, 52, 56, 72, U.
64	53, 27, 40, 1, 8, 14, 21, 54, 43, 62, 70, 71, 10, 16, 23, 52, 72, U, S.
62	53, 27, 40, 1, 8, 14, 21, 31, 54, 63, 64, 70, 71, 10, 16, 23, 52, 56, 72, U, S.
54	53, 27, 40, 1, 8, 14, 21, 31, 43, 62, 63, 64, 71, 10, 16, 23, 52, 56, 72, U, S.
21	31, 54, 43, 62, 63, 64, 70, 71, 10, 16, 23, 52, 56, 72, U, S.

W106LP2 Connector Pins

E, G, L against unused pins and case.

Unused pins against case.
Unused pins - A, B, C, D, F. H, J, K, M, U, P, R, S.

3.7 Capacitor characteristics. The voltages across the terminals of the charged capacitors listed in Table IV shall be 23 vdc min. 3.5 seconds min. after the voltage has been removed, when tested as specified in 4.4.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Table IV

Terminals	Volts (min.)
From (-) 53 to (+) 27	23
From (-) 53 to (+) 40	23
From (-) 53 to (+) 1	23
From (-) 53 to (+) 8	23
From (-) 53 to (+) 14	23
From (-) 53 to (+) 21	23

3.8 Diode characteristics. The voltage drop across the diodes in the forward direction and the current in the reverse direction shall be as specified below when tested as specified in 4.4.6.

Item No.	Diode	+ Voltage to Terminal	- Voltage to Terminal	Maximum Voltage or Current
1	CR2	16	52	1 Volt*
2	CR2	52	16	1 Milliampere**

* Voltage drop across diode.
** Leakage current through diode.

3.9 Environmental testing. The training warhead section shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The training warhead section shall also comply with 3.5, 3.6, 3.7 and 3.8 before and after each environmental test. Testing shall be as specified in 4.4.7. Tests shall be conducted in the order specified.

3.9.1 High temperature. The training warhead section shall withstand exposure to a temperature of 160 ±5 degrees Fahrenheit (°F) without damage and while at this temperature shall meet the requirements of 3.6, 3.7, and 3.8 when tested as specified in 4.4.7.1. After returning to ambient temperature (80° ±20°F) the warhead section shall meet the requirement of 3.5.

3.9.2 Low temperature. The training warhead section shall withstand exposure to a temperature of -65 ±5°F without damage and while at this temperature shall meet the requirements of 3.6, 3.7, and 3.8 when tested as specified in 4.4.7.2. After returning to ambient temperature (80° ±20°F) the warhead section shall meet the requirement of 3.5.

3.9.3 Shock. The training warhead section, packed in the shipping and storage container in accordance with dwg 8882046, shall withstand shocks of edgewise drop, end impact and rollover impact without evidence of damage or impairment of operation when tested as specified in 4.4.7.3. Upon completion of the shock tests, the training warhead section shall meet the requirements of 3.5, 3.6, 3.7, and 3.8.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.9.4 Transportation vibration. The training warhead section, packed in accordance with dwg 8882046 in the shipping and storage container, shall withstand vibration in an axis perpendicular to the container base surface at the frequencies and amplitudes specified in Table V without evidence of damage or affecting function when tested as specified in 4.4.7.4. Upon completion of the vibration test, the training warhead section shall meet the requirements of 3.5, 3.6, 3.7, and 3.8.

Table V

Frequency Range Hertz	Constant Acceleration or Double Amplitude	Cycle Time
6-20-6	1 g ± 0.1 Gravity (g)	15 min.
21-60-21	0.060 ± 0.006 inch	10 min.
61-300-61	10 g ± 1 g	25 min.
301-500-61	10 g ± 1 g	25 min.

3.10 Weight. The training warhead section with probe assembly attached shall weigh 1581 ±50 pounds when weighed as specified in 4.4.8.

3.11 Center of gravity. The training warhead section with probe assembly attached shall have a center of gravity at station 100.4, measured 38.6 ±0.5 inch forward of station 139, when tested as specified in 4.4.9.

3.12 Soldering. All soldering shall comply with the requirements specified in MIL-STD-1460.

3.13 Workmanship.

3.13.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.13.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.13.3 Burrs. Parts shall be free from burrs.

3.13.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.13.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

3.13.6 Electrical. Cable assemblies and wires shall be dressed in such a manner as to prevent pinching or chafing of the wire insulation. Ends of wires shall be free from burrs, sharp edges, or points. All parts shall be free from flux, chips, dirt, grease, rust or foreign material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contractor requires first article inspection, the contractor shall submit 1 complete assembly (see dwg 8862925) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table VI. Tests shall be conducted in order specified in Table VI.

Table VI

First article inspection and tests

Inspection or Test	Dest	Non-Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Circuit resistance and continuity (see 3.5)		X
3. Insulation resistance (see 3.6)		X
4. Capacitor characteristics (see 3.7)		X
5. Diode characteristics (see 3.8)		X
6. High temperature (see 3.9.1)		X
7. Low temperature (see 3.9.2)		X
8. Shock (see 3.9.3)	X	
9. Transportation vibration (see 3.9.4)	X	
10. Weight (see 3.10)		X
11. Center of Gravity (see 3.11)		X

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table VII and Table VIII), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Table VII
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Table VIII
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-9	all	14-16	12	28-33	16	77-121	20
10	9	17-18	13	34-41	17	122-273	21
11	10	19-22	14	42-54	18	over 273	22
12-13	11	23-27	15	55-76	19		

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Probe assembly (dwg 8862543).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Probe does not assemble correctly to retaining block	Gage
	102. Objective evidence relating to material missing or improper (see 3.1)	Visual
	103. Evidence of poor workmanship (see 3.13)	Visual
Minor:		
	201. Vanes bent or not securely pinned	Visual/Manual
	202. Incorrect or illegible marking	Visual
	203. Bare spot in protective coating except for slight scratches	Visual

4.3.2.1.2 Warhead section, training: M138E6 (see dwg 8862925) prior to assembly of probe assembly.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Major:

101.	Incorrect location of connectors at Station 139	Gage
102.	Incorrect location of alignment pins	Gage
103.	Retaining block does not accept probe	Gage
104.	Warhead Section does not accept sling	Visual/Manual
105.	Objective evidence relating to material missing or improper (see 3.1)	Visual
106.	Evidence of poor workmanship (see 3.1)	Visual

Minor:

201.	Incorrect location of PAL connectors	Visual
202.	Improper fit of PAL dust cap assembly	Visual/Manual
203.	Serialization improper or missing (see 3.3)	Visual

4.3.2.1.3 Warhead section, training: M138E6 (see dwg 8862925).

Categories	Characteristics	Method of Inspection

Critical: None defined.

Major:

101.	Bolt assemblies inoperable	Manual
102.	Vent doors not flush or inoperable	Manual
103.	Mismatch at station 10	Visual/Manual
104.	Mismatch at station 8.125	Visual/Manual
105.	Loose component	Visual/Manual
106.	Missing component	Visual
107.	Damaged component	Visual

Minor:

201.	Incorrect, illegible or missing markings	Visual
202.	Bare spot in protective coating except for slight scratches	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.2.1.4 Packing for M138E6 warhead section (see dwg 8882046) prior to inserting warhead section.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Loose internal component	Visual/Manual
	102. Damaged internal component	Visual
Minor:		
	201. Foreign matter in container	Visual
	202. Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.5 Packing for M138E6 warhead section (see dwg 8882046) prior to closing container.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Incorrect torque of bolts	Gage
	102. Insecure fastening of static probe package	Manual/Visual
	103. Incorrect tension of straps	Visual/Manual
Minor:		
	201. Missing dust caps	Visual
	202. Loose dust caps	Visual/Manual
	203. Evidence of poor workmanship (see 3.13)	Visual
	204. Marking not in accordance with applicable drawing (see 5.3)	Visual

4.3.3 Testing. All tests shall be performed. Tests need not be performed in the order specified.

Test	Test Classification
a. Circuit test resistance and continuity	Major
b. Insulation resistance	Major
c. Capacitor characteristics	Major
d. Diode characteristics	Major
e. Weight	Major
f. Center of gravity	Major

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Circuit resistance and continuity, insulation and resistance, capacitor characteristics, diode characteristics, weight and center of gravity. Each warhead section shall be tested in accordance with 4.4.1 through 4.4.6 inclusively, 4.4.8 and 4.4.9. If any item fails to comply with 3.5 through 3.8 inclusively, 3.10 and 3.11, the lot shall be rejected.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (See EL-8869273). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Rotary switch circuit resistance. The circuit resistance between terminals specified in 3.5.1, Table I, shall be measured with a Wheatstone Bridge or Digital Ohmmeter. The rotary switch shall be energized with +28 volts direct current (vdc) applied to terminal 31 and return to terminal 56 and stepped from positions 1 to 6. (Positions 7 to 12 are not used.)

4.4.2 Latching relay, latch position circuit resistance. The circuit resistance between terminals 43 to 62 shall be measured with a Wheatstone Bridge or Digital Ohmmeter. The relay circuit shall be energized with +28 vdc to terminal 64 and return to 56.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.2.1 Latching relay, unlatch position circuit resistance. The circuit resistance between terminals 43 to 62 shall be be measured with a Wheatstone Bridge or Digital Ohmmeter. The relay circuit shall be energized with +28 vdc to terminal 64 and return to 56.

4.4.3 Continuity loop resistance. The resistance between the terminals specified in 3.5.3, Table II, shall be measured with a Keithly Milliohmmeter or an instrument of equivalent accuracy.

4.4.4 Insulation resistance. The insulation resistance shall be measured with an insulation resistance tester at 500 +50 vdc. All unused terminals of the connector shall be connected together and tested as one terminal. The malfunction (K2) relay shall be in the remove position and the latching relay (K1) in the latch position and the step switch in position 1.

4.4.5 Capacitor characteristics. The terminal voltages, when read with a 20,000 ohm/volt voltmeter, shall be as specified in 3.7 when a potential of 45 +5 vdc is applied across the capacitor terminals listed in Table IV. The readings shall be taken 3.5 seconds after the power supply has been disconnected.

4.4.6 Diode characteristics. For measurement of the voltage drop in the forward direction and the current in the reverse direction, contacts of K2 relay shall be placed in the insert portion by energizing the relay solenoid circuit with 28 vdc across terminals 52 and 23 for a maximum of 2 seconds. The 28 vdc potential shall be removed before proceeding with the test. Apply test voltages and currents (see Figure 1 for test circuit schematic) as specified below. The period of application of the voltages and currents to the diode shall not exceed 15 seconds.

+ Voltage to terminal	- Voltage to terminal	Applied Forward Current	Applied Reverse Voltage	Voltage Drop Across Diode	Reverse Current thru Diode
16	52	500-550 ma		1 vdc max.	
52	16		400-440 vdc		1 ma max.

4.4.7 Environmental testing (see 3.9).

4.4.7.1 High temperature. The training warhead section shall be placed in a test chamber. The chamber's temperature shall be raised and stabilized at 160 +5°F. (See 6.4.) After the training warhead section has been subjected to this stabilized temperature for a minimum of 4 hours and while

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

still at this temperature, it shall be tested for compliance with the requirements of 3.6, 3.7 and 3.8. After the temperature of the warhead section has been returned to ambient, the warhead section shall be tested for compliance with the requirements of 3.5.

4.4.7.2 Low temperature. The training warhead section shall be placed in a test chamber. The chamber's temperature shall be lowered and stabilized at -65 +5°F (see 6.4). After the training warhead section has been subjected to this stabilized temperature for a minimum of 4 hours and while still at this temperature, it shall be tested for compliance with the requirements of 3.6, 3.7, and 3.8. After the temperature of the warhead section has been returned to ambient, the warhead section shall be tested for compliance with the requirements of 3.5.

4.4.7.3 Shock. The shipping and storage container containing the training warhead section shall be subjected to the shocks specified in 4.4.7.3.1 through 4.4.7.3.3. Upon completion of these shocks, the warhead section shall be inspected for evidence of damage and tested for compliance with the requirements of 3.5, 3.6, 3.7, and 3.8.

4.4.7.3.1 Edgewise drop. Support the loaded shipping and storage container on one end of its base on a wood sill 5 ± 1/2 inches high and placed normal to the skids. The opposite end of the container shall be raised and allowed to drop freely from a height of 12, 24, and 36 ± 1/2 inches respectively. The three drops shall be made on concrete or a similar hard surface. Apply the test to both ends of the container.

4.4.7.3.2 End impact. The loaded shipping and storage container shall be placed in a fixture which will allow free axial movement. The end of the container shall strike against a solid flat vertical abutment having a wooden face of 2 inch minimum thickness. The direction of motion shall be 90° ±5° with the impact surface and the velocity at impact shall be 10.5 ±1.5 feet per second. Apply the test to both ends of the container.

4.4.7.3.3 Rollover impact. The loaded shipping and storage container on its base on a hard level floor shall be tipped slowly sideways until it falls freely on its side. The procedure shall be repeated from the side to the top, from the top to the other side, and from the other side to its base, thus completing one revolution.

4.4.7.4 Transportation vibration. Place the shipping and storage container containing the training warhead section on a suitable vibration machine and vibrate for the durations, frequencies and amplitudes specified in Table V. At the completion of this test, the warhead section shall be inspected for evidence of damage and tested for the requirements of 3.5, 3.6, 3.7 and 3.8.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.8 Weight. The warhead section shall be weighed on an approved weighing device.

4.4.9 Center of gravity. The warhead section shall be attached to an approved device to determine its center of gravity.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The warhead section shall be packaged in accordance with dwg 8882046 using the specified moisture barrier.

5.1.2 Level C. The warhead section shall be packaged in accordance with dwg 8882046 except that the moisture barrier may be omitted.

5.2 Packing.

5.2.1 Level A and C. The warhead section shall be packed in accordance with dwg 8882046.

5.3 Marking. Marking shall be as specified in accordance with dwg 8882046.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.

b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 or specification when specified on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-T.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description PA-PD-1669 Rev. 1 dated 17 February 1966.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. 1115-A055

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.