MIL-B-29186(YD)
AMENDMENT-1
2 January 1979

MILITARY SPECIFICATION

BARRIER SYSTEM: FLOATING, OIL AND DEBRIS CONTAINMENT
(FOR PERMANENT INSTALLATION)

This amendment forms a part of Military Specification MIL-B-29186(YD), dated 27 October 1978, and is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 10

3.5.11, Delete subparagraph (a) in its entirety.

PAGE 14

After page 14, insert page 14a.

Page 17

4.6.2.1.8, line 4: Delete "15 minutes" and substitute "5 minutes."

PAGE 20

4.6.2.1.18, line 2: Delete "15 lb" and substitute "25 lb."

Preparing activity:

Navy - YD

Project No. 1945-N041

FSC 1945

Source: https://assist.dla.mil -- Downloaded: 202640-20T22:07Z
Check the source to verify that this is the current version before use.

4.6 Tests.

4.6.1 First article test plan. A written test plan for the performance of the first article tests of 4.6.2 shall be prepared and submitted to the Government contracting officer by the contractor at least 8 weeks prior to the commencement of tests as specified in the contract (see 6.2.1). The test plan shall include, but not be limited to, the following:

(a) Calendar schedule for conduct of:

(1) Laboratory tests as specified in 4.6.2.1.
(2) Practice session for field test as specified in 4.6.2.2.
(3) Field tests as specified in 4.6.2.2.

(b) Location and brief description of facilities used for the laboratory tests of 4.6.2.1.
(c) Procedure outline for conduct of each of the tests of 4.6.2.1.
(d) Procedure outline for conduct of each of the field tests of 4.6.2.2.
(e) Description of instrumentation to measure: water current and wind velocity relative to the boom, boom skirt and freeboard angle and catenary gap distance as required for the tests of 4.6.2.2.
(f) List of boats and personnel involved and a schematic illustration of their deployment and utilization for the tests of 4.6.2.2.

4.6.2 First article.

4.6.2.1 Laboratory first article tests. The boom first article and its components shall be subjected to the laboratory tests specified in 4.6.2.1.1 through 4.6.2.1.18. Failure to meet the minimum acceptable test results listed in the appropriate paragraphs in Section 3, of this specification shall be cause for the Government to refuse acceptance of all booms until corrective action has been taken and the minimum acceptable tests results are met. Tests shall be conducted by the contractor and in the presence of Government representatives.

4.6.2.1.1 Tensile strength (boom material). When coated or impregnated woven fabric is used as the boom material, the ultimate tensile strength shall be determined for conformance to 3.5.3.1 in accordance with grab Method 5100.1 of FED TEST METHOD STD No. 191. Samples of the material in both the warp and fill direction shall be tested. Results from five individual tests of these samples shall be averaged and reported

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:07Z
Check the source to verify that this is the current version before use.