NOT MEASUREMENT SENSITIVE

MIL-P-29196B(YD)
20 June 1991
SUPERSEDING
MIL-P-29196A(YD)
18 February 1985

MILITARY. SPECIFICATION

PAVING MACHINES, BITUMINOUS MATERIAL, CRAWLER- OR RUBBER TIRE-MOUNTED, SELF-PROPELLED

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers two types of commercial, self-propelled, bituminous material paving machines, (hereinafter referred to as the paver), capable of laying a strip from 4 1/2 feet to 12 feet wide.

1.2 Classification. The paver shall be of the following types and classes as specified (see 6.2):

Type I - Rubber tire mounted.
Type II - Crawler track mounted.

Class I - Gasoline engine driven.
Class II - Diesel engine driven.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3895

DISTRIBUTION STATEMENT A Approved for public release, distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

* 2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

W-B-131 - Battery, Storage, Vehicular, Ignition, Lighting, and Starting.

MILITARY

MIL-T-3351 - Tractor, Full-Tracked, Low-Speed; Tractor Wheeled, Agricultural; and Tractor Wheeled, Industrial: and Their Attachments, Packaging of.

STANDARDS

FEDERAL

FED-STD-595 - Colors.

MILITARY

MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.

(Copies of military specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

* 2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DEPARTMENT OF LABOR (DoL)
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

Occupational Safety and Health Standards.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

2.2 NonGovernment publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents which are current on the date of the solicitation (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

B117 - Salt Spray (Fog) Testing, Standard Method of.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

(Non-Govemment standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The paver shall be self-propelled, engine driven, and hydraulically operated. Traction shall be provided by rubber tires for type I or crawler tracks for type II as required. The paver shall essentially consist of a receiver hopper, material spreading augers, and a vibrating heated screed. The paver shall be capable of laying bituminous concrete strips from 4 1/2 feet up to 12 feet wide.

3.2 First article. When specified (see 6.2), the contractor shall furnish one complete paver, of the type and class required, for first article inspection and approval (see 4.2.1 and 6.4).

3.3 Standard commercial product. The paver shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer’s standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer’s standard commercial product, shall be included in the paver being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer’s catalogs, or brochures, and represents the latest production model.

3.4 Construction. The paver shall be designed and constructed to facilitate field maintenance. All adjustments and replaceable accessories shall be readily accessible. Conditions which can be hazardous to personnel or deleterious to the equipment shall not be permitted.

3.5 Interchangeability AU units of the same classification furnished with similar options under a specific contract shall be identical to the extent

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

*3.6 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. the term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. Unless otherwise specified, none of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification.

3.7 Safety. All parts subject to high operational temperatures that are of such a nature or are so located as to be or become a hazard to the safety of the operating personnel shall be insulated, enclosed, or fully guarded to the extent necessary to eliminate the hazard. The paver shall comply with applicable OSHA regulations in effect at time of manufacture.

* 3.8 Performance. The paver shall receive from dump trucks paving material mixed with bituminous concrete, and shall lay and finish the material to form a strip of pavement. The bituminious strip shall be laterally and longitudinally smooth within a tolerance of ±1/8 inch measured with a 12-foot straight edge. The paver shall have, as a minimum, a paving width range of 4 1/2 feet up to 9 feet and shall be expendable to a laying width of 12 feet by hydraulically telescoping the screed wings. While the receiving hopper is being filled with paving material, the paver shall have the capability to simultaneously push a fully-loaded 5-ton dump truck and to lay a pavement strip 12 feet wide. The paver shall meet all requirements specified herein while operating on level ground.

3.9 Traction drives. The traction drives shall be powered by separately controlled independent hydraulic motors. The traction drives shall propel the paver forward and rearward from zero to not less than 120 feet per minute (fpm). When specified (see 6.2), a traction drive speed increaser for traveling up to 180 fpm shall be provided. The traction drives shall provide a zero degree turning radius and shall be capable of rotating the paver about its center point, in both directions.

3.10 Mountings.

3.10.1 Type I, rubber tire-mounted. The type I paver shall be mounted on 10 or 12 soft solid traction tires suitable for paver operations.

3.10.2 Type II, crawler track-mounted. The type II paver shall be mounted on full crawlers with self-cleaning type treads not less than 14 inches wide. Total ground contact shall be not less than 780 inches. Crawler takeup adjustment provisions shall be furnished.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

3.11 Operator's platform and controls. An operator's platform shall be provided and shall be located so that the operator will have the optimum view of all operations. The platform shall be made of expanded metal capable of supporting two operators. The expanded metal shall provide an antiskid surface and hole spacing shall allow bituminous materials to fall through. All controls (except the speed range and screed controls) necessary for operation shall be accessible and located so that the operator can control all operations from both the right and left sides of the platform. All controls shall be identified.

3.12 Hopper. The receiving hopper shall have a capacity of not less than 5 tons and shall receive material directly from commercial type 5-ton dump trucks. The hopper shall be equipped with adjustable gates to control the flow of material to the screed. Each hopper gate shall be individually controlled. The paver frame shall be equipped with the manufacturer's standard push roller(s) to push the dump truck dual wheels while charging the hopper.

3.13 Spreader screws. The spreader screws shall be hydraulically powered and independently controlled to distribute bituminous material evenly the whole width of the screed or across either half of the screed as an independent operation.

3.14 Screed. The manufacturer's standard full floating vibratory screed shall be furhished. The screed shall be lifted and lowered hydraulically. operator(s) movement on the paver shall not vary the screed height settings or mat finish. The screed shall incorporate adjustments to control the thickness of the pavement strip. Sufficient adjustment shall be provided to lay pavement at any thickness from zero to not less than 5 inches. Controls shall be provided to vary the negative crown from zero to not less than 2 inches and the positive crown from zero to not less than 2 inches of the finished mat.

3.15 Screed heating system. The manufacturer's standard liquified petroleum gas, screed heating system shall be furnished.

3.16 Wash-down system. The manufacturer's standard electric motor driven wash-down system, with a hose long enough to reach all parts of the paver, shall be furnished. The wash-down system reservoir capacity shall be not less than 5 gallons and shall be mounted on the paver.

* 3.17 Engine. The engine furnished for the specified paver classes shall be the manufacturer's standard commercial or optional engine and shall have the horsepower, torque and speed characteristics to meet satisfactorily all the equipment performance requirements specified. The engine shall be complete with a 12-volt starting and charging system.

3.17.1 Gasoline engine. The class I paver shall be furnished with an air cooled, internal combustion, four-stroke cycle gasoline engine. The engine furnished shall provide the required paver performance when operated on unleaded fuel with a research octane rating of 91.

3.17.2 class II. diesel engine driven. The class II paver shall be equipped with an air cooled, compression ignited diesel engine.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

3.17.3 Storage battery{s). Unless otherwise specified (see 6.2), the manufacturer's standard commercial storage battery(s) furnished shall be of the maintenance-free type and shall conform to W-B-131. When specified (see 6.2), the manufacturer's standard commercial storage battery(s) normally furnished to make a complete electrical system shall be furnished dry charged and moisture sealed. Electrolyte shall not be furnished.

3.18 Hydraulic system.

3.18.1 Hydraulic fluid reservoir. A hydraulic fluid reservoir shall be provided and shall have sufficient capacity to hold the required volume of hydraulic fluid, with not less than 10 percent for expansion space. The reservoir shall be provided with a filler opening, a removable oil strainer, and a vented filler cap, accessibly located to facilitate filling the tank. The vented filler cap shall have means to preclude fluid splashing out of tank during movement of the paver and prevent entrance of water with cap in place from rain or hosing down. Provisions shall be made for draining of the reservoir. A sight level or dip stick gauge shall be furnished to determine level of fluid.

3.18.2 Hydraulic oil filter. The manufacturer's standard disposable cartridge hydraulic oil filtration system shall be furnished. The cartridge shall be capable of removing 25 micron (nominal) particles.

3.18.3 Hydraulic pump(s)system. A hydraulic pump(s) with necessary pressure and flow capacities to operate all hydraulic powered components shall be provided. The hydraulic pump(s) shall be close coupled to the engine. The pumping system shall include an adjustable pressure relief valve or unloading valve with the necessary range of adjustment.

3.18.4 Hydraulic cylinders. All hydraulic cylinders shall incorporate seals to prevent entrance of moisture and dirt into the cylinders and leaks of hydraulic fluid from the cylinders. All hydraulic cylinder piston rods shall be chrome plated to withstand a 30-hour salt spray test in accordance with ASTM B117.

3.18.5 Hydraulic lines and fittings. Hydraulic lines shall be located to facilitate maximum ease of removal and installation, or visual inspection for failure and maximum protection from damage during operation of the paver. Flexible hydraulic hose or collector rings shall be used where flexing of hydraulice lines is encountered, and where installation of components requires a flexible connection. Hydraulic lines and fittings shall be installed to preclude vibration and chafing. Hose assemblies and all seamless steel hydraulic lines shall be adequate for the rate of flow, temperature, and pressures required to operate the system smoothly and efficiently.

3.19 Cleaning, treatment, or painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. The color of the finish coat shall be as specified (see 6.2). Color of finish coat shall be in accordance with FED-STD-595. Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects.

3.20 Lubrication. Unless otherwise specified in 5.1, lubrication shall be in accordance with the manufacturer's recommendations. Pressure lubrication shall not damage seals or other parts. All parts requiring lubrication shall be lubricated prior to delivery and tagged to show the type and temperature rating of the lubricant used. Hydraulic lubrication fittings shall conform to SAE J534.

3.21 Instruction plates. The paver shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment. The plate shall be of a material which will last and remain legible for the life of the equipment, and shall be securely affixed thereto with nonferrous screws or bolts of not less than 1/8-inch diameter.

* 3.22 Identification plate. A name plate will be furnished by the contracting officer for each paver. The contractor shall stamp all necessary data in the blank spaces of the plate provided for that purpose, and securely affix a plate to each paver in a conspicuous place with brass or stainless steel screws, rivets or bolts not less than 1\8 inch in diameter. The applicable nomenclature contained in the contract item description shall be placed in the top blank.

3.23 Lifting and tiedown attachments. The paver shall be equipped with lifting and tiedown attachments. Lifting and tiedown attachments shall conform to type II or type III of MIL-STD-209. A nonferrous transportation plate shall be provided and mechanically attached to the paver.
Transportation plates shall be inscribed with a diagram showing the lifting attachments and lifting slings, the capacity of each attachment, and the required length and size of ezch sling cable. A silhouette of the item furnished showing the center of gravity shall be provided on the transportation plate. Tying down attachments may be identified by stenciling or other suitable marking. Tiedown marking shall clearly indicate that the attachments are intended for the tie down of the paver on the carrier when shipped.

3.24 Workmanship.

3.24.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.24.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.24.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivets. Rivet heads shall-be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.24.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surfacr of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.24.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

* 4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one complete paver when a first article is required (see 3.2 and 6.4). This inspection shall include the examination of 4.3, the tests of 4.4, and, when specified, the preproduction pack inspection of 4.6 (see 4.6 and 6.2). The first article may be either a first production item or a standard production item from the supplier’s current inventory provided the paver meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.5, and the packaging inspection of 4.6.

4.3 Examination. Each paver shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. When a first article is required, the first article shall be subjected to the tests specified in 4.4.1 through 4.4.3. Failure to pass any phase of the tests shall be cause for rejection.

4.4.1 Propulsion test. The paver shall be self-propelled to verify conformance to all parts of 3.9. Climbing ability shall be tested by negotiating a 25 percent grade with the receiving hopper of the paver empty.

4.4.2 Truck push test. Without sustaining frame damage, the paver shall push a commercial 5-ton dump truck while receiving paving material from the truck to verify conformance to 3.12.

4.4.3 Paving test. The receiving hopper shall be filled to the manufacturer's specified maximum capacity (not less than 5 tons) with bituminous material. The screed shall be heated and the paver adjusted to lay and finish two widths of mat 1 1/2 inches (nominal) thick. Each mat shall be approximately 100 feet long and the following widths:

a. 4 1/2 feet (nominal).
b. 9 feet (nominal).

The paver shall also lay a 3-inch (nominal) thickness by 12 foot wide (nominal) by approximately 100-foot long strip of bituminous material. Each strip shall be smooth in accordance with 3.8.

4.4.4 Production sample. Upon acceptance of the first article, the first article shall remain at the manufacturing facility as a production sample, and shall be the last paver delivered on the contract. The first article shall be reconditioned, including replacement of abnormally worn parts and paint touch-up or repainting, prior to delivery to enable it to be accepted as a contract item. The contractor shall maintain the first article in a serviceable condition for the duration of the contract.

4.5 Production unit operation test. Each paver produced in fulfillment of a Government contract shall be completely assembled, adjusted, lubricated, or otherwise serviced for operation. The engine shall be started and subjected to a warmup period as recommended by the manufacturer. The paver shall be given a run-in test and all controls operated a sufficient number of times to ascertain that the components and mechanisms actuated by the controls operate promptly, fully, and without restriction or malfunction. Hydraulically actuated

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

components shall be observed for evidence of lurching or binding, or leaking of fluids. Failure to pass any phase of this test shall be cause for rejection.

* 4.6 Packaging inspection. The inspection of the preservation, packing, and marking shall be in accordance with the requirements of section 4 of MIL-T-3351 or ASTM D 3951 for Commercial Packaging. The inspection shall consist of the quality conformance inspection; and, when specified (see 6.2), a preproduction pack shall be furnished for examination and test within the time frame required (see 6.2).

5. PACKAGING

5.1 Preservation, packing, and marking. The presentation, packing, and marking of the pavers shall be in accordance with type II unboxed (mobile) requirements of MIL-T-3351. The level of preservation and level of packing shall be as specified (see 6.2).

6. NOTES

6.1 Intended use. The paver covered by this specification is intended for use where large capacity paving machines would lack maneuverability. Paver finishing capability is from 4 1/2 feet up to 9 feet, and laying capability up to 12 feet.

* 6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type and class of paver required (see 1.2).
c. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
d. When a first article paver is required for inspection and approval (see 3.2, 4.2.1, and 6.4).
e. When a traction drive speed increaser is required (see 3.9).
f. When storage battery(s) shall be dry charged and moisture sealed (see 3.17.3).
g. Color of finish coat required (see 3.19).
h. When a preproduction pack inspection is required and the time frame required for submission (see 4.2.1 and 4.6).
i. Level of preservation and level of packing required (see 5.1).

* 6.3 Data requirements. When this specification is used in an acquisition and data are required to be delivered, the data requirements shall be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved Contract Data Requirements List (CDRL) incorporated into the contract. When the provisions of DoD Federal Acquisition Regulations (FAR) Supplement, Part 27, Sub-Part 27.475-1 (DD Form 1423) are invoked and the DD Form 1423 is not used, the data should be delivered by the contractor in accordance with the contract or purchase order requirements.

6.4 First article. When a first article inspection is required, the item will be tested and should be a first production item or it may be a standard production item from the contractor's current inventory as specified in 4.2.1.

Source: https://assist.dla.mil - Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

The first article should consist of one unit (see 2.2). The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

* 6.5 Subject term (key word) listing.

Engine
Hydraulic
Material spreading
Receiver hopper
Vibrating heated screed

* 6.6 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate. the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

* 6.7 Subject term (key word) listing

Bottom fired
Burner
Kerosene fueled
Melting tank
Tube fired

Custodian:

Navy - YD

Preparing Activity:

Navy - YD

(Project 3895-N316)

Source: https://assist.dla.mil - Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-P-29196B(YD)	2. DOCUMENT DATE (YYMMDD) 20 JUNE 1991

3. DOCUMENT TITLE
PAVING MACHINES, BITUMINOUS MATERIAL, CRAWLER-OR RUBBER, TIRE-MOUNTED, SELF-PROPELLED

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME B.E. LEWIS	b. TELEPHONE (Include Area Code) (1) Commercial: (805) 982-5464 (2) AUTOVON: 551-5464
c. ADDRESS (Include Zip Code) NCBC CODE 1564L PORT HUENEME, CA 93043	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil - Downloaded: 2026-10-20T22:11Z
Check the source to verify that this is the current version before use.