| NOT MEASUREMENT |
| SENSITIVE |

MIL-B-22353D
17 November 1988
SUPERSEDING
MIL-B-22353C
16 July 1982

MILITARY SPECIFICATION

BATCHING PLANT, AGGREGATE, (WHEEL-MOUNTED, 30 TON CAPACITY)

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a frame supported, manually-operated, wheel-mounted, pneumatic-tired, two- or three-compartment, aggregate batching plant having not less than 30 tons total storage bin capacity.

1.2 Classification. The batching plants will be of the following types as specified (see 6.2).

Type I - Two-compartment.
Type II - Three-compartment.

1.2.1 Part or identifying numbers (PIN). The PINs for the batching plants covered by this specification are as follows:

Type I - M22353-01.
Type II - M22353-02.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043-5000, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3895

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

PPP-B-601 - Boxes, Wood, Cleated-Plywood.
PPP-B-621 - Boxes, Wood, Nailed and Lock-Corner.
PPP-P-40 - Preservation of Packing of Hand Tools; Tools and Tool Accessories For Power Driven, Metal and Woodworking Machinery.
PPP-T-60 - Tape: Packaging, Waterproof.

MILITARY

MIL-C-104 - Crates, Wood; Lumber and Plywood Sheathead, Nailed and Bolted.
MIL-P-116 - Preservation, Methods of.
MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-P-130 - Paper, Wrapping, Laminated, and Creped.
MIL-V-173 - Varnish, Moisture-and-Fungus-Resistance (For Treatment of Communications, Electronics, and Associated Equipment).
MIL-C-3774 - Crates, Wood: Open 12,000- and 16,000-Pound Capacity.

STANDARDS

MILITARY

MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-209 - Slinging and Tiedown Provision for Lifting and Tying Down Military Equipment.

(Unless otherwise indicated, copies of Federal and Military specifications and standards are available from the Naval Publications and Forms Center (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

2.1.2 Other Government documents. The following other Government documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues are cited in the solicitation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

NATIONAL BUREAU OF STANDARDS (NBS)

NBS Handbook 44 - Specifications, Tolerances, and Regulations for Commercial Weighing and Measuring Devices.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

(Unless otherwise indicated, copies of other Government documents should be obtained from the contracting officer or as directed by the contracting officer.)

2.2 Non-Government publications. The following document forms a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of the documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

TIRE AND RIM ASSOCIATION, INC. (TRA)

TRA Yearbook.

(Application for copies should be addressed to the Tire and Rim Association, Inc., 3200 West Market Street, Akron, OH 44313.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specifications, specifications sheets or MS standards), the text of this specification takes precedence. Nothing in this specification, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The batching plant, aggregate, hereinafter called the batching plant, shall be a frame supported, wheel-mounted, compartmented unit for dispensing concrete aggregates. The batching plant shall weigh accurately successive batches of aggregate adequate for charging a 16 cubic foot capacity mixer. The batching plant shall be type I or II (see 1.2), overhead storage bin with gates, complete with a weighing hopper, weighing scales, supports, and all detail parts and accessories necessary for the successful performance of the batching plant. The entire batching plant, except for certain operating accessories, shall be made of steel. The entire batching plant

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

shall be designed for quick assembly and disassembly. The batching plant shall be equipped with retractable or removable pneumatic-tired wheels and with suitable means for towing from one location to another.

3.2 Standard commercial product. The batching plant shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the batching plant being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures, and represents the latest production model.

3.3 First article. When specified in the contract or purchase order (see 6.2), a sample shall be subjected to first article inspection (see 4.2.1 and 6.4).

3.4 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. Unless otherwise specified, none of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification.

3.4.1 Dissimilar metals. Intimate contact which can be expected to cause galvanic corrosion shall be avoided. When such contact cannot be avoided, an interposing insulating material shall be provided to minimize the corrosive affect.

3.5 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.6 System of measurement. The dimensions used in this specification are not intended to preclude the use of the metric system of measurement in the fabrication and production of the material, individual parts, and the finished product, provided form, fit, and function requirements are satisfied.

3.7 Performance. The batching plant shall be capable of dispensing two or three different size aggregates in accurately measure increments. The storage bins shall have a capacity of not less than 30 tons (20 cubic yards). The batching plant shall be capable of being towed at 10 miles per hour when empty.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

3.8 Maintainability. The batching plant design, together with component and accessory location and installation, shall permit ready accessibility to all items requiring periodic maintenance service in the field, which will be accomplished with the use of conventional, general-purpose tools associated with equipment of this nature. The replacement and adjustment of components and accessories shall be accomplished with minimum drainage requirements and minimum disturbance to other elements of the batching plant.

3.8.1 Dimensions. The overall dimensions of the batching plant shall be not greater than the following limits: Bin charging height, 12 feet; overall width when ready for travel, 8 feet.

3.8.2 Storage bin. The storage bin shall have a total heaped capacity of not less than 30 tons based on aggregates weighing 3,000 pounds per cubic yard. The storage bin shall be divided into the number of compartments as specified (see 1.2 and 6.2). The compartments shall be of approximately equal volume and formed by means of steel bulkheads projecting above the bins. The bin may be equipped with removable for folding top extension panels. The bin shall be designed for aggregates having an angle of repose of 40 degrees with the horizontal. The slope of the sides of the bin hopper shall be not less than 45 degrees with the horizontal. The interior surfaces of the bin shall be free from obstruction, and all joints and connections shall be finished so as to allow free movement of aggregates. The bin wall and sloping bottom shall be fabricated of steel with not less than a nominal thickness of 0.1345 inch (U.S. revised standard gage No. 10).

3.8.2.1 Bin gates. Bin gates shall be provided for the bottom of the compartment openings. The bin gates shall be of the single-clam or double-clam type with manual control, easily operated, durable and shall be accurate in cutting off material. Clear openings of bin gates shall be not less than 180 square inches.

3.8.3 Batcher. The batcher hopper shall be located under the storage bin, shall have a capacity for weighing aggregates for a 16 cubic feet capacity mixer batch, and shall be of all welded construction with steep slopes to insure clean and rapid discharge of the aggregate. The discharge gate shall be of the single-clam or double-clam type with manual control. Clearance between the discharge gate and grade elevation shall be not less than 24 inches. Openings shall be provided in the hopper for removal of overweight.

3.8.4 Weighing scales. The weighing scales shall conform to the applicable requirements of the section on scales in NBS Handbook 44 and as specified herein. The weighing scales shall consist of a torque lever assembly suspended from the bin, supporting the weighing hopper, and of a scale beam box to which the load shall be transmitted from the torque levers by means of an extension lever. The scale beam box shall be equipped with the appropriate number of weighing beams. Each weighing beam shall be graduated in increments of 100 pounds and 2 pounds. Each weighing beam shall be provided with a major and minor poise, movable over the weighing beam. The

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

scales shall be arranged for accumulative weighing of three aggregates in sequence. A springless dial indicator shall be provided which will give visible indication to the operator when the aggregate in the weighing hopper is approaching the correct weight, and when the aggregate is at the exact weight for each of the weighing beams successively. Ten 50-pound test weights, complete with hanger, shall be provided. The scale beams shall be housed in a scale beam box which shall be removable for safekeeping.

3.8.5 Operating levers and pedals. The batcher bin gates and weighing hopper gates shall be controlled by not less than the number of hand levers or foot pedals necessary for operation by one man. The levers and pedals shall be located convenient to the operator.

3.8.6 Tires and rims. The tire and rim rating shall conform to the TRA Yearbook recommendations for the type and size of tires furnished. Tire and rim sizes shall be the same for all wheels. Tires shall be tube or tubeless type with highway tread. Tires shall be of rated capacity not less than equal to the load imposed on each tire, measured at each wheel at the ground. Tires shall be not less than 100 level quality. When tube type tires are furnished, inner tubes shall be heavy-duty type, and shall be of proper size for tires furnished.

3.9 Toolbox. A toolbox shall be provided. The toolbox shall be large enough to store all tools required for field service or maintenance, but shall not have external closed dimensions less than 14 inches in length, 6 inches in width, and 6 inches in height. The toolbox shall be of a nominal 0.0747-inch (U.S. revised standard gage No. 14) thick steel with a hinged lid and a truck drawbolt to keep the lid secure when vibrated. The toolbox shall be mounted in a protected, accessible location.

3.10 Safety. All moving parts, which are of such nature or so located as to be a hazard to operating or maintenance personnel, shall be fully enclosed or properly guarded. Protective devices shall not impair the operating functions.

3.11 Lubrication. Lubrication shall be in accordance with the equipment manufacturer's recommendations and shall be compatible with lubricants specified herein. Pressure lubricant shall not damage seals or other parts. All parts requiring lubrication shall be lubricated prior to delivery and tagged to show the type and temperature rating of the lubricant used.

3.12 Fungus resistance. When specified (see 6.2), electrical components and circuit elements, including terminal and circuit connections, shall be coated with varnish conforming to MIL-V-173, except that:

a. Components and elements inherently inert to fungi or in hermetically sealed enclosures need not be coated.
b. Current-carrying contact surfaces, such as relay contact points, shall not be coated.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

3.13 Lifting and tiedown attachments. The batching plant shall be equipped with lifting and tiedown attachments. Lifting and tiedown attachments shall conform to type II or type III of MIL-STD-209. A nonferrous transportation plate shall be provided and mechanically attached to the batching plant. Transportation plates shall be inscribed with a diagram showing the lifting attachments and lifting slings, the capacity of each attachment, and the required length and size of each sling cable. A silhouette of the item furnished showing the center of gravity shall be provided on the transportation plate. Tiedown attachments may be identified by stenciling or other suitable marking. Tiedown markings shall show which attachments are intended for the tie down of the batching plant on the carrier when shipped.

3.14 Instruction plates. The equipment shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment. Plates shall be of a material which will last and remain legible for the life of the equipment. Plates shall be securely affixed to the equipment with nonferrous screws or bolts of not less than 1/8-inch diameter.

3.15 Identification plate. An identification plate will be furnished by the contracting officer for each batching plant. The contractor shall stamp all necessary data in the blank spaces of the plate provided for that purpose, and securely affix a plate to each batching plant in a conspicuous place with nonferrous screws, rivets, or bolts not less than 1/8-inch in diameter. The applicable nomenclature contained in the contract item description shall be placed in the top blank.

3.16 Servicing and adjusting. Prior to acceptance of the batching plant by the Government, the contractor shall service and adjust the batching plant for immediate operational use as required in the operator's manual. The servicing and adjusting shall include at least the following:

a. Inflation of all tires.
b. Adjustment of brakes.
c. Proper functioning of all lighting and electrical systems.
d. Wheel alinement.
e. Complete lubrication with grades of lubricants recommended for ambient temperature at the delivery point.

The batching plant shall be conspicuously tagged to identify the lubricants and their temperature range.

3.17 Cleaning, treatment, and painting. Portions of the batching plant normally painted shall be cleaned, treated, and painted as specified herein. The color of the finish coat shall be as specified (see 6.2). Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat of acrylic-based enamel. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects.

3.18 Workmanship.

3.18.1 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the metal, may be used instead of shearing and sawing. All bends shall be made by controlled means to insure uniformity of size and shape. Precautions shall be taken to avoid overheating and heated metal shall be allowed to cool slowly. External surfaces shall be free from burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.18.2 Bolted connections. Boltholes shall be punched or drilled within manufacturer's design tolerances and shall have the burrs removed. Washers or lockwashers shall be provided and all bolts, nuts, and screws shall be tight.

3.18.3 Riveted connections. Rivet holes shall be punched or drilled within manufacturer's design tolerances and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.18.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.18.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practic to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one batching plant when a first article is required (see 3.3 and 6.2). This inspection shall include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.4, and the packaging inspection of 4.5.

4.3 Examination. Each batching plant shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 Tests. Every unit shall be tested in accordance with 4.4.1. The first article shall be tested in accordance with 4.4.2. Failure to pass any phase of the required tests shall constitute cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

4.4.1 First article test. The following tests shall be performed only when a first article sample is required (see 3.3).

a. Fill the storage bin to struck capacity using a different size aggregate in each bin compartment.

b. Fill the weighing hopper to capacity, drawing a portion of the total load from each bin. While filling, open and close each bin compartment discharge gate not less than five times.

c. Move the weighing hopper to a normal discharge position. While discharging, open and close discharge gate not less than five times.

d. Operate the weighing hopper through not less than five complete cycles of filling, weighing, dumping, and return, changing the aggregate proportions each time to simulate different mix designs. The accuracy of the weighing scales shall be tested after each cycle, and after the mobility test in accordance with 3.8.4.

e. Tow the batching plant over a circular unpaved course for not less than 10 miles at an average speed of 10 miles per hour.

4.4.1.1 Lifting and tying down attachment tests. When required, the lifting and tying down attachments shall be tested to determine conformance to 3.13.

4.4.2 Acceptance tests. Each batching plant and components shall be tested as follows, under "no-load" conditions.

4.4.2.1 Scale tests. The weighing scales shall be adjusted and tested for accuracy in accordance with 3.8.4.

4.4.2.2 Operational tests. The gate, hopper, and other component controls shall be operated a sufficient number of times to determine ease of operation and responsiveness.

4.5 Packaging inspection. The preservation, packing, and marking of the item shall be inspected to verify conformance to the requirements of section 5.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial, as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Methods of preservation. Cleaning processes, drying procedures, preservatives, and methods of preservation specified in the following paragraphs are listed in MIL-P-116 and shall conform to the requirements of MIL-P-116 and any applicable specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

5.1.1.2 Disassembly. Disassembly shall be the minimum necessary to protect parts subject to damage or loss, and to accomplish reduction in cube. Removed bolts, nuts, pins, screws and washers shall be reinstalled in mating parts and secured to prevent their loss.

5.1.1.3 Matchmarking. Parts removed and mating parts on the equipment and attachments shall be matchmarked to facilitate reassembly. Parts and accessories removed, and mating parts on the equipment, shall be identified with weatherproof tags attached to mating parts and locations. Markings shall be applied to the tags with a waterproof material.

5.1.1.4 Cleaning and drying. Prior to the application of preservative compounds or paint, surfaces shall be cleaned by process C-1 and dried by any applicable procedure of MIL-P-116.

5.1.1.5 Unprotected surfaces. Unprotected exterior metal surfaces requiring the application of a contact preservative in accordance with MIL-P-116 and not specifically provided for herein shall be preserved as follows:

5.1.1.5.1 Unfinished (not machined) surfaces. Unfinished exterior metal surfaces shall be coated with type P-1 preservative.

5.1.1.5.2 Machined surfaces. Exposed machined surfaces shall be coated with type P-6 or P-11 preservative and wrapped or covered, as applicable, with barrier material conforming to MIL-B-121, type I, grade A, class 2. The material shall be secured in place with waterproof tape.

5.1.1.6 Wheels, axles, bearings, and tires. When wheels are removed, the tires shall be inflated to two-thirds of the specified operating pressure. The wheel nuts shall be replaced on the studs and the exposed threaded surfaces shall be coated with type P-1 preservative. When wheels and hubs are removed from axles or spindles, the interior bearing surfaces of the hubs and the bearings or bearing surfaces of the axles or spindles shall be coated with type P-11 preservative. The coated surfaces of the axles or spindles shall be wrapped and hub openings shall be covered with barrier material conforming to MIL-B-121, type I, grade A, class 2. The barrier material shall be secured in place with tape conforming to PPP-T-60, type IV. Bearings removed from the wheels shall be coated with type P-11 preservative and preserved method IA-8. When wheels are not removed, the tires shall be inflated to 10 pounds above the specified operating pressure and wheel bearings shall be preserved with type P-11 preservative.

5.1.1.7 Weighing scales.

5.1.1.7.1 Torque lever assembly U-bolts and hook bolts. The U-bolts and hook bolts shall be wrapped in sets with paper conforming to MIL-P-130, type II, secured with waterproof tape conforming to PPP-T-60, type IV.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

5.1.1.7.2 Scale beam box. The interior surfaces of the scale beam box, including all moving parts, shall be coated with type P-7 or type P-10, grade 2 preservative. Where practicable, the assemblies within the scale beam box shall be wrapped or covered with barrier material conforming to MIL-B-121, type I, grade A, class 2; secured in place with waterproof tape. The poises, weights, weighing beams, and the dash pot shall be cushioned and securely blocked in place to prevent movement.

5.1.1.7.3 Dial indicator. The interior surface of the dial including all moving parts shall be coated with type P-7 or P-10, grade 2 preservative. The fulcrum arm shall be secured to prevent movement. The dial glass shall be protected from breakage with a fitted piece of suitable material such as hardboard, plywood, fiberboard, styrofoam, or other materials, tape conforming to PPP-T-60, type IV, the dial indicator shall be wrapped with barrier material conforming to MIL-B-121, type II, grade A, class 2, secured with waterproof tape.

5.1.1.7.4 Dial indicator connecting rod. The dial indicator connecting rod shall be wrapped with barrier material conforming to MIL-B-121, type II, grade A, class 2, and the wrap secured with waterproof tape. The package shall be placed in the scale beam box and cushioned and blocked to prevent movement.

5.1.1.7.5 Closure. The cover of the scale beam box shall be secured in place and the cover joint sealed with waterproof tape conforming to PPP-T-60, type IV.

5.1.1.8 Maintenance tools. Maintenance tools shall be preserved in accordance with level A preservation and packaging requirements of PPP-P-40.

5.1.1.9 Technical publications. Technical publications for each piece of equipment shall be preserved method 1C-1 or 1C-3.

5.1.1.10 Consolidation. Tool boxes shall be utilized for the consolidation of loose components, tools, and publications. The remainder of the components that will not fit in tool boxes shall be consolidated, along with dissembled components, in boxes conforming to PPP-B-601, overseas type; or PPP-B-621, class 2. Boxes shall be secured to the equipment with appropriate strapping. Arrangement and location on the equipment shall be such so as not to increase cubage or interfere with lifting or mobility of the equipment.

5.1.2 Commercial. The equipment shall be preserved in accordance with the contractor's standard practice in a manner to prevent deterioration and damage.

5.2 Packing. The packing shall be level A or commercial, as specified (see 6.2).

5.2.1 Level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

5.2.1.1 Plant (except storage bin). The weighing hopper, disassembled components, structural members of the supporting frame, extension panels, wheels and axles, and tow bar shall be packed in crates conforming to MIL-C-3774, type II, style a. The contents shall be anchored, blocked, and braced in accordance with the crate specification.

5.2.1.2 Storage bin. The storage bin with the extension panels removed shall be placed and secured on a crate base conforming to MIL-C-104, style a. Blocking, bracing, and anchoring shall be in accordance with the crate specification.

5.2.2 Commercial. The equipment shall be prepared for shipment in a manner which will insure arrival at destination in a satisfactory condition. Preparation for delivery shall comply with applicable carrier rules and regulations.

5.3 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The batching plant is intended to be used to hold and dispense measured amount of concrete aggregate by weight.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification.
b. Type (see 1.2).
c. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
d. When first article and inspection sample is required (see 3.3 and 4.2.1).
e. If storage bins are two or three compartments (see 3.8.2).
f. When treatment for fungus resistance is required (see 3.12).
g. Color of finish coat (see 3.17).
h. Level of preservation and level of packing (see 5.1 and 5.2).

6.3 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423, Contract Data Requirements List (CDRL) and invokes the provisions of DOD Federal Acquisition Regulations (FAR) Supplement 27.410-6, the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL (DD Form 1423) incorporated into the contract. When the provisions of DOD FAR 27.410-6 are not invoked, the data should be delivered in accordance with the contract requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.

6.4 First article. When a first article inspection is required, the item should be a first production item, or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of first article test results and disposition of first article. Invitations for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract.

6.5 Subject term (key word) listing.

Aggregate
Batching plant
Wheel-mounted

6.6 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Navy - YD

Preparing activity:
Navy - YD

Project 3895-N261

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T12:08Z
Check the source to verify that this is the current version before use.