MILITARY SPECIFICATION
BOMB, SMOKE, BLU-17/B

1. SCOPE

1.1 This specification covers the BLU-17/B smoke bomb.

2. APPLICABLE DOCUMENTS

2.1 Government documents. The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-C-215 - Chemical Agent, White Phosphorus (WP).

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

US ARMY MUNITIONS COMMAND

DL14-5-2808 - Bomb, Smoke, BLU-17/B.

(All drawings referenced in this specification are listed on the above Edgewood Arsenal drawing.)

FSC 1325

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

EDGEWOOD ARSENAL INSPECTION STANDARD

R8-1 - Grenade, Hand and Rifle, Smoke, WP, M34.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials and components.

3.1.1 Materials. All materials cited on Drawing DL14-5-2808 or on the subsidiary drawings shall conform to the specifications listed thereon or to the specific characteristics set forth on the drawings.

3.1.2 Components. All components of the bomb shall conform to the specifications and drawings listed on Drawing DL14-5-2808 and subsidiary drawings.

3.2 Filling. The bomb shall be clean, free from foreign matter, and filled with molten WP conforming to MIL-C-215(see 6.2 and 6.3). The process water used in the filling lines shall be buffered by a suitable alkaline salt to maintain a pH value between 6.5 and 8.0. The surface of the WP in the filled bomb shall be 1/8 to 3/8 inch below the lowest point on the bomb cap and the depth of water remaining on the surface of the WP shall not exceed 1/8 inch when tested in accordance with 4.2.4.1.

3.3 Cleaning. The filled and closed bomb and the interior of the burster well shall be cleaned to remove any grease, oil, WP or other contamination and dried prior to inserting the fuze (see 6.4).

3.4 Assembly. The bomb shall be assembled as shown on Drawing D14-5-2808.

3.5 Leakage. The unfuzed bomb shall not leak subsequent to removal from a 10 - 15 minute storage period at a temperature of 207° - 212°F when tested in accordance with 4.2.4.3. The bomb temperature shall be measured by thermocouples inserted into the burster wells of at least 2 bombs, each located in a different oven bay in an oven batch.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

3.6 Functioning. After release of the fuze lever, the bomb shall burst within 4.1 and 5.2 seconds and disperse the WP when tested in accordance with 4.2.4.4. The delay time for the fuze shall be between 4.0 and 5.0 seconds.

3.7 Workmanship. The bomb shall be free from damage such as dents, cracks and deformations which would adversely affect its intended use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.

4.1.1 Supplier's responsibility. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.2 Objective evidence. The supplier shall provide objective evidence acceptable to the contracting officer that the requirements of 3.1 for which specific inspection has not been provided in this specification have been satisfied.

4.2 Regular production.

4.2.1 Lotting. A lot shall consist of the bombs produced by one manufacturer, at one plant, from the same materials and under essentially the same manufacturing conditions. However, no more than one lot of fuzes shall be represented in any one lot of assembled bombs.

4.2.2 Sampling.

4.2.2.1 For examination and nondestructive tests. Sampling shall be conducted in accordance with MIL-STD-105.

4.2.2.2 For destructive tests. Sampling shall be conducted in accordance with MIL-STD-105, level S-1 for the fuze prior to assembly into the bomb and level S-4 for the assembled bomb. An AQL of 0.65 shall be used for the fuze and an AQL of 1.5 shall be used for the assembled bomb.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

4.2.3 Inspection.

4.2.3.1 For examination and nondestructive tests. Sample bombs shall be examined and tested in accordance with the classification of defects and with MIL-STD-105.

4.2.3.2 For destructive tests. Sample bombs shall be tested in accordance with 4.2.4.4. The AQL for the fuze is 0.65 percent defective and the AQL for the assembled bomb is 1.5 percent defective.

4.2.3.3 Critical defects. Each bomb in the lot shall be inspected for its critical characteristics listed in the classification of defects.

4.2.3.4 Classification of defects.

(a) Bomb, smoke, BLU-17/B (Dwg D14-5-2808).

Categories	Defects	Acceptance standards
Critical:		
1	WP leakage	4.2.4.3
2	WP contamination	4.2.4.2
Major:	AQL 0.65 percent defective	
101	Filling excessive	4.2.4.1
	AQL 1.0 percent defective	
102	Component missing	
103	Component incorrectly assembled	
104	Excess water in bomb	4.2.4.1
105	Marking missing or incorrect	
106	Torque incorrect	
107	Workmanship (3.7)	
Minor:	AQL 2.5 percent defective	
201	Protective finish missing	
202	Filling insufficient	4.2.4.1

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

4.2.4 Tests.

4.2.4.1 Filling. The filling height and the depth of water remaining on the surface of the WP in the filled bomb shall be determined with the bomb oriented in the base-down position using Edgewood Arsenal Inspection Standard R8-1 while the temperature of the WP is 130° ± 10°F.

4.2.4.2 Cleaning. The cleaning procedure and the method for determining WP contamination shall be approved by the Government prior to their use.

4.2.4.3 Leakage. The unfuzed bomb shall be placed in an oven with the filling port in the "UP" position at the specified temperature for the required period of time. After removal from the oven, the bomb shall be observed for leakage.

4.2.4.4 Functioning. The bomb shall be fired by using either a remote control firing device to withdraw the safety pin or a bomb launcher provided with a barricade (see 6.2).

5. PREPARATION FOR DELIVERY

Packaging, packing and marking information is not applicable to this specification.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

(a) Title, number and date of this specification.
(b) The supplier will not be required to furnish radiographic equipment.

6.2 Precaution. Due to the hazards inherent in the handling of WP, suppliers are cautioned to protect personnel from injury while filling and testing bombs.

6.3 Filling aid. Bombs filled to a height of 25/32 to 15/16 inch below the top of the cap have been found to comply with 3.2 provided the internal configuration of the bomb is within the tolerances specified on the drawings. This information is furnished as an aid to procurement and not as a criterion for filling.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

6.4 Cleaning. The filled bomb may be cleaned by passing through a hot water and detergent spray washer or by flushing with hot water while vigorously scrubbing with steel wool. Additional cleaning of the burster well may be accomplished with a steam lance and a power-driven wire brush.

6.5 Supersession data. This specification supersedes Edgewood Arsenal Purchase Description 196-131-827, dated 20 May 1965.

Custodian:

Army - MU

Preparing activity:

Army - MU (EA)

Project No. 1325-A194

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.