MILITARY SPECIFICATION

PRIMER, PERCUSSION, M62
METAL PARTS FOR

This Amendment forms a part of Military Specification MIL-P-60096 (MU), dated 3 November 1964.

Page 1, paragraph 2.1, Specifications, Military: Delete "MIL-I-45208 ... for".

Page 1, paragraph 2.1, Standards, Military: Add "MIL-STD-1168 - Lot Numbering of Ammunition".

Page 3: Delete paragraphs 4.1.1, 4.1.2 and 4.1.3 and substitute the following:

"4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions specified within this specification.

b. Number of units of product inspected.

c. Results obtained, by defect code, for all inspections performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization."

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

"4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records."

Page 5, paragraph 4.3.1: Delete and substitute the following:

"4.3.1 Lot formation.-A lot shall consist of metal parts produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The examinations and tests listed herein shall be performed on inspection lots submitted in accordance with Standard MIL-STD-105 or MIL-STD-1235, as applicable. The criteria and procedures for the assignment of lot numbers shall be in accordance with Standard MIL-STD-1168."

Page 6, paragraph 4.3.2: Delete and substitute the following:

"4.2.2 Examination.-Inspection for critical defects shall be 100 percent. Sampling plans and procedures for major and minor defects shall be in accordance with Standard MIL-STD-105. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect except where 100 percent inspection is specified. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4."

Page 11: Delete paragraphs 5.1, 5.1.1, 5.2 and 5.3 and substitute the following:

"5.1 Packing

5.1.1 Level C.-Packing and marking shall be in accordance with Specification MIL-P-10025."

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

Page 12, paragraph 6.1: Delete and substitute the following:

"6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167."

Page 13: Delete paragraph 6.3.5 and substitute the following:

"6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7."

Page 14, paragraph 6.3.6: Add the following:

"Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7."

Page 14, paragraph 6.3.7: Delete and substitute the following:

"6.3.7 Submission of contractor designs.-Unless otherwise specified on the IEL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.

"permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt."

Page 14, paragraph 6.5: Delete and substitute:

"6.5 Submission of initial production samples.-Instructions as to the location of the initial production inspection shall be obtained from the contracting officer. Upon receipt of such a request, the contracting officer shall advise Picatinny Arsenal, ATTN: SMUPA-NI, and instructions will be issued accordingly."

Page 14, paragraphs 6.6, 6.6.1 and 6.6.2: Delete in their entirety.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1390-A545

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:08Z
Check the source to verify that this is the current version before use.