MIL-S-55590C(EL)
Amendment 1

MILITARY SPECIFICATION 22 February 1973

SHELTER, ELECTRICAL EQUIPMENT S-390( )/TRC-145(V)

This amendment forms a part of Military Specification MIL-S-55590C(EL), dated 19 January 1972, and is approved for use by all Departments and Agencies of the Department of Defense.

Page 1

2.1 Add

SPECIFICATIONS

MILITARY

MIL-C-55427 Cable Assembly, Radio Frequency General Specification for

Page 3

3.1 First Article of Production: Delete this paragraph and substitute the following:

"3.1 First Article. - When specified in the contract or purchase order, the contractor shall furnish first article units in accordance with 4.3."

3.3.1 Delete "Power system wiring and components" and substitute "Power systems and components installation".

Page 4

3.3.3 Change paragraph title to: "Signal (audio) system wiring and components installation." and add "(See 4.7.3)".

3.3.3.1 and 3.3.4.1 Change titles to: "Continuity of conductors."

3.3.4 Change paragraph title to: "Video and radio frequency (rf) system wiring and components installation."

FSC 5820

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

Page 5

3.3.5 Delete this paragraph and substitute the following:

"3.3.5 Cable Assemblies. - (See 4.4)

3.3.5.1 Cable Assemblies, Power and Audio Frequency. - All power and audio frequency cable and cord assemblies shall be fabricated in accordance with the drawings and meet the continuity, dielectric, insulation resistance, and pull-out requirements of MIL-C-3885.

3.3.5.2 Cable Assemblies, Radio Frequency. - Radio frequency cable assemblies required for operation of major items of equipment in 6.1 shall be fabricated in accordance with the drawings and meet the following requirements when tested in accordance with MIL-C-55427:

3.3.5.2.1 DC Resistance. - When tested as specified, the point to point resistance of the conductor shall not be greater than 1 ohm.

3.3.5.2.2 Pull-out Load for Terminations. - When tested as specified the cable assembly shall show no evidence of mechanical damage when a load of 25 pounds is applied.

3.3.5.2.3 Dielectric Withstanding Voltage. - When tested as specified the cable assembly shall show no evidence of breakdown with a test potential of 1500 volts RMS, 25-100 hertz.

3.3.5.2.4 Insulation Resistance. - When tested as specified the insulation resistance shall not be less than 100 megohms with a test potential of 500 volts DC.

3.3.5.2.5 Voltage Standing Wave Ratio. - When tested as specified the VSWR shall not exceed 1.20."

Page 6

3.11 Add: "(See 3.22)"

Page 7

3.13 Delete "(See 4.4)" and substitute "(See 3.22 and 4.4)".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

3.14 Add "(See 3.22)"

3.15 Add "(See 3.22)"

Page 8

3.16 Add "(See 3.22)"

3.17 Add "(See 3.22)"

3.18 Add "(See 3.22)"

Page 9

3.19 Add "(See 3.22)"

3.20 Add "(See 3.22)"

Page 10

3.22 Add "(See 4.17)" to end of paragraph. Delete "3.21 Interchangeability" from list.

Page 11

4.1 Responsibility for inspection: Delete second sentence and substitute the following:

"Except as otherwise specified in the contract or purchase order, the contractor may utilize his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government."

4.1.1 Contractor quality assurance: Delete this paragraph.

4.1.2 Government verification: Delete this paragraph.

4.1.3 Accommodation and assistance: Delete this paragraph.

Page 12

4.3 First article inspection: Delete this paragraph and substitute the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

"4.3 First article. - Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor. (See 3.1)

4.3.1 First article units. - The contractor shall furnish one (1) first article unit of the complete S-390( )/TRC-145(V).

4.3.2 First article inspection. - The first article inspection shall consist of inspections specified in Table I and shall be performed in theorder specified therein.

4.3.3 First article data. - The first article test plan and test report(s) shall be as required in the contract or purchase order.

4.3 Delete TABLE I with the notes at bottom and substitute the following:

TABLE I First Article Inspection

Inspections	Rqr Para	Test Para
1. Inspection covered by subsidiary documents	-	4.4
2. Interchangeability	3.21	4.16
3. Mounting Insert	3.10	4.14.1
4. Solderless-terminal-lug connectors	3.20.4	4.15
5. Visual and Mechanical	3.22	4.17
6. Power systems and components installation	3.3.1	4.7.1
7. Power distributional and operational function	3.3.2	4.7.2
8. Signal (audio) system wiring and components installation	3.3.3	4.7.3
9. Video and radio frequency (RF), system wiring and components installation	3.3.4	4.7.4
10. System operation	3.4	4.8
11. Vehicular transportation	3.5	4.9

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

TABLE I First Article Inspection
(contd)

Inspections	Rqr Para	Test Para
12. Rail transportation	3.6	4.10
13. Flat drop	3.7	4.11.1
14. Rotational drop	3.7	4.11.2
15. Watertightness	3.8	4.12
16. Fording	3.9	4.13
17. Repeat 6. Power systems and components installation	3.3.1	4.7.1
18. Repeat 7. Power distributional and operational function	3.3.2	4.7.2
19. Repeat 8. Signal (audio) system wiring & components installation	3.3.3	4.7.3
20. Repeat 9. Video and radio frequency (RF) system wiring and components installation	3.3.4	4.7.4
21. Repeat 10. System operation	3.4	4.8

4.5 Quality conformance inspection of equipment before preparation for delivery: Delete "(See 4.1.2)" and the last sentence.

4.5.1 Group A inspection: Delete this paragraph and substitute the following:

"4.5.1 Group A inspection. - Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table II. Lots shall be formed only from units that pass this inspection. Factors of lot composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, and AQL's indicated in Table II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

4.5.1.1 Order of inspection within Group A. - Group A inspection shall be performed in the order listed in Table II."

Page 14

Delete TABLE II Lot Formation

Replace TABLE III with the following:

TABLE II - Group A Inspection

Inspection	Rqr Para	Insp Para	AQL % Def Major	Minor	
Visual and Mechanical	3.22	4.17	1.0	4.0	
Electrical installation				**	
Power systems and component installation					
Continuity of conductors	3.3.1.1	4.7.1.1			
Dielectric breakdown voltage	3.3.1.2	4.7.1.2			
Insulation resistance	3.3.1.3	4.7.1.3			
Power distributional and operational function	3.3.2	4.7.2 thru 4.7.3.2			
Signal (audio) system wiring and components installation					1.0 for the entire group of power, signal and video wiring and waveguide assemblies
Continuity of conductors	3.3.3.1	4.7.3.1			
Dielectric breakdown voltage	3.3.3.2	4.7.3.2			
Insulation resistance	3.3.3.3	4.7.3.3			
Video and radio frequency (RF), system wiring and components installation					
Continuity of conductors	3.3.4.1	4.7.4.1			
Dielectric breakdown voltage	3.3.4.2	4.7.4.2			
Insulation resistance	3.3.4.3	4.7.4.3			
VSWR	3.3.4.4	4.7.4.4			

** All defects are major

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

Page 15

4.5.2 Group B inspection. - Delete this paragraph and substitute the following:

"4.5.2 Group B inspection. - Group B inspection shall normally be performed on inspection lots that have passed Group A inspection, except for Interchangeability and Mounting Insert Inspections which are performed prior to Group A. This inspection shall conform to Table III and to the special inspection levels of Table I of MIL-STD-105."

4.5.2.1 Group B sampling plans. - Replace "TABLE IV" with "TABLE III."

Page 16

4.5.2.2 Order of inspection within Group B. - Delete "in which they appear" and substitute "listed in TABLE III."

Change table number from "TABLE IV" to "TABLE III" and add the following note to TABLE III Group B inspection:

"NOTE: The order of inspection of Group B with respect to Groups A and C shall conform to the order specified in 4.3. The order of inspection within Group B shall be as in 4.5.2.2."

4.5.3 Group C Inspection. - In this paragraph in title of Group C Inspection Table and in note at bottom of table, change "TABLE V" to "TABLE IV".

Page 17

4.5.3.2 Change title of paragraph from "Sampling for inspection of construction evaluation" to "Sampling for inspection of construction verification."

4.5.3.5 Delete this paragraph and replace with the following:

"4.5.3.5 Group C failures. - Actions required relative to Group C failures shall be as specified in the contract or purchase order."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

Page 18

4.5.4 In first line delete "Group B and", in third line delete "Group B" and "or both," and in fourth line change "Group C" to "Group A".

Page 20

4.7.1.1 Continuity of conductors. - In first sentence delete "which meets" and substitute "tests to meet".

Page 21

4.7.1.2 Dielectric breakdown voltage. - In first sentence delete "which meets" and substitute "to meet".

Page 22

4.7.1.3 Insulation resistance. - In first sentence delete "which meets" and substitute "tests to meet".

Page 26

4.7.3.1 Continuity of conductors. - In first sentence delete "which meets" and substitute "tests to Meet".

Page 29

4.7.3.2 Dielectric breakdown voltage. - In first sentence delete "which meets" and substitute "to meet".

Page 30

4.7.3.3 Insulation resistance. - In first sentence delete "which meets" and substitute "tests to meet".

Page 31

4.7.4 Change to the following:

"4.7.4 Video and radio frequency (RF) system wiring and components installation."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

4.7.4.1 Continuity of conductors. - In first sentence delete "which meets" and substitute "tests to meet".

Change "TABLE VI" to "TABLE V".

Page 32

4.7.4.2 Dielectric breakdown voltage. - In first sentence delete "which meets" and substitute "to meet".

Page 33

4.7.4.3.a Change "4.7.4.2.a" to "4.7.4.2.c".

Page 46

4.10 Change title to "Rail transportation test", in sixth line add "(contractor furnished)" after slings, and add after the sentence ending in line fifteen, the following new sentence - "All cars shall have standard (rigid) draft gear".

Page 47

4.10.1 Test flatcar. - In line seven delete "power" and in line ten delete "not".

4.10.2.a Delete "springly" and substitute "springy".

Page 51

4.14 Mounting insert tests. - Replace "Preproduction " with "First article" in 4.14.1 and table.

Change "TABLE VII" to "TABLE VI".

Page 52

Change "TABLE VIII" to TABLE VII".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.

In table add the following to major defects:

"13. Center pin of rf cable assemblies improperly crimped or solder, loose or protruding".

Custodian:
Army - EL

Preparing Activity:
Army - EL
Project No. 5820-A596

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:40Z
Check the source to verify that this is the current version before use.