OO-T-1848
AMENDMENT-2
March 13, 1975

SUPERSEDING
OO-T-1848
Interim Amendment-1 (GL)
May 23, 1974

FEDERAL SPECIFICATION

TUNNEL, FINISHING, GARMENT, STEAM ELECTRIC

This amendment, which forms part of Federal Specification OO-T-1848, dated January 30, 1974, was approved by the Commissioner, Federal Supply Service, General Services Administration, for the use of all Federal agencies.

PAGE 2

2.1, under "Military Specification". Add "MIL-T-43853 - Trousers, Men's, Tan 445 (Durable Press)".

PAGE 6

3.5.1 Add to end of paragraph the following sentence: "The temperature of the exterior surfaces shall not exceed 115 F over 25 percent of its area and shall not exceed more than 200 F over 15 percent of its area during tunnel operation and shall be tested as specified in 4.7.2."

3.5.1.1 Delete first sentence in its entirety and substitute: "The interior of the cabinet shall be provided with means for totally exposing garments to steam."

3.5.1.2.1.1 Delete in its entirety and substitute:

"3.5.1.2.1.1 Thermostat and safety controls. The thermostat shall regulate drying air temperature to a maximum of 350 F at the point of entry into the tunnel. Safety disconnect switches shall be provided to prevent operation when machine is being serviced and a high temperature limiting switch shall be provided in the heater circuit. The machine shall be equipped with a hot air thermostat and a circuit breaker or fuse panel. A means shall be provided to indicate tunnel air operating temperature. All controls shall be mounted on the front side of the cabinet."

FSC 3510

Source: https://assist.dla.mil -- Downloaded: 202610-26T12:01Z
Check the source to verify that this is the current version before use.

PAGE 7

3.6 Delete in its entirety and substitute:

"3.6 Performance. When tested as specified in 4.7.1, the tunnel shall be capable of processing the required number of garments per hour as indicated in table I. Fabric appearance in the dried and finished garments shall be wrinkle free and approximate 4.0 durable press rating when compared with applicable AATCC Durable Press Fabric Appearance Replicas."

Table I Delete in its entirety and substitute:

"TABLE I. Capacity

	Garments Per Hour		
		Type I	Type II
Size	(30 min) Wet (35 ± 5% moisture	Damp (lightly extracted) (20 ± 5% moisture)	Dry (5 ± 1% moisture)
1	-	-	100
2	-	-	250
3	120	180	800
4	180	270	1200
5	400	600	1800

PAGE 12

4.7.1 Delete in its entirety and substitute:

"4.7.1 Functional test. Tunnels furnished under this specification shall be connected to necessary utility services and operated with laundered and/or dry cleaned garments for 2 hours through complete steaming and drying cycles at the machine's rated capacity. Performance characteristics of the machine shall be determined with laundered and/or dry cleaned garments in the following manner: Fifty garments manufactured in accordance with MIL-T-43853 - Trousers, Men's, Tan 445, Durable Press, Class 1 (50/50 polyester/cotton - 6.0 oz. per sq. yd.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

shall be weighed under ambient conditions to the nearest ounce. The weighed garments shall then be saturated in the following manner:

TABLE III. Test sample

Operation	Time Minutes	Water Level	Temperature Degrees F	Supplies/100 lbs. Synthetic Detergent 1/
Suds	5	High	140	16 oz. (by volume)
Rinse	3	High	125	None
Rinse	3	High	110	None
Rinse	3	High	90	None

1/Detergent, Laundry, Type II - FSN 7930-252-6979

Equipment used for laundering shall be of such capacity that the load is not greater than 2/3 the rated machine capacity.

For processing wet garments in a Type I tunnel, garment shall be removed from the washer, hung on hangers, allowed to drip for 30 minutes and then processed immediately. Shirts shall be buttoned at one or more places. Trousers shall be hung by the waist with the front closure fastened at the top. Finished garments shall be dried to the extent that no visible evidence of moisture is evident, except for a maximum of two (2) garments per 50 garments.

For processing damp or lightly extracted garments in Type I equipment, the garments shall be removed from the washer and the moisture content reduced by a centrifugal extractor to 20 ± 5 percent of the dry weight of the garments. The extracted garments shall then be hung on hangers for processing. Shirts shall be buttoned at one or more places. Trousers shall be hung by the waist with the front enclosure fastened. Finished garments shall be dried to the extent that no visible evidence of moisture is evident, except for a maximum of two (2) garments per 50 garments.

For processing laundered garments through Type II equipment, the garments shall be laundered and tumble dried at 160 F ± 5 F until dry (5 ± 1 percent moisture). The last five minutes of the drying cycle shall be a cool down period with all drier heat shut-off. The garments shall be immediately removed from the drier and hung on hangers for processing.

Source: https://assist.dla.mil -- Downloaded: 202610-26T12:01Z
Check the source to verify that this is the currentversion before use.

Dry cleaned garments shall be processed through Type II equipment after dry cleaning and deodorizing.

Fabric appearance in the dried and finished garments shall be compared with applicable AATCC Durable Press Fabric Appearance Replicas. Evaluation shall be made by an experienced observer. Inability of the tunnel to meet the hourly capability specified in Table I, or produce garments with the fabric appearance rating specified shall constitute test failure."

4.7.2 Delete and substitute:

"4.7.2 Surface temperature. At an ambient temperature of 80 F, the tunnel shall be operated at the maximum temperature setting for three complete cycles. Using a pyrometer, twenty readings shall be taken on each side and a minimum of ten readings on each end (minimum total of 60 readings). The pyrometer readings shall be spaced approximately 13 inches apart on increments of 18 inches from any corner. When the temperature exceeds 115 F over 25 percent of the total area or is more than 200 F over 15 percent of its area as specified in 3.5.1 the tunnel shall be rejected."

Custodians:

Army - GL
Air Force - 45

User activity:

Navy - MC

Preparing activity:

Army - GL

Civil Agency Coordinating Activities:

GSA - FSS
VA - DMS

Project No. 3510-0250

Source: https://assist.dla.mil -- Downloaded: 202610-26T12:01Z
Check the source to verify that this is the current version before use.