FEDERAL SPECIFICATION

TUNNEL, FINISHING, GARMENT, STEAM ELECTRIC

This specification was approved by the Commissioner, Federal Supply Service, General Services Administration, for the use of all Federal agencies.

1. SCOPE AND CLASSIFICATION

1.1 Scope. This specification covers the requirements for a steam and electrically heated garment finishing tunnel for removing the wrinkles from laundered and drycleaned polyester blend and knit garments.

1.2 Classification.

1.2.1 Types and sizes. Types and size shall be as specified (see table I, 6.2, and 6.5).

Type I - Wet to finished.
Type II - Dry to finished.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

Federal Specifications:

CC-M-636 - Motors, Alternating Current (Fractional Horsepower).
CC-M-641 - Motors, Alternating Current (Integral Horsepower) 200 hp and Smaller).

Federal Standard:

Fed. Std. No. 123 - Marking for Domestic Shipment (Civil Agencies).

FSC 3510

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

(Activities outside the Federal Government may obtain copies of Federal Specifications, Standards, and Handbooks as outlined under General Information in the Index of Federal Specifications and Standards and at the prices indicated in the Index. The Index, which includes cumulative monthly supplements as issued, is for sale on a subscription basis by the Superintendent of Documents, U. S. Government Printing Office, Washington, DC 20402.

(Single copies of this specification and other Federal Specifications required by activities outside the Federal Government for bidding purposes are available without charge from Business Service Centers, at the General Services Administration Regional Office in Boston, New York, Washington, DC, Atlanta, Chicago, Kansas City, MO, Fort Worth, Denver, San Francisco, Los Angeles, and Seattle, WA.

(Federal Government activities may obtain copies of Federal Specifications, Standards, and Handbooks and the Index of Federal Specifications and Standards from established distribution points in their agencies.)

Military Specification:

MIL-L-3153	-	Laundry and Dry-Cleaning Machinery and Equipment (For Fixed Installations), Preparation for Delivery for Domestic and Overseas Shipment.

Military Standards:

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-130	-	Identification Marking of U.S. Military Property.

LAWS AND REGULATIONS

29 CFR 1910	-	OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA) STANDARDS

(The Code of Federal Regulations (CFR) and Federal Register (FR) are for sale on a subscription basis by the Superintendent of Documents, U. S. Government Printing Office, Washington, DC 20402. When indicated, reprints of certain regulations may be obtained from the Federal agency responsible for issuance thereof.)

(Copies of Military Specifications and Standards required by supplier in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless a specific issue is identified, the issue in effect on date of invitation for bids or request for proposal shall apply.

Source: https://assist.dla.mil -- Downloaded: 202610-26T12:01Z
Check the source to verify that this is the currentversion before use.

National Electrical Manufacturers' Association (NEMA) Standards Publication:

ICS - Industrial Controls and Systems (1970)

(Application for copies should be addressed to the National Electrical Manufacturers' Association, 155 East 44th Street, New York, NY 10017.)

National Fire Protection Association (NFPA) Standard:

No. 70 - The National Electrical Code

(Application for copies should be addressed to the National Fire Protection Association, 470 Atlantic Avenue, Boston, MA 02210.)

American Society for Testing and Materials (ASTM) Specifications

A167 - Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet and Strip

A176 - Stainless and Heat-Resisting Chromium Steel, Plate, Sheet and Strip

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

American Iron and Steel Institute (AISI)

Steel Products Manual, Carbon Steel Sheets

Hot Dipped No. 4

(Application for copies should be addressed to the American Iron and Steel Institute, 150 East 42nd Street, New York, NY 10017.)

Technical Manual of the American Association of Textile Chemists and Colorists

(Application for copies of the AATCC Manual should be addressed to the American Association of Textile Chemists and Colorists, Research Triangle Park, Post Office Box 12215, Durham, NC 27709.)

(Technical society and technical association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), the supplier shall furnish a sample of the item to be procured under this specification for first article inspection and approval (see 4.3 and 6.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

3.2 Standard product. The tunnel delivered under this specification shall be the manufacturer's commercial product, except for any changes necessary to comply with specification requirements. All like items furnished on any one contract, including parts and subassemblies thereof shall be new and interchangeable.

3.3 Codes and standards. Tunnels shall comply with the applicable requirements of OSHA 29 CFR 1910 or NEMA No. ICS-1970, and NFPA No. 70.

3.3.1 Compliance. Prior to approval of the first article, if one is submitted, or prior to commencing production, the supplier shall submit to the contracting officer or his authorized representative satisfactory evidence that the tunnel that he proposes to furnish under this specification meet the applicable requirements of OSHA, NEMA No. ICS-1970, and NFPA No. 70.

3.3.1.1 OSHA. Acceptable evidence of meeting the applicable safety and health standards of OSHA shall be a certificate of compliance certifying that the steam tunnels furnished conforms to OSHA Standard 29 CFR 1910.264.

3.3.1.2 NEMA. Acceptable evidence of meeting the requirements of NEMA standards shall be a certificate of compliance that the motor controllers, switches, relays, and time delays, conform to NEMA Standard Publication No. ICS-1970.

3.3.1.3 NFPA. Acceptable evidence of meeting requirements of NFPA standard shall be a certificate of compliance that the tunnel is wired in accordance with NFPA Standard No. 70.

3.4 Materials and components. Materials and components shall be as specified herein. Materials not definitely specified shall be of the quality normally used by the manufacturer in his standard commercial tunnel provided that the completed item complies with all provisions of this specification.

3.4.1 Corrosion-resistant steel. The steel used in the fabrication of the tunnels shall be either stainless steel conforming to requirements of ASTM Specifications A167 or A176, as applicable or a hot dipped low carbon steel conforming to AISI No. 4. Frame members not in contact with steam or hot moist air may be fabricated of hot rolled steel.

3.4.2 Materials for fasteners. Rivets, bolts, screws, nuts, and washers shall be of carbon or alloy steel, except where corrosion-resistant metal is to be fastened, in which case they shall be corrosion-resistant metal. Where dissimilar metals are fastened, bolts, rivets, screws and nuts shall be of corrosion-resistant metal.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

3.4.3 Pipe, tube, fittings, and valves. Pipe, tube, fittings, and valves used for water, steam, and to condensate lines shall comply with accepted plumbing practice.

3.4.4 Conduit, fittings, and electirc wire. Electrical conduit shall be rigid electrical metallic tubing or flexible conduit. When exposed to steam or hot moist air, electrical metallic tubing or liquid tight electrical conduit shall be used. All electrical wire shall be heat-resistant stranded or solid copper, thermo-plastic insulated.

3.4.5 Motors. Motors shall be continuous, drip proof or splash proof type for operation in a 40 degree Centigrade (C) ambient temperature. All motors shall conform to the requirements of CC-M-636 or CC-M-641, as applicable and to the following requirements:

(a) All motors shall have windings impregnated to resist moisture.
(b) Each motor shall have the proper starting characteristics, ample power, and adequate thermal dissipation capacity to comply with requirements specified herein, with a reasonable factor of safety, commensurate with the application and expected duty cycle to which each motor might be subjected under normal operating conditions.
(c) Motors shall be equipped with ball bearings, except that motors of 1/2 horsepower or less when used for horizontal applications may have sleeve bearings.
(d) Motor bearings shall be of permanently lubricated type or shall have adequate and accessible means for lubrication.
(e) Each motor of 1/8 horsepower rating or larger shall be provided with manually reset thermal-overload protection incorporated as a part of the motor or installed in the controller. When a D.C. conveyor drive motor is used, the motor may be protected by fuses.

3.5 Design and construction. The tunnel shall be an inclosed insulated cabinet consisting of one or more compartments or series of cabinets and equipped with a conveyor to which garments can be attached manually to hangers. The conveyor system when activated shall permit the garments to enter the machine in line or in parallel. The tunnel conveyor shall be adaptable for loading and unloading from accessory automatic conveyors or fixed slick rails. The machine shall be furnished complete with all piping, wiring, switches, and controls, ready for installation, or when required the machine may be site assembled.

3.5.1 Cabinet. The cabinet shall consist of an outer shell and inner shell framed by ferrous metal to provide rigid support. The outer shell shall be fabricated from 0.0359-inch thick, minimum, steel or iron and the inner liner from 0.0320-inch thick, minimum, corrosion-resistant metal, as specified in

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

3.4.1, or aluminum that shall not discolor garments. The space between the outer shell and inner liner shall be insulated. The cabinet shall be vented at the top to remove excess steam and heat, and each compartment shall be provided with service access panels. The entrance to the cabinet shall be designed to permit proper alignment of garments and hangers as they enter the cabinet.

3.5.1.1 Steaming. The interior of the cabinet shall be provided with corrosion-resistant steam nozzles or spray heads to totally expose garments to steam. The steaming time shall be adjustable for different weight garments. The steaming process shall be activated by a photo electric cell or other automatic device located at the entrance to the compartment or when garment is in position to receive steam. Means shall be provided to eliminate condensation without use of a floor drain.

3.5.1.1.1 Cabinet, piping. Necessary integral pipe, fittings, condensate traps, pressure reducing valves, and all other valves for steam and drains shall be installed or furnished as complete assemblies suitable for installation with unions or other standard fittings. All steam lines shall be installed to comply with accepted plumbing practice. Installation instructions shall be furnished with uninstalled assemblies.

3.5.1.1.2 Valves and traps, steam. Steam, drain, condensate (with three-valve-by-pass and trap) and other operational valves shall be so installed that they are readily accessible for operation and maintenance.

3.5.1.1.3 Working pressure, steam. Assemblies of pipes, tubes, fittings, heat exchanger, etc., through which steam flows or is consumed shall be designed for a 125 pounds per square inch gage (psig) steam working pressure and shall not leak when tested as specified in 4.7.3.

3.5.1.2 Drying. Shall be accomplished by circulation of air heated by a steam heat exchanger or a combination of electric heaters and steam heat exchanger.

3.5.1.2.1 Electric heat. Electric heat shall be provided by a thermostatically controlled coil or strip type electric heaters.

3.5.1.2.1.1 Thermostat and safety controls. The thermostat shall regulate drying temperature to the optimum processing temperature recommended for the particular fabric being processed and the temperature shall not exceed 300°F. Safety disconnect switches shall be provided to prevent operation when machine is being serviced and a high temperature limiting switch shall be provided in the heater circuit. The machine shall be equipped with a hot air thermostat and a circuit breaker panel or fuse panel. All controls shall be mounted on the front side of the cabinet. The exterior surfaces shall not exceed 115°F over 85 percent of its area and 15 percent shall not exceed 200°F during tunnel operation and shall be tested as specified in 4.7.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

3.5.1.2.2 Steam heat. Steam heat shall be provided by a heat exchanger fabricated from stainless steel or copper and aluminum alloy. Timing and other required controls shall be cabinet mounted.

3.5.2 Conveyor. The conveyor shall transport garments through the tunnel and transfer finished garments to a 5-foot-long drop off section which shall be adaptable to a slickrail or screw type conveyor except when remote sorting is required (see 3.5.4). The conveyor motor shall drive the conveyor, without slippage, when the conveyor is loaded to maximum capacity. The conveyor shall be equipped with a device to prevent damage to conveyor or motor in case of jamming. To permit processing of different weight fabrics, controls shall be provided to change the speed of the conveyor or regulate exposure time of the garments to each tunnel cycle. When specified, the tunnel feed entrance shall be right or left hand feed (see 6.2 and 6.4).

3.5.3 Conveyor loader. When specified (see 6.2), tunnels shall be provided with a conveyor loader to feed garments to the tunnel conveyor.

3.5.4 Automatic remote sorting. When specified (see 6.2), tunnels shall be equipped with an automatic remote sorting feature, connecting conveyor and storage lanes if conveyor loader is not specified. The length of the conveyor, number of storage lanes, distance between the lanes and length of the lanes shall be as specified (see 6.2).

3.6 Performance. When tested as specified in 4.7.1, the tunnel shall be capable of processing the required number of garments per hour (see table I) containing not more than 35 ± 5 percent of their dry weight in moisture for the type I tunnel, and not more than 5 ± 1 percent for the type II tunnel. Garments to be processed shall be laundered or drycleaned in accordance with standard procedures for polyester blend garments. Garments after processing shall have an overall appearance rating of 4.0, a seam appearance of 3.5 and a crease retention rating of 4.0, when examined as specified in 4.7.1.

TABLE I.

	Hourly Capability		
		Type I	Type II
Size	Wet (dripping)	Damp (lightly extracted)	Dry
1	150	180	1000
2	200-300	320-500	900-1200
3	400-500*	1500	2000
4	800-900**	3000	3000

*w/o auxiliary dryer.
**w/auxiliary dryer.

Source: https://assist.dla.mil -- Downloaded: 202640-26T12:01Z
Check the source to verify that this is the current version before use.

3.7 Electrical characteristics. The electrical parts of the tunnel shall be suitable for the voltage, frequency, and number of phases for alternating current (AC) or voltage for direct current (DC) as specified (see 6.2).

3.8 Finish. Unless otherwise specified (see 6.2), the exterior surface of the tunnel shall be finished according to the manufacturer's standard commercial practice. The interior surface, when fabricated from galvanized steel as specified in 3.4.1 shall be phosphatized, baked epoxy primed and finished with one coat of baked enamel. In addition, emergency stop and normal stop push buttons shall be red, and the red shall be limited to stop push buttons. The color of the start push buttons shall be in accordance with the manufacturer's standard commercial practice.

3.8.1 Exposed corrosion-resistant metals. Stainless steel and plated metal shall be free from scale.

3.9 Identification marking. For Military procurements each item of equipment and replacement part covered by this specification shall be marked for identification in accordance with MIL-STD-130. For civil agency procurements, marking may be in accordance with the manufacturer's standard practice provided the items are legibly and permanently marked with the manufacturer's name or trademark of such known character that the source of manufacture may be determined and contains the type and size of the item, and the electrical characteristics, as applicable.

3.10 Workmanship. The completely fabricated item shall be free from defects such as fractures, splits, punctures, tears, dents, creases, bows, miscasts, deteriorations, or malformations. There shall be no sharp edges, burrs, or slivers.

3.10.1 Application of finish. The finish supplied to the end item shall be continuous, smooth, adherent, have no imbedded foreign matter, and contain no sags, runs, drips, creeps, laps, bubbles, or streaks. No rust or toolmarks shall show through the coating.

3.10.2 Welding and brazing. All surfaces of parts to be welded or brazed shall be clean. Welding and brazing shall be accomplished in a manner to prevent the occurrence of burn holes, cracks, fractures, or incomplete fusion. All scale and flux deposits shall be removed from finished welds.

3.10.3 Soldering. Soldering shall be complete and adherent with all flux and residue removed and shall contain no pinholes.

3.10.4 Threaded fasteners. Threaded fasteners shall not be broken, stripped, fractured, or loose.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

3.10.5 Rivets. Rivets shall be driven to completely fill the holes, with full size heads finished and in full contact with the surface of the riveted members, and shall not be loose.

3.10.6 Electrical wiring. Wiring shall not be cut, abraded, or have excess insulation stripped, and shall be securely joined at terminals. Wiring shall have slack to provide strain relief.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and service conform to prescribed requirements.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

1. First article inspection (see 4.3).
2. Quality conformance inspection (see 4.4).

4.3 First article. When a first article is required, the tunnel shall be examined for defects in table II and specified dimensions and tested as specified in 4.7.1, 4.7.2, and 4.7.3. The presence of any visual, dimensional defect or failure of any test shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Except as otherwise specified herein, sampling for inspection shall be performed in accordance with the provisions set forth in MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1 above, components and materials shall be inspected and tested in accordance with all the requirements of referenced specifications, drawings and standards unless otherwise excluded, amended, modified or qualified in this specification or applicable purchase document.

4.4.2 End item inspection. The inspection lot shall be all tunnels offered for inspection at one time.

4.4.2.1 Visual inspection. The tunnel shall be examined for the defects in table II. The inspection level shall be II with an AQL (acceptable quality level) of 2.5 for major defects and 6.5 for total defects, expressed in terms of defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

TABLE II. Classification of defects

Examine	Defect	Classification Major	Classification Minor
Finish	Not finished where required	X	
	Not color specified (if other than manufacturer's standard)		X
	Scale on stainless steel or plated metal		X
	Emergency stop and normal stop push buttons not red	X	
	Color red used on other than stop push buttons	X	
	Not continuous, smooth, adherent, imbedded foreign matter, has sags, runs, drips, creeps, laps, bubbles, or streaks (painted components)		X
	Rust or toolmarks		X
	Not stainless or corrosion-resistant metal where specified	X	
Construction	Any component missing or not specified type	X	
	Any component split, punctured, torn, dented, creased, deteriorated, or malformed	X	
	Sharp burr, sliver, or sharp edge	X	
	Push button not protected or recessed	X	
	Push button control stations not convenient to operator	X	
	Any functioning component that requires abnormal force to operate	X	
Welding and brazing (where applicable)	Missing, incomplete, burn holes, fractured, or not fused	X	
	Slag inclusion, undercut, not smooth and uniform, or deposit of scale and flux not removed	X	
Soldering (where applicable)	Missing, incomplete, or not adherent	X	
	Not clean, (flux or residue not removed) or contains pinholes		X
Threaded fasteners	Broken, stripped, or fractured	X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

TABLE II. Classification of defects (cont'd)

Examine	Defect	Classification Major	Classification Minor
Construction (cont'd)			
Rivets	Broken, not peened, or not peened sufficiently	X	
	Rivets loose		X
Electrical apparatus wiring	Wiring cut, abraded, insulation stripped, not joined, or loose at terminal	X	
	Not inclosed in specified conduit, where required	X	
	Wiring not terminated in junction box	X	
	Slack not provided for wiring to relieve strain		X
Piping, tubing, fittings and valves	Improperly connected or installed, (threads stripped, leaks)	X	
Gages and instruments	Not properly mounted or no means for adjustment	X	
Lubrication	Not lubricated where required		X
	Excessive lubrications		X
	Fitting not accessible for lubrication	X	
Marking for identification	Missing, incomplete, illegible, not specified type or size, or not in proper location		X

4.4.2.2 Dimensional examination. The tunnels shall be examined for compliance with dimensions specified. Any dimensions not within this specification tolerance shall be a defect. The inspection level shall be S-2 with an AQL of 4.0 defects, expressed in terms of defects per hundred units.

4.4.2.3 End item testing. When a first article is not required, the first produced tunnel shall be examined and tested as specified in 4.7.1, 4.7.2 and 4.7.3. Each sample tunnel shall be tested as specified in 4.7.1, 4.7.2 and 4.7.3. Failure to pass a test shall be cause for rejection of the inspection lot. The inspection level shall be S-2 with an AQL of 2.5 defects, expressed as defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

4.5 Code and standard examination. Certificate of compliance, certified test reports, approval labels or listing marks for codes and standards, as applicable, that are submitted as proof of compliance with specification requirements shall be examined and validated.

4.6 Examination of preparation for delivery. Examination of preparation for delivery shall be in accordance with MIL-L-3153.

4.7 Tests.

4.7.1 Functional test. Tunnels furnished under the specification shall be connected to necessary utility services and operated with laundered and/or dry cleaned garments, having a minimum weight of 5 ounces per square yard, for 2 hours through complete steaming and drying cycles at the machine's maximum capacity. Inability of the tunnels to meet the hourly capability specified in table I, or produce garments with ratings specified in 3.6 shall constitute test failure. The garments used in the test of the type I tunnel after washing and then a light extract cycle or after washing and allowed to drip for 30 minutes shall be processed immediately. The garments used in the test of the type II tunnel after washing, extracting tumbling dry or drycleaning and tumbling dry shall be examined using lighting procedures, apparatus, and photographic standards in accordance with American Association of Textile Chemists and Colorists Manual (AATCC).

4.7.2 Surface temperature. At an ambient temperature of 80°F., the tunnel shall be operated at the maximum temperature setting for three complete cycles. Using a pyrometer, twenty readings shall then be taken on each side and both ends (total of 80 readings). The pyrometer settings shall be spaced approximately 18 inches apart and 18 inches from any edge. When more than 15 readings from all surfaces are in excess of 155°F., the total area of excessive heat (116°F to 200°F) shall be calculated and the area percentage obtained by dividing total tunnel surface area into the excessive heat surface area. When the area of excessive heat is greater than 15 percent of the total area or when any reading is greater than 200°F. as specified in 3.5.1.2.1.1, the tunnel shall be rejected.

4.7.3 Hydrostatic pressure. Assemblies of pipe, tubes, fittings, heat exchanger shall be subjected to a hydrostatic pressure based on a working pressure of 125 psig, for ten minutes. Inability of the assemblies to meet the requirements of 3.5.1.1.3 shall constitute failure of the test.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging and packing. Preservation, packaging and packing shall be in accordance with levels A, B, and C requirements of MIL-L-3153, as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

5.2 Marking.

5.2.1 Civilian agencies. In addition to any special marking required by the contract or order (see 6.2), interior packages and shipping containers shall be marked in accordance with Fed. Std. No. 123.

5.2.2 Military agencies. In addition to any special marking required by the contract or order (see 6.2), interior packages and shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The tunnels and accessory conveyors covered by this specification are intended for use in fixed laundries and drycleaning plants for finishing (removal of wrinkles) of polyester blend and knit fabrics.

6.2 Ordering data. Purchasers should select the preferred options permitted herein and include the following information in procurement documents:

(a) Title, number, and date of this specification.
(b) Type and size tunnel required (see 1.2.1).
(c) First article (see 3.1, 4.3 and 6.3).
(d) Whether feed entrance to machine is to be right or left hand (see 3.5.2 and 6.4).
(e) When a conveyor loader is required (see 3.5.3).
(f) When automatic remote sorting is required (see 3.5.4). (NOTE: Remote sorting is not available when a conveyor loader is required.)
(g) Length of conveyor, number and length of storage lanes and distance between lanes (see 3.5.4).
(h) Electrical characteristics required (voltage, phase, cycles) (see 3.7).
(i) Finish when other than specified (see 3.8).
(j) Levels of preservation, packaging and packing required (see 5.1).
(k) Special marking when required (see 5.2.1 and 5.2.2).

6.2.1 Contract data requirements. Any data items to be delivered under any contract for items covered by this specification should be specifically called for in the contract in accordance with the applicable regulations of the procuring activity.

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of ASPR 7-104.55. The first article should be a preproduction sample, initial production item or other specific item described under the definition of a first article in the ASPR. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in all procurement instruments regarding arrangements for inspection and approval of the first article.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:01Z
Check the source to verify that this is the current version before use.

6.4 Location of feeding side. The location of the feeding side is determined when facing the feed/receiving end of the machine.

6.5 Type I - For processing wet (laundered and/or laundered and lightly extracted) to finished garments.

Type II - For processing dry (tumble dried) to finished garments.

6.6 Successful commercial application. Invitation for bids should specify that no item of equipment shall be acceptable unless the manufacturer has had equipment of approximately the same type and design as that specified operating successfully in a commercial or institutional laundry or laundries for at least one year. Equipment installed for test purposes in a manufacturer's plant or laboratory shall not come within the category of successful commercial application.

Custodians:

Army - GL
Navy - MC
Air Force - 45

User activities:

Navy - YD, SH

Preparing activity:

Army - GL

Civil Agency Coordinating Activity

GSA-FSS
VA - DMS

Project No. 3510-0238

Source: https://assist.dla.mil -- Downloaded: 202610-26T12:01Z
Check the source to verify that this is the current version before use.