MIL-F-52569B(ME)
21 October 1980
SUPERSEDING
MIL-F-52569A(ME)
22 October 1971

MILITARY SPECIFICATION

FOOTWALK ASSEMBLY: ALUMINUM,

FOR BRIDGE, BAILEY

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers an aluminum footwalk for the Bailey fixed bridge.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

QQ-S-781	- Strapping, Steel and Seals.
PPP-T-97	- Tape, Pressure-Sensitive Adhesive, Filament Reinforced.

MILITARY

MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-16173	- Corrosion Preventive Compound, Solvent Cutback, Cold-Application.

FSC 5420

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

DRAWINGS

ME

TA13205E5395	- Footwalk Assembly: Aluminum, for Bridge, Bailey.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN WELDING SOCIETY (AWS)

A5.10 - Aluminum-Alloy Welding Rods and Bare Electrodes.

(Application for copies should be addressed to the American Welding Society, 2501 N.W. 7th Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, United Engineering Center, 345 East 47th Street, New York, NY 10017.)

3. REQUIREMENTS

3.1 Description. The footwalk assembly shall be as shown on TA13205E5395 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. No deviations from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the currentversion before use.

Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The contractor shall furnish two footwalk assemblies for examination and testing within the time frame specified to prove, prior to starting production, that his production methods will produce footwalk assemblies that comply with the requirements of this specification. One footwalk assembly shall be complete with painting, stenciling, and die stamping and the other footwalk assembly shall be complete, but shall only have the necessary prime coat of paint specified. Examination and test shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Material not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.4 Welding electrodes. Welding electrodes for aluminum shall conform to AWS A5.10, classification ER4043, size as required.

3.5 Identification marking. The footwalk assembly shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The footwalk assembly, except the bridge pin retainer, shall be cleaned, treated, and painted as specified on the drawings. The bridge pin retainer shall be coated with a corrosion-preventive solvent cutback coating, hard film type, conforming to MIL-C-16173, grade 1.

3.7 Stenciling. The nomenclature, national stock number, weight, and cube shall be stenciled on each component. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Marking shall be Gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704.

3.8 Workmanship.

3.8.1 Aluminum fabrication. Aluminum used in the fabrication of the footwalk assembly shall be free from kinks and sharp bends. Straightening of material shall be done by methods that will not cause injury to the metal. Surfaces and edges of all finished members shall be smooth and free from kinks, bends, and winds. All bends of a major character shall be made with metal dies or fixtures to insure uniformity of size and shape. Sharp instruments shall not be used for marking bend lines. Aluminum shall not be cut by methods using heat. Aluminum less than 3/8 inch thick may be cut by shearing; aluminum 3/8 inch thick and over shall be cut by routing or by high-speed saws. Shearing and sawing shall be done neatly and accurately.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

3.8.2 Jigs and fixtures. Components and parts of the assembly shall be assembled in jigs or fixtures and joined while held in position. Jigs or fixtures shall be designed to prevent distortion or to limit the distortion to an amount that can be removed by straightening and stress relieving without changing the physical characteristics of the metal.

3.8.3 Welders and welding.

3.8.3.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by the following listed code for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined by the code:

Welding Qualifications of the ASME Boiler and Pressure Vessel Code (Section IX).

3.8.3.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of part B, Section IX (Welding Qualifications) of the ASME Boiler and Pressure Vessel Code. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wire brushed clean. Aluminum members to be welded may be preheated for welding to a temperature of not more than 400° F. Aluminum welds may be filed, wire brushed, or chipped but shall not be hammered.

3.8.4 Interchangeability. Components and parts of like description shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

3.8.5 Assembly. The footwalk assemblies shall be capable of being joined together properly by means of the brackets without any misfit.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsiblity for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

4.1.2 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Supplementary Quality Assurance Provisions (SQAP) shown on the drawings. The drawings specify the characteristics requiring SQAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.4 and 6.5).

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of packaging (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction footwalk assembly shall be examined for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The preproduction footwalk assemblies shall be tested as specified in 4.5.2. Failure of the test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

4.5 Inspection procedure.

4.5.1 Examination. The footwalk assembly shall be examined as specified herein for the following defects:

Major

101. Any part or component not in accordance with the SQAP requirements as shown on the drawings.
102. Material not as specified.
103. Components missing or not as specified.
104. Workmanship not as specified.
105. Weld defects such as flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusion with parent metal.

Minor

201. Dimensions other than those identified by SQAP data not as specified.
202. Identification marking incorrect, missing or illegible.
203. Treatment and painting not as specified.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:25Z
Check the source to verify that this is the current version before use.

4.5.2 Test. The two footwalk assemblies shall be joined together by means of the brackets. Failure to assemble properly without any misfit shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection of pack.

4.6.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Samples selected in accordance with 4.6.1.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

106.	Materials not as specified for level A.	Each incorrect material shall be considered one defect.
107.	Bridge pin retainers and locking brackets not secured together and attached to footwalk as specified for level A.	
108.	Quantity per bundle not as specified for level A.	
109.	Bundling not as specified for level A.	
110.	Wood strips not as specified and placed under the two end straps on bundles for level A.	
111.	Strapping not as specified for level A.	
112.	Marking missing, illegible, incorrect, or incomplete for level A or commercial.	

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Preservation. The footwalk assembly, cleaned, treated and painted as specified on the drawings and the bridge pin retainers coated as specified in 3.6 shall not require additional preservation.

5.1.1.2 Bridge pin retainers and locking brackets. Two bridge pin retainers shall be secured to each leg of the two locking brackets with tape conforming to PPP-T-97, type IV, size 3/4 inch. They shall then be secured to the underside of the end grating of the footwalk with soft annealed wire by passing the wire through the holes on the brackets and the grating.

5.1.2 Commercial. The component parts of the footwalk assemblies shall be preserved in accordance with MIL-STD-1188.

5.2 Packing. Packing shall be level A or commercial as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

5.2.1 Level A. Eight footwalk assemblies preserved as specified in 5.1, shall be bundled together using not less than four flat steel straps. The two end straps shall be placed adjacent to the end block and full 1-inch by 2-inch wood strips the same height as the bundle shall be placed under the straps. Two intermediate straps, without the wood strips, shall be placed equal distances between the end straps. The strapping shall conform to QQ-S-781, type I or IV, regular duty, finish B, size 3/4 inch by 0.035 inches.

5.2.2 Commercial. The footwalk assemblies, preserved as specified in 5.1, shall be packed in accordance with MIL-STD-1188.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection shall be in accordance with MIL-STD-129.

5.3.2 Commercial. Marking for commercial packaging shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Inteneded use. The footwalk assemblies are intended to be used outside the trusses on the Bailey bridge to provide a walkway for pedestrian traffic.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of specification.
(b) Time frame required for submission of preproduction model (see 3.2).
(c) Degree of preservation and degree of packing required (see 5.1 and 5.2).

6.3 Preproduction model. Any changes or deviations of production footwalk assemblies from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish footwalk assemblies conforming to this specification.

6.4 Supplementary quality assurance provisions (SQAP). The contracting officer should require the contractor to maintain records of all SQAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified SQAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

6.5 Definitions.

6.5.1 Supplementary quality assurance provisions (SQAP). A SQAP is a contractual requirement that supplements Section 4 of the specification. SQAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.6 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.3).

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A315

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-F-52569B(ME) Footwalk Assembly: Aluminum, for Bridge, Bailey

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:25Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID

U.S.MAIL

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research and
Development Command
DRDME-DS
Fort Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.