MIL-F-60323A (PA)
AMENDMENT 3
1 April 1975
SUPERSEDING
AMENDMENT 2
26 August 1974

MILITARY SPECIFICATION

FUZE, PD, M525, M526 AND M527B1
LESS HEAD ASSEMBLY
METAL PARTS FOR

This Amendment forms a part of Military Specification MIL-F-60323A (MU), 20 October 1971, and is approved for use by all Departments and Agencies of the Department of Defense.

1. Page 1, Paragraph 2.1 - Delete:

"MIL-F-22191 - Films, Transparent, Flexible, Heat Sealed for packaging applications"

Substitute:

"MIL-B-22191 - Barrier Materials, Transparent, Flexible, Heat-Sealable"

2. Page 2, PUBLICATIONS Section - Delete:

"PUBLICATIONS

ORDNANCE CORPS

IEL-8802176 - Index of Inspection Equipment Lists for Fuze, Point Detonating, M525
ET - 9201391- Index of Inspection Equipment Lists for Fuze, Point Detonating, M526
IEL-9200698 - Index of Inspection Equipment Lists for Fuze, Point Detonating, M527B1

Substitute:

"HANDBOOKS

MIL-HDBK-204 - Inspection Equipment Design"

FSC: 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:29Z
Check the source to verify that this is the current version before use.

3. Page 3, Paragraph 3.4.2.2 - Delete in its entirety and substitute:

"3.4.2.2 Horizontal - There shall be no pore exceeding 1/32 inch or no more than two pores of size ranging between 1/64 to 1/32 inch within 1/32 inch from extremities of the slider guide pin or setback cavities when sectioned as specified in Paragraph 4.4.2.2."

4. Page 7, Paragraph 4.3.2.1, Characteristic 210 - Delete: "max." and substitute: "min."

5. Page 7, Paragraph 4.3.2.1 - Add:

"227. Concentricity of slider plug counterbore to thread. . . . . Gage"

6. Page 7, Paragraph 4.3.2.1 - Add:

"228. Perpendicularity of shell thread to shoulder . . . . Gage"

7. Page 8, Paragraph 4.3.2.3, Major Category - Delete: "None defined" and substitute:

"Major: AQL 0.40 Percent
101. Screw driver slot missing or shallow to the extent of not being usable . . . . . Visual"

8. Page 8, Paragraph 4.3.2.3, Minor Category - Delete Minor 207 in its entirety and substitute:

"207. Concentricity of cap outside diameter to thread . . . . . Gage"

9. Page 9 - Delete "4.3.7" and substitute "4.3.2.7".

10. Page 16, Paragraph 4.3.4 - Delete in its entirety and substitute:

"4.3.4 Inspection Equipment. - The inspection equipment required to perform the examinations and tests prescribed herein is described in the "Method of Inspection" column starting with Paragraph 4.3.2.1 and the "Test Methods and Procedures" section starting with Paragraph 4.4.1. The contractor shall submit for approval inspection equipment designs in accordance with the terms of the contract. See Section 6."

11. Page 16, Paragraph 4.3.4.1 - Delete "IEL and ET" and substitute: "contract".

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:29Z
Check the source to verify that this is the current version before use.

12. Page 19, Paragraph 5.1.1.5 - Delete: "Ten thousand (10,000) cups" and substitute: "Twenty thousand (20,000) cups".

13. Page 21, Paragraph 6.2 - Delete Paragraph 6.2 in its entirety and substitute the following:

"6.2 Inspection Equipment Designs. - Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) and contractor designs. SIE designs are designated by drawing number in the "Method of Inspection" column starting with Paragraph 4.3.2.1 or the "Test Methods and Procedures" section starting with Paragraph 4.4.1. Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.2.2 and 6.2.3 should he elect to do so."

14. Page 21, Paragraph 6.2.1 - Delete Paragraph 6.2.1 in its entirety and substitute the following:

"6.2.1 SIE Designs. - SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein."

15. Page 21, Paragraph 6.2.2 - Delete Paragraph 6.2.2 in its entirety and substitute the following:

"6.2.2 Contractor Designs. - Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:29Z
Check the source to verify that this is the current version before use.

(Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public). Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.2.1.c.). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204 "Inspection Equipment Design" for guidance. The specification number and paragraph number shall be referenced on each contractor design, together with the component or assembly drawing number, revision letter and date to which the specific design applies."

16. Page 21, Paragraph 6.2.3 - Delete Paragraph 6.2.3 in its entirety and substitute the following:

"6.2.3 Submission of Designs for Approval. - Contractor designs shall be approved by the Government prior to fabrication or procuring equipment. Designs shall be submitted for approval in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements Lists (DD Form 1423). Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs and the required delivery schedule as stipulated in the contract. The specific segment of Picatinny Arsenal to which designs shall be sent is SARPA-QA-T."

17. Page 22, Paragraph 6.2.4 - Delete Paragraph 6.2.4 in its entirety.

18. Page 22, Paragraph 6.2.5 - Delete Paragraph 6.2.5 in its entirety.

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 1390-A-091

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:29Z
Check the source to verify that this is the current version before use.