14 MAY 1987

MILITARY SPECIFICATION

MAINTENANCE PLATFORM, AIRCRAFT

"This specification is approved for use within the Department of the Air Force and is available for use by all Departments and Agencies of the Department of Defense.

1 SCOPE

1.1 Scope. This Specification provides the criteria for the design, construction and testing of an Aircraft Maintenance Platform.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications standards, and handbooks. Unless otherwise specified. the following specifications. standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation form a part of this specification to the extent specified herein,

SPECIFICATIONS

MILITARY

MIL-S-8512	Support Equipment, Aeronautical, Special, General specification for the Design of
MIL-M-8090	Mobility Requirements, Ground Support Equipment, General Specification for
MIL-S-81733	Sealing & Coating Compound, Corrosion Inhabitive
MIL-W-5044	Walk Way Compound Nonslip

STANDARDS

FEDERAL

FED-STD-595	Colors

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: San Antonio ALC/MMEDO, Kelly AFB, TX 78241-5990 by using the self-addressed Standardization Document Improvement Proposal ((DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 1730

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-STD-130	Identification Marking of US Military Property
MIL-STD-143	Standards & Specifications. Order of Precedence for the Selection of
MIL-STD-162	Materials Handling Equipment; Preparation for Shipment, Storage, Cyclic Maintenance, Routine Testing & Processing
MIL-STD-808	Finishes Protective, & Codes for Finishing Schemes for Ground & Ground Support Equipment
MIL-STD-882	System Safety Program for Systems Assoicated Subsystems and Equipment Requirements for
MIL-STD-889	Dissimilar Metals
MIL-STD-1472	Human Engineering Design Criteria for Military Systems, Equipment & Facilities
MIL-STD-1595	Test, Aircraft, Missile and Aerospace Welders Qualification.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues shall be those in effect on the date of the solicitation.

DRAWINGS

Air Force 7747223	Space Envelope, B-52 Dragchute Installation Platform

PUBLICATIONS

Air Force Technical Orders
35-1-3

2.2 Other publications . The following document(s) form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DODISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS shall be the issue of the nongovernment documents which is current on the date of soliciaton

Boeing Company 24-1071	B-52G Loft Data
34-1800	B-52H Loft Data

(Applicatlon for copies should be addressed to the Boeing Company, 7755 E. Marginal Way, P.O. Box 3707, Seattle WA 98124).

(Nongovernment standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services,)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

2.3 Order of precedence, In the event of a conflict between the test of this specification and the references cited herein (except for associated detail specifications , specification sheets or MS standards) , the text of this specification shall take precedence, Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3* REQUIREMENTS

3.1 First Article. This specification makes provisions for the First Article (reproduction) Testing (see 4.4).

3.2 Selection of Specifications & Standards. Specifications and standards for necessary commodities and services not specified herein shall be selected in accordance with MIL-STD-143.

3.2.1 Commercial parts. Commercial parts having suitable properties may be used where , on the date of invitation for bids, there are no suitable standard parts. In any case, commercial utility parts, such as screws, bolts, nuts and cotter pins having suitable properties may be used provided:

a. They can be replaced by the standard parts (MS or AN) without alteration.

b. The corresponding standard part numbers are referenced in the parts list

3.2.2 Standard Parts. With the exception of 3.2.1. MS or AN standard parts shall be used where they suit the purpose,

3.3 Materials

3,3.1 Metals. Metals shall be of the 6061-T6 aluminum type or suitable treated to resist corrosion due to fuels, salt spray, or atmospheric conditions likely to be met in storage or normal service, When materials are used that are subject to corrosion, they shall be protected against such corrosion in a manner that will in no way prevent compliance with the performance requirements specified herein. The use of any protection coating that will crack, chip, or scale with age or extremes of atmospheric conditions shall be avoided.

3.3.2 Dissimilar Metals. Unless suitably protected against electrolytic corrosion, dissimilar metals shall not be used in intimate contact with each other. Dissimilar metals are defined in MIL-STD-889.

3.4 Design & Construction. The design and construction of the maintenance platform shall Incorporate the various performance requirements together with the features specified herein. The maintenance platform shall be designed to the requirements of MIL-S-8512 and MIL-STD-1472. Design must include use of standard commercial components to the extent that replaceable item equivalents be available during the expected 20 years service life of the platform. It shall be built to withstand the jars, strains, vibrations and other conditions incident to shipping, storage and service. Stress calculations shall be submitted to show compliance with MIL-S-8512. The main frame shall be of 6061-T6 aluminum cross-sections and shall be mainly pinned (fittings, rivets, bolts, clamps) construction with the least possible welds.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

3.4.1 Maintenance Platform Design (General). The maintenance platforms shall be designed to meet the Working Level Heights depicted by USAF drawing number 7747223 and all other design features specified herein. The maintenance platform shall be mobile and must be designed to be easily moved by three average size individuals. The maintenance platform weight shall not exceed 2800 pounds and its towbar will be designed to allow one man to lift it from the ground with a maximum force of 20 pounds. The maximum force required to start moving the platform from rest shall not exceed 60 pounds force. All internal structural members adjacent to the upper platform cut-out and the interior side of the lower platform shall be inset to allow at least 10 inch clearance between aircraft and stand structure to preclude inadvertent contact of stand structure and aircraft. There shall be two working levels, Upper, and Lower.

3.4,1,1 Upper Level Floor. The upper level floor shall provide adequate working area to safely install the dragchute. The floor elevation and fuselage cut-out size and configuration shall be as shown in USAF drawing 7747223 and shall meet the following requirements:

a. A fuselage cut-out shall be provided to accommodate the tail end of the B-52 H model symmetrically from the platform rear. There shall be a working floor area on both sides of the aircraft extending up to fuselage station 1824 shown in USAF Drawing 7747223 and having a minimum width of 42 inches.

b. A removable saddle contoured adapter is required for use with the B-52G aircraft. The adapter shall easily be mounted and removed and shall reduce cut-out depth by five inches at the tail end of the cut-out. The adapter is to prevent the front end of the upper floor from contacting the ALQ-117 antenna fairings.

c. Boeing Company drawings 24-1071 and 34-1800 provide tail loft data for B-52 G & H models respectively.

d. The cut-out shall allow clearance to install bumper specified in paragraph 3.4.9 and a three inch clearance between the bumnper and the aircraft.

e. A 30 inch minimum walk way width shall be provided to allow personnel to walk around the tail end of the aircraft.

f. A 24 X 30 inch staircase landing shall be provided on the upper floor forward end.

g. A folding floor panel is required on the platform rear right (aircraft left side) to clear pneumatic system access door opening and dragchute door handcrank rotation and to allow headroom when cranking from lower level floor. The floor panel shall meet the following requirements:

(1) Provide a five inch hand clearance for dragchute door handcrank turning.

(2) Provide enough clearance to open and close pneumatic system access door when platform bumpers are against fuselage side.

(3) The middle horizontal handrail behind the folding floor panel shall be at an elevation to allow a five inch hand clearance for swinging the folding floor panel to and from its opened position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

(4) A stop mounted on the handrail behind the folding floor panel shall be provided to support the door in its opened position. The stop shall be made of angle iron at least .25 inches thick. A positive lock shall be provided in the opened or closed position.

(5) A ladder grab handle shall be provided on the upper deck contour side next to the klckplate and forward of the folding floor panel. The handle shall be similar to the lift handle on folding floor panel. The handle shall be sturdy enough to support 200 pounds without bending or breaking.

3.4.1.2 Lower Level Floor. The lower level floor shall provide adequate working area to safely operate the dragchute door handcrank and perform necessary dragchute installation connections and adjustments inside the pneumatic system access door. The handcrank throw is 8.5 inches and projects 10 inches The door opens up and is locked open at an 80 angle, The lower level floor is required only on the right side of the stand (lef side of aircraft) and will start at fuselage station 1824 and extend to 1873.50. It shall have a minimum width of 42 inches. The elevation and fuselage clearance of the lower level floor shall be as shown in USAF drawing 7747223.

3.4.1.3 Platform Section The platform shall be designed in sections to allow assembly/disassembly and transportation capability. The sections shall be kept to a highway transprotation cubage envelope 9 feet high by 8 feet wide by 20 feet long.

3.4.1.4 Platform Sections lifting Provisions. Each maintenance platform section shall have lifting eyes with an inside diameter of at least 2 inches The lifting eyes shall not Interfere with the assembly nor present a safety harzard after the platform is erected. The lifting eyes shall be located so the crane can perform necessary positioning of the sections for assembly requiring the least manual handling

3.4.1.5 Platform Section Weight Information. Each maintenance platform section shall have a data plate located in a conspicuous area indicating its weight. This is required for personnel safety and convenient lifting equipment selection

3.4.2 Reliability, The maintenance platform reliability will be to the extent that all acceptance and pre-production test requirements are successfully met.

3.4.3 Maintainability. The maintenance platform shall be designed and constructed
as specified herein and to provide the following:

a. Minimum number of parts consistent with reliability and performance as specified.

b. Minimum amount of training and time necessary for assembly, disassembly, location of trouble sources, and maintenance, including servicing. Where practical, parts and components shall be located or positioned for rapid and simple inspection and recognition of excessive wear or potential failure.

c. permit adjustments, Servicing, replacement of parts and components, and other maintenance with minimum disturbance to other equipment parts and components. Parts and components shall be located for ample and rapid access unnless

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

performance or reliablilty will be appreciably degraded by the accessible location. In performing maintenance, if engineering reasoning or date determines the physical or visual interface between items cannot be avoided, the item predicted to require the most maintenance shall be located for best accessibility,

d. Permit maintenance with general-purpose tools and equipment normally available commercially, Use of special purpose tools and equipment shall be subject to approval by the procuring activity,

e. Minimumnumber of tools required for maintenance by design practices such as reducing the variety of bolt head sizes to the practical Minimum.

f. Primary bolted structure. Welds shall be used only when there is no other mechanical means to make a connection.

3.4.4 Drainage Provisions, The maintenance platform shall include provisions for the continous drainage of water from the steps, platform, structural members and other components. All drain holes shall have a minimum diameter of 0.25 inches.

3.4,5 Safety considerations. Means shall be provided to include, but be limited to, safety features as noted below and contained elsewhere herein:

a. Warning plates. Warning plates shall be provided at proper locations as required to prevent uunsafe conditions/operations .

b. Weight Limit Warning Information. A warning plate shall be provided to specify the maximum allowable weight on each step, the individual floors and the entire maintenance platform.

c. Flooring Surfaces. All flooring surfaces including stair steps shall be expanded metal material and shall meet the requirements of MIL-STD-1472. The entrance corner of all the steps shall be coated with nonslip compound MIL-W-5044, Type II, Class II, color FED-STD-595 number 37028. The compound w1ll be applied from where the nonslip expanded metal ends to over the full corner radius,

d. Stability The maintenance platform must remain stable under all conditions stated herein,

e. Reflectors, Reflectorized tape shall be added on the stand in accordance with T.O. 35-1-3, page 2-2, paragraph 2-20,

f. Hoist Gears. Chain hoist exposed gears shall be covered, reference MIL-STD-1472 para 5.13.7.2.1.

g. Stencils, Stencil ‘Maximum Towing Speed 5 MPH” on top of both tierod guards. The letters shall be at least one inch high. A stencil shall be added on the main stair steps “WARNING STEEP STAIRS”. Tire inflation stencil ‘Tire air inflation XXX PSI shall be located on the frame above each tire.

3.4.6 Mobility. Maintenance platform mobility shall be in accordance with MIL-M-8090, Type I, Class 2, Group C, except as noted below:

a. Wheels or casters shall be located outside the frame and have pneumatic tires. Tire size shall be at least 6.00-6.90 X 9. Minimum caster tire size will be

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

sixteen (16) inches. Four (4) way swivel lock and foot brake will be included in the caster assemblies.

b. Turning radius shall be 20 feet minimum. Stops shall be provided to limit turning radius.

c. Maximum speed limit shall be 5 mph,

d. Parking brakes (except when using casters) to brake both rear wheels shall be included in the running gear, Parking brakes control shall be located on the forward left hand corner of the frame, at a height of 48 inches and easily accessible so persons moving the platform can stop the platform as required.

e. Towbar shall be provided at the front of the maintenance platform. The towbar shall be permanently attached and shall have provisions to be locked in place in its vertical position. The towbar weight shall be held to the minimum to allow one person to steer the maintenance platform into position against the aircraft.

3.4.7 Platform Load Capacity. Load capacities shall be as follows:

a. Upper level floor - 1000 pounds

b. Lower level floor - 500 pounds

c. Upper level floor folding door - 400 pounds

d. Total platform - 1000 pounds

e. Staircase stair - 200 pounds

3.4.8 Platform Guard Rails, All platform floor levels shall be surrounded by sturdy, guard rails, Guard rails shall contain a kick guard four inches high and shall otherwise be designed to the requirements of MIL-STD-1472.

3,4.8.1 Upper Floor Level Guard Rails. Guardrails shall be provided around the upper floor including the platform landing except for that width where the stairs meet the platform landing, and around the fuselage floor cut-out, however a four inch kick guard shall be included all the way around the fuselage cut-out edge.

3.4.8.2 Lower Floor Level Guard Rails. The floor end next to the stabilizer shall not have a guard rail but shall have a 4 inch kick guard. The inboard floor side shall also have a 4 inch kick guard, The outboard floor side guard rail must clear the aircraft stabilizer by at least 24 inches. Where handrails are ommitted, removable safety nylon netting shall be used to meet safety requirements. The netting shall enclose the platform end and extend around to join with the guard rail. The netting shall extend between the lower and upper level floors and shall be attached to both floors. The netting on the platform end shall be fitted loosely to allow at least 8 inch give in the middle between the lower and upper floors.

3.4.9 Upper Floor Level Bumper.

a. A flexible rubber bumper, four inch O.D. shall be securely fastened to the rear platform ends around the fuselage floor cut-out, to prevent damage to the aircraft being serviced,

b. Double bumpers shall be installed in the saddle contour end contacting

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

the aircraft tail end. Double bumpers shall also be installed on the B-52G saddle contour adapter specified in paragraph 3.4. l.l.b. The double bumpers shall cover tail end contour cut-out and extend at least six inches on each side beyond full tail radius. The double bumpers shall be stiffened to prevent kinking and to serve as a stop against the aircraft tail.

c. Both floor rear end bumpers will be tapered as they approach the bevel corners. The upper level folding door bumper will also taper on the bevel corner.

3.4.10 Stairs & Handrails. Stairs and handrails shall be provided as part of the maintenance platform, Design shall conform to the requirements of MIL-STD-1472, using the recommended values, except the stair width shall be 24 inches. Each step on the stairs must be bolted into place to permit easy replacement. The main stairs shall be located on the front of maintenance platform positioned to give access to the upper level and further positioned so that the B-52H cannon extending through the forward face of the stand does not interfere with safe use of the stairway. A 24 by 30 inch landing shall be provided at the top of the stairs. A ladder shall be provided to give access from upper to lower levels when the folding floor panel is opened . Reference paragraph 3.4. l.l.g.

3.4.11 Chain Hoist. A Chain Hoist shall be installed on the maintenance platform upper floor level left hand side. The chain hoist shall be mounted on an overhead monorail , The chain hoist shall have a 500 pound lift capacity and a 5 to 1 retrieve ratio.

3.4. 11.1 Hoist Performance. The hoist shall safety and efficiently raise the dragchute pack from the ground, over the handrails, and to the aircraft dragchute cannister centerline fuselage station 1868, The dragchute pack is rectangular shaped 24 X 24 X 36 inches long. The dragchute is raised along its long side by attaching hoist slip hooks to the dragchute opposite side laces,

3.4, 11.2 Chain Hoist Brake. A mechanical brake shall automatically stop and hold the load upon release of the chain, whether the release is intentional or accidental. There shall be no interference owing to the mechanical brake, such as binding, slipping, and jerky action.

3.4. 11.3 Chain Hoist Manual Operation. The chain hoist shall operate manually by one Person and be capable of raising or lowering the 250 pound dragchute load a minimum distance of 268 inches from the ground. The hoist shall have a capacity of 500 pounds. The effort to raise and lower the capacity load shall not exceed 40 pounds. The hoist shall be operational from within the upper floor without interference or adjustments throughout its full traveling range.

3.4. 11.4 Hoist Installation. The hoist supporting structures shall have enough overhead clearance for working personnel, shall not intrude into the work area, and shall provide enough overhand to prevent dragchute pack from snagging to platform side resulting from the vertical twisting of the dragchute pack. Provisions shall be made to stow the monorail inside the envelope of the platform during towing and when the platform is not in use.

3.4. 11.5 Hoist Chain Hooks. The chain end shall terminate in a fitting to which four chains are attached. The four chains shall be welded steel (weight to keep unloaded line taut) 18 inches long with slip hooks on the loading ends.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

3.5 Performance. The maintenance platform shall withstand the following conditions without detrimental effect to subsequent, operation:

Operation in ambient temperatures randing from -40 F to +125 F, storage in ambient temperatures ranging from -65 F to +160 F and relative humidity of 100 percent, including rain.

3.5.1 Stability.

a. The maintenance platform shall withstand a wind velocity of 40 miles per hour when unsupported by aircraft contact, with 500 pounds on the top platform, Under these conditions, the horizontal movement of the upper floor level shall not exceed 1.5 inches in either direction from center. Calculations may be submitted to prove stability of the maintenance platform for wind conditions.

b. When loaded with 600 pounds evenly distributed on the side 33% of the upper floor the side of the platform shall not lower more than 1 inch.

3.5,2 Concentrated Load. Representative areas of the maintenance platform proper shall be subjected to a concentrated load of 200 pounds over a six inch square area with maximum deflection of . 25 inch and without permanent set.

3.5.3 Steps Proof Test Load, The steps shall be capable of withstanding a load of 400 pounds without damage or permanent deformation when the load is placed at or near the center of each step,

3.5,4 Proof Test Load. The following individual test loads shall be performed to prove structural integrity of the maintenance platform (loads distributed evenly over the supporting areas) :

a. Upper level floor - 2000 pounds

b. Lower level floor - 1000 pounds

c. Upper level floor folding door - 800 pounds

d. Total platform - 3000 pounds

e. Staircase stairs - 400 pounds

There shall be no damage or permanent deformation anywhere on the structure of the maintenance platform.

3.6 Finishes & Protective Coatings

3.6.1 Cleaning Plating & Painting Clenaing plating and metal pre-treatment shall be in accordance with MIL-STD-808, Type 1 exposure, film designation ES for structure , BG for handrails and guardrails and NG for stencils.

3.6.2 Welded Assembles. Assenblies that are welded or brazed after painting shall be thoroughly cleaned of welded material and re-painted as specified in 3.6.1.

3.6.3 Fasteners. Permanently installed (non-removable) fasteners penetrating exterior surfaces shall be wet-installed using a corrosion inhibiting sealant as specified in MIL-S-81733.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

3.6,4 Faying Surfaces, All faying surfaces (non-welded) shall be assembled wet using a corrosion inhibiting sealant as specified in MIL-S-81733.

3.7 Markings.

3.7.1 Data Plates. The manufacturers standard name plates and data plates will be acceptable but shall be permanently attached to the maintenance platform, The contract number, serial number, part number and other pertinent Information shall be shown on the plates.

3.7.2 Identification of Product, Equipment, assembles , and parts shall be marked for identification in accordance with MIL-STD-130.

3.8 Workmanship.

3.8.1 The maintenance platform, including all parts and accessories, shall be constructed and finished in a thorough, workmanship manner. Particular attention shall be given to neatness, thoroughness of painting, welding brazing, machine screw assembles, and freedom of parts from burrs and sharp edges,

3,8.2 All welded joints shall be free from cracks, injurious porosity, and oxide inclusions. Welding shall be performed only by a welder or weldlng operators who have met the requirements of MIL-STD-1595 for the particular group of materials and types of welding involved

3,8.3 The maintenance platform shall be thoroughly cleaned of loose, spattered, excess solder and weld, metal chips, and other foreign materials. After final assembly, burrs, sharp edges, and weld slag that may crumble shall be removed.

3,9 System Safety, A system safety program shall be initiated by the contractor in accordance with MIL-STD-882. Hazard analysis reports shall be provided.

4. QUALITY ASSURANCE PROVISIONS

4,1 Resposibility for Inspect Ion. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein with the exception of USAF portion of testing specified in 4.6.6, Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government, The Government reserves the right to perform any of the inspections get forth herein where such inspections are deemed necessary to assure supplies and service conform to prescribed requirement,

4.2 Classification of Tests. The inspection and testing of the maintenance platform shall be classified as follows:

a. Preproduction tests.

b. Quality conformance tests.

4.3 Test Conditions, Unless otherwise specified herein, tests shall be performed under normal ambient room temperature and atmospheric conditions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

4.4 Preproduction (first article) Test. Production tests shall consist of all tests described under 4,6,

4.4.1 Test Sample. One maintenance platform shall be manufactured and certified to paragraph 4.5. l.a. and shall be subjected to the preproduction tests.

4.5 Quality Conformance Tests. Quality conformance tests shall consist of:

a. Individual tests.

b. Periodic sampling tests.

4,5.1 Individual Tests. Each maintenance platform shall be subjected to the following tests as described under 4.6:

a. Examination of product,

4.5.2 Periodic Sampling Tests. Sampling tests shall consist of the tests described in 4.6.4.c.

4.5.2.1 Sampling Plan. One maintenance platform shall be selected from each 5 or fraction thereof on the contract or order and subjected to the sampling tests. The test sample shall be selected at random from production units which have successfully completed all individual tests.

4.5.2.2 Rejection and Retest. When one item selected from a production run fails to meet the requirements specified herein, no items still on hand or later produced shall be accepted until the extent and cause of failure are determined,

4.5.2.3 Individual Test May Continue, For operational reasons, individual tests may continue pending the investigation of a sampling plan test failure, but final acceptance of items on hand or produced later shall not be made until it is determined that items meet all the requirements specified herein.

4.5,3 Defects in Items Already Accepted. The investigaton of a test failure could indicate the defects may exist in items already accepted. If so, the contractor shall fully advise the produring activity of all defects likely to be found and methods of correcting them.

4.6 Test Methods.

4.6.1 Examination of Product, The maintenance platform shall be inspected to determine compliance with the requirements specified herein. Particular attention shall be given to workmanship, materials, dimensions, and markings. A checklist shall be prepared to verify requirements specified in section three which are not verified by testing,

4.6.2 Mobility Tests. The maintenance platform shall be subjected to the mobility tests as specified in MIL-M-8090 (see 3,4.6).

4.6.3 Stability Tests.

4.6.3.1 Wind Test, With the maintenance platform configured as specified in 3.5. l.a,
it shall be subjected to intermittent winds of 40 miles per hour and shall meet the

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

stability requirements specified in 3.5. l.a. In place of the intermittent winds, an equivalent force method may be used. If so, it shall be applied alternately to both sides of the maintenance platform, at a right angle to the longitudinal axis. For the equivalent force method, air resistance shall be computed by the formula: Air Resistant (Force) equals coefficient drag, times air velocity squared in feet per second, times air velocity squared in feet per second, times density in slugs per cubic foot, times area in square feet, times one-half. The force shall be aplied at the centroid of the platform. The coefficient of drag shall be 1.17.

4.6.3.2 Top Platform Side Loading Test. With the top platform loaded as specified in 3.5. l.b, the maintenance platform shall meet the requirements as statedin 3.5. l.b.

4,6.4 Loading Tests.

a. Concentrated Load. The maintenance platform shall be subjected to the static loading and meet the requirements as specified in 3.5.2.

b. Steps Proof Test Load. The steps shall be subjected to the proof loading and meet the requirments as specified in 3.5,3.

c. Proof Load. The maintenance platform shall be subjected to the loading and meet the requirements as specified in 3.5.4.

4.6.5 Maintainability Evaluation. The maintenance platform shall be inspected, and evaluated from the standpoint of ease of maintenance, servicing and operation. Particular attention shall be given maintenance with a minimum number of common tools, servicing and operation by personnel wearing heavy gloves, and provisions made to prevent accumulation of dirt, snow, ice, and anything that may hinder servicing and operation.

4.6.6 Compatability and Reliability Testing (USAF) . After successful completion of all previous tests, the maintenance platform shall be delivered to the USAF for compatability and reliability testing (see 6.1) , for a period of 30 days. Although tests are conducted by the USAF, the maintenance platform manufacturer is responsible for assuring the testing activity is provided proper platform erection instructions and maintenance of the equipment, and for maintaining surveillance with that activity in the event problems should arise. Results of this testing shall be obtained from the USAF by the contractor and form a part of the test report. Should problems with the maintenance platform become apparent during this testing, where problems are due to non-compliance with the requirements of this purchase description the contractor shall be responsible for taking the necessary corrective action without additional cost to the USAF, Delivery to and from the USAF testing activity shall be contractor responsibility. Test location shall be specified by the USAF (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

5. PACKAGING

Preservation, Packaging, Packing and Marking. The maintenance platform shall be preserved and packaged level A or C, packed level A, B, C and marked in accordance with MIL-STD-162 (see 6.2) .

6. NOTES

6.1 Intended Use. The maintenance platform is intended for use interchangeably with the B-52 G & H aircraft for dragchute loadings and servicings.

6.2 Ordering Data. Procurement documents should specify the following:

a. Title, number and date of this specification.

b. Selection of applicable levels of preservation, packaging, and packing (see 5.1)

c. Location for USAF compatibility and reliability testing (see 4.6.6).

6.2.1 First article. When a first article inspection is required, the item should be a first article sample or is may be a standard production item from the contractors current inventory as specified in 4.4 The first article should consist of (one) unit. The contracting officer should include specific instruction in the acquisition documents regarding arrangements for examinations, approval of first article test results and disposition of first articles Invitations for bids should provide that the government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract,

6.3 Subject Term (Keyword) Listing

Antenna Fairings
Casters
Chain Hoist
Dragchute
Fuselage Cut-out
Guard Rails
Handrails
Maintenance Platform
Rubber bumpers
Towbar
Upper Level Floor/Lower Level Floor

CUSTODIAN:
AIR FORCE - 99

PREPARING ACTIVITY:
AIR FORCE - 82

AGENT :
AIR FORCE - 99
(PROJECT NO. 1730F298)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements All users of military standardization documents are invited to provide suggestions This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems Enter in block 6 any remarks not related to a specific paragraph of the document If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered

NOTE This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements

(Fold along this line)

(Fold along this line)

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO 4966 Alexandria, VA

POSTAGE WILL BE PAID BY

HQ AFLC CASC/CBBBT
BATTLE CREEK MI 49016-3094

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2 DOCUMENT TITLE
MIL-M-87977	AIRCRAFT MAINTENANCE PLATFORM

3a NAME OF SUBMITTING ORGANIZATION	4 TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)* _____

5 PROBLEM AREAS

a. Paragraph Number and Wording

b Recommended Wording.

c Reason/Rationale for Recommendation

6 REMARKS

7a NAME OF SUBMITTER *(Last, First, MI)* – Optional	b WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c MAILING ADDRESS *(Street City, State, ZIP Code)* – Optional	8 DATE OF SUBMISSION *(YYMMDD)*

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:28Z
Check the source to verify that this is the current version before use.