MIL-T-50382(AR)
AMENDMENT 3
17 August 1984
SUPERSEDING
AMENDMENT 2
6 August 1982

MILITARY SPECIFICATION

TELESCOPE, PANORAMIC: M113E1

This Amendment forms a part of Military Specification MIL-T-50382(MU), dated 16 June 1970, and is approved for use by the US Army Armament, Munitions and Chemical Command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

* Title: Change from "M113E1" to "M113A1" and wherever it appears in the specification.

* 2.1, Specifications: Add "MIL-L-50778 Liquid Scintillation System for Radioactive Fire Control".

* Drawings: Change from "Frankford Arsenal" to "Armament Research and Development Center".

PAGE 2

* 2.2: Change "DSAM 4158.8" to "DSAM 4145.8" (2 places).

Add: MIL-HDBK-204 Military Standardization Handbook, Inspection Equipment Design".

* 3.1: Change "DSAM 4158.8" to "DSAM 4145.8".

PAGE 3

3.6.1, line 3: Delete "with less than 0.2 psig loss, for a minimum period of two hours" and substitute "for a period of one hour with no evidence of leakage".

PAGE 4

3.7.7, line 3: Change: "within the limits of 0.75 and 1.0 diopters" to "within the limits of -0.75 and -1.0 diopters".

FSC 1240

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:23Z
Check the source to verify that this is the current version before use.

PAGE 5

3.9.2, line 7: Delete "and spring action of the electrical contact".

Change: "Handle, Elebow Detent Lock Pin" to "Handle and Elbow Detent Lock Pin".

PAGE 6

* Add new paragraph 3.10.3:

"3.10.3 External tritium contamination. There shall be no trace of tritium in excess of 1000 disintegrations per minute (dpm)/100 sq. cm. on the external surfaces of the telescope."

PAGE 7

* 4.3.2.2, Table I: After Critical change "100% Inspection" to "none".

Add "MAJOR: 100% Inspection" above characteristics 1 and 2.

Add "3. External Tritium Contamination, 3.10.3, 4.7.2.5.2".

124: Change "4.7.2.1" to "4.7.2.5.1".

125: Change "4.7.2.2" to "4.7.2.5.2".

Add: "128. Fabrication, 3.2, MIL-F-13926 and Visual".

PAGE 8

* 4.4.1: Delete and substitute:

"4.4.1 Three telescopes shall be selected at random by a Government representative as a special sample from each 100 produced or from each month's production, whichever occurs first, and be subjected to the requirements and tests of Table II."

Table II: Delete 301, 302, and 303.

304: Add "(-80°F(-62°C) and +160°F(+71°C))", delete "4.6.1.2" and substitute "4.6.1.1, Visual/Tactile".

305: Add "(-40°F (-40°C) and +150°F(+65°C))". delete "4.6.1.2" and substitute "4.6.1.1".

Source: https://assist.dla.mil -- Downloaded: 202640-22T20:23Z
Check the source to verify that this is the current version before use.

306: Delete: "(storage and oper. temp)".

307: Delete "(storage & oper. Temp)".

PAGE 14

4.7.2.2.5, line 3: Change "3.8.2.7" to "3.8.2.2".

PAGE 15

* Add new paragraph 4.7.2.5.3:

"4.7.2.5.3 External tritium contamination. Contamination test shall be performed by wiping the telescope with filter paper moistened in distilled water. The wiping shall be performed with moderate finger pressure. The damp filter paper shall be placed in a container with the proper portion of scintillation liquid. The scintillating system used to measure contamination must be calibrated and meet the minimum requirement of MIL-L-50778. The readout shall be within 10% of the known standard value when counted to a total of 1000 disintergrations. The actual test for determining contamination is performed by placing the container into the scintillation system. The measured contamination shall be within the limits specified in 3.10.3."

PAGE 16

* 6.2: Add new subparagraph e:

"e. Contract data requirement for submission of inspection equipment designs conforming to data item description DI-R-1714, Tailored, see 6.4.1."

* Add new paragraphs 6.4 and 6.4.1:

"6.4 Inspection equipment design.

6.4.1 Submission of designs for approval. Contractor designs for final acceptance inspection shall be approved by the Government prior to fabrication or procuring the equipment. The contractor is referred to MIL-HDBK-204 for guidance. Submission of design concept on inspection equipment is permissible for tentative approval. The completion date for design review will be based on the date of the final submission of designs and the required delivery schedule as stipulated in the contract.

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:23Z
Check the source to verify that this is the current version before use.

Submit designs as required to: Commander, US Army Armament Research and Development Center, ATTN: DRSMC-QAF-I(D), Dover, NJ 07801-5001. When the cotractor submits inspection equipment designs to the government for approval, he shall give the following information in his letter of transmittal:

a. The contract number.

b. The contract item (name, model number, etc.).

c. The designs remaining to be submitted and the expected date of submittal."

The margins of this amendment are marked with an asterisk or vertical lines to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army-AR

Preparing Activity:
Army-AR

(Project 1240-A819)

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:23Z
Check the source to verify that this is the current version before use.