MILITARY SPECIFICATION

MINE, ANTI-PERSONNEL
NM, M25, LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers quality assurance provisions and special requirements not covered by the drawings, for the loading, assembling and packing for one type of mine designated as Mine, Anti-Personnel, NM, M25.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116 - Preservation, Methods of.
MIL-A-2550 - Ammunition and Special Weapons; General Specification for.
MIL-I-45208 - Inspection Requirements, General Specification for.
MIL-D-45483 - Detonator, Percussion, M46; Loading, Assembling and Packing.
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of.
MIL-I-45608 - Designs and Drawings, Ordnance Inspection Equipment.
MIL-M-60038 - Mine, Anti-Personnel, NM, M25, Parts for.

FSC 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

8796522 - Marking Diagram and Sealing for Wood Packing Boxes.
8864074 - Mine Apers, NM, M25 Assembly.
8887507 - Box, Wirebound, Packing, Ammunition for Mine, Apers, NM, M25.
8887508 - Support, Packing, Ammunition for Mine, Apers, NM, M25.
8887509 - Bag, Packing, Ammunition for Mine, Apers, NM, M25.

PUBLICATIONS

ORDNANCE CORPS

IEL 8864074 - Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by contractor's in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Materials.-Materials shall be in accordance with applicable drawings and specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

3.2 Parts.-Parts shall be in accordance with Specification MIL-M-60038.

3.3 Detonator.-Detonators shall be in accordance with Specification MIL-D-45483.

3.4 Mine assembly.-Mine assemblies shall comply with requirements specified on Drawing (dwg.) 8864074 and with all requirements specified in applicable specifications.

3.5 Airtightness at body sealing joint.-The body assembly, with the plug secured firmly in position shall be submerged in water having a temperature of 70 degrees plus or minus 15 degrees Fahrenheit (F.) in a closed container under a vacuum of 3 inches (in.) of mercury. The mine shall be subjected to the required vacuum for a minimum (min.) of 60 seconds (sec.). There shall be no evidence of air leakage at the body sealing joint.

3.6 Non-functioning.-The mine with the safety clip in place will not function when a load of 50 pounds, min. is applied centrally to the vertical axis of the mine.

3.7 Functioning.-The mine with the safety clip removed shall function when a load of 16 to 26 pounds is applied centrally to the vertical axis of the mine.

3.8 Penetration.-The shaped charge jet of the mine upon functioning shall make a complete penetration of mild steel plate, when the plate is in direct contact with the top of the charge container.

3.9 Workmanship.-The mines shall be free of cracks, chipped edges, chips, dirt, grease and other foreign materials or defects affecting the serviceability of the item. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-The supplier's responsibilities will be as specified in the contract or purchase order. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Contractor quality assurance system.-The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL-I-45208. The contractor's quality assurance system shall contain a procedure for the reporting of critical defectives found during the course of his inspection and during inspection by the Government. Any critical defect encountered, unless annotated by an asterisk (*) to the right of the characteristic code number (see 6.2), will be reported within 48 hours. A monthly summary report covering those critical defects annotated by an asterisk will be furnished. The agencies to whom the reports will be furnished are identified in paragraph 6.4. The reports shall contain, as a minimum, the following information:

a. Contractor and contract number.
b. Number and revision date of specification.
c. Characteristic code number.
d. Lot or serial number.
e. Number of defectives found.
f. Assignable cause or analysis of occurrence.
g. Corrective action taken or recommended. When the corrective action is beyond the control of the contractor or the scope of the contract, the report shall contain the contractor's recommendation to the Government.

4.1.2 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

a. A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

b. Number of units of product inspected.

c. Results obtained for all inspection performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Statements of findings on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL-I-45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection.

4.2.1 Submission.-The contractor shall submit an initial production sample to a Government approved facility, as designated by the contracting officer (see 6.5), for evaluation in accordance with the provisions of 4.2.2. The sample shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

consist of 48 complete assemblies and 12 charge explosives which have been produced by the contractor, or furnished by a supplier, and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by statements of findings or tests, as applicable, or both for materials. An initial production sample or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply such as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer.

4.2.2 Inspections to be performed.-Each assembly and charge explosive shall be inspected for every dimension and requirement of the applicable drawing and shall be tested as specified in 4.3.3.1.

4.2.3 Rejection.-The initial production sample shall be rejected if one or more assemblies, subassemblies or charge explosives fail to conform to any or all of the drawing dimensions or requirements or any of the requirements of 4.3.3.1. The Government reserves the right to terminate its inspection upon any failure of any component in the sample to comply with any or all of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4.3 Inspection provisions.

4.3.1 Lot formation.-A lot shall consist of mines produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification and process changes not affecting safety, performance, or fit, as determined by the Government shall not necessitate changing the lot interfix number. Each lot shall contain:

a. RDX from not more than one batch or blend of batches which assure homogeneity of the lot.

b. Detonators from not more than one interfix lot number from one manufacturer.

c. Parts from not more than one interfix lot number from one manufacturer.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sample plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Charge explosive (see dwg. 8864062 covering a detail of dwg. 8864074).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical: None defined.			

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 percent		
101.	Outside diameter, maximum (max.)	Gage	01001
102.	Overall length, max	Gage	01002
103.	Cone angle	Gage	01003
104.	Depth of cone, minimum (min.)	Gage	01004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	01005

4.3.2.2 Loaded detonator housing (see dwg. 8864074).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Detonator assembled into housing in reverse position	Visual	02001
102.	Detonator loose in housing	Manual	02002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	02003

4.3.2.3 Loaded charge container (see dwg. 8864074).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Excessive solvent at joint	Visual	03001
102.	Marking improper	Visual	03002
103.	Internal components loose	Manual	03003

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.0 percent		
201.	Components missing or damaged.....	Visual	03004
202.	Evidence of poor workmanship (see 3.9).....	Visual	03005

4.3.2.4 Loaded body assembly (see dwg. 8864074).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Internal components missing (prior to sealing).....	Visual	04001
102.	Excessive cement at joint.....	Visual	04002
103.	Marking improper.....	Visual	04003
Minor:	AQL 1.0 percent		
201.	External components missing or damaged.....	Visual	04004
202.	Evidence of poor workmanship (see 3.9).....	Visual	04005

4.3.2.5 Support, packing, ammunition, for Mine, Apers, NM, M25, prior to insertion into bag (see dwg. 8887508).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Suppprt cracked.....	Visual	05001
102.	Parts loose in support.....	Manual	05002
Minor:	AQL 0.65 percent		
201.	Components missing.....	Visual	05003

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4.3.2.6 Bag, packing, ammunition, for Mine, Apers, NM, M25, prior to sealing (see dwg. 8887509).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Bag punctured	Visual	06001
102.	Strap stitched improperly	Visual	06002
Minor: None defined.			

4.3.2.7 Bag, packing, ammunition, for Mine, Apers, NM, M25, after sealing (see dwg. 8887509).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Heat seal improper	Visual	07001
102.	Tear strip inadequate	Visual	07002
Minor: None defined.			

4.3.2.8 Box, wirebound, packing, ammunition for Mine, Apers, NM, M25, prior to sealing (see dwg. 8887507).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Contents packed improperly	Visual	08001
Minor: None defined.			

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4.3.2.9 Box, wirebound, packing, ammunition for Mine, Apers, NM, M25, after sealing (see dwg. 8887507).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.65 percent		
101.	Box damaged to extent that contents are exposed	Visual	09001
102.	Sealing of box improper	Visual	09002
103.	Marking improper	Visual	09003
104.	Contents loose	Manual	09004
Minor: None defined.			

4.3.3 Testing.

4.3.3.1 Initial production (see 4.2).-The samples submitted as the initial production quantity shall be tested as specified herein after being examined for all applicable drawing dimensions and requirements.

4.3.3.1.1 Airtightness (see 3.5) - Major defect, Code No. 10001, non-functioning (see 3.6) - Major defect, Code No. 10002, functioning (see 3.7) - Major defect, Code No. 10003, penetration (see 3.8) - Major defect, Code No. 10004 and weight of charge explosive (see dwg. 8864062) - Major defect, Code No. 01006.-The sample shall be tested as specified in 4.4 using test equipment specified in 4.3.4. The initial production quantity shall be rejected if any assembly or charge explosive fails to comply with the specified requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4.3.3.2 Production.

4.3.3.2.1 Airtightness (see 3.5) - Major defect, Code No. 10001, nonlfunctioning (see 3.6) - Major defect, Code No. 10002, functioning (see 3.7) - Major defect, Code No. 10003 and penetration (see 3.8) - Major defect, Code No. 10004.-A sample of 48 complete assemblies shall be selected, at random, from each lot. If one or more assemblies fail to comply with each and every requirement the lot shall be rejected. The tests shall be performed as specified in the following:

4.4.1 Airtightness
4.4.2 Non-functioning
4.4.3 Functioning and penetration

4.3.3.2.2 Weight of charge explosive (see dwg. 8864062) - Major defect, Code No. 01006.-A sample of 12 charge explosives shall be selected, at random, from each lot. If one or more charges fail to comply with the requirement specified the lot shall be rejected. The test shall be performed as specified in 4.4.4 using test equipment as specified in 4.3.4.

4.3.3.2.3 Check test for possible deterioration of detonators (see 6.6) - Major defect, Code No. 10005.-If the total time between original acceptance of the detonator lot and the assembly of the detonators into the mine exceeds two years, or if the detonators show evidence of having been subjected to adverse environmental conditions for any time, however brief, the detonator lot shall be subjected to check test for possible deterioration specified in Specification MIL-D-45483. The detonator lot shall be considered usable if the test results conform to the requirements of Specification MIL-D-45483. This test shall be performed when required, by the contractor on detonators selected by the inspector at the facility assembling the mine. The test shall be conducted at Government expense without cost to the contractor who produced the detonator or the contractor assembling the detonator into the mine, and shall not constitute a basis for rejection against either contractor except where deterioration has occured as a direct result of carelessness in handling, storage, etc. of the detonator lot while the detonator lot was under the jurisdiction of either contractor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4.3.3.2.4 Heat seal test of sealed bag (see dwg. 8887509) - Major defect, Code No. 10006.-Sampling, acceptance criteria and test procedures for this test shall be as specified in Specification MIL-P-116.

4.3.3.2.5 Quality assessment sample.-A sample of 10 mines shall be selected, at random, from each lot and be forwarded to the responsible engineering agency for such inspection and evaluation as is deemed appropriate. Results of this evaluation will not affect lot acceptance but may form the basis for corrective action in subsequent lots.

4.3.4 Inspection Equipment.-Index of Inspection Equipment Number IEL-8864074 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection and test equipment.-The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of it's accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

4.4 Test methods and procedures.

4.4.1 Airtightness.-The body assembly with the plug secured firmly in position shall be submerged in water at the temperature, under the vacuum and for the time as specified. Observations shall be made for air leakage at the body sealing joint.

4.4.2 Non-functioning.-The mine, after successful passage of the airtightness test, shall be reassembled with the charge container installed and the safety clip in place and shall be installed in the applicable test fixture specified in 4.3.4. A load of 50 pounds, min. shall be applied centrally to the vertical axis of the mine without the mine functioning. A mine that functions shall be classed defective.

4.4.3 Functioning and penetration.-The assembled mines after successful passage of the non-functioning test shall be inverted and positioned on a steel plate, SAE 1020 having a nominal thickness of 0.25 inches, which has been leveled on hard packed sand or soil. The charge container shall be in direct contact with the plate. After removal of the safety clip, a load continuously variable from 0 to 26 pounds shall be applied to the lower body. Mines that fail to function or failure of the explosive jet to make a complete penetration shall be classed defective.

4.4.4 Weight of charge explosive.-The charge explosive shall be weighed using equipment of an accuracy within 0.1 grams. Any charge explosive, the weight of which exceeds the specified requirement shall be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Unit packaging.-The mines shall be preserved and packaged in accordance with dwg. 8887508.

5.1.2 Intermediate packaging.-The unit packaging shall be packed in accordance with dwg. 8887509.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

5.2 Packing

5.2.1 Outer pack.-The intermediate packaging shall be packed in accordance with dwg. 8887507.

5.3 Marking

5.3.1 Outer pack.-Outer pack shall be marked in accordance with dwg. 8796522.

5.4 Data cards.-Data card information shall be prepared for each lot in accordance with the procedure specified in Specification MIL-A-2550.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify title, number and date of this specification.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242-3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

as specified in 6.3.7.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designed in the IEL by the following codes:

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above.

6.3.7 Submission of contractor designs.-Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normlly be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Submission of critical defect reports.-For U. S. Army Munitions Command procurements, one copy of each critical defect report will be furnished the cognizant Government inspection agency; the Army Ammunition Procurement and Supply Agency, ATTN: SMUAP-RO; Picatinny Arsenal, ATTN: SMUPA-ND.

6.4.1 Reporting to other services.-For other than U. S. Army Munitions Command procurements, critical defect reporting shall be as prescribed by the Contracting Officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.

6.5 Submission of Initial Production, Pre-Production or Qualification Samples.-Instructions, as to the location for the evaluation of Initial Production, Pre-production, or product qualification shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-NI.

6.6 Check test expense.-The contracting officer should arrange to have the contractor reimbursed for any expense incurred in the performance of the check test for possible deterioration.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1345-A152

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:06Z
Check the source to verify that this is the current version before use.