MILITARY
SPECIFICATION

MIL-T-55020(SigC)
Amendment No. 1
12 Sept 1958

TERMINAL, TELEPHONE AN/TCC-24( )

1. Delete paragraph 4.2.1 and substitute the following paragraphs for the correspondingly numbered paragraphs in the specification:

3.7.6(b) Spiral-4 cable connections shall be made by means of a type MS3102A16S-1S connector as specified in Military Standard MS 3102(ASG) and paralleled with Spiral-4 Binding Posts U-106( )/U.

4. QUALITY ASSURANCE PROVISIONS

4.1 Classification of inspection. - Inspection shall be classified as follows:

(a) Preproduction inspection (does not include preparation for delivery). (See 4.2).

(b) Procurement inspection. Procurement inspection shall be the inspection performed by the contractor and by the Government, as specified by 4.3 and 4.16.

(1) Procurement inspection of items before preparation for delivery. (See 4.3).

(2) Procurement inspection of preparation for delivery. (See 4.16 and section 5).

4.2 Preproduction inspection. This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the preproduction inspection specified in Table I, and the Group A and nondestructible Group B inspection specified in Tables II and III, respectively. Other nondestructive tests on preproduction samples may be performed to determine compliance with specified requirements. The preproduction inspection will normally be performed in this order: (1) vibration, (2) bounce, (3) shock, benchhandling and (4) shock, drop. Other preproduction inspection may precede, follow, or be interspersed between the foregoing.

4.3 Procurement inspection of items before preparation for delivery. - The contractor shall perform the inspection specified by (a) through (d) below, to demonstrate compliance with specified requirements. However, this does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection records. In addition the Government -- at its discretion -- may perform all or any part of the inspection specified in (a), to verify the contractor's compliance with specified requirements. (The amount of such verification inspection will depend on the extent to which the contractor's inspection procedures and records insure that the equipment on contract meets the specified procurement inspection.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:15Z
Check the source to verify that this is the current version before use.

(a) Procurement inspection shall consist of group A and group B, inspection as specified in 4.3.1 through 4.3.2.3.

(b) When Standard MIL-STD-105 specifies actions by the Government, the Government may authorize the contractor to perform any of such actions except that responsibility for acceptance rests with the Government.

(c) Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. However, the order may be varied when it is considered more practical to select separate samples for group B inspection.

(d) Each unit which will be subjected to group A or group B inspection shall be preconditioned after final assembly. (See 3.14).

4.3.1 Group A inspection. - This inspection (including sampling) shall conform to table II and Standard MIL-STD-105. Unless otherwise specified, normal inspection shall be used at the start of the contract. Group A inspection shall be performed in any order which is satisfactory to the Government, except that operational inspection shall be last.

4.3.2 Group B inspection. - This inspection (including sampling) shall conform to table III and the Appendix to Standard MIL-STD-105. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R-1. Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with 4.3.4 and the requirements of Standard MIL-STD-105 for disposition of rejected product.

4.3.3 Procedure in case of failure. - When an inspection lot fails, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken. If the contractor and Government inspector cannot agree on the effectiveness of the corrective action, the matter shall be referred to the contracting officer for resolution.

4.3.4 Disposition of nonconforming product. - When defective sample units or failed inspection lots are submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:15Z
Check the source to verify that this is the current version before use.