MIL-M-20439A
26 NOVEMBER 1958

SUPERSEDING
MIL-M-20439
3 DECEMBER 1951

MILITARY SPECIFICATION

MINE, ANTIPERSONNEL, PRACTICE, M8 LOADING, ASSEMBLING, AND PACKING

This specification has been approved by the Department of Defense and is mandatory for use by the Departments of the Army, the Navy, and the Air Force.

1. SCOPE

1.1 Scope. This specification covers the loading, assembling, and packing of one type of mine designated as Mine, Antipersonnel, Practice, M8.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids, form a part of this specification:

SPECIFICATIONS

MILITARY

JAN-P-223 – National Military Establishment Specification Powder, Black,

MIL-G-2550 – General Specification for Ammunition Except Small Arms Ammunition.

STANDARDS

MILITARY

MIL-STD-105 – Sampling Procedures and Tables for Inspection by Attributes.

M1L-STD-109 – Inspection Terms and Definitions.

DRAWINGS

ORDNANCE CORPS

82-0-112 – Mine, Anti-Personnel, Practice, M8 & Fuze, Mine, Combination, M10A1 Complete Assembly.

F7548180 –Box, Packing, for Practice Anti-Personnel Mine, M8 with Replacement Parts Assembly and Details.

F7548411 – Container, Metal, for Replacement Parts for Anti-Personnel Practice Mine, M8. Assembly, Details, Packing, and Marking.

GL-8802226 – Index to List of Inspection Equipment.

PUBLICATIONS

ORDNANCE CORPS

ORD-M608-11 – Procedures and Tables for Continuous Sampling by Attributes.

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

FSC 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:48Z
Check the source to verify that this is the current version before use.

3.1 Material. Materials and parts shall be in accordance with applicable specifications and drawings.

3.2 Assembly. The assembly shall comply with all requirements specified on Drawing (dwg.) 82-0-112 and all drawings referenced thereon and with all requirements specified in applicable specifications except as modified herein.

3.3 Moisture content of black powder. The moisture content of the black powder shall not exceed .80 percent when tested in accordance with 4.4.1,

3.4 Functioning. The mine shall function and meet the burning time limits of 3.8 to 5.5 seconds when tested in accordance with paragraph 4.4.2.

3.5 Workmanship. All parts shall be free of chips, dirt, grease, rust, and other foreign material. The cleaning method used shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents used.

4. QUALITY ASSURANCE PROVISIONS

4.1 General provisions. The detailed quality assurance provisions of this specification are applicable to inspection performed by or for the Government and shall be performed as prescribed below. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein.

4.1.1 Contractor quality assurance system. The contractor shall provide and maintain an effective Quality Assurance System acceptable to the Government covering the supplies procured under this specification. A current written description of the system shall be submitted to the contracting officer prior to initiation of production. The contractor shall not be restricted to a particular quality assurance system. However, the system adopted must be one which consistently results in material meeting the requirements as evidenced by the evaluation specified in 4.1.2.1. In all testing inspection, the use of the equipment specified and the methods of test prescribed in this specification and other documents referenced herein shall be mandatory. Results of all examinations and tests performed under this quality assurance system shall be made available to the Government. The contractor shall notify the Government of and obtain approval for any change to the written procedure that affects the degree of assurance required by this specification and other documents referenced herein.

4.1.1.1 Submission of data. At the time the product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct. and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions and requirements as required by the contractual documents.

(b) Number of units of product inspected.

(c) Results obtained for all inspections performed

(d) Drawing and specification numbers and dates, together with an identification and date of changes.

(e) Number of items in lot.

(f) Certificates of analysis including results of tests on materials used in the lot.

(g) Date submitted.

4.1.1.2 The certificate shall be signed by a responsible agent of the certifying organization and shall be accompanied by evidence of the agent's authority to bind his principal.

4.1.2 Government verification.

4.1.2.1 At the beginning of the contract and until such time as the contractor has oper-

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:48Z
Check the source to verify that this is the current version before use.

ated under an established and approved quality assurance system which has resulted in an acceptable product, Government verification will consist of (1) performance of all inspections and tests listed in the detail specification and other documents referenced therein, which are not reserved for sole performance by the contractor, (2) monitoring of those inspections reserved for sole performance by the contractor, and (3) monitoring of the contractor's quality assurance operations, At no time will complete Government verification be reduced less than that permitted by MIL-STD-105 and ORD-M608-11 except under those conditions prescribed in 4.1.2.2.

4.1.2.2 Under the following conditions further reduced Government inspection may be initiated on a complete or individual operation basis.

(a) On a voluntary basis the contractor includes in his quality assurance provisions written quality control procedures evaluated and approved by the Government.

(b) Verification inspection by the Government in accordance with 4.1.2.1 indicates that the quality of product continues to be equal to or better than that required by this specification and the referenced documents,

4.1.2.3 At such time as the contractor meets the conditions of 4.1.2.2 above, Government verification will consist of, as a minimum, inspection for critical defects, monitoring of contractor's quality assurance system for strict compliance to the written plan and review' of contractor records on all inspection performed. If the contractor's quality deteriorates or a departure from the written plan is noted, the Government inspector will immediately notify the contractor to take corrective action and until the deficiencies have been corrected, Government verification in accordance with 4.1.2.1 will be performed on those characteristics involved to determine acceptability of the product. If corrective action is not taken by the contractor, as requested by the Government, acceptance of the product may be suspended. Upon correction of the deficiencies, the Government will continue inspection as prescribed in paragraph 4.1.2.2.

4.2 Preproduction lot. Prior to the start of regular production, the contractor shall submit a preproduction lot manufactured by the same methods and equipment that will be utilized in performing the work under contract, The contracting officer will furnish instructions for shipment of the lot to a designated Government laboratory or proving ground for examination and test. The preproduction lot shall consist of the following:

(a) 16 complete mine assemblies.

(b) 25 sets of component parts.

Each assembly and component part shall be inspected for all the requirements of the applicable drawings and specifications.

4.2.1 Results of the tests will be furnished to the contractor. (Approval or disapproval of the preproduction samples will be given by the responsible testing activity). Instructions for the submission of new samples in case of disapproval of the original sample will be issued by the testing activity. Regular production shall not proceed until the preproduction sample has been approved.

4,3 Acceptance inspection.

4.3.1 Lot, A lot shall consist of mines produced by one manufacturer under one contract, in one unchanged process in accordance with the same drawing, same drawing revision, same specification, and same specification. revision.

4.3.2 Examination. Examination inspection will be performed as specified in MIL-G-2550 and as indicated below. Sampling criteria will be in accordance with Standard MIL-STD-105 or Publication ORD-M608-11 as appropriate.

Source: https://assist.dla.mil -- Downloaded: 202610-19T07:48Z
Check the source to verify that this is the current version before use.

4.3.2.1 Classification of defects, Inspection of the mines shall be as indicated in the following subparagraphs.

4.3.2.1.1 Spotting charge assembly (see Drawing (dwg) 8.2-15-26 covering a detail of Dwg. 82-0-112).

	Categories and defects	Method of inspection
Major	AQL 0.25 percent	
1.	Delay assembly missing	Visual.
2.	Delay charge missing	Visual.
Minor	AQL 0.40 percent	
41.	Incomplete 360 degree crimp of shell disc in Assembly.	Visual.

4.3.2.1.2 Tube assembly (see dwg. 82-15-26, covering a detail of dwg. 82-0-112).

	Categories and defects	Method of inspection
Major	AQL 0.40 percent	
1.	Diameter of spotting charge hole	Gage.
2.	Outside diameter	Gage.
3.	Height	Gage.
Minor	AQL 1.00 percent	
41.	Protective coating inadequate	Visual.
42.	Assembly damaged	Visual.

4.3.2.1.3 Container, metal, prior to sealing (see dwg. F7548411) .

	Categories and defects	Method of inspection
Major	AQL 0.25 percent	
1.	Incorrect number of spotting charges or igniter charges (as applicable).	Visual.

4.3.2.1.4 Contain ers, metal (see dwg. F7548411).

	Categories and defects	Method of inspection
Major	AQL 0.25 percent	
1.	Air pressure test failure	Approved tests.
Minor	AQL 1.50 percent	
41.	Contents loose upon shaking	Manual.
42.	Protective coating inadequate	Visual.
43.	Key missing	Visual.
44.	Marking missing, misleading or illegible.	Visual.

4.3.2.1.5 Box, packing (prior to seeding) (see dwg. lV.5.48180).

	Categories and defects	Method of inspection
Major	AQL 0.40 percent	
1.	Incorrect number of mines, caps, metal containers, wire spools, fuzes, or tube assemblies.	Visual.
2.	Waterproof bag damaged	Visual.
3.	Waterproof bag improperly sealed.	Visual.
Minor	AQL 0.40 percent	
41.	Contents insecure or improperly located.	Visual-manual.

4.3.2.1.6 Box, pazking (see dwg, F7548180),

	Categories and defects	Method of inspection
Minor	AQL 1.50 percent	
41.	Strapping insecure	Visual.
42.	Car seal improperly assembled	Visual.
43.	Failure to encircle box with light blue band of paint.	Visual.
44.	Marking missing, misleading or illegible.	Visual.

4.3.3 Test inspection. Test inspection will be conducted as follows: The test specified below shall be conducted by the contractor as specified in MIL-G-2550 in accordance with the methods specified in paragraph 4.4.

4.3.3.1 Functioning. Fifteen sample mines shall be selected for the test described in 4.4.2. A retest may be made if requested by the contractor if:

(a) No premature burst occurs (see 6.1).

(b) More than one but not more than three duds occur.

(c) Not more than one mine bursts at a height of less than 6 feet above the surface of the ground, or

(d) Not more than one mine fails to burst at a height above 6 feet with an audible report within 3.8 to 5.5 seconds,

Double the number of samples shall be used in the retest. The lot will be rejected if in the combined test and retest:

(a) A premature burst occurs (see 6.1).

Source: https://assist.dla.mil -- Downloaded: 202610-19T07:48Z
Check the source to verify that this is the current version before use.

(b) More than three duds occur.

(c) More than one mine bursts below 6 feet above the surface of the ground, or

(d) More than one mine fails to burst at a height above 6 feet with an audible report within 3.8 to 5.5 seconds.

4.3.4 Examination equipment,

4.3.4.1 Government verification inspection. Government verification inspection will be accomplished with the use of gages and equipment that has been certified, by the contracting officer, to the design specified in the "List of Inspection Equipment, number GL-8802226."

4.3.4.2 Contractor inspection, Unless otherwise specified herein, contractor inspection will be accomplished with the use of gages and equipment designed to perform, to the required accuracy, the inspections and controls delineated in the contractor's written description specified in 4.1.1, In inspecting the contractor's inspection equipment the Government will determine that the contractor has available and utilized correctly, gaging, measuring and test equipment of required accuracy and that the instruments are of proper type and range to make measurements of the required accuracy. The contractor shall have available a set of master gages, standards, and appropriate instruments for regularly scheduled calibration of his inspection equipment. Records of such regularly 'scheduled calibration shall be maintained by the supplier and made available for review by the Government. The calibration of gages, standards, and instruments will be periodically checked by authorized Ordnance personnel.

4.4 Test methods and procedures.

4.4.1 Determination of the moisture content of black powder. The moisture content of the black powder shall be determined at the loading station at the time of loading, The method of determining the percentage of moisture shall be in accordance with Specification JAN-P-228.

4,4.2 Functioning, The sample mines shall be assembled with M10A1 fuzes being packed with the mines and tested as follows:

4.4.2.1 Plant each mine in a hole with base on firm ground. Cover entire mine up to the top of fuze and fire with pull wire. Observe for proper functioning.

4.5 Acceptance, The lot of mines will be accepted on the following basis:

4.5.1 At the beginning of the contract and as long as the Government inspector continues to perform the verification specified in 4.1.2.1, acceptance will be based on the results of the Government verification SPEcified in 4.1.2.1.

4.5.2 After reduced Government verification specified in 4.1.2.2 has been initiated, acceptance will be based on the results of the contractors inspection and quality control and the inspections reserved solely for performance by the Government and the results of the monitoring by the Government of the contractor's quality assurance system.

5. PREPARATION FOR DELIVERY

5.1 Level A — Packaging, packing, and marking, Packaging, packing, and marking shall be in accordance with dwgs. F7548411 and F7548180.

5.2 Data cards. Data and information shall be as specified in Specification MIL-G-2550.

6. NOTES

6.1 Premature burst. A premature burst is defined as a burning or functioning of the mine in less than 2 seconds.

6.2 Ordering data. Procurement documents should specify the title, number, and date of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:48Z
Check the source to verify that this is the current version before use.

Notice. This specification, together with specifications and drawings pertaining to it and bearing a "Notice" of similar restrictions, is intended for use only in connection with procurement by the United States Government, and shall not be reproduced either wholly or in part except when authorized in connection with Government procurement., nor be used for any other purpose except when specifically authorized by the Chief of Ordnance, Department of the Army.

Custodian :
Army--Ordnance Corps
Navy—Bureau of Ordnance
Air Force-WADC

Preparing activity:
Army-Ordnance Corps

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:48Z
Check the source to verify that this is the current version before use.