MIL-P-20442B(AR)
AMENDMENT 2
10 August 1981
SUPERSEDING
AMENDMENT 1
22 August 1969

MILITARY SPECIFICATION

PLUGS, LIFTING (EYEBOLT TYPE)
FOR PROJECTILES

This amendment forms a part of Military Specification MIL-P-20442B (MU), dated 8 May 1968.

Page 1

Add the following Preamble underneath the title: "This specification is approved by the US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense."

2.1 Specifications:

Add: Federal

QQ-S-781-Steel, Stopping Flat
PPP-B-587-Boxes, Wood, Wirebound Pallet Type

Add: Military

"MIL-B-121-Barrier Material, Water Vaporproof, Flexible

"MIL-B-13239-Barrier Material, Waterproofed, Flexible all Temperature."

Drawings, Army, 10520911: Delete "Detonator" and substitute "Detector."

Page 4

*4.2.1, lines 4 and 5: Delete "assemblies and twenty-five each of every component "and substitute "lifting plugs (20 plugs unphosphated and unpainted and 5 phosphated and painted)."

FSC 1320

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:49Z
Check the source to verify that this is the current version before use.

Page 6

*4.3.2.1:

Major Category: Add "107 Perpendecularity of pitch diameter of threads with shoulder...Gage 01015. 108. Distance from thread undercut to outside of flange 360° min...Gage 01016."

Minor Category: Add "209. Chamfer missing...Visual 01017."

Page 7

4.3.2.4, Minor Category:

201: Delete "and collar"
206: Delete "Gage" and substitute "Visual"

Page 8

4.3.2.5, Major Category: Delete Major Defect 108 in its entirety and substitute the following: "108. Perpendicularity of pitch diameter to collar...Gage 05008." Add Major Defect 111 to read as follows: "111. Perpendecularity of pitch diameter to shoulder ...Gage 05019."

Page 10

Delete Section 5 in its entirety and substitute the following: "5. PREPARATION FOR DELIVERY"

5.1 Level C

5.1.1 Lifting plugs shall be packaged and packed in accordance with Standard MIL-STD-1169.

5.1.2 Alternatively, Type G lifting plugs shall be packed in a wood, pallet type, wirebound box with interior packing as described herein.

5.1.2.1 Trays - 36 lifting plugs shall be placed in a tray, Panta-Pak Number L. A. 36 cavity, made from 10-mil thick natural color polyethylene 13 1/2 inches by 16 1/8 inches (see 6.4); trays of equivalent design may also be used. The tray shall be placed in a 125-pound test, B flute, corrugated fiberboard tray. The tray shall be made from a corner cut sheet 17 5/8 by 20 1/4

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:49Z
Check the source to verify that this is the current version before use.

inches, outside dimensions, cut and scored to form 2-inch flaps. The inside tray dimensions when the flaps are folded 90° shall be 16 1/4 by 13 5/8 inches.

5.1.2.2 Shipping Container - 42 trays (1512 lifting plugs), shall be arranged 2 by 3 trays in a layer, 7 layers high, in a wirebound pallet box conforming to the general requirements of Type 1, Class 2 of Federal Specification PPP-B-587 and the following requirements. The inside dimensions shall be approximately 32 3/4 by 41 1/4 by 23 1/8 inches. All dimensions for the base, sides and top stated below are minimum dimensions. A sheet of CW 2 or T2 barrier paper complying with requirements of Military Specification MIL-B-13239 shall be located across the top of the load and completely cover the top layer of trays. Alternately, Type 2, Grade A, Class 1 barrier material complying with Military Specification MIL-B-121 may be used. Box assembly shall include driving a minimum of three, 2 1/2 inch long, 11 gage (.120 diameter) drive screw nails through the sheathing and bottom cleat of each side section into the adjacent riser batten of the base. Two 3/4 x .028 steel straps complying with Type I or IV, Class A or C, of Federal Specification QQ-S-781 shall be applied parallel with the stringers, around the box over the 1 1/8 x 7/8 inch battens of the top.

5.1.2.2.1 The pallet base shall be constructed with three stringers 3 5/8 x 1 5/8. Three riser battens 2 3/4 wide by 15/16 thick shall be located at 90° to the stringers and 17/32 deck material located at 90° to the riser battens Bottom deck boards are not required.

5.1.2.2.2 The four-section box sidewalls shall consist of two edge and two intermediate 13/16 by 7/8 inches cleats at each section. The cleat dimensions from the bottom cleat to the intermediate cleats shall be approximately 6 and 16 inches. Sheathing shall consist of eight 3 5/8 wide by 3/8 inch thick boards at the corners of the made-up box. Additionally, two boards of like dimensions shall be located about 8 inches in from each outside corner of the longest sections of the box (front and back). The remaining portions of each box panel shall be sheathed with 7/32 veneer. One 12 gage galvanized binding wire ending in wide and narrow loops shall be stapled over row of cleats, and one at the approximate center of the panel. Staple spacing shall not exceed 1 1/2 inches.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:49Z
Check the source to verify that this is the current version before use.

5.1.2.2.3 The top shall be made of sheathing material which is 5/16 inch resawn boards stapled to three 2 1/4 wide x 3/8 inch think liners equally spaced and two 1 1/8 inch x 7/8 inch thick battens, with ends mitered at 45 degrees, located midway between the outside and intermediate 3/8 thick liners. The liners and battens shall be on the outside of the top with the sheathing fitted inside the side cleats. Liners shall extend over the top cleats of the front, back and sides.

5.1.3 Marking - Marking shall be in accordance with Standard MIL-STD-1169

Section 6, add:

"6.4 Panta-Pak trays are a product of the Pantacote Company, Panta-Pak Division, 26 Jefferson Street, Passaic, New Jersey 07056 (see 5.1.2.1)."

"The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment."

Custodian:
Army - AR

Preparing Activity:
Army - AR

Project No: 1320-A611

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T07:49Z
Check the source to verify that this is the current version before use.