MILITARY SPECIFICATION

ANTENNA ASSEMBLY AT-197()/GR

This amendment forms a part of Military Specification MIL-A-4946B, dated 18 March 1965, and is mandatory for use by all Departments and Agencies of the Department of Defense.

Page 2, paragraph 2.1: Under Military standards, following "MIL-STD-196" add "MIL-STD-202-Test Methods For Electronic and Electrical Component Parts."

Page 6, paragraph 4.3, at end of sentence add: "as specified in MIL-STD-202."

Page 6, paragraph 4.3.1, delete and substitute:
"4 3.1 Order of tests. The tests shall be run in the order shown in Table I "

Page 7, paragraph 4.5.1. delete and substitute·
"4.5.1 Inspection of product for delivery. Inspection of product for delivery shall consist of groups A, B, and C."

Page 7. table III, column 5, under AQL (% Defective): Delete entire column.

Page 8, following paragraph 4.5.1.4.2 add.
"4.5.1 5 Group C inspection. Group C inspection shall consist of the power test (see 4.6.3.6), vibration (4 6.4 7) and rain (4.6.4.9) and shall be conducted on one antenna out of each lot of 200 or fraction thereof produced on the contract or order, except that the first samples selected shall be from the first units produced.

4 5.1.5.1 Disposition of sample units Sample units which have been subjected to group C inspection shall not be delivered on the contract or order

4.5.1.5.2 Noncompliance. If a sample fails to pass group C inspection, the supplier shall take corrective action on the materials, process, or both, as warranted, and on all units of product which can be corrected and which were manufactured under essentially the same conditions, with essentially the same materials, processes, etc, and which are considered subject to the same failure. Acceptance of the product shall be discontinued until corrective action, acceptable to the Government, has been taken. After the corrective sample units (all inspection, or the inspection which the original sample failed, at the option of the Government). Groups A and B inspection may be reinstituted; however, final acceptance shall be withheld until the group C inspection has shown that the corrective action was successful. In case of failure after reinspection, information concerning the failure and corrective action taken shall be furnished the contracting officer."

Page 9, paragraph 4.6.3.6, add the following sentence:
"The continuity and VSWR shall then be checked in accordance with 4.6.2 and 4.6.3.2."

Page 9, paragraph 4.6.4, add the following sentence:
"After each environmental test, the continuity and VSWR shall be checked in accordance with 4.6.2 and 4.6.3.2 "

Page 9, paragraph 4.6.4.1, add the following sentence:
"A certified statement by the contractor that all materials are non-nutrient will be acceptable in lieu of this test."

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:55Z
Check the source to verify that this is the current version before use.

Page 10, paragraph 4.6.4 9(c) and (d), add the following sentence:
"1132 volts, 60 Hz with one ampere available may be used instead of 1 KW RF."

Page 10, paragraph 4.6.4.9, last sentence: Delete "herein" and substitute "in section 3."

Page 11, paragraph 5.1.2, delete and substitute:
"5.1.2 Level C. Each antenna shall be packaged in a manner that will afford adequate protection against corrosion, deterioration and physical damage during shipment from the supply source to the first receiving activity for immediate use or controlled humidity storage. Packaging may conform to suppliers commercial practice when such meets the requirements of this level."

Custodians:
Army - EL
Air Force - 85

Review activities
Army - EL
Air Force - 85

User activities
Army - AV
Air Force - 17

Preparing activity:
Air Force - 85

(Project 5985-0593)

Code "C"

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:55Z
Check the source to verify that this is the current version before use.