MILITARY SPECIFICATION

MAINTENANCE PLATFORM

This specification is approved for use by the Department of the Air Force, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE.

1.1 Scope. This specification covers one type of aircraft maintenance platform.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

UU-T-81	Tag, Shipping and Stock
PPP-B-601	Boxes, Wood, Cleated Plywood

MILITARY

MIL-P-116	Preservation, Methods Of
DOD-D-1000	Drawing, Engineering and Associated Lists
MIL-C-3774	Crate, Wood, Open 12,000 And 16,000 Pound Capacity

STANDARDS

FEDERAL

FED-STD-595	Colors

MILITARY

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: the Engineering Division, San Antonio ALC/MMEDO, Kelly APB, Texas 78241 by using the self addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 1730

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

MIL-STD-105	Sampling Procedures And Tables For Inspection By Attributes
MIL-STD-129	Marking For Shipment And Storage
MIL-STD-130	Identification Marking Of U.S. Military Property
MIL-STD-143	Standards And Specifications, Order Of Precedence For The Selection Of
MIL-STD-162	Materials Handling Equipment, Preparation For Shipment, Storage, Cyclic Maintenance, Routine Testing And Process
MIL-STD-794	Part And Equipment Procedures For Packaging And Packing Of
MIL-STD-808	Finish, Materials And Processes For Corrosion Preventive And Control in Support Equipment
MIL-STD-831	Test Reports, Preparation For
MIL-STD-1186	Cushioning, Anchoring, Bracing, Blocking, And Waterproofing, With Appropriate Test Methods

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

DRAWING S

Air Force

53J21491	Maintenance Platform Assembly, Aircraft, Type B-3
56J6283	Wiring Diagram - Aircraft Maintenance Platform Schematic
56J6284	Electric Cable - Aircraft Maintenance Platform, Installation Of
56J6291	Hydraulic System - Aircraft Maintenance Platform, Installation Of

* (Copies of specifications and standards required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3951 Standard Practice for Commercial Packaging.

(Application for copies of ASTM publications should be addressed to the American Society for Testing and Materials, 1916 Race Street, Phila PA 19103.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 First article. When specified, the contractor shall furnish a complete maintenance platform for first article inspection in accordance with 4.2 (see 6.3). The first article shall be identical with the proposed production

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

items, and shall be made assembled by the same methods that are to be used in production of the items to fulfill the terms of the contract. When specified, a first article test report shall be prepared in accordance with MIL-STD-831 and submitted to the contracting officer for approval. The approved samples and the first article report shall be used as the production standard.

3.2 Selection of specifications and standards. Specifications and standards for necessary commodities and services not specified herein shall be selected according to MIL-STD-143 except as provided in 3.2.1 and 3.2.2.

3.2.1 Commercial parts. Commercial parts having suitable properties may be used where, on the date of invitation for bids, there are no suitable standard parts. In any case, commercial utility parts, like screws, bolts, nuts, cotter pins, having suitable properties may be used provided:

a. They can be replaced by the standard parts (MS and AN) without alteration.

b. The corresponding standard part numbers are referenced in the parts list and, if practical, on the contractor's drawings.

3.2.2 Standard parts. With the exception of 3.2.1, MS and AN standard parts shall be used where they suit the purpose. They shall be identified on the drawings by their part numbers.

3.3 Design and construction. The design and construction of the maintenance platform shall conform to Drawings 53J21491, 56J6283, 56J6284 and 56J6291. If this specification and the drawings conflict, the specification shall govern.

3.4 Interchangeability. All parts having the same manufacturer's part number shall be functionally and dimensionally interchangeable. The drawing number requirements of DOD-D-1000 shall govern changes in the manufacturer's part number.

3.5 Finishes and protective coatings. All components of the maintenance platform shall be adequately protected against environmental deterioration. Interior surfaces shall be finished in accordance with MIL-STD-808, finishing scheme F105 or F106, whichever is applicable. Exterior surfaces shall be finished in accordance with MIL-STD-808, finishing scheme F101. The color shall be orange-yellow, color No. 13538 of FED-STD-595.

3.6 Erection instruction. Complete dismantling and erection instructions, including diagrams or photographs, written procedure in proper sequence, and reference to all parts by number, shall be provided in a waterproof envelope. A suitable container for storage of erection instructions shall be attached to the platform.

3.7 Performance. The maintenance platform shall be capable of operating during or immediately following subjection to each of the following conditions:

a. Operation during subjection to a 1000-pound static load (see 4.6.3).

b. 1,500 pounds applied to the work platform with the elevating system in the fully extended position (see 4.6.4).

Source: https://assist.dla.mil -- Downloaded: 2026l0-17T03:52Z
Check the source to verify that this is the currentversion before use.

c. 1,460 volts alternating current (AC) 60 cycle root mean square (rms) applied between each power cord and a metal part of the maintenance platform (see 4.6.1).

d. 50 cycles of operation with a platform load of 500 pounds (see 4.6.2).

3.8 Identification of product. Equipment, assemblies, and parts shall be marked for identification in accordance with MIL-STD-130.

3.9 Workmanship.

3.9.1 General. The maintenance platform including all parts and accessories, shall be fabricated and finished in a workmanlike manner; particular attention shall be given to the following:

a. Freedom from blemishes, defects, burrs, and sharp edges.

b. Accuracy of dimensions, radii of fillets, and marking of parts and assemblies.

c. Thoroughness of soldering, welding, brazing, painting, wiring and riveting.

d. Alignment of parts and tightness of assembly screws and bolts,

3.9.2 Riveting. Riveting operations shall be carefully performed to insure that the rivets are tight and satisfactorily headed.

3.9.3 Cleaning. The maintenance stand shall be thoroughly cleaned. Loose, spattered, or excess solder, metal chips, and other foreign material shall be removed.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of Inspections. The inspections of maintenance platforms shall be classified as follows:

a. First article inspection (see 4.3)

b. Quality conformance inspection (see 4.4)

4.3 First article inspection. Unless otherwise specified (see 6.3), first article inspection shall consist of the examination in 4.5 and all tests in 4.6. Failure of the preproduction sample to pass the preproduction inspection shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection. Quality conformance inspection shall consist of:

a. Examination (see 4.5).

b. Sampling plan (see 4.4.1).

4.4.1 Sampling plan. A random sample of platforms shall be selected from each lot and subjected to the tests specified in 4.6. The sample shall be selected in accordance with MIL-STD-105, General Inspection Level II. Unless otherwise specified, the AQL shall be 2.5.

4.4.2 Lot. For the purpose sampling, a lot shall be considered all platforms offered for inspection at one time.

4.5 Examination. Each platform shall be examined to determine compliance with this specification. All features and components shall be inspected with respect to design, construction, materials, workmanship and finishes. Particular attention shall be given to welds.

4.6 Sampling tests. Each of the sample platforms selected in accordance with 4.4.1 shall be subjected to the following tests. Any sample failing to pass any of the tests shall be rejected and if the total number of rejections exceed the acceptance number for the sample, the lot represented by the sample shall be rejected.

4.6.1 Dielectric test. The maintenance platform shall be subjected to a dielectric test of 1460 volts AC rms, 60 cycles, for a period of one minute between each lead of power cord and a metal part of the platform. For this test, an Ideal Commutator Dressor Company’s model 36 tester, or equal, may be used.

4.6.2 Endurance test. With a platform load of 500 pounds, the maintenance platform shall be operated through 50 cycles. A cycle shall be one complete operation from the lowest position to the highest position and back again to the lowest position. Two of these cycles shall be by manual operation. Inspection shall reveal no failure of welds, materials, bolts, elongation of bolt holes, or leakage of hydraulic fluid.

4.6.3 Static load test. The maintenance platform shall be completely assembled and a static load of 1,000 pounds placed at or near the center of the maintenance platform. The maintenance platform shall then be operated two times through the entire range. The load shall then be removed and the maintenance platform operated two times through its entire range. Inspection shall reveal no failure of welds, materials, bolts, elongation of bolt holes, or leakage of hydraulic fluid.

4.6.4 Settling test. With a load of 1,500 pounds on the maintenance platform, the elevating systems shall be in the fully extended position. The maintenance platform shall be allowed to remain under load for a period of one hour without locking devices in use. The settling rate of either elevating mechanism under this test load shall not exceed 0.020 inches per hour.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

4.6.5 Tear down inspection. After completion of the tests specified in 4.6.1, 4.6.2, 4.6.3 and 4.6.4, the maintenance platform shall be completely disassembled and inspected for failure of hydraulic packing.

4.7. Inspection for preparation for delivery. The presentation, packaging, packing and marking of the maintenance platform shall be examined and tested to determine conformance with the requirements of Section 5 of this specification, and as required by specifications referenced therein. Except as required by referenced specifications, inspection lots and sampling shall be level L-5 in accordance with M1L-STD-105 and the AQL shall be 4.0 percent defective.

5. PACKAGING

5.1 Preservation. Preservation shall be Level A,. C or standard practice for Commercial packaging (See 6.2).

5.1.1 Disassembly and matchmaking. Disassembly shall be the minimum necessary to safeguard parts known to be subject to damage, loss or breakage in transit and to accomplish reduction in cube. Bolts, nuts, screws, pins, washers and other attaching parts removed shall be reinstalled in one of the mating parts and secured to prevent their loss. When necessary to facilitate reassembly, parts removed and mating parts shall be matchmarked. Matchmaking shall be printed on shipping tags conforming to UU-T-81, Type A. The printed tags shall be waterproofed in accordance with MIL-STD-129,

5.1.2 Level A. The maintenance platform shall be preserved in accordance with Method I of MIL-P-116. All bare or unpainted metal surfaces subject to rust or corrosion shall be coated with P-1 type preservative. The hydraulic systems shall be preserved in accordance with MIL-STD-162. The electric cable shall be preserved and packaged Method IC of MIL-P-116.

5.1.3 Level C. The Level A preservation for the maintenance platform shall conform to the MIL-STD-794 requirements for this level.

5.1.4 Commercial. Commercial packaging shall be in accordance with ASTM D 3951.

5.2 Packing. Packing shall be Level A, B, C or Commercial (See 6.2).

5.2.1 Level A. The maintenance platform preserved and packaged as specified in 5.1.2 shall be packed in a container conforming to MIL-C-3774, Type II. All loose parts shall be packed in a container conforming to PPP-B-601, overseas type which shall be secured within the MIL-C-3774 crate. Containers shall be closed and strapped in accordance with the appendix of the applicable specification.

5.2.2 Level B. Same as level A, except the PPP-B-601 container shall be domestic type.

5.2.3 Level C. The Level C packing for maintenance platforms shall conform to the MIL-STD-794 requirements for this level.

5.2.4 Commercial. The preserved maintenance stands shall be packed in accordance with the requirements of ASTM D 3951.

Source: https://assist.dla.mil -- Downloaded: 202610-17T03:52Z
Check the source to verify that this is the current version before use.

5.3 Physical protection. All cushioning, blocking, bracing and bolting shall be in accordance with MIL-STD-1186.

5.4 Marking. In addition to any special marking required by the contract or order, interior containers and shipping containers shall be marked in accordance with the requirements of MIL-STD-129.

6. NOTES

6.1 Intended use. The maintenance platform covered by this specification is intended to facilitate maintenance and inspection of elevated portions of heavy aircraft.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number and date of this specification.

b. First article sample inspection when required and sample quantity and test report if different (see 3.1).

c. First article inspection if different (see 4.3).

d. Level of preservation, packaging, and packing (see 5.1).

6.3 First Article. When a first article inspection is required, the item will be tested and should be a first article sample or it may be a standard production item from the contractor's current inventory. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, tests and approval of the first article.

6.4 Changes from previous issue. The margins of this specification are marked with asterisks to indicate where changes (additions, modifications, corrections , deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
Air Force - 99

Preparing Activity:
Air Force - 82

Project No. 1730-F268

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
3b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)*. _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	7b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
7c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use submitting comments and suggestions for improvements. All users of military standardization documents are invited to provi suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, a mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE AIR FORCE

NO POSTAG
NECESSAR
IF MAILE
IN THE
UNITED STA

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 73236 WASHINGTON D C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE AIR FORCE

Engineering Division
San Antonio ALC/MMEDO
Kelly AFB, TX 78241

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T03:52Z
Check the source to verify that this is the current version before use.