MIL-C-21529D (Wep)
10 September 1962
Superseding
MIL-C-21529C (Weps)
4 October 1961

MILITARY SPECIFICATION

CABLE ASSEMBLIES , ELECTRICAL

This Specification has been approved by the Bureau of Naval Weapons, Department of the Navy.

1. SCOPE

1.1 Scope - This specification states the requirements for cable assemblies used on missile launcher tubes which are a part or the following missile launching systems:

Launcher Tubes	Launching Systems
Mark 4 Mods 0 1, 2, and 3	Mark 17 Mods 0 and 1
Mark 8 Mods 0 and 1	Mark 17 Mod 2 Mark 21 Mod 0
Mark 10 Mod 0	Mark 21 Mod 1

2. APPLICABLE DOCUMENTS

2.1 Documents - The following documents of the issue in effect on date of invitations for bids from a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-C-915	Cable, Cord, and Wire, Electrical (Shipboard Use)
MIL-C-3432	Cable, Flexible and Extra Flexible, 200 and 600 Volts
MIL-C-7078	Cable, Power., Electrical Copper, Shielded, Aircraft, 600-Volt

FSC 1440

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

MIL-E-5272	Environmental Testing, Aeronautical and Associated Equipment, General Specification for
MIL-F-18870	Fire Control, Equipment Naval Ship and Shore: General Specification
MIL-F-21568	Fluid Silicone, Dimethyl Polysiloxane

STANDARDS

MILITARY

MIL-STD-104	Limits for Electrical Insulation Color
MIL-STD-129	Marking for Shipment and Storage

DRAWINGS

NAVY DEPARTMENT

BUREAU OF NAVAL WEAPONS, Code Ident 10001

BuWep Dwg 2000441	Control Cable, Launcher Tube
Buwep Dwg 2000442	Instrumentation Cable, Launcher Tube
BuWep Dwg 2000443	Control Cable, Support Ring
BuWep Dwg 2024501	Cable Assembly (Straight)
BuWep Dwg 2024502	Cable Assembly (180 degrees)
BuWep Dwg 2024503	Cable Assembly (Branched)

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

BuWep Dwg 2025026	Cable 48-Conductor
BuWep Dwg 2025352	Hydrostatic Test Pressure Vessel
BuWep Dwg 2025358	Endurance Test Fixture
BuWep Dwg 2025363	Corrosion Test Fixture
BuWep Dwg 2025398	Hydrostatic Test Pressure Vessel
BuWep Dwg 2025526	Connector, Diaphragm Detonator
BuWep Dwg 2025527	Cable Asembly, Adapter Ring
BuWep Dwg 2025563	Cable Assembly
BuWep Dwg 2025567	Cable Assembly
BuWep Dwg 2025568	Cable, Assembly (Branched)
BuWep Dwg 2025569	Cable Assembly
BuWep Dwg 2244774	Cable Assembly (Control
BuWep Dwg 2244782	Cable Assembly (24 Conductor)

PUBLICATIONS

NAVY DEPARTMENT

BUREAU OF NAVAL WEAPONS

NAVWEPS OP 400	General Instructions for the Design, Manufacture, and Inspection of Naval. Ordnance Equipment
NAVWEPS OP 2230	Workmanship and Design Practies
NAVORD INST 4355.1	Equipment for Use by Government Inspectors in Final Inspection Naval Ordnance Items

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

BUWEPS INST 4355.5 Bureau of Naval Weapons Calibration Program

Standards Laboratory Information Manual

(Copies of specifications, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other Publications - The following documents form a part of this specification. Unless otherwise indicated, the issue in effect on date of Invitation for bids shall apply:

NATIONAL BUREAU OF STANDARDS

Handbook H28 Screw-Thread Standards for Federal Services

(Application for copies should be addressed to the Superintendent of Documents, Government Printing 0ffice, Washington 25, D.C.)

CONSOLIDATED CLASSIFICATION COMMITTEE

Uniform Freight Classification Rules

(Application for copies should be addressed to the Consolidated Classification Committee, 202 Chicago Union Station, Chicago 6, Illinois.)

3. REQUIREMENTS

3.1 Description -"The electrical cable assemblies provide the circuitry which links the launcher tube electrical components and instrumentation with the outer-tube connectors. The cable assemblies are individually identified as:

Cable Assembly	BuWep Dwg	Launching System
Control Cable, Launcher Tube	2000441	Mk 17 Mods 0, 1, and 2

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

Instrumentation Cable, Launcher Tube	2000442	Mk 17 Mods 0, 1, and 2
Control Cable, Support Ring	2000443	Mk 17 Mods O and 1
Control Cable, Support Ring	2024501	Mk 17 Mod 2 and Mk 21 Mods O and 1
Control Cable, Support Ring	2024502	MK 17 Mod 2 and MK 21 Mods 0 and 1
Control Cables Support Ring	2024503	Mk 17 Mod 2 and Mk 21 Mods O and 1
Control Cable, Support Ring	2025026	MK 17 Mod 2 and MK 21 Mods 0 and 1
Connector, Diaphragm Detonator	2025526	MK 21 Mod 1
Adapter Ring Cable	2025527	MK 21 Mod 1
Cable Assembly	2025563	MK 21 Mod 1
Cable Assembly	205567	MK 21 Mod 1
Cable Assembly	2025568	MK 21 Mod 1
Cable Assembly	2025569	MK 21 Mod 1
Control Cable	2244774	MK 21 Mod 1
Cable (24 Connector)	2244782	MK 21 Mod 1

3.2 General Requirements

3.2.1 Preproduction Sample - Unless otherwise specified in contract or order, preproduction samples of cable assemblies shall be manufactured using the methods and procedures proposed for the production lot. These Samples will be tested as specified in section 4 herein and are for the purpose of determining that the production item meets the requirements of this specification (refer to 4.2.1]. At the discretion of the “procuring agency, the requirement for a preproduction sample may be waived and shall then be satisfied by substitution or a production unit chosen at random by the Government Inspector.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

3.2.2 Materials - Unless otherwise specified in the contract, requisition, or order, all materials and purchased parts entering into the final cable assemblies shall conform strictly to the detailed requirements of the specifications, standards, and publications indicated on the drawings listed in 3.1.

3.2.2.1 Toxic Materials - A list shall be prepared of materials proposed for use in Cable assemblies, which may have a toxic potenttial. Use of materials which are toxic in submarine environment will not be approved. Potentially toxic materials include certain potting compounds and electrical Insulation.

3.2.3 Finishes, Coatings, Construction, and Dimensions - Finishes, coatings, construction, and dimensions for the cable assemblies shall be in accordance with applicable specifications, standards, and publications indicated on the drawings listed in 3.1.

3.2.4 Marking - The cable assemblies shall be marked to indicate the year of manufacture, and such marking shall conform to Specification MIL-C-915. Additional marking, if necessary, shall be in accordance with the applicable drawings listed in 3.1.

3.2.5 Interchangeability - Individual cable assemblies manufactured in agreement with their applicable -drawings and specifications shall be interchangeable with like numbered assemblies.

3.2.6 Gages - The contractor shall provide himself with whatever gages are necessary and adequate to insure that the material to which this specification applies will meet the dimensional requirements shown on the applicable drawings. If so stipulated in the contract, requisition, or order; the Government will furnish drawings of Navy Final Inspection Gages for guidance in the design of the contractor's inspection gages. However, such procedure shall not serve to relieve the contractor of his responsibility in the design and manufacture of such gages as may be required for the satisfactory fulfillment of the contract requirements, but is intended to facilitate acceptance of all components and assemblies by Navy Final Inspection Gages.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

Threads - Unless otherwise specified, all threads shall be in accordance with the National Bureau of Standards Handbook H28. The class or fit for threads shall be as specified on the applicable drawings.

3.2.8 Requests for Deviations - The procedure for requesting deviations from this specification or any specification, publication, material, or process specified herein, shall be as set forth in NAVWEPS OP 400.

3.2.9 Conflicting Requirements - In event of conflict between this specification and any specification, publication, or drawing referenced herein, this specification shall govern.

3.2.10 Tolerance - Unless otherwise specifically noted, tolerances and accuracies stated herein are absolute.

3.3 Performance Requirements

3.3.1 Dielectric Strength - The cable assemblies shall withstand a test voltage of 325-volts AC (rms) for 1 minute.

3.3.2 Insulation Resistance - The cable assemblies shall have an insulation resistance of at least 3 megohms when subjected to a test volage of 500-volts DC as specified in Specification MIL-F-18870.

3.3.3 Continuity - The cable assemblies shall provide continuous circuits between terminal points.

3.3.4 Flexure Endurance.

3.3.4.1 Cable Assembly - The cable assembly shall withstand 300 cycles of flexure at the rate of 1 cycle-per-minute.

3.3.4.2 Cable Connectors - The cable connectors shall withstand 300 cycles of flexure.

3.3.5 Ignition - The cable assembles shall have a minimum ignition time of 30 seconds, a maximum burning time of 120 seconds, and a maximum flame travel of 2 inches.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

3.3.6 Splicing - The individual internal conductors shall be continuous with no splicing. No test is specified for this requirement.

3.3.7 Color Coding - Multiple conductor cables shall be color coded in accordance with the applicable drawings, using a system consisting of basic colors with bands of varying widths. Colors should be readily distinguishable under incandescent light and should resist fading, running, or disclosuring due to heat. The colors shall be in accordance with Standard MIL-STD-104. No test is specified this requirement.

3.3.8 End Seals - To prevent absorption or moisture during shipment or storage in a manufacturer's plant, all cable ends shall be sealed in accordance with Specification MIL-C-915. No test is" specified for this requirement.

3.3.9 Forming - Cable assemblies shall have a circular cross section and uniform flexibility except in the location of a moulded breakout. No test is specifiecd for this requirement.

3.3.10 Shielding - Cables or conductors requiring shielding shall conform to the applicable requirements of Specification MIL-C-7078, Type II. The shielding shall be insulated and show a resistance of 1.5 megohms between any shield and all other shields or between any shield and ground when subjected to a test voltage of 500-volts DC as specified in Specification MIL-F-18870.

3.3.11 Fillers - All fillers shall be fungus inert and nonconducting.

3.4 Environmental Conditions

3.4.1 Temperature and Humidity - The cable assemblies shall withstand a relative humidity of 100 percents at temperatures between +70 and +160 degrees Fahrenheit, for 240 hours, shall show no damage, and. thereafter shall be capable of meeting all performance requirements of this specification

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

3.4.2 Low Temperature - The cable assemblies shall withstand ambient air temperature of -30 ± 5 degrees Fahrenheit for 20 hours, shall show no damage, and thereafter shall be capable of meeting all performance requirements of this specification.

3.4.3 Corrosion - The cable assemblies shall withstand submersion in sea water at temperatures between +28 and +100 degrees Fahrenheit for 90 consecutive days, shall show no corrosion, and thereafter shall be capable of meeting all performance requirements of this specification.

3.4.4 Hydraulic Fluid - The cable assemblies shall withstand the effects of silicone hydraulic fluid (MIL-F-21568) without damage, and thereafter shall be capable of meeting all performance requirements of' this specification.

3.4.5 Hydrostatic Pressure - The cable assemblies shall withstand an external hydrostatic pressure of 867 psig without leakage or damages and thereafter shall be capable of meeting all performance requirements of this specification.

3.4.6 Funges - The cable assemblies shall be capable of withstanding fungus conditions and shall be tested in accordance with MIL-E-5272.

3.4.7 Heat/Pressure Cycle - Cable assemblies Dwg 2024501, 2024502, 2024503, and 2025026, shall withstand the enviroment of 5 consecutive steam heat/pressure cycles without damage, and thereafter shall be capable of meeting all performance requirements of this specification. A steam heat/pressure cycle shall consist of a change in pressure from atmospheric pressure to 115 ± 15 psig and return to atmospheric pressure coincident with a temperature change from ambient to 325 ± 25 degrees Farhrenheit to 210 ± 20 degrees Fahrenheit within a maximum of 1 second, and then to ambient temperature within a maximum of 10 minutes.

3.5 Cleanup - Prior to and after final assembly, all parts, components and the assemblies shall be thoroughly cleaned of loose, spattered; or excess solder, metal chips, and other foreign matter. Burrs and sharp edges as well as rosin flash shall be removed.

3.6 Workmanship - The cable assemblies, including all parts and accessories, shall be constructed and finished in a manner to assure compliance with this specification. Particular attention shall be paid to neatness and thoroughness of soldering, wiring, marking of assemblies, and freedom of cables from lumps, bulges, burrs and sharp edges. NAVWEPS OP 2230 shall be used as a guide for determining acceptable workmanship.

Source: https://assist.dla.mil -- Downloaded: 2026l0-19T09:48Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Contractor's Inspection - Unless otherwise specified herein, the contractor is responsible for the performance of all inspection requirements prior to submission for Government inspection and acceptance. Except as otherwise specified, the contractor may utilize his own facilities or any commercial laboratory acceptable-to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order.

4.2 Government Inspection - The Government Inspector will make such inspections as are necessary to determine that components and assemblies are in accordance with the requirements of the contract, pertinent drawings and specifications. Unless otherwise specified, these inspections will be conducted in accordance with instructions contained in NAVWEPS OP 400. Production tests of final" assemblies shall be on a 100-percent basis. No sampling is permitted for acceptance inspection purposes. Only those assemblies which pass final inspection shall be accepted by the Navy; a rejected assembly may be reworked and submitted in accordance with NAVWEPS OP 400.

4.2.1 Preproduction Sample - The preproduction sample specified in 3.2.l shall be submitted to the Government Inspector for preproduction tests at an activity designated in the contract, or by the procuring activity, for purposes of determining compliance with requirements of the contract, specifications, and drawings. Further production of the item by the contractor prior to approval of the contracting activity, or the completion of tests on the preproduction samples, shall be at the contractor's risk. Preproduction samples accepted will be applied as part of the quantity specified by the contract or order.

4.3 Classification of Tests - The inspection and testing of the cable assemblies shall be classified as follows:

4.3.1 Production Tests - These tests are to be accomplished on each cable assembly being submitted for acceptance under the contract. Production tests shall be either performed by the manufacturer and witnessed by the Government Inspector, or these tests may be conducted by the Government Inspector. These tests are detailed in 4.5.

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

4.3.2 Preproduction Tests - Preproduction tests are those which are accomplished on samples selected as specified in 4.2.1 which are representative of the production of' the cable assemblies to determine that the production meets the requirements of this specification. These tests are detailed in 4.5 and 4.6. Acceptance shall be based on no defects in the sample. Failure of the sample to comply with these requirements will result in the cessation of production until determination of cause of failure is made and appropriate correction is approved by the procuring activity.

4.3.3 Tests After Delivery - Unless otherwise specified in the contract, the Government reserves the right to conduct any or all of the tests specified herein as deemed necessary after installation of the cable assemblies. Any defects discovered before, during, or after these tests, due to the contractor's failure to comply with drawings or specifications for this equipment, shall be corrected by the contractor at no expense to the Government, provided the contractor is notified of such defects within the guarantee period of the contract.

4.4 Special Test Equipment - The following items of special test equipment are required to perform the acceptance tests set forth in this specification:

Hydrostatic Pressure Test Vessel	BuWep Dwg 2025352
Endurance Test Fixture	BuWep Dwg 2025358
Corrosion Test Fixture	BuWep Dwg 202363
Hydrostatic Pressure Test Vessel	BuWep Dwg 2025398

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

4.5. Production Tests

4.5.1 Responsibility - The contractor or Government Inspector shall conduct production tests as specified in paragraph 4.3.1 to assure that the cable assembly is in compliance with the requirements of 3.3.1, 3.3.2, 3,3.3, 3.3.10, and 3.4.5.

4.5.2 Test Condition - Unless otherwise specified, the cable assemblies shall be subjected to production tests under the following conditions:

Temperature:	Ambient, +65 to +85 degrees Fahrenheit
Attudutite:	Normal ground atmospheric pressure
Vibration:	None
Humidity:	Relative humidity of 50 percent or less at +78 degrees Fahrenheit

4.5.3 Test and Inspection Equipment and Facilities - The manufacturer shall furnish and maintain all necessary test equipment, facilities, and personnel for performing all production tests. The test equipment shall be adequate in quantity and, unless definite requirements are specified, shall be of sufficient accuracy and quality to “permit performance of the required production tests.

4.5.3.1 Calibration - Measuring equipment and test instrumentation shall be calibrated as required by NAVORD INST 4355.1, BuWeps INST 4355.5, and in accordance with the policies specified in the Standards Laboratory Information Manual issued by Bureau of Naval Weapons Representative, Pomona, California.

4.5.4 Test Procedure

4,5.4.1 Dielectric Strength Test - To meet the requirements of 3.3.1, each cable assembly shall be subjected to a test voltage of 325-volts AC (rms) for 1 minute and shall show no damage.

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

4.5.4.2 Insulation Resistance Test - Each cable assembly shall be subjected to a test voltage of 500-volts DC, applied between any conductor and all other conductors, or between any conductor and the test fixture, and shall show an insulation resistance of at least 3 megohms to meet the requirement specified in 3.3.2.

4.5.4.3 Continuity Test - To meet the requirements of paragraph 3.3.3, each cable assembly shall be subjected to a point-to-point continuity check of each conductor within the assembly-and shall show no damage.

4.5.4.4 Hydrostatic Pressure Test - To meet the requirements of 3.4.5, each cable assembly shall be subjected to an external hydrostatic pressure of 867 ± 10 psig for 10 minutes, using test fixture (2025352 or 2025398). Upon completion of the tests the cable shall show no damage and shall pass the dielectric, insulation resistance, and continuity tests.

4.5.4.5 Shielding Resistance Test - Each cable assembly shall be subjected to a test voltage of 500-volts DC, applied between any shield and all other shields, or between any shield and ground, and shall show a resistance of at least 1.5 megohms to meet the requirement specified in 3.3.10.

4.6 Preproduction Tests

4.6.1 Flexure Endurance Tests

4.6.1.1 Cable Assembly - To meet the requirements of paragraph 3.3.4.1, one 18-inch section of a cable assembly, having passed the dielectric, insulation resistance, and continuity tests, shall be mounted in a test fixture (2025358) and tested by anchoring one end of the cable and flexing the free end through a vertical ellipse having radii of 6 inches vertically and 4 inches horizontally. The cable shall be flexed for 300 cycles at the rate of 1 cycle-per-minute. After testings the cable shall show no damage and shall pass the dielectric, Insulation resistance, and continuity tests.

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

4.6.1.2 Cable Connectors - To meet the requirements of paragraph 3.3.4.2, the cable connectors shall be flexed 90 degrees to each side, in two positions, for a total of 300 times, with a continuity check after each 25 flexures. After testing, the connectors shall show no damage and shall pass the dielectric, insulation resistance, and continuity tests,

4.6.2 Ignition Test - To meet the requirements of paragraph 3.3.5, one 18-inch (minimum) section of a control cable assembly, having passed the dielectric, insulation resistance, and continuity tests, shall be subjected to an ignition test in accordance with Specification MIL-C-915. The cable shall have a minimum ignition time of 30 seconds, a maximum burning time of 120 seconds, and a maximum flame travel of 2 inches.

4.6.3 Fungus Test - To meet the requirements of paragraph 3.4.6, one control cable assembly, after having passed the dielectric, insulation resistance, and continuity tests, shall have the main cable end sealed and be subjected to the fungus test as specified in Specification MIL-E-5272 for a period of 28 days. Upon completion Of the test, the cable assembly shall be examined in accordance with Specification MIL-E-5272 and shall pass the dielectric, insulation resistance, and continuity tests.

4.6.4 Temperature and Humidity Test - To meet the requirements of 3.4,1, one control cable assembly, having passed the dielectric, insulation resistance, and continuity tests, shall have the main cable end sealed and be subjected to temperatures between +70 and +160 degrees Fahrenheit, with a relative humidity of 100 percent, for a period-of 240 hours. The humidity cycle shall be in accordance with Specification MIL-E-5272. After testing, the cable shall show no damage and shall pass the dielectric, insulation resistance, and continuity tests.

4.6.5 Low Temperature ‘Test - To meet the requirements of 3.4.2, one 10-foot (minimum) section of a control cable assembly, having passed the dielectric, insulation resistance, and continuity tests, shall be refrigerated “to -30 $\pm$ 5 degrees Fahrenheit for 20 hours and then subjected to bending in accordance with Specification MIL-C-3432. After testing, the cable shall show no damage and shall pass the dielectric, insulation resistance, and continuity tests .

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

4.6.6 Corrosion Test - To meet the requirements of paragraph 3.4.3, one control cable assembly, having passed the dielectric, insulation resistance, and continuity tests, shall be mounted in a test fixture (2025363), have the ends sealed, and be immersed in sea water at temperatures between +28 and +100 degrees Fahrenheit for 90 consecutive days. As an alternate, the cable assembly may be tested by 15 cycles of submersion. A cycle shall consist of submerging the cable in sea water at temperatures between +28 and +100 degrees Fahrenheit for a minimum of 22 hours, removing the cable from the water for 2 hours, and then washing it with fresh water. After testing, the cable shall show no damage and shall pass the dielectric, insulation resistance, and continuity tests.

4.6.7 Hydraulic Fluid Test -To meet the requirenments of 3.4.4, one 3-foot (minimum) section or a control cable assembly, having passed the dielectric, insulation resistance, and continuity tests, shall have the ends sealed and be immersed in silicone dimethyl polysiloxane fluid, Specification MIL-F-21568, at a temperature of +68 $\pm$ 5 degrees Fahrenheit, for 10 consecutive days, in accordance with Specification MIL-C-915. After testing, the cable shall show no damage and shall pass the dielectrics, insulation resistance, and continuity tests.

4.6.8 Heat/Pressure Cycle Test - One each of the cable assemblies listed in 3.4.7 shall be installed in a prototype launcher (Peashooter), or an acceptable equivalent test apparatus, and shall be subjected to a heat/pressure test environment to meet the requirements specified in 3.4.7.

4.7 Rejection - Failure of the cable assemblies to meet any of the requirements and tests of this specification shall be considered cause for rejection.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging - Preservation and packaging of the electrical cable assemblies shall be Level A or Level C as follows:

5.1.1 Level A - Level A shall be as specified by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

5.1.2- Level C - Cleaning, drying, preservation, and unit packaging shall be in accordance with the manufacturer's commercial practice. Each electrical cable assembly shall be packed one to a package.

5.2 Packing - Packing of the electrical cable assembly shall be Level A or Level C as follows:

5.2.1 Level A - Level A shall be as specified by the procuring activity.

5.2.2 Level C - The electrical cable assembly, packaged as specified in 5.1.2, shall be packed to afford protection against damage during shipment from the supply source to the first receiving activity for immediate use, Containers shall comply with Uniform Freight Classification Rules or other common-carrier regulations applicable to the mode of transportation.

5.3 Marking - Unit packages and shipping containers shall be marked in accordance with the requirements of Standard MIL-STD-129.

6. NOTES

6.1 Ordering Data - Procurement documents should specify the following:

(a) Title, number, and date of this specification.

(b) Exceptions to this specification, applicable drawings, and other documents.

(c) Selection of applicable levels of preservation, packaging and packing.

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, uses or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T09:48Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

Chief, Bureau of Naval Weapons
Engineering Division
Attn: Code RREN-5
Department of the Navy
Washington, D. C. 20360

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

ORGANIZATION *(Of submitter)* | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?.

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 APR 63 1426 REPLACES NAVSHIPS FORM 4863, WHICH IS OBSOLETE C-8279

Source: https://assist.dla.mil -- Downloaded: 202610-19T09:48Z
Check the source to verify that this is the current version before use.