MILITARY SPECIFICATION

CONTROL PANEL: 10526300

This amendment forms a part of Military Specification MIL-C-60208(MU), dated 8 March 1965.

Following paragraph 4.1.1, add paragraphs 4.1.2, 4.1.2.1 and 4.1.2.2.

"4.1.2 First article (initial production) approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of three (3) control panels manufactured in the same manner using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.1.2.1 Government testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.1.2.2 Contractor testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected and a record of this inspection, including certificates of conformance for materials shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection."

Paragraph 4.2.3: Add the following sentence: "No lots shall be accepted until control samples have been satisfactorily tested."

Paragraph 4.3.2 Delete first sentence and substitute:

"Control panels shall be selected at random by a Government representative as control samples from each three (3) months production or portion thereof as follows:

3 units per first 100 produced
5 units per 200
7 units per 300
9 units per 400
10 units per 500
12 units per 700
15 units per 1000
and 2 units for each 100 items produced in excess of 1000."

FSC 1220

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:17Z
Check the source to verify that this is the current version before use.

Paragraph 4.5.1.3.2: Delete in its entirety and substitute:

"4.5.1.3.2 Operating.- This test shall be conducted in accordance with the humidity test defined in Procedure III of MIL-F-13926, except that the humidity shall be maintained at 92 to 97 percent for the 24 hour period, and the test shall cease at the end of that period (Method 106 of MIL-STD-202 shall be excluded). Throughout the test period, the unit shall be capable of performing the tests of 4.5.2.2 through 4.5.2.8. In order to demonstrate this capability, the tests of 4.5.2.2 through 4.5.2.8 shall be performed a minimum of once each 6 hours of the 24 hour period."

Paragraph 4.5.2.5(b): Delete "+125 ±5vdc" and substitute "+125 ±5vdc ground return".

Paragraph 4.5.2.5(c): Delete "-125VDC" and substitute "+125vdc ground return".

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1220-A188



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:17Z
Check the source to verify that this is the current version before use.