MILITARY SPECIFICATION

PROJECTILE, GUIDED,
155MM, XM712, WARHEAD FOR

This amendment forms a part of Military Specification MIL-P-63226(AR), dated 1 August 1979, and is approved for use by the US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

Title: Add "M712" to title and wherever it appears in this specification.

Specifications, Military: Add, "MIL-C-450C Coating Compound Bituminous Solvent Type".

PAGE 2

DRAWINGS: Delete the following:

"9300922 - "Adhesive, Explosive Compatible Epoxy, Two Component
"9307009 - Seal, End Closure
"9307046 - Wiring Harness,Warhead - 3W1 - 3W2".

DRAWINGS: Add the following:
"9300374 - Filler, Molded
"9300786 - Adhesive, Explosive Compatible
"9300790 - Adhesive, Epoxy, Two Component
"9300792 - Powder Fluorescent
"9300793 - Release Agent
"9307062 - Seal, Cable Exit
"9307069 - Wiring Harness"

Delete the following in its entirety:

"Equipment Operating Instructions

"EOI 9304456 - Warhead Test Set, Equipment Operating Instruction"

FSC: 1320



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.

PAGE 3

3.2.1.1, line 8: Delete "9307046 and substitute "9307069"

3.2.1.2, line 8: Delete "9307046" and substitute "9307069". Delete the following: "This requirement does not include fuze wiring.".

3.2.1.3, line 2: Delete "installation" and substitute "electrical connection".

line 3: Add "The electrical checks per Table 1 are not required, at the warhead section level, if performed as part of the warhead section/control section cable resistance checks."

PAGE 4

3.2.1.4, line 2: Delete "$10^{-4}$" and substitute "$10^{-2}$".

PAGE 6

3.2.1.5.7.2(b): Delete in its entirety and substitute the following:

"3.2.1.5.7.2(b) Cavitation, cracks or annular rings in segments A or B in excess of that permitted by the applicable requirement, but not in excess of twice that permitted, except that such cavities when located more than 1.00 inch from the warhead axis in segment A shall be disregarded."

PAGE 7

Add the following paragraphs:

"3.2.1.9 Bonding aft harness.

"3.2.1.9.1 After bonding the harness to 4.03 diameter surface, assure smooth, void and air bubble free adhesive in slots and under and around cables.

"3.2.1.9.2 After bonding glass cloth tape strips to 4.03 diameter, assure smooth continuous outer surface of adhesive and smooth continuous fillets covering all edges of the glass cloth tape. No voids, bubbles, or adhesive starved areas shall be visible.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.

"3.2.1.9.3 After bonding the metal shims assure no voids, discontinuities of air bubbles are visible along any edge of shim."

PAGE 10

4.5.3: Delete in its entirety and substitute the following:

"4.5.3 Leak test. The empty warhead assembly shall be pressurized to 15 ± 1.0 psig. The leakage rate shall not exceed the equivalent of $10^{-2}$ cc/sec of air at standard conditions. A leak rate of $10^{-4}$ cc/sec of air at standard conditions may be detected by immersion in water or other clear liquid for 30 seconds minimum. A continuous stream of bubbles will be emmitted if the leak exceeds $10^{-2}$ cc/sec."

4.5.4.3: Delete in its entirety and substitute the following:

"4.5.4.3 Warhead section test. The electrical characteristics of the warhead section shall be tested and shall meet the requirements of Table I. If the fuze module was mechanically installed in the warhead prior to the time of the tests of 3.2.1.2 were conducted, it is not necessary to retest conductors 6 thru 18 in Table I. Resistance measurements shall be made with the positive output of the meter connected to the "From" conductor and the negative output of the meter connected to the "To" conductor of Table I. The test current shall be limited to 1 milliamp or less. The electrical checks per Table 1 are not required, at the warhead section level, if performed as part of the warhead section/control section cable resistance checks. However, if the warhead is supplied as GFM, then all of the tests in Table I are applicable."

PAGE 16

Add the following paragraph:

"4.5.12 Explosive leakage inspection. The warhead shall be inspected to verify conformance to the non-leakage requirement of 3.2.1.6."

PAGE 22

Critical 1, 2, and 3: Delete in their entirety and substitute the following:



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.

| | | | | |
|---|---|---|---|---|
| "1 | No explosive material, other than within charge cavity | 100% | 3.2.1.6 | 4.5.12 |
| "2 | Warhead cavity finish/ cleanliness | 100% | 3.2.1.7 | 4.5.9 |
| "3 | Defects in explosive charge | 100% | 3.2.1.5.7.1 | 4.5.5<br>4.5.6" |

PAGE 25

Major 108: Delete in it's entirety and substitute the following:

| | | | | |
|---|---|---|---|---|
| "108 | Distance between face of liner and datums A and B | 0.40% | Dwg | Gage" |

PAGE 28

Critical: Delete the following in their entirety:

| | | | | |
|---|---|---|---|---|
| "1 | Thickness | 100% | Dwg. | Gage |
| "2 | Material | NA | Dwg | Vendor Lot Certification |
| "3 | Hardness | 100% | Dwg | Gage" |

Major: Add the following:

| | | | | |
|---|---|---|---|---|
| "101 | Thickness | 100% | Dwg | Gage |
| "102 | Material | NA | Dwg | Vendor Lot Certification |
| "103 | Hardness | 100% | Dwg | Gage" |

PAGE 33

Critical: Delete the following in their entirety:

| | | | | |
|---|---|---|---|---|
| "1 | Inspection of weld and heat treatment, including cracks. | 100% | Dwg | 9300967 |
| "2 | Material | 100% | Dwg | 9300967 |
| "3 | Dry lube on groove surface | 100% | Dwg | Visual |
| "4 | Runout of aft interface shoulder to forward and aft datums | 100% | Dwg | Gage |



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.

| | | | | |
|---|---|---|---|---|
| "5 | Length of aft interface cylinder | 100% | Dwg | Gage |
| "6 | Location of lock ring groove from aft interface shoulder | 100% | Dwg | Gage" |

Critical: Add the following:

| | | | | |
|---|---|---|---|---|
| "1 | Inspection of weld | 100% | Dwg | 9300967 |
| "2 | Heat treatment, yield and ultimate strength | Dwg | Dwg | 9300967 |
| "3 | Inspection for cracks | 100% | Dwg | 9300967" |

Major: Add the following:

| | | | | |
|---|---|---|---|---|
| "111 | Material | 100% | Dwg | 9300967 |
| "112 | Dry lube on groove surface | 100% | Dwg | Visual |
| "113 | Runout of aft interface shoulder to forward and aft datums | 100% | Dwg | Gage |
| "114 | Length of aft interface cylinder | 100% | Dwg | Gage |
| "115 | Location of lock ring groove from aft interface shoulder | 100% | Dwg | Gage |
| "116 | Heat treatment, elongation | Dwg | Dwg | 9300967" |

PAGE 38

Critical: Delete the following in their entirety:

| | | | | |
|---|---|---|---|---|
| "1 | No unsolidified paint in charge cavity | 100% | 3.2.1.7 | 4.5.9 |
| "2 | Finished surfaces | 100% | 3.2.1.7 | 4.5.9 |
| "3 | Adhesive | NA | Spec. | 9300922 - Vendor lot Certification" |



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.

Critical: Add the following:

| | | | | |
|---|---|---|---|---|
| "1 | Adhesive explosive compatibility | NA | Dwg | 9300786 |
| "2 | Bond of aft harness | 100% | 3.2.1.9.1 | Visual |
| "3 | Bond of glass cloth | 100% | 3.2.1.9.2 | Visual |
| "4 | Bond of metal shim | 100% | 3.2.1.9.3 | Visual |
| "5 | Adhesive | NA | Spec. | 9300790 - Vendor lot Certification" |

PAGE 39

Critical 1, 2, and 3: Delete in their entirety and substitute the following:

| | | | | |
|---|---|---|---|---|
| "1 | No explosive material, other than within charge cavity | 100% | 3.2.1.6 | 4.5.12 |
| "2 | Warhead cavity finish/ cleanliness | 100% | 3.2.1.7 | 4.5.9 |
| "3 | Defects in explosive charge | 100% | 3.2.1.5.7.1 | 4.5.5<br>4.5.6" |

PAGE 41

Critical 1,2, and 3: Delete in their entirety and substitute the following:

| | | | | |
|---|---|---|---|---|
| "1 | No explosive material other than within charge cavity | 100% | 3.2.1.6 | 4.5.12 |
| "2 | Warhead cavity finish/ cleanliness | 100% | 3.2.1.7 | 4.5.9 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.

| | | | | |
|---|---|---|---|---|
| "3 | Defects in explosive charge | 100% | 3.2.1.5.7.1 | 4.5.5<br>4.5.6<br>Review existing radio-graphs" |

Custodians:
Army-AR

Preparing activity:
Army-AR

(Project 1320-A733)



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:26Z
Check the source to verify that this is the current version before use.