MIL-S-50001B
12 July 1978
SUPERSEDING
MIL-S-50001A
3 March 1970

MILITARY SPECIFICATION

SHOWER UNIT, SAFETY, ROCKET PROPELLANT NEUTRALIZER, 100-GALLON WATER TANK AND TWO AIR CYLINDERS, W/HEATING PROVISIONS

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a 100-gallon, skid-mounted, aluminum emergency shower unit for washing rocket propellant spills from propellant-handling personnel.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

FF-B-575	- Bolts, Hexagon and Square.
FF-N-836	- Nut: Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding, and Single Ball Seat.

FSC 4230

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

FF-W-84	- Washers, Lock (Spring).
QQ-S-781	- Strapping, Steel, and Seals.
RR-C-271	- Chains and Attachments, Welded and Weldless.
RR-C-901	- Cylinders, Compressed Gas: With Valve or Plug and Cap; ICC 3AA.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.
PPP-B-636	- Boxes, Shipping, Fiberboard.

MILITARY

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-T-7081	- Tube, Aluminum Alloy, Seamless, Round, Drawn, 6061, Aircraft Hydraulic Quality.
MIL-I-16562	- Insulation, Synthetic, Rubber-Like, Chemically Expanded, Cellular (Sheet Form).
MIL-I-17244	- Indicators, Temperature, Direct-Reading Bimetallic, (3 and 5 Inch Dial).
MIL-G-17801	- Gages, Pressure, Dial Indicating, Compressed Gas Application.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.
MS39224	- Cylinder, Compressed Gas: DOT Specification 3AA.

DRAWINGS

ME

TA13217E2515	- Shower Unit Assembly.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

B 316 - Aluminum-Alloy Rivet and Cold Heading Wire and Rods, Spec. for.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, 2501 North West Seventh Street, Miami, FL 33125.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

DEPARTMENT OF TRANSPORTATION (DOT)

Title 49 CFR, Subchapter A - Hazardous Materials Regulation Board.
AMF 71-4 - Packaging and Handling of Dangerous Materials for Transportation by Military Aircraft.

(Applications for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Applications for copies should be addressed to the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096.)

(Technical society and technical association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

3. REQUIREMENTS

3.1 Description. The shower unit shall be as shown on Top Assembly drawing TA13217E2515 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the shower unit. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (first produced shower unit). The contractor shall furnish one or more shower units as specified (see 6.2) for examination and testing within the time frame specified (see 6.2) to prove prior to starting production that his production methods will produce shower units that comply with the requirements of this specification. Examination and

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Material not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.6).

3.3.1 Insulation. Insulation shall conform to MIL-I-16562. The insulating material shall be securely bonded to the tank. The insulating material shall then be covered with a protective coating of plastic or vinyl lacquer, not less than 10 mils thick in accordance with the coating manufacturer's recommendations for pretreatment of insulation and application of coating.

3.4 Bolts, nuts, and lockwashers. Bolts, nuts, and lockwashers shall conform to FF-B-575, Type II; FF-N-836, Type I, Style 1; and FF-W-84, Class A, Style 2. Bolts, nuts, and lockwashers shall be cadmium or zinc plated.

3.5 Rivets. Flat headed rivets shall be aluminum alloy conforming to ASTM B 316, Composition 6061-T6.

3.6 Chain. Chain shall be zinc-coated steel conforming to RR-C-271, Type I, Grade B, Class 1.

3.7 Water tank. All seams of the tank shall be machine welded. The completed tank shall withstand a test pressure of not less than 100 pounds per square inch (psi) without leakage, buckling, or deformation.

3.7.1 Pressure relief. The tank shall be protected from overpressure by a pressure relief valve having a 0.375-inch external inlet, with bottom outlet, set to open at 45 psi and to be full-open at 50 psi. The valve shall be capable of venting the entire contents of the compressed air cylinder in case of complete failure of the pressure regulator.

3.7.2 Drain plug. A 0.75-inch galvanized cast iron drain plug with a hexagon head shall be located at the bottom of the tank. Four additional 0.75-inch galvanized cast iron hexagon head drain plugs, three of which shall have a fusible core melting at plus 135° F (57° C), shall be included. The additional plugs shall be carried in the plug holder.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:01Z
Check the source to verify that this is the current version before use.

3.7.3 Thermometer. The tank shall be provided with a thermometer conforming to MIL-I-17244 except the scale range shall be plus 30° F (-1° C) to plus 180° F (82° C) and the case weatherproof. The thermometer shall have a 4-inch stem length and be back connected. The vibration test, shock test, and inclination test shall not be required.

3.8 Pressure regulator. The pressure regulator shall be capable of reducing an initial air pressure of 2200 psi to 10 psi. The regulator shall have a total capacity of 14 cubic feet in one minute at 68° F (31° C) and 40 psi. The regulator outlet shall have a flange integral with the regulator body. The outlet pressure of the regulator shall be externally adjustable between 10 psi and 50 psi. The regulator shall be constructed throughout of corrosion-resistant material.

3.8.1 Pressure gages. The pressure regulator shall be provided with a low-pressure gage, Type E, 2-inch dial, and a high-pressure gage, Type A, 2-inch dial, conforming to MIL-G-17801. The gages shall have weatherproof cases. Both gages shall face toward the front of the shower unit, and when connected, the numbers on the dial shall be in a vertical position.

3.8.2 Hose. The flexible hose between the pressure tanks and the regulator shall conform to SAE J-517 designation 100R1, single-wire braid, rubber-covered hydraulic hose, 0.25-inch nominal size.

3.9 Hose and pipe fittings. The hose and pipe fittings when assembled shall withstand a hydrostatic pressure of not less than 4000 psi without leakage or damage.

3.10 Heating system. The heating system shall consist of an electric immersion type heater as specified on the drawings.

3.11 Shower. The shower head shall be an adjustable type capable of delivering not more than 100 gallons of water in one minute at a discharge pressure of 10 to 20 psi.

3.12 Compressed air cylinders. The shower shall be equipped with two compressed air cylinders, fully charged, conforming to RR-C-901, Type II, Class 1, DOT-3AA-2265 psig., MS39224-1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

3.13 Skid. Tubing shall conform to MIL-T-7081, Temper T6.

3.14 Leakage. When tested as specified in 4.5.2.3, there shall be no visible water leakage through the valve to the shower head, and there shall be no air leakage through the filler cap when hand tight or through the pressurizing system.

3.15 Identification marking. The shower unit shall be identified in accordance with MIL-STD-130. The marking shall be applied to the shower unit on plates conforming to MIL-P-514, Type I, Style 3, Composition C, of Type I, Grade A, Class 1 material. Each plate shall be attached by screws, bolts, or rivets in a location where the plate will be both visible and legible.

3.16 Instruction plates. Each shower unit shall be equipped with instruction plates or diagrams, including warnings and cautions, describing any special or important procedures to be followed in assembling, operating, or servicing the shower unit. Instruction plates shall conform to MIL-P-514, Type III, Composition C, of Type I, Grade A, Class 1 material. Each plate shall be attached by screws, bolts, or rivets in a location where the plate will be visible and legible.

3.17 Treatment and painting. All portions of the shower unit normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, Type A, color as specified (see 6.2).

3.18 Workmanship.

3.18.1 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of materials shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing and sawing. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

3.18.2 Bolted connections. Bolt holes shall be accurately formed and shall have the burrs removed. Washers and lockwashers shall be provided where necessary. Matching thread areas securing bolts conforming to SAE J429 or capscrews shall be of sufficient strength to withstand the tensile strength of the bolt. All fasteners shall be correctly torqued and shall have full thread engagement. Bolts shall protrude not more than 2 full threads.

3.18.3 Riveted connections. Rivets shall fill the holes completely. The upset rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member, and shall be in accordance with SAE J492.

3.18.4 Machine work. Tolerances and gages for metal fits shall conform to the limits specified herein and on the applicable drawings.

3.18.5 Welders and welding.

3.18.5.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

AWS D1.1, Structural Welding Code, Section 5, Qualification.
ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

Contractors who make only horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS or ASME codes.

3.18.5.2 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale that can be removed by chipping and wire brushing, and other foreign matter. Parent materials, weld filler metals, and fabrication techniques shall be as required to

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

enable the shower unit to conform to the examination and test requirements specified in Section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more than 0.188 inch unless appropriate bridging techniques are used. Unless otherwise specified (see 6.2), the welding process used in fabrication of the shower unit shall be at the option of the contractor.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings as applicable.

4.1.2 Disassembly inspection. Failure of any test by the first produced shower unit shall be cause for disassembly, in the presence of a Government representative, of the first produced shower unit to the extent necessary to determine the cause of failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejection of the first produced shower unit. Reassembly with replacement parts and retesting shall be the responsibility of the contractor.

4.2 Classification of inspections. Inspection requirements specified herein are classified as follows:

(a) First produced shower unit inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of packaging (see 4.6).

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:01Z
Check the source to verify that this is the currentversion before use.

4.3 First produced shower unit inspection.

4.3.1 Examination. The first produced shower unit shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The first produced shower unit shall be tested as specified in 4.5.2. Failure of any test shall be cause for rejection or for performing the disassembly inspection specified in 4.1.2.

4.4 Quality conformance inspection.

4.4.1 Examination. Each shower unit shall be examined for the defects listed in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4.2 Tests. Each shower unit shall be subjected to the tests specified in 4.5.2. Failure of any test shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The shower units shall be examined as specified herein for the following defects:

101. Any part or component not in accordance with the SQAP requirements as shown on the drawings.
102. Components missing or not as specified.
103. Incomplete or incorrectly assembled.
104. Nonfunction of parts and components.
105. Nonfunction of safety devices and guards.
106. Treatment and painting not as specified.
107. Misalinement of fit at joints and seams.
108. Welding broken, not fused, or not as specified.
109. Incomplete or inadequate fasteners.
110. Identification marking missing, incomplete, or illegible.
111. Workmanship not as specified.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:01Z
Check the source to verify that this is the current version before use.

4.5.2 Tests.

4.5.2.1 Tank. Immediately after the tank has been fabricated and prior to the installation of the insulation and the outer covering, each tank shall be tested for leaks. All openings shall be properly sealed and the tank subjected to an internal hydrostatic pressure of 100 psi, plus or minus 3 psi. Nonconformance to 3.7 shall constitute failure of this test.

4.5.2.2 Hose and pipe fittings. The hose and pipe fittings shall be hydrostatically tested to 4000 psi. Nonconformance to 3.9 shall constitute failure of this test.

4.5.2.3 Operation and leaks. The shower unit shall be charged with not less than 100 gallons (US gallons) of water and pressurized from the compressed air cylinder. The unit shall then be actuated by pushing of upright handle to determine the proper function of all components of the unit. When the handle is allowed to return to its original position, the valve shall completely close and shut off the water supply. After the unit has been actuated, the valve shall be inspected to determine that the water in the shower pipe will drain out. The contents of the tank shall be discharged within one minute. Visible or audible leakage at any fitting or joint, or failure of contents of the tank to be discharged within one minute shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection.

4.6.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Samples selected in accordance with 4.6.1.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

112.	Pipe and shower head assembly not disconnected and secured as specified for Level A.
113.	Valve actuating handle not secured as specified for Level A.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:01Z
Check the source to verify that this is the current version before use.

114. Tank not drained and left open as specified for Level A.
115. Flares, when specified, not preserved as specified for Level A.
116. Air cylinders not secured as specified for Level A.
117. Power cable not coiled, not tied, and not secured as specified for Level A.
118. Consolidated packaging not as specified for Level A.
119. Containers or materials not as specified for Level A or Level B. Each incorrect material and each incorrect container shall constitute one defect.
120. Blocking, bracing, anchoring, or waterproofing not as specified for Level A or Level B.
121. Marking illegible, incorrect, incomplete, or missing for Level A, Level B, or Commercial.

5. PACKAGING

5.1 Preservation. Preservation shall be Level A or Commercial, as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Preservatives. Preservatives specified herein shall conform to the applicable specifications listed in and shall be applied in accordance with MIL-P-116.

5.1.1.2 Disassembly. The pipe and shower head assembly shall be disconnected at the union and secured to the unit in a manner to provide the minimum cube. The valve actuating handle shall be secured with the valve in the closed position.

5.1.1.3 Tank. The drain plug shall be removed and the tank and connecting pipe shall be drained. The drain shall be left open. The drain plug shall be placed in the canvas pouch attached to the tank.

5.1.1.4 Air cylinders. The air cylinders shall be secured in the space provided.

5.1.1.5 Heater power cable. The power cable shall be coiled; tied with cotton tape or twine, and secured to the unit.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:01Z
Check the source to verify that this is the current version before use.

5.1.1.6 Repair parts. The preservative application criteria and applicable method(s) of preservation of MIL-P-116 shall be used to preserve repair parts.

5.1.1.7 Technical publications. Technical publications shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

5.1.1.8 Consolidation. The repair parts and technical publications for each shower unit shall be consolidated in a close-fitting box conforming to PPP-B-636, W6c, W5c, or V3c, as applicable, style optional. Cushioning shall be provided to control movement of components within the box.

5.1.2 Commercial. Each shower unit with repair parts and technical publications shall be preserved in accordance with MIL-STD-1188.

5.2 Packing. Packing shall be Level A, Level B, or Commercial, as specified (see 6.2).

5.2.1 Level A. Each shower unit, with repair parts and technical publications, shall be packed in a close-fitting nailed wood box conforming to PPP-B-621, Class 2, Style 7. Blocking, bracing, anchoring, and waterproofing shall be in accordance with MIL-STD-1186. Closure and strapping shall be in accordance with the appendix to the box specification. Strapping shall conform to QQ-S-781, Class 1, Type I or IV, size as applicable. Unless otherwise specified (see 6.2) strapping shall be Finish B. When specified (see 6.2) strapping shall be Finish A.

5.2.2 Level B. Each shower unit, with repair parts and technical publications shall be packed as specified in 5.2.1 for Level A except that the box shall be Class 1 and waterproofing shall not be required. Box closure and strapping shall be in accordance with the appendix to the box specification.

5.2.3 Commercial. Each shower unit, with repair parts and technical publications, shall be packed in accordance with MIL-STD-1138.

5.3 Marking.

5.3.1 Military. Marking shall be in accordance with MIL-STD-129 and in addition shipping containers shall be marked in accordance with DOT, Title 49 CFR, Subchapter A and in accordance with AMF 71-4.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:01Z
Check the source to verify that this is the current version before use.

5.3.2 Commercial. Marking for Commercial packaging shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The shower unit is intended as an emergency shower, self-contained, to be used at locations where water is not available, for the purpose of washing accidental spills of harmful rocket propellants from personnel.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of first produced shower unit, and number of shower units required (see 3.2).
(c) Color required (see 3.17).
(d) Welding process when other than specified (see 3.18.5.2).
(e) Degree of preservation and packing required (see 5.1 and 5.2).
(f) When other than Finish B strapping is required (see 5.2.1).

6.3 First produced shower unit. Any changes or deviations of production shower units from the approved first produced shower unit during production will be subject to the approval of the contracting officer. Approval of the first produced shower unit will not relieve the contractor of his obligation to furnish shower units conforming to this specification.

6.4 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operation manual to be furnished with each shower unit.

6.5 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including special tools), and instructions regarding shipment of shower units.

6.6 Recycled material. It is encouraged that recycled material be used, when practical, as long as it meets the requirements of this specification (see 3.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

Custodians:
Army - ME
Air Force - 99

Review activity:
DLA - GS

Preparing activity:
Army - ME

Project 4230-0069

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers' vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE MIL-S-50001B Shower Unit, Safety, Rocket Propellant Neutralizer, 100-Gal. Water Tank & Two Air Cylinders, w/Heating Provisions

NAME OF ORGANIZATION AND ADDRESS	CONTRACT NUMBER
	MATERIAL PROCURED UNDER A ☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

   A. GIVE PARAGRAPH NUMBER AND WORDING

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*	TELEPHONE NO.
	DATE

DD FORM 1426 JAN 72

REPLACES EDITION OF 1 JAN 68 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research
and Development Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:01Z
Check the source to verify that this is the current version before use.