MIL-T-49200(CR)
21 May 1979

MILITARY SPECIFICATION

TEST SET, RADIO,
AN/USM-306( )

This specification is approved for use by the Communications Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification defines a transmission measuring system operating from 1KHz to 33.5 MHz combining the functions of an RF tuning unit, an AF/RF frequency monitor, a spectrum analyzer, and a visual display and herein after called the equipment.

1.2 Classification. The equipment defined by this specification shall be Type II, Class 5, Style E, Color R per MIL-T-28800 and as herein with the rack-mountable capability.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on the date of invitation for bids, or the request for proposal, form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Communications Research and Development Command, ATTN: DRDCO-CM-DM, Fort Monmouth, New Jersey 07703 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 6625

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the currentversion before use.

SPECIFICATIONS

MILITARY

MIL-T-28800	Test Equipment for Use with Electrical and Electronic Equipment General Specification for

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures for Inspection by Attributes
MIL-STD-461	Electromagnetic Interference Characteristics, Requirements for Equipments
MIL-STD-462	Electromagnetic Interference Characteristics, Measurement of
MIL-STD-781	Reliability Design Qualification and Production Acceptance Tests: Exponential Dist.

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Classification of requirements. The requirements for the equipment are classified as follows:

REQUIREMENT	PARAGRAPH
Safety	3.2
Parts, materials, and processes	3.3
Design and construction	3.4
Electrical power sources and connections	3.5
Dimensions and weight	3.6

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the currentversion before use.

REQUIREMENTS	PARAGRAPH
Enclosure requirements	3.7
Marking and identification	3.8
Environmental requirements	3.9
Reliability	3.10
Performance requirements	3.11

3.2 Safety. Unless otherwise specified herein, the equipment shall comply with the Type II safety requirements specified in MIL-T-28800.

3.3 Parts, materials and processes. Unless otherwise specified herein, the equipment shall comply with the Type II parts, materials and processes requirements of MIL-T-28800.

3.3.1 Restricted materials. Equipment shall comply with the restricted material requirements of MIL-T-28800 including the requirement for mercury or radioactive materials and shall contain no combination of materials which cause deterioration of any material contained in the equipment due to effects of outgassing.

3.4 Design and construction. Unless otherwise specified herein, the equipment shall comply with the Type II, Class 5, Style E, Color R, design and construction requirements of MIL-T-28800 with the rack-mountable capability.

3.4.1 First article. When specified, the contractor shall furnish five sample equipments for first article inspection and approval. (See 4.3 and 6.2)

3.4.2 Mainframe plug-in concept. Equipment utilizing externally accessible, externally removable subassemblies (mainframe plug-in concept) do not meet the requirements of this specification and therefore are unacceptable. Items using this concept may be offered, provided the plug-in(s) shall not be removable by access through the front panel or rear panel with the unaided hand. A system part number shall be assigned to any such mainframe plug-in combination required to meet the requirements of this specification. The system part number shall be marked on the mainframe identification plate and any plug-in(s).

Source: https://assist.dla.mil -- Downloaded: 202610-26T03:59Z
Check the source to verify that this is the current version before use.

3.4.3 Controls. Unless otherwise specified herein, built-in adjustments and compensating devices shall not be externally accessible.

3.4.3.1 Front panel controls. All controls which are required to operate the equipment throughout its specified performance characteristics shall be located on the front panel.

3.4.4 Accessibility. The equipment shall be constructed so that:

3.4.4.1 Subassemblies. Subassemblies and chassis components can be removed without removing any other hard wired subassembly, printed circuit card or component.

3.4.4.2 Adjustments. Adjustments can be made without removing any component, printed circuit card or subassembly except the use of extender cards is permitted.

3.4.4.3 Printed circuit cards. Printed circuit cards can be removed without the need to unsolder cables and interconnecting wiring (connections to all printed circuit cards shall be through pin and socket connectors). Printed circuit cards (mother boards) designed primarily to distribute power and signals to other printed cards (daughter boards) are excluded from this requirement. When such mother boards are used, they shall be accessible from both sides to allow maintenance testing.

3.4.4.4 Indicator lights. Unless approved by the procuring activity upon presentation of acceptable reliability data, indicator lights other than light emitting diodes (LEDs) shall be accessible from the operator's side of the front panel.

3.4.4.5 Encapsulation and embedment. Encapsulation and embedment (potting) of subassemblies shall not be used.

3.4.5 Solid-state construction. Unless otherwise specified herein, the equipment shall be of solid-state, modular, miniaturized construction.

3.4.6 Components. The equipment shall consist of the following major components and power and interconnecting cables and cords as required.

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the currentversion before use.

a. RF Tuner
b. AF/RF Monitor
c. Spectrum Analyzer
d. Cabinet/Rack Assembly
e. Probe with multiple connector heads
f. Probe subassembly
g. Adapters as required
h. Cart Assembly

3.5 Electrical power sources and connections. Unless otherwise specified herein, the equipment shall comply with the Type II electrical power sources and connections requirements of MIL-T-28800. The equipment shall operate from a nominal 115/230 volts, single phase, 50, 60 and 400Hz source.

3.5.1 Maximum power. The maximum power consumption of the equipment shall be 180 voltamperes broken down to the major components as follows:

a.	RF Tuner	110 voltamperes
b.	AF/RF Monitor	25 voltamperes
c.	Spectrum Analyzer	40 voltamperes

3.5.2 Input power selection device. An input power selection device shall be provided for selection of input power voltages of 115 VAC or 230 VAC. Provision shall be incorporated to prevent accidental switching. When the equipment is delivered, the power selection device shall be in the 115 VAC position.

3.5.3 Fuses and circuit breakers. Fuses and circuit breakers shall be in accordance with MIL-T-28800. (115VAC/230VAC) Either common or separate fuseholders may be provided. If only one fuseholder is used (common), the equipment shall be provided with the 115VAC fuse installed and the 230VAC fuse shall be stowed with the accessories.

3.5.4 Input power switch. A front panel mounted power switch shall be provided. The ON position shall have panel identification lights for AC operation. The switch shall break both sides of the power source.

3.6 Dimensions and weight.

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the currentversion before use.

3.6.1 Dimensions

3.6.1.1 RF Tuner. The overall dimensions of the RF Tuner shall be 140 mm (5.5 in) maximum height, 432 mm (17 in) maximum depth, and the width as specified in MIL-T-28800 for rack-mounted equipment.

3.6.1.2 AF/RF Monitor. The overall dimensions of the AF/RF Monitor shall be 140 (5.5 in) maximum height, 406 mm (16 in) maximum depth, and the width as specified in MIL-T-28800 for rack-mounted equipment.

3.6.1.3 Spectrum Analyzer. The overall dimensions of the Spectrum Analyzer shall be 140 mm (5.5 in) maximum height, 380 mm (15 in) maximum depth, and the width as specified in MIL-T-28800 for rack-mounted equipment.

3.6.1.4 Cabinet/rack assembly. The overall dimensions of the Cabinet/ Rack Assembly shall be 1400 mm (55 in) maximum height, 864 mm (34 in) maximum depth, and the width as specified in MIL-T-28800 for equipment designed to receive rack-mounted equipment. A blank plate may be required to fill in the front of the cabinets rackface.

3.6.2 Weight. The maximum weight of the major components and the total equipment shall be as noted below.

a.	RF Tuner	13.6 kg (30 lbs)
b.	AF/RF Monitor	10.0 kg (22 lbs)
c.	Spectrum Analyzer	10.7 kg (23.5 lbs)
d.	Cabinet/Rack	57.0 kg (125 lbs)
e.	Total Equipment	95.5 kg (210 lbs)

3.7 Enclosure requirements. Unless otherwise specified herein, the equipment shall comply with the Style E enclosure requirements of MIL-T-28800.

3.7.1 Cables and Adapters. Space shall be provided within the equipment to store cables and adapters when not in use.

3.8 Marking and identification. Unless otherwise specified herein, the equipment shall comply with the Type II marking and identification requirements of MIL-T-28800.

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the current version before use.

3.8.1 Supplemental identification plate. The supplemental identification plate specified in MIL-T-28800 shall contain only the data listed below. Each major component shall have a supplemental identification plate.

a. Nomenclature.
b. Procurement instrument identification number (PIIN).
c. Serial number.
d. National stock number.
e. US

3.9 Environmental requirements. Unless otherwise specified herein, the equipment shall comply with the Class 5 environmental requirements of MIL-T-28800.

3.9.1 Electromagnetic interference. The equipment shall comply with the follcwing emission and susceptibility requirements of Notice 4, MIL-STD-461.

CE02	CS02	RE02.1	RS03
CE04	CS03	RE02	
	CS04		
	CS06		

RE02.1 and RS03 shall be performed from 14KHz to 10GHz with RS03 at a susceptibility level of one volt per meter (1V/m).

3.9.2 Humidity. The equipment shall meet the humidity requirements in accordance with the test specified in para 4.5.5.1.1.3 of MIL-T-28800.

3.9.3 Vibration. The equipment shall comply with the Class 5 vibration requirements of MIL-T-28800, except that the equipment need not be operating during vibration.

3.10 Reliability requirements.

3.10.1 Reliability burn-in. Each equipment delivered against this specification shall be submitted to a minimum 96-hour on-time burn-in procedure as specified in 4.4.4. The last 24 hours of burn-in shall be failure free.

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the currentversion before use.

3.10.2 Reliability. Reliability shall comply with requirements as specified herein. The specified MTBF shall be 2500 hrs when tested as specified in 4.4.4. A failure shall be defined in MIL-STD-781, para 3.1, and as any departure from the required performance or operation of the required accuracies (not correctable by normal use of the operating controls) after the test is initiated.

3.10.3 Maintainability requirements. The equipment shall comply with the Type II maintainability requirements of MIL-T-28800. (See 6.4)

3.11 Performance characteristics.

3.11.1 RF Tuner.

3.11.1.1 Internal clock oscillator.

3.11.1.1.1 Frequency. 1.0 MHz

3.11.1.1.2 Accuracy. The clock setting accuracy shall be ± 2 parts in 10^7. The overall accuracy shall be ±(setting accuracy ± stability).

3.11.1.1.3 Stability. The clock stability with respect to aging rate (per week after 30 days) and to variations in temperature or line voltage shall be as noted below:

a. Aging rate, ± 1.5 parts in 10^7.

b. Temperature (±15°C to +40°C), ± 5 parts in 10^9/°C.

c. Line voltage (± 10%), ± 7.5 parts in 10^8.

3.11.1.1.4 Warm-up time. Warm-up time for the clock shall be a maximum of 30 minutes for operational use after a 3 hour period on stand-by. With the equipment MAIN switch in the OFF position and the power cord plugged into a live power line, the clock oscillator shall be running for a 3 hour period prior to warm-up. The OFF plugged in condition shall be considered as the stand-by condition.

Source: https://assist.dla.mil -- Downloaded: 202610-26T03:59Z
Check the source to verify that this is the current version before use.

3.11.1.2 Frequency.

3.11.1.2.1 Outputs. The frequency ranges, accuracies, and stabilities for fixed frequency and coarse and fine frequency tuning outputs shall be as noted below.

a. Fixed frequency. 19.0MHz ± 2%.

b. Coarse frequency tuning. 40.1 to 73.6 MHz with clock accuracy and stability.

c. Fine frequency tuning. 18.775 to 18.895 MHz with an accuracy of ± (10 Hz ± clock accuracy) and a stability of ±(2 Hz/°C ± clock stability).

3.11.1.2.2 Readouts. The equipment frequency readout ranges and minimum reading increments shall be as noted below.

a. Locked mode. 0 to 33.5 MHz with a minimum reading increment of 10 Hz.

b. Continuous mode. 0 to 33.5 MHz with a minimum reading increment of 0.1 MHz.

3.11.1.3 Output voltage levels. The equipment output levels shall be as noted below.

a. Fixed frequency. 34 millivolts rms ± 3 millivolts across 50 ohms.

b. Coarse tuning. 125 mv rms ± 10 mv at 1.0 MHz with a maximum variation of 40 mv over the frequency range.

c. Fine tuning. One output for general use at 200 to 250 mv and one output for the spectrum analyzer at 90 mv rms ± 20 mv across 50 ohms.

3.11.2 AF/RF monitor.

3.11.2.1 Frequency range. The overall frequency range shall be 1.0 KHz to 33.5 MHz with individual tuning ranges as noted below.

a. Coarse tuning. 0 to 33.5 MHz (phase-locked in 100 KHz steps).

b. Continuous tuning. 0 to 32 MHz.

3.11.2.2 Frequency accuracy. The typical accuracy shall be ± 60 Hz ± 1

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the current version before use.

count with a filter center frequency tolerance of ±50 Hz and a counter uncertainty of ±10 Hz ±1 count.

3.11.2.3 Frequency stability. The stability with respect to aging (per week after 30 days) and to variations in temperature or line voltage shall be as noted below.

a. Aging, ±(0.30 + 15 parts in 10^7) Hz.

b. Temperature (+15°C to +40°C), ±(0.25 + 1.25 parts in 10^7) Hz.

c. Line voltage (±10%), ±(0.15 + 0.75 parts in 10^7)Hz.

3.11.2.4 Level.

3.11.2.4.1 Measurement range. The overall measurement range shall be -109 to +22 dbm (-89 to +22 dbm full scale).

a. Low sensitivity. For the range of 1 KHz to 33.5 MHz, -89 to +22 dbm.

b. High sensitivity. For the range of 60KHz to 33.5MHz with a 20db gain increase, -109 to +2dbm.

c. Meter range. The meter shall have a normal scale of -25 to +2db and an extended scale of -2 to +2db with 0.1db per division.

3.11.2.4.2 Measurement accuracy. At the reference frequency of 1MHz and level 0dbm the measurement accuracy shall be ±0.2db.

3.11.2.5 Frequency response.

3.11.2.5.1 Coarse tuning. The frequency response for low and high sensitivity shall be as shown below for the noted frequency ranges.

a. Low sensitivity.

1.0KHz to 10KHz	±0.7db
10 KHz to 22MHz	±0.3db
22 MHz to 32MHz	±0.7db
32 MHz to 33.5MHz	±1.5db

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the currentversion before use.

b. High sensitivity.

60 KHz to 22 MHz	+0.3db
22 MHz to 33.5 MHz	+1.7db

3.11.2.5.2 Fine tuning. The frequency response on fine tuning shall be ±0.1db over the entire frequency range.

3.11.2.6 Attennator accuracy. The accuracy of the noted attennators shall be as noted below for the indicated frequency ranges.

a. 10db/step

1.0 KHz to 22 MHz	±0.2db
1.0 KHz to 33.5 MHz	±0.3db

b. 1.0db/step

1.0 KHz to 33.5 MHz	±0.1db

3.11.2.7 Crystal filter selectivity. The selectivity for wide and narrow band filters shall be as shown below.

a. Wideband

3db points	3.1 ± 0.2 KHz
60db points	8.0 ± (0.5-1.0) KHz

b. Narrowband

3db points	250 ± 50 Hz
60db points	1000 ± 100 Hz

3.11.2.8 Signal output. The unit shall supply 20.99 to 21.11 MHz across 50 ohms for the spectrum analyzer.

3.11.2.9 Amplitude Modulation detection. The equipment shall be capable of detecting both double-sideband transmitted-carrier and single-sideband suppressed-carrier types of amplitude modulation. An audio detector shall be provided for listening to the AF AM components of the RF signal under test.

Source: https://assist.dla.mil -- Downloaded: 202610-26T03:59Z
Check the source to verify that this is the current version before use.

3.11.3 Spectrum Analyzer.

3.11.3.1 Frequency. The overall frequency range shall be 1.0 KHz to 33.5 MHz.

3.11.3.2 Sweep width. The unit shall have three (3) fixed sweep widths; 120 KHz, 12 KHz, and 3.6 KHz.

3.11.3.3 Frequency accuracy. The frequency accuracy shall vary with sweep width as noted below.

a. 120 KHz (10 KHz/div.) ± 1.0 KHz

b. 12 KHz(1.0 KHz/div.) ± 200 Hz

c. 3.6 KHz (0.3 KHz/div.) ± 200 Hz

3.11.3.4 Frequency resolution. The frequency resolution shall vary with sweep width as noted below.

a. 120 KHz Signal separation of 1500 Hz, 60db down.

b. 12 KHz Signal separation of 60 Hz, 40db down.

c. 3.6 KHz Signal separation of 60 Hz, 40db down.

3.11.3.5 Frequency stability. The display unit stability over the operating temperature range for the individual sweep widths shall be as noted below.

a. 120 KHz ± 2500 Hz

b. 12 KHz ± 250 Hz

c. 3.6 KHz ± 250 Hz

3.11.3.6 Tuning accuracy. The tuning accuracy with the use of a marker shall be as noted below for the individual sweep widths.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.

a.	120 KHz	± 1000 Hz
b.	12 KHz	± 35 Hz
c.	3.6 KHz	± 35 Hz

3.11.3.7 IF bandwidth. The nominal IF bandwidth for the individual sweep widths shall be as noted below.

a.	120 KHz	at -3db, 400 Hz at -60db, 2400 Hz
b.	12 KHz and 3.6 KHz.	at -3db, 35 Hz at -60db, 180 Hz

3.11.3.8 Sweep rates. The sweep rates for the specific sweep widths shall be as noted below.

a.	120 KHz	Normal.	3.5 sec/sweep
		Search.	1.0 sec/sweep
b.	12 KHz and 3.6 KHz	Normal	10 sec/sweep
		Search	3.5 sec/sweep

3.11.3.9 Attenuator range. The input attenuator range shall be from 0db to 40db in 20db steps with a vernier control from +5db to -20db continuously variable.

3.11.3.10 Cathode ray tube. The face of the cathode ray tube shall be coated with a long persistance P7 type phosphor having a blue fluorescence, and a yellow persistance.

3.11.3.11 Impedance. The unit shall have an input impedance of 50 ohms nominal.

3.11.4 Cabinet/rack assembly.

3.11.4.1 Cabinet. The cabinet shall be a steel cabinet open at the front for receiving rack-mounted modules. It shall have an access door at the rear. The cabinet shall be equipped with slide rails for mounting the rack-mounted units. The rails shall permit sliding the modular units into and out of the cabinet for inspection and maintenance. The cabinet shall have vented sides and shall have a small fan mounted on the access door to provide for air circulation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.

3.11.4.2 Cart assembly. The cabinet shall be mounted on a cart assembly made of chrome-plated steel tubing. The cart assembly shall have 4 each 5 inch swivel casters with brakes and soft rubber tires. The cart construction shall allow the cabinet to be tilted up and down through a series of positions.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections. The inspections required herein are classified as in a and b.

a. First Article inspection (see 4.3).
b. Quality conformance inspection (see 4.3).

4.3 First article and quality conformance inspection. Unless otherwise specified herein, the first article and quality conformance inspections shall be in accordance with MIL-T-28800.

4.3.1 Test plan. Unless otherwise stated in the contract, the contractor shall prepare a test plan in accordance with paragraphs 4.3(a) and 4.4(a) of MIL-T-28800, for use with both classes of inspection. The test plan shall include as a minimum the tests listed in TABLES I, II, & III, the tests noted in section 4.4, and a description of the satisfactory operation check and satisfactory operation test, as defined in para 4.5 of MIL-T-28800. Unless otherwise required, the tests and inspections to be performed shall be identical for both classes of inspection.

4.3.2 Inspection sampling plan. The inspection sampling to be performed during both classes of inspection shall be as specified in MIL-T-28800, except as indicated below:

4.3.2.1 Quality conformance inspection. Unless otherwise specified herein or

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.

TABLE 1

Examination and Test Groups

DESCRIPTION	RQMT.	TEST METHOD
Group A Preoperational Inspection Leakage Current Level A Performance	4.5.3.1 * 3.2.1.3.1* TABLE II	4.3.1
Group B Level B Performance	TABLE III	4.3.1
Group C Electrical Power Environmental Requirement Humidity Vibration	3.5 3.9 3.9.2 3.9.3	4.3.1
Group D Electromagnetic Interference	3.9.1	4.4.1
Group E Dimensions Weight Front Panel Marking Cabinet/Rack	3.6.1 3.6.2 3.8 3.11.4	4.3.1
Group F Reliability	3.10	4.3.1, 4.4.2

* Paragraphs of MIL-T-28800

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the current version before use.

TABLE II

Level A Performance Tests 1/

DESCRIPTION	REQUIREMENTS
RF tuner	3.11.1
Clock frequency	3.11.1.1.1
Clock setting accuracy	3.11.1.1.2
Frequency outputs	3.11.1.2.1
Frequency readouts	3.11.1.2.2
Coarse tuning	3.11.1.3 b
AF/RF monitor	3.11.2
Frequency range	3.11.2.1
Frequency accuracy	3.11.2.2
Meter range	3.11.2.4.1 c
Measurement accuracy	3.11.2.4.2
Coarse tuning response	3.11.2.5.1
Attenuation accuracy	3.11.2.6
Signal output frequency	3.11.2.8
Spectrum analyzer	3.11.3
Frequency	3.11.3.1
Sweep width	3.11.3.2
Frequency accuracy	3.11.3.3
Tuning accuracy	3.11.3.6
Attenuation range	3.11.3.9
Cathode ray tube	3.11.3.10

1/ Level A testing is abbreviated testing (see 6.4.1)

Source: https://assist.dla.mil -- Downloaded: 20260410-26T03:59Z
Check the source to verify that this is the current version before use.

TABLE III

Level B Performance Tests

DESCRIPTION	REQUIREMENTS
RF tuner	3.11.1
Clock stability	3.11.1.1.3
Warm-up time	3.11.1.1.4
Output voltage levels	3.11.1.3
AF/RF monitor	3.11.2
Frequency stability	3.11.2.3
Level	3.11.2.4
Frequency response	3.11.2.5
Crystal filter selectivity	3.11.2.7
AM detection	3.11.2.9
Spectrum analyzer	3.11.3
Frequency resolution	3.11.3.4
Frequency stability	3.11.3.5
IF bandwidth	3.11.3.7
Sweep rates	3.11.3.8
Impedance	3.11.3.11

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.

in the contract, the Group C, D, E & F quality conformance inspections shall be performed on the first production lot only.

4.3.2.2 Group D and Group F tests. The Group D EMI tests and Group F Reliability test shall be performed during quality conformance inspection only if not performed during first article testing.

4.4 Quality assurance tests. Unless otherwise specified herein, the following tests shall be performed in accordance with MIL-T-28800.

4.4.1 Electromagnetic interference. The equipment shall be subjected to an EMI test for compliance with the requirements of 3.9.1. All test set-ups and procedures shall comply with the measurement techniques of Notice 3, MIL-STD-462. All emission and susceptability tests shall be performed with the probe and cable assembly connected to, and extended parallel with, the front of the equipment. The equipment shall be fully operational and processing appropriate signals during all tests.

4.4.2 Humidity. The equipment shall be subjected to the humidity test specified in para 4.5.5.1.1.3 of MIL-T-28800.

4.4.3 Vibration. The equipment shall be subjected to the vibration tests specified in MIL-T-28800, for Class 5 equipment, except that the equipment shall not be operated during the test. The satisfactory operation test shall be performed prior to and following vibration testing.

4.4.4 Reliability. The reliability tests shall be performed as follows:

4.4.4.1 Burn-in. Each deliverable equipment shall be subjected to a minimum 96 hours on-time burn-in period, prior to Group A testing. During the last 24 hours of burn-in, the equipment must operate failure free. Up until this time, equipment will be allowed to accumulate failures. Each equipment which fails during the final 24 hour period shall be repaired and returned to test until it successfully survives a 24 hour period without failure. Failures which occur during the burn-in test shall be noted and reported, but shall not count toward the establishment of equipment MTBF. Prior to burn-in, the satisfactory operation test of 4.3.1 shall be conducted. Daily satisfactory operation checks (4.3.1) shall be conducted. For the last 24 hour failure free period, a complete satisfactory operation test shall be conducted prior to and after the period.

4.4.4.2 Reliability sampling plan.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.

4.4.4.2.1 First Article. The Group F reliability demonstration shall be conducted on at least five (5) samples. The use of ten (10) samples is encouraged, but not more than ten (10) samples shall be used (see 4.3.2.1)

4.4.4.2.2 Quality conformance inspection. The Group F reliability tests shall be performed on the first production lot, only if not performed during First Article testing. From those units of the first lot that have passed the required Group A and B tests, a random sample of ten (10) units shall be selected, for Group F testing (see 4.4.4.2.1)

4.4.4.2.3 Reliability test plan. The reliability tests shall be conducted in accordance with the following test plan:

O_o = 2500 hrs

Number of Failures	Total Test Time * Accept ** (Equal or More)	Reject *** (Equal or Less)
0	2000	N/A
1	3750	558
2	5375	2063
3	6875	3850
4	8375	5725
5	9875	7725
6	11375	11375 ****

* Total test time is total unit hours of "equipment ON" time (in hours).
** Accept if test time is greater than or equal to that listed.
*** Reject is test time is less than or equal to that listed.
**** Reject if test time is strictly less than 11375 with 6 failures.

4.4.4.3 Test length. Testing shall continue until the total unit hours together with the total count of relevant equipment failures permit either an accept or reject decision in accordance with the specified test plan. Only equipment "ON" time may be used in MTBF or longevity determinations. Testing shall be monitored in such a manner that the times to failure may be estimated with reasonable accuracy. No single equipment "ON" time shall be less than one-half the average operating time of all equipments "ON" test.

4.4.4.4 Test conditions.

4.4.4.4.1 Operating mode (duty cycle). Prior to the burn-in, a satisfactory operation test according to Table III, Level B Performance Test shall be performed on a sample chosen according to MIL-STD-105B. Daily satisfactory operation checks according to Table II Level A Performance Tests shall be conducted.

Source: https://assist.dla.mil -- Downloaded: 202640-26T03:59Z
Check the source to verify that this is the current version before use.

For the last 24 hour failure-free period, a complete satisfactory operation test shall be conducted on a sample prior to and after the period.

4.4.4.4.2 Test level. While under test, the equipment shall be subjected to the test conditions specified for fixed ground equipment with thermal stress B of MIL-STD-781.

4.4.4.4.3 Input voltage cycling. When so directed by the procuring activity, voltage cycling shall be accomplished as follows: The input voltage shall be maintained at one hundred ten percent (110%) nominal voltage for one-third of the equipment "ON" cycle, at the nominal value for the second one-third of the equipment "ON" cycle, and at ninety percent (90%) for the final one-third of the equipment "ON" cycle. This cycling procedure is to be repeated continuously throughout the reliability test.

4.4.4.5 Reliability examination and test method. The following inspections shall be used to verify equipment operation during reliability testing. The satisfactory operation test of 4.3.1 shall be used to confirm proper equipment operation prior to and following reliability testing. The satisfactory operation test shall also be performed weekly to verify equipment operation. The satisfactory operation check of 4.3.1 shall be used to monitor proper operation of the equipment daily.

4.4.4.6 Reliability failure actions, Group F. In the event of failure(s) during reliability testing, failure action shall be taken as required in MIL-STD-781, para 5..6.

4.4.4.7 Corrective action, Group F. In the event the reliability test reaches a reject decision, corrective action shall be taken as required in MIL-STD-781, para 5.9.

4.4.5 Optional quality assurance system. The procuring activity may substitute tests from a Department of Defense (DOD) approved supplier's quality assurance system for any or all tests in TABLE I.

5. PACKAGING

5.1 Preservation, packaging. Packaging for delivery shall be in accordance with MIL-T-28800 and as specified by the procuring activity.

6. NOTES

6.1 Intended use. The equipment is intended for use in maintaining electronic communications equipment by equipment repair units in intermediate and depot maintenance.

Source: https://assist.dla.mil -- Downloaded: 202610-26T03:59Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number and date of this specification and any amendment thereto.

b. Packaging requirements (see Section 5).

c. When rough handling and functional tests are required.

d. Place of final inspection.

e. Technical literature required.

f. Quantity of tools and running spare parts required.

g. Marking for shipment and shipping containers.

h. Test plans and test reports.

i. Classification of inspection and number of samples required.

j. Rack mounting requirements.

k. Alternate power requirements.

l. Maintainability rationale.

m. Reliability rationale.

6.3 Contract data requirements.

a. Nomenclature assignment.

b. National stock number.

c. Equipment sample test plans.

d. Pretest performance records.

e. First production test data.

f. Identification plate drawing.

6.4 Definitions.

6.4.1 Level A performance tests. Level A testing (TABLE II) is a reduced amount of testing which is performed on each equipment produced. Its purpose

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.

is to insure that all functions and modes of operation of the equipment are evaluated without extensively checking each parameter as required in the Level B test (TABLE III). The approved equipment test procedure shall specify the actual amount of testing to be performed.

6.4.2 Reliability rationale. Reliability rationale submitted with the bid should provide clear and concise rationale showing how the reliability of the equipment complies with minimum requirements of the solicitation. This may include data from previous reliability tests, reliability predictions and other data available to the offeror. In the absence of such data on the equipment being offered, such data on similar equipment of equal or greater complexity produced by the offeror may be submitted. However, such data must be clearly identified as comparative data, and accomplished with specifications and technical literature on the similar equipment. The acceptance of the submitted rationale does not relieve the successful bidder of performing and successfully completing the production reliability testing.

6.4.3 Maintainability rationale. Maintainability rationale submitted with the bid should provide clear and concise rationale showing how the maintainability of the equipment complies with requirements of the solicitation. This may include data from previous maintainability tests, records of repair and calibration data, and other data on the equipment available to the offeror. Data on selection of module size and other design features relevant to maintainability may also be submitted.

Custodian:
Army-CR

Review Activities:
Army - MD

User Activities:
Army -

Preparing Activity:
Army - CR

(Project 6625-A753)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:59Z
Check the source to verify that this is the current version before use.