MIL-F-11106A (Ord)
8 June 1962
SUPERSEDING
MIL-F-11106 (Ord)
25 April 1951

MILITARY SPECIFICATION

FUZE, POINT, DETONATING, M8
LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of point detonating fuze designated as Fuze, Point Detonating, M8.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for
MIL-I-45208 - Inspection Requirements, General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109 - Inspection Terms and Definitions
MIL-STD-350 - Jolt Test for Use in Production of Fuzes
MIL-STD-351 - Jumble Test for Use in Production of Fuzes

FSC: 1390

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:07Z
Check the source to verify that this is the current version before use.

DRAWINGS

ORDNANCE CORPS

73-2-311 - Fuze, Point Detonating, M8, Assembly
76-1-1193 - Container, Metal for Fuze, Point Detonating, M8 Assembly, Details and Packing and Marking
76-1-1194 - Box, Packing, Ammunition for Fuze, Point Detonating M8 Assembly, Details and Packing

PUBLICATIONS

ORDNANCE CORPS

ORD-M608-11 - Procedures and Tables for Continuous Sampling by Attributes
GL-7254184 - Index of Inspection Equipment Lists

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Fuze assembly.-The fuze assembly shall comply with all requirements specified on Drawing (dwg.) 73-2-311 and with all requirements specified in applicable specifications.

3.3 Jolt and jumble.-The fuze shall withstand the jolt and jumble tests specified in Standard MIL-STD-350 and MIL-STD-351 when tested as specified in 4.4.2.

3.4 Functioning (proving ground).

3.4.1 Safety.-The fuze shall show no evidence of premature burst or separation of parts in the gun tube or in flight.

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:07Z
Check the source to verify that this is the currentversion before use.

3.4.2 Minimum (min.).-The fuze shall function the shell satisfactorily when the round is assembled with 7 propellant increments and tested as specified in 4.4.3.1.

3.4.3 Maximum (max.).-The fuze shall function the shell satisfactorily when the round is assembled with 28 propellant increments and tested as specified in 4.4.3.2.

3.5 Workmanship.-All manufacturing, processing and assembly operations shall be correctly performed in a thoroughly workmanlike manner. Parts shall be of the proper finish (see Specification MIL-A-2550) and be free from burrs, chips, dirt, grease, rust, and other foreign material. The cleaning method used shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agents.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-The supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Contractor quality assurance system.-The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL-I-45208.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:07Z
Check the source to verify that this is the current version before use.

4.1.2 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

b. Number of units of product inspected.

c. Results obtained for all inspection performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of analysis on all material procured directly by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL-I-45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:07Z
Check the source to verify that this is the currentversion before use.

4.2 Initial production inspection

4.2.1 Submission.-The contractor shall submit an initial production sample consisting of (26) consecutively produced assemblies which have been produced by the production process which the contractor will use in fulfilling the contract, to a Government-approved facility designated by the contracting officer. All parts and materials shall be obtained from the same source of supply as will be used in regular production. The initial production sample shall be accompanied by certificates of analyses for all materials. An initial production sample shall also be submitted whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed.-Each assembly shall be inspected by the Government for all the inspections specified in 4.3 and 4.4 of this specffication and for all additional requirements of the applicable drawings. The 26 assemblies shall be divided into two equal groups of 13 each. Thirteen assemblies shall be subjected to the minimum functioning test specified in 4.4.3.1 and the remaining 13 assemblies shall be subjected to the maximum functioning test specified in 4.4.3.2.

4.2.3 Rejection.-If any assembly fails to comply with the applicable requirement, the initial production sample shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit new or supplemental quantities until such time as an acceptable sample is submitted or until otherwise directed by the contracting officer.

4.3 Inspection provisions

4.3.1 Lot formation.-A lot shall consist of fuze assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot number. Each lot shall contain:

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:07Z
Check the source to verify that this is the currentversion before use.

a. Parts and parts assemblies of one interfix lot number from one manufacturer.

b. Detonators from not more than one interfix lot number from one manufacturer.

c. Tetryl from not more than one lot.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Handbook ORD-M608-11 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance wtith 4.3.4.

4.3.2.1 Slider assembly, prior to assembly in fuze (see Dwg. 73-2-311)

Categories	Defects	Method of Inspection	Code No (see 6.3)
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Detonator missing	Visual	01001
102.	Detonator inverted	Visual	01002
103.	Lock pin missing	Visual	01003
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	01004

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:07Z
Check the source to verify that this is the currentversion before use.

4.3.2.2 Assembly prior to assembling slider and plug (see Dwg. 73-2-311)

Categories	Defects	Method of Inspection	Code No
Critical:	None defined		
Major:	AQL 0.25 percent		
101.	Striker point bent or blunted	Visual	02001
102.	Lead cup protrudes in slider cavity	Visual	02002
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship in slider cavity (see 3.5)	Visual	02003

4.3.2.3 Assembly, prior to assembling burster tube (see Dwg. 73-2-311)

Categories	Defects	Method of Inspection	Code No
Critical:	None defined		
Major:	AQL 0.25 percent		
101.	Lead charge missing	Visual	03001
Minor:	AQL 1.50 percent		
201.	Burster tube cavity threads damaged	Visual	03002
202.	Lead charge broken	Visual	03003
203.	Evidence of poor workmanship in burster tube cavity (see 3.5)	Visual	03004

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:07Z
Check the source to verify that this is the current version before use.

4.3.2.4 Assembly (see Dwg. 73-2-311)

Categories	Defects	Method of Inspection	Code No
Critical:			
1.	Ring assembly missing	Visual	04001
2.	Cotter pin not spread	Visual	04002
3.	Shear wire missing	Visual	04003
Major:	AQL 1.00 percent		
101.	Shell threads damaged	Visual	04004
102.	Tube loose	Visual	04005
Minor:	AQL 1.50 percent		
201.	Concentricity of tube	Gage	04006
202.	Protective coating missing or contains bare spot	Visual	04007
203.	Evidence of poor workmanship (see 3.5)	Visual	04008

4.3.2.5 Sealed metal container (see Dwg. 76-1-1193)

Categories	Defects	Method of Inspection	Code No
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.50 percent		
201.	Contents loose	Manual	05001
202.	Marking misleading or unidentifiable	Visual	05002
203.	Protective coating damaged	Visual	05003

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:07Z
Check the source to verify that this is the current version before use.

4.3.2.6 Sealed wood packing box (see Dwg. 76-1-1194)

Categories	Defects	Method of Inspection	Code No
Critical:	None defined		
Major:	AQL 0.25 percent		
101.	Board broken or split	Visual	06001
102.	Strapping missing, broken or loose	Visual	06002
Minor:	AQL 1.50 percent		
201.	Contents loose	Manual	06003
202.	Strapping improperly assembled	Visual	06004
203.	Marking misleading or unidentifiable	Visual	06005

4.3.3 Testing

4.3.3.1 Jolt and jumble (see 3.3) Critical defect - Code No 04009 and 04010.

4.3.3.1.1 Beginning with the first lot produced, and continuing until three consecutive lots have complied with the acceptance criteria specified, a sample of 36 fuzes shall be selected from each lot for these tests. If any fuze fails to meet the requirement specified the lot shall be rejected. The tests shall be performed as specified in Standard MIL-STD-350 and MIL-STD-351.

4.3.3.1.2 After three consecutive lots have met the criteria of 4.3.3.1.1, a sample of 12 fuzes shall be selected from each lot for this test. If any fuze fails to meet the requirement specified the lot shall be rejected.

4.3.3.2 Determination of binder-lubricant content of tetryl (see Dwg. 73-2-315 and 73-2-317) Major defect - Code No 04011.-The binder-lubricant content of the tetryl shall be determined for each lot at the time of loading. A sample of 5 grams shall be selected and tested as specified in 4.4.1. If the binder-lubricant content is in excess of the percentage specified and loading, has not begun, the lot of tetryl shall be rejected until proper corrective

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:07Z
Check the source to verify that this is the current version before use.

action has been accomplished as verified by repeating the binder-lubricant test specified in 4.4.1. If the loading has begun, action on the unloaded tetryl shall be as specified herein and all fuzes loaded with the questionable tetryl shall be rejected.

4.3.3.3 Functioning (see 3.4) Major defect

4.3.3.3.1 Minimum Code No 04012

4.3.3.3.1.1 Beginning with the first lot produced, and continuing until three lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL-STD-105, Table IV A, code letter J, and an AQL of 2.5 percent.

4.3.3.3.1.2 After three consecutive lots have met the criteria of 4.3.3.3.1.1, the sampling plan shall be in accordance with Table IV A, code letter G, and an AQL of 2.5 percent.

4.3.3.3.2 Maximum Code No 04013

4.3.3.3.2.1 Beginning with the first lot produced, and continuing until three lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Table IV A, code letter J and an AQL of 0.65 percent.

4.3.3.3.2.2 After three consecutive lots have met the criteria of 4.3.3.3.2.1, the sampling plan shall be in accordance with Table IV A, code letter G, and an AQL of 0.65 percent.

4.3.3.4 Check test for possible deterioration of detonators (see applicable detonators specifications). If the total elapsed time between original acceptance of any detonator lot and the assembly of that lot into the fuzes exceeds two years, or if the detonators have been subjected to adverse conditions, however brief, at any time since previous tests, the detonators lots shall be subjected to and must satisfactorily pass the check test specified in the applicable detonator specification. The check test shall be performed by the contractor (see 6.4) prior to assembling the detonators into the fuze.

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:07Z
Check the source to verify that this is the currentversion before use.

4.3.4 Inspection equipment.-Index of Inspection Equipment Lists Number GL7254184 identifies available approved inspection equipment designs. The contractor may, however, design alternate inspection equipment in order to facilitate his operation. Designs of any acceptance inspection equipment prepared by the contractor to support his approved written inspection plan (see 4.1.1) shall be approved by the Government prior to fabrication or procuring of such equipment (see 6.2). All acceptance inspection equipment shall be certified by the Government as complying with the approved design prior to its use. Supply and maintenance of inspection equipment shall be in accordance with Specification MIL-I-45607.

4.4 Test methods and procedures.

4.4.1 Determination of binder-lubricant content of tetryl.-An accurately weighed portion of 5 grams shall be transferred to a tared medium porosity sintered glass filtering crucible. The sample shall be extracted with four 10 milligram (ml.) portion of acetone maintaining each portion in contact with the residue for approximately 5 minutes before applying suction. Any lumps which may persist shall be broken up and the sides of the crucible washed down with each 10 ml. portion of acetone to insure complete removal of the tetryl. The residue shall be aspirated until the odor of acetone is no longer detectable. The crucible and contents shall be placed in a drying oven at 100 degrees centigrade (C) to 150 degrees C. for 1/2 hour, cooled in a desiccator and weighed. The above extraction shall be repeated, drying and weighing with individual 10 ml. portions of acetone until the loss in weight on subsequent extractions totals less than 0.0005 gram. The weight of residue in the crucible shall be calculated to the percentage of total binder-lubricant.

4.4.2 Jolt and jumble.-The fuzes, less burster tube assembly, shall be assembled to the test fixture specified in 4.3.4 and subjected to the jolt test specified in Standard MIL-STD-350. After completion of the jolt test the same fuzes shall be subjected to the jumble test specified in Standard MIL-STD-351.

4.4.3 Functioning.

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:07Z
Check the source to verify that this is the currentversion before use.

4.4.3.1 Minimum.-The fuze shall be assembled to a WP loaded shell for which it is standard. Seven propellant increments shall be assembled to the shell. The shell shall be fired for impact on flat, level, firm ground from a 4.2 inch, M2 Mortor set at an elevation of 1065 MILS. Observation shall be made for compliance with the requirement specified.

4.4.3.2 Maximum.-The fuze shall be assembled to a WP loaded shell for which it is standard. Twenty eight propellant increments shall be assembled to the shell. The shell shall be fired for impact on the flat, level, firm ground from a 4.2 inch, M2 Mortor set at an elevation of 900 MILS. Observation shall be made for compliance with the requirement specified.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level A.-The fuzes shall be preserved and packaged in accordance with dwg. 76-1-1193.

5.2 Packing

5.2.1 Level A.-The metal containers shall be packed in accordance with dwg. 76-1-1194.

5.3 Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Specification MIL-A-2550.

6. NOTES

6.1 Ordering data.-Procurement documents should specify the title, number and date of this specification.

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:07Z
Check the source to verify that this is the currentversion before use.

6.2 ubmission of contractor-developed equipment designs.- Documentation of contractor-developed inspection equipment designs shall be submitted in duplicate and identified with the associated examination or test required by the specification, to Picatinny Arsenal, Dover, New Jersey, ATTN: ORDBB-ND, for approval. This documentation shall include special equipment designs and a complete description of the use and application of all standard devices and set-ups as well as special equipment designs. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.3 Inspection code numbers.-The five-digit code numbers assigned to the inspection herein are to facilitate future data collection and analysis by the Government.

6.4 Cost of check test.-The contracting officer should arrange for the contractor to be reimbursed for the expense incurred in the performance of the check tests. The test shall be conducted at Government expense without cost to the contractor who loaded the detonators or to the contractor assembling the detonators in the fuze and shall not constitute a basis of rejection against either contractor except where deterioration has occured as a direct result of carelessness in handling, storage, etc., permitted while the detonator lots were under the jurisdiction of either contractor.

Notice.-When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Custodian:
Army-Ordnance Corps

Preparing activity:
Army-Ordnance Corps

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:07Z
Check the source to verify that this is the current version before use.