INCH-POUND

MIL-M-10289C
23 May 1990

Superseding
MIL-M-10289B
21 July 1958

MILITARY SPECIFICATION

MOUNTING MT-791( )/U

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the general requirements and tests for Mounting MT-791( )/U.

1.2 Description. Mounting MT-791( )/U is a metal mount used with Voice Frequency Line Unit TH-5( )/TG, Telephone-Telegraph Signal Converter TA-182 and Filter F-98( )/U.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards and handbooks. The following specifications, standards and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Communications-Electronics Command and Fort Monmouth, ATTN: AMSEL-ED-TO, Fort Monmouth, New Jersey 07703-5000 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5805

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-R-3065	-	Rubber and Synthetic Rubber Compounds; Mechanical and General Purpose.
MIL-M-13231	-	Marking of Electronic Items.
MIL-F-14072	-	Finishes for Ground Signal Equipment.
MIL-E-15090	-	Enamel, Equipment, Light-Gray (Formula No. 111).

STANDARDS

MILITARY

MIL-STD-22	-	Welded Joint Design.
MIL-STD-202	-	Test Methods for Electronic and Electrical Component Parts.
MIL-STD-252	-	Wired Equipment, Classification of Visual and Mechanical Defects for.
MIL-STD-454	-	Standard General Requirements for Electronic Equipment.
MIL-STD-810	-	Environmental Test Methods and Engineering Guidelines.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from: Standardization Documents Order Desk, Bldg 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

SIGNAL CORPS

SC-DL-42669 - Mounting MT-791

(Copies required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

NATIONAL BUREAU OF STANDARDS

Handbook H-28 - Screw-Thread Standards for Federal Services.

(Application for copies should be addressed to the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402)

AMERICAN SOCIETY OF TESTING AND MATERIALS

ASTM E 125 Reference Photographs for Magnetic Particle Indications on Ferrous Castings.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, Pennsylvania 19103.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article.

3.1.1 First article. When specified (see 6.2(d)), the contractor shall furnish sample units for first article inspection (see 6.3) in accordance with paragraph 4.4.

3.2 Construction.

3.2.1 Fabrication. The equipment shall be constructed in accordance with Drawing and Data List SC-DL-42669 including the requirements for parts, materials, and processes therein.

3.3 Parts, materials and processes.

3.3.1 Parts, materials and processes. Parts, materials and processes shall be such as to enable the equipment to meet its performance and other requirements, including the selection requirements, as specified herein.

3.3.2 Metals. The metals used shall be the proper alloy and hardness necessary to provide the required strength and rigidity. Materials shall be of corrosion-resisting types or shall be suitably processed to resist corrosion. Dissimilar metals used in contact with each other shall be carefully selected in accordance with the

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:44Z
Check the source to verify that this is the current version before use.

requirements of MIL-F-14072 to prevent electrolytic corrosion in the presence of moisture.

3.3.3 Rubber. Rubber shall be of the proper grade for its intended use and shall be in accordance with MIL-R-3065.

3.3.4 Riveting. Thickness of counter sunk metal which accepts the head of flush rivets shall not be less than the height of the rivet heads. The distance from the centers of rivet holes to the edges of the material in which the holes are formed shall be at least 1 1/2 times the rivet diameter. Rivets shall be used where practicable in preference to other means of securing aluminum or magnesium structural parts if joint is subjected to dynamic tension loads when the equipment is exposed to specific service conditions and if the parts do not require removal when the equipment is serviced. After riveting, the joints shall be tight, the joined parts shall be undamaged, and the rivet heads shall be properly seated and tight against their bearing surfaces.

3.3.5 Welding. Welds shall be of ample size. Where tack or spot welds are employed, the number of welds shall be sufficient to provide adequate strength and at least two welds shall be used to hold each welded part. Spot or tackle welds in aluminum or magnesium shall be limited to lightly stressed, non-critical structures. Wherever practicable, the welded joint shall conform to MIL-STD-22 and shall be such that grinding on the finished weld will be unnecessary.

3.3.6 Cleaning. Surfaces to be welded shall be cleaned to the extent that they are free from rust, scale, paint, grease and other foreign material. Welded assemblies shall be cleaned to remove scale, oxidation products, and excess flux by sandblasting; wire brushing, and other suitable means. Acid used for cleaning shall be completely neutralized and removed.

3.3.7 Process. Preheating shall be employed where distortion is likely to result from welding. Welds shall have thorough penetration and good fusion and shall be free from scabs, blisters, abnormal pockmarks, and other harmful defects. Where undesirable internal stresses are likely to result from welding, the welded assembly shall be stress relieved. Inert-gas-shielded arc welding shall be used when practicable, for welding of aluminum or magnesium.

3.4 Systems safety engineering.

3.4.1 Personnel hazards. Personnel hazards shall be kept to a minimum. The criteria of MIL-STD-454, requirement 1 and 8 shall be made applicable for tasks and efforts such as the selection of parts, the complete manufacturing and assembly process, and any product baseline configuration changes that may be implemented during the course of the contract. Verification that compliance with this requirement has been achieved shall be through a visual inspection (see 4.12).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

3.4.2 Edge rounding exposed. Exposed edges shall be rounded to a minimum radius of 0.04 inch (1 mm), and exposed corners to a minimum of 0.5 inch (13 mm).

3.4.3 Radioactive materials. Radioactive materials shall not be used (e.g. luminous dials/marking, electron tubes, surge arrestors and lenses).

3.5 Protective finish . The equipment shall be given a protective finish in accordance with MIL-F-14072. The final paint film on Type I surfaces shall be semigloss, light gray enamel conforming to MIL-E-15090.

3.6 Marking.

3.6.1 General. Marking shall be in accordance with MIL-M-13231. Serial numbers are not required.

3.7 Screws, other threaded devices, and related items.

3.7.1 Form and fit. Unless otherwise specified, screw threads shall conform to Handbook H-28 and supplement thereto; the Unified Thread Form and Series shall be Class 2A or 2B fit, and the American National Thread Series shall be Class 2 fit.

3.8 Interchangeability. Corresponding units and replaceable assemblies, sub-assemblies, and parts on contract shall be physically and functionally interchangeable as complete items without modification thereof or of other articles with which the items are used (see 4.13). When dimensions, ratings, characteristics, etc., are not specified, the manufacturer's design limits shall be used to determine compliance with the foregoing. If the contractor's in doubt as to whether a particular assembly, sub-assembly, or part is to be considered replaceable, the contracting officer shall be consulted.

3.9 Service conditions. The equipment shall meet the requirements of this specification while subjected to any of the following conditions successively or in combinations likely to be encountered during worldwide operations:

a. Temperature. Exposure in the range of $\pm 160^{\circ}F$ to $-80^{\circ}F$; however, exposure at the high temperature extreme not to exceed 4 hours and at low temperature extreme not to exceed 24 hours at any one time (see 4.10.1).

b. Relative humidity. Relative humidity up to 97 percent; and exposure to 100 percent relative humidity, with condensation, for 4 hours (see 4.10.2).

c. Salt spray, corrosion. Salt spray corrosion test, shall meet the requirements of Method 101A in MIL-STD-202 (see 4.10.3).

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:44Z
Check the source to verify that this is the current version before use.

3.10 Bounce. The equipment shall meet the full specification requirements. No physical damage except surface abrasion is permitted after inspection (see 4.9).

3.11 Preconditioning. The equipment shall be capable of meeting the inspection of section 4, without subsequent processing, after subjection to the bounce preconditioning (see 4.9).

3.12 Workmanship. The equipment shall be manufactured and assembled in accordance with requirements of MIL-STD-252 and in accordance with the applicable portions of the following paragraphs:

Paragraphs

3.3.4 Riveting
3.3.5 Welding
3.5 Protective finish
3.6 Marking

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements; however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.4).

b. Quality conformance inspection of items before packaging (see 4.5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

4.3 Inspection conditions. Unless otherwise specified, all inspections shall be performed in accordance with the test conditions specified in Table I.

4.4 First article inspection. This inspection shall consist of the environmental conditions specified in Table I and the group A, group B, and group C inspection specified in Tables II, III, and IV respectively. Nondestructive tests on first article samples may be performed to determine compliance with specified requirements. Two sample units are generally required so that lengthy environmental tests can be completed on one sample while complete performance measurements can be made on the second sample. The environmental test requirements of Table I will normally be performed in the following order: 1. Bounce; 2. Salt spray corrosion.

TABLE I. Environmental test conditions.

Inspection (For Additional Inspections see 4.2)	Requirement paragraph	Inspection paragraph
Bounce.....	3.10	4.9
Salt spray, corrosion....	3.9(c)	4.10.3

4.5 Quality conformance inspection of items before packaging. The minimum inspection performed by the contractor shall be as specified by a and b below to demonstrate compliance with specified requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's records. In addition, the Government, at its discretion, will verify by product inspection the contractor's compliance with specified requirements (see 6.9). Such verification shall not exceed the amount of inspection required herein of the contractor.

a. Quality conformance inspection shall consist of group A, group B and group C inspection as specified in 4.6 through 4.8.

b. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. In addition, group C inspection shall normally be performed on sample units that have been subjected to and met group B inspection. However, the order may be varied when it is considered more practical to select separate samples for group B or group C in inspection or both.

4.5.1 Preconditioning. Each unit which will be subjected to group A, group B, or group C inspection shall be preconditioned after each final assembly (see 3.11).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

4.6 Group A inspection. This inspection, including sampling, shall conform to table II. Unless otherwise specified, normal inspection shall be used at the start of the contract. Group A inspection shall be performed in any order which is satisfactory to the Government.

TABLE II. Group A inspection.

Inspection	Requirement paragraph	Inspection paragraph
Visual and Mechanical		
Parts, materials, and processes.....	3.3	4.12
Marking.....	3.6	4.12
Workmanship.....	3.12	4.12

4.7. Group B inspection. This inspection including sampling shall conform to table III. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be S-3. Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with 4.8.4 for disposition of rejected product.

4.7.1 Group B sampling plans. The group B sampling plans, as listed in table III shall be as follows:

Group	Inspection Level For Normal Inspection	Inspection Level For Reduced Inspection
B-2	S-4	S-3

TABLE III. Group B inspection.

Inspection	Requirement paragraph	Inspection paragraph	Group B Plan
Interchangeability...	3.8	4.13	B-2
Riveting.....	3.3.4	4.12	
Welding.....	3.3.5	4.11	

4.7.2 Order of inspection within group B. Group B inspection shall be performed in any order which is satisfactory to the Government.

4.7.3 Procedure in case of failure. When an inspection lot fails, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken. If the contractor and the Government inspector cannot agree on the effectiveness of the corrective action, the matter shall be referred to the contracting officer for resolution.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

4.8 Group C inspection. This inspection shall be as listed in table IV.

TABLE IV. Group C inspection.

Characteristic	Requirement paragraph	Inspection paragraph	Sample plan
Service conditions...	3.9	4.10	2 units per month

4.8.1 Sampling for inspection of equipment. Two units for each group C inspection shall be selected each month, without regard to their quality.

4.8.2 Noncompliance. If a sample unit fails group C inspection, the contractor shall immediately investigate the cause of failure and shall report to the Government the results thereof and details of the corrective action taken on the process and all units of product which were manufactured with the same conditions, materials, processes, etc (see 6.6).

4.8.3 Reinspection of conforming group B and group C sample units. Unless otherwise specified sample units which have been subjected to and passed group B or group C inspection, or both, may be accepted on contract, provided that they are resubjected to and pass group A inspection after repair of all visible damage.

4.8.4 Disposition of nonconforming product. The following shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault:

a. Sample units found defective during group A, B, or C inspection.

b. Inspection lots which failed during group A or B inspection.

c. Product which has been reworked as a result of failure during group C inspection.

The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.9 Bounce preconditioning. The unit, with shock mounts (if any) removed or blocked, shall be placed in its normal operating position on the table of the package tester, as made by the L.A.B. Corporation, Skaneateles, New York, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32 inch thick strip of material under one corner or edge of the equipment to a distance of 3 inches as the unit bounces. The unit shall be subjected to this preconditioning for 1 minute.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

After bounce preconditioning, the unit shall not be repaired, alined, cleaned or otherwise changed prior to subjection to acceptance inspection (see 3.10).

4.10 Service conditions test. The following tests shall be performed on at least one preproduction sample. In the event the information for bid or contract deletes preproduction sampling, at least one production sample shall be subjected to service conditions test.

4.10.1 Temperature test for unit. The equipment shall be subjected to the temperature cycle test as specified in MIL-STD-810 (see 3.9(a)).

4.10.2 Humidity. The equipment shall be subjected to the moisture resistance test cycle as specified in MIL-STD-810 (see 3.9(b)).

4.10.3 Salt spray. The equipment shall be subjected to the salt spray (corrosion) test as specified in Method 101A of MIL-STD-202, test conditions B (see 3.9(c)).

4.11 Welding inspection. Welding shall be inspected by the magnetic particle method as specified in ASTM E 125 and by the ultrasonic method using a reflectoscope, as made by Sperry Products, Inc., Danbury, Conn., or equal. Both tests shall be performed on each sample unit.

4.12 Visual and mechanical inspection. A thorough inspection shall be made on each completed equipment for mechanical fit, loose nuts and screws, welding, riveting, finish, marking, poor workmanship, and other defects. Fastening devices shall be checked for proper mechanical operation. Welds, finishes, ground connections and the like shall be checked for satisfactory workmanship and compliance with MIL-STD-252. An inspection shall be performed to verify compliance with those portions of 3.4 (Systems safety engineering) which can be determined visually.

4.12.1 Lense test, thorium content. A test shall be performed to determine that the thorium content of any lense covered in Title 10, Code of Federal Regulations, Part 40.13(c) is below 500 parts/million by weight. Results of this test shall be included in the ionizing Radiation Test Report if required in the contract.

4.13 Inspection for interchangeability. .The dimensions listed below shall be gaged or measured to determine compliance with the physical interchangeability requirements of 3.8. When a listed dimension is not within specified or design limit, it shall be considered a major defect.

a. External and internal dimensions of insertable assemblies, when such dimensions affect mating of parts.

b. Location of hinges and fasteners, which must mate.

Source: https://assist.dla.mil -- Downloaded: 20260-17T13:44Z
Check the source to verify that this is the current version before use.

c. Location of locking pins, fasteners, slides and mountings which receive mating parts.

d. Size and form of special threads.

5. PACKAGING

5.1 Packaging requirements. The packaging requirements for the desired level(s) of protection shall be as specified by the acquisition activity (see 6.2).

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. Mounting MT-791( )/U is used as a support for Voice Frequency Line Unit TH-5( )/TG, Telephone-Telegraph Signal Converter TA-182 and Filter F-98( )/U in vehicles or fixed station installations.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Type required.

c. Levels of preservation and packing (see section 5).

d. First article inspection.

e. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced.

6.3 First article. When first article inspection is required, the contracting officer should provide specific guidance to offerors whether the item(s) should be a preproduction sample, a first article sample, a first production item, a sample selected from the first production items, a standard production item form the contractor's current inventory, and the number of items to be tested as specified in 4.4. The contracting officer should also include specific instructions in acquisition documents regarding arrangements for examinations, approval of first article test results, and disposition of first articles. Invitations for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

6.4 Nomenclature. The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example MT-791A. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

6.5 Location of the operational inspection. It is desirable that the operational inspection be performed at a location that will minimize handling (which might cause damage to the equipment) after this inspection is completed. It is recommended that the entire lot (including all previously inspected sample units) be sampled and inspected prior to packaging.

6.6 Group C inspection. Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action (see 4.8).

6.7 Inspection. Inspection is the examination or testing, or both, of supplies to determine compliance with applicable requirements. Sampling is an element of inspection.

6.8 Examination. Examination consist of simple, generally nondestructive determinations of compliance, without use of special testing equipment.

6.9 Testing. Testing consists of determination of compliance using technical means.

6.10 Verification inspection. The amount of verification inspection (by the Government) will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product, and will normally be identified by the categories listed below:

a. Type A. The total of that inspection set forth in the Quality Assurance Provisions of this specification or the contract.

b. Type B. That inspection set forth in the Quality Assurance Provisions of this specification.

c. Type C. A reduced inspection procedure resulting in a material reduction in the amount of inspection set forth in the Quality Assurance Provisions of this specification. The amount of inspection is less than that provided for in Type B and is based upon a consistently acceptable product resulting form a planned quality control system voluntarily employed by the contractor in the production of the product.

6.11 Subject Term (keyword) Listing.

Converter, Telephone-Telegraph Signal TA-182
Filter F-98( )/U
Mount, Metal
Voice Frequency Line Unit TH-5( )/TG

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

6.12 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodians:

Army-CR
Air Force-17

Review Activity:

Air Force-99

User Activities:

NAVY-MC
Air Force-80

Preparing Activity:

Army-CR

(Project 5805-0047)

☆U.S. GOVERNMENT PRINTING OFFICE: 1990 - 704-034/30623

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-M-10289C	2. DOCUMENT DATE (YYMMDD) 23 May 1990

3. DOCUMENT TITLE: MOUNTING MT-791( )/U

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME U. S. Army Communications-Electronics Command	b. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON
c. ADDRESS (Include Zip Code) AMSEL-ED-TO Fort Monmouth, NJ 07703-5000	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:44Z
Check the source to verify that this is the current version before use.