MILITARY SPECIFICATION

TENT, FRAME-TYPE, INSULATED, SECTIONAL, WITH FLOOR, 16 FEET WIDE, M1948, COMPLETE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This document covers one type of general purpose insulated frame-type tent with floor. Identical parabolic ends with entrance doors provide for a detachable vestibule that may be used at either end. When erected, inside width at floor level is 16 feet, and inside length is expandable in multiples of 4 feet. One each electrical outlet and switch assembly for lighting is designed for use with a combination of sectional units completing an inclosure of 16 by 16 feet in size.

2. APPLICABLE DOCUMENTS

* 2.1 Government documents. Unless otherwise specified, the following documents of the issue in effect on the date of invitation for bids or request for proposal form a part of this document to the extent specified herein.

SPECIFICATIONS

FEDERAL

A-A-2094	- Tape, Insulation, Electrical (Friction)
J-C-580	- Cord, Flexible, and Wire, Fixture
L-P-349	- Plastic Molding and Extrusion Material, Cellulose Acetate Butyrate

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 8340

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202640-17T13:38Z
Check the source to verify that this is the current version before use.

V-T-285	- Thread, Polyester
W-F-406	- Fittings for Cable, Power, Electrical and Conduit, Metal, Flexible
W-J-800	- Junction Box: Extension, Junction Box; Cover, Junction Box (Steel, Cadmium, or Zinc-Coated)
FF-B-584	- Bolts, Finned Neck; Key Head; Machine; Ribbed Neck; Square Neck; Tee Head
FF-H-116	- Hinges, Hardware, Builders
FF-N-105	- Nails, Brads, Staples and Spikes: Wire, Cut and Wrought
FF-S-111	- Screw, Wood
FF-P-386	- Pins, Cotter, (Split)
FF-T-1813	- Tack
QQ-S-571	- Solder, Tin Alloy: Tin-Lead Alloy; and Lead Alloy
QQ-S-698	- Steel Sheet and Strip, Low Carbon
QQ-S-700	- Steel Sheet and Strip, Medium and High Carbon
QQ-S-781	- Strapping, Steel, and Seals
RR-C-271	- Chains and Attachments, Welded and Weldless
RR-W-365	- Wire, Fabric (Insect Screening)
TT-C-598	- Caulking Compound, Oil and Resin Base Type (for Building Construction)
TT-E-529	- Enamel, Alkyd, Semigloss
TT-P-636	- Primer Coating, Alkyd, Wood and Ferrous Metal
UU-P-268	- Paper, Kraft, Wrapping
DDD-L-20	- Label: for Clothing, Equipage, and Tentage, (General Use)
MMM-A-181	- Adhesives, Phenol, Resorcinol, or Melamine Base
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner
PPP-C-843	- Cushioning Material, Cellulosic
PPP-T-45	- Tape, Gummed, Paper, Reinforced and Plain for Sealing and Securing
PPP-T-60	- Tape: Packaging, Waterproof

MILITARY

MIL-C-496	- Clips, End, Strap
MIL-P-501	- Pins, Tent, Metal
MIL-W-530	- Webbing, Textile, Cotton, General Purpose, Natural or in Colors
MIL-B-543	- Buckles, Tongueless and Web Strap
MIL-L-1709	- Lines, Tent
MIL-S-1734	- Slips, Tent Line
MIL-C-2399	- Cement, Liquid, Tent Patching

Source: https://assist.dla.mil -- Downloaded: 202640-17T13:38Z
Check the source to verify that this is the current version before use.

MIL-R-3390	- Rings, Dee
MIL-C-10799	- Cloth, Coated, Cotton, Vinyl Coated, Fire and Mildew Resistant
MIL-F-10884	- Fasteners, Snap
MIL-V-13811	- Varnish, Waterproofing, Electrical, Ignition
MIL-G-16491	- Grommet, Metallic
MIL-R-30500	- Rope, Polyester
MIL-T-43566	- Tape, Textile, Cotton, General Purpose, Natural or in Colors
MIL-S-43770	- Snap Hook
MIL-W-44049	- Webbing, Textile and Tape, Textile, Polypropylene, General Purpose, Natural or in Colors
MIL-C-52950	- Crates, Wood, Open and Covered

STANDARDS

FEDERAL

FED-STD-751	- Stitches, Seams, and Stitchings

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	- Marking for Shipment and Storage

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

5-4-181	- Tent, Frame-Type, Insulated, Sectional, with Floor, 16 X 16, M-1948, Complete; Illustration, Assembly and Views
5-4-182	- Floor Units
5-4-183	- Arch Segments and Miscellaneous Details
5-4-184	- End Blanket Assembly and Details
5-4-185	- Door Frame Assembly and Details
5-4-186	- Roof Blanket, Guy Band, Vestibule Covers
5-4-187	- Vestibule Details
5-4-188	- Locking Device and Alternate Threshold
5-4-296	- Lighting Unit
5-4-1261	- Crate for Protection of Arch Ends

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

OTHER GOVERNMENT DOCUMENTS

Department of the Army Field Manual FM 10-16 -
General Repair of Tents, Canvas and Webbing

(Copies of documents required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

* 2.2 Other publications. Unless otherwise specified, the following documents of the issue in effect on the date of invitation for bids or request for proposal form a part of this document to the extent specified herein.

UNITED STATES DEPARTMENT OF COMMERCE

Product Standard PS 1 - Softwood Plywood, Construction and Industrial

Commercial Standard CS35 - Hardwood, Plywood

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

National Electrical Code

(Application for copies should be addressed to National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.)

UNDERWRITERS LABORATORIES (UL)

Standards for Fire and Casualty Hazards

(Application for copies should be addressed to Underwriters Laboratories, 333 Pfingsten Road, Northbrook, IL 60062.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 108 - Standard Quality Cold-Finished Carbon Steel Bars
A 513 - Electric-Resistance-Welded Carbon and Alloy Steel Mechanical Tubing
A 519 - Seamless Carbon and Alloy Steel Mechanical Tubing
A 576 - Special Quality Hot-Wrought Carbon Steel Bars
A 675 - Mechanical Properties of Special Quality Hot-Wrought Carbon Steel Bars

Source: https://assist.dla.mil -- Downloaded: 202640-17T13:38Z
Check the source to verify that this is the current version before use.

B 633 - Electrodeposited Coatings of Zinc on Iron and Steel
D 2016 - Standard Test Methods for Moisture Content of Wood
E 18 - Rockwell Hardness and Rockwell Superficial Hardness of Metallic Materials

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Technical society and technical association documents are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

* 2.3 Order of precedence. In the event of conflict between the text of this document and the references cited herein (except for associated detail specifications, specification sheets, or MS standards), the text of this document shall take precedence. Nothing in this document, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified in the contract or purchase order, a sample shall be subjected to first article inspection (see 4.3, 6.2, and 6.4).

3.2 Codes and standards. The tents shall comply with the applicable requirements of UL Standards for Fire and Casualty Hazards and NFPA National Electrical Code, as applicable (see 4.1.1.1.1 and 4.1.1.1.2).

3.3 Materials and components.

3.3.1 Cloth, coated, cotton. The vinyl-coated cotton cloth shall conform to type II, class 1 of MIL-C-10799. The colors shall be Olive Drab 7 and light green (see 3.4.1).

* 3.3.2 Tape, textile, cotton. The tape for the wrench containers and for the ties shall be dyed Olive Drab 7 and shall conform to type I, class 4, 1 inch and 3/4 inch, respectively, of MIL-T-43566. Alternatively, the tape shall be polypropylene conforming to type I, class 2, Olive Drab 7 of MIL-W-44049.

* 3.3.3 Webbing, textile, cotton. The webbing shall be dyed Olive Drab 7 and shall conform to type III, class 4 of MIL-W-530 as follows:

a. For buckle chapes, hook chapes "A" and "B" - 1 inch width
b. For tent section corner reinforcements, roof guy band reinforcements and dee-ring chapes - 1 1/2 inch width.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

Alternatively, the webbing shall be polypropylene conforming to type III, class 2, Olive Drab 7, of MIL-W-44049.

3.3.4 Thread, polyester. The thread shall conform to type I, class 1, subclass B, shade S-1 (CA 66022) of V-T-285. The dyed thread shall show fastness to weathering equal to or better than the standard shade sample (see 6.3). When no standard shade sample is available, the dyed thread shall show good fastness to weathering. Thread sizes shall be as follows:

a. For all stitching except stitching indicated by "Z" on drawings - size FF for needle and bobbin

b. For stitching indicated by "Z" on drawings - size FF for needle, size F for looper

3.3.5 Lines, tent. The tent lines shall conform to type V (for tent line lug) and type XXIV (for guy line) of MIL-L-1709.

3.3.6 Rope, polyester. The polyester rope, 3/4-inch circumference, shall conform to MIL-R-30500.

3.3.7 Insulation. The insulation material used between the top and bottom floor panels, in the roof and end blankets, including the doors in the end blankets, shall be composed of glass fibers firmly bonded with a thermosetting plastic resin into a resilient mat structure 1 inch thick (+3/4, -0 inch tolerance) (see 4.5.1.1) having a weight of 2.1 pounds ± 10 percent per 24 square feet. The insulation shall be one continuous piece for each roof blanket and end section (i.e., piecing shall not be permitted).

3.3.7.1 Compressional recovery. The compressional recovery of the material shall be not less than 90 percent when determined in accordance with 4.5.1.2.

3.3.8 Adhesive. The adhesive used in the fabrication of the tent shall conform to type I or type II of MMM-A-181.

3.3.9 Caulking compound. The caulking compound used as a weather seal shall be gray in color and shall conform to type I of TT-C-598.

3.3.10 Fabric, wire. The wire fabric shall conform to type II, 18 X 16 regular mesh of RR-W-365.

3.3.11 Plastic sheet. The transparent, uncolored plastic sheet for the window panes and transoms shall be made of cellulose acetate butyrate molding material meeting the requirements of L-P-349 for any type or class. The sheet shall be 0.060 ± 0.010 inch thick, with polished finish on both sides.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

3.3.12 Lumber. The wood used to fabricate various parts of the tent shall be uniformly dried to a moisture content of 8 to 12 percent at time of fabrication when tested as specified in 4.5.2 and shall be free from shakes, checks, splits, or splintery surface. No more than two sound, tight knots up to 1/2 inch in diameter or not more than one sound, tight knot from 1/2 to 3/4 inch in diameter will be permitted per square foot. Boards shall be finished on all sides to drawing dimensions. Any of the following species of wood may be used on all parts of the tent, unless otherwise specified:

Cedar, Port Orford	Douglas Fir
Pine, White	Tupelo, Water or Black
Pine, Southern Yellow	Sweet Gum (Red Gum)
Pine, Norway or Ponderosa	Ash
Larch	Spruce (Eastern, Sitka)
Hemlock, Western	Basswood
Hickory	Oak
Maple	Cypress
Chestnut	Yellow Poplar

3.3.12.1 Exterior laminations. The exterior laminations of the arch segments shall be fabricated from yellow poplar, oak, hickory, ponderosa pine, or white pine.

3.3.12.2 Window assemblies. All wooden parts of the window assemblies shall be fabricated from a species of wood, such as ponderosa or white pine, that will not be susceptible to splintering.

3.3.13 Plywood. The plywood shall be either exterior type, grade A-C, sanded two sides, in accordance with Product Standard PS 1, or hardwood, type I, grade 2-3, high or medium density face, regular sanded, according to Commercial Standard CS35 (see 2.2).

3.3.14 Grommets, metallic. The grommets shall conform to type III, class 3, size No. 4 and type II, class 3, size No. 1 of MIL-G-16491.

3.3.15 Clips, end. The strap end clips shall conform to type I, class 1, size 1 inch of MIL-C-496.

3.3.16 Slips, tent line. The tent line slips shall conform to type II of MIL-S-1734.

* 3.3.17 Snaphook, 1 1/4 inch, bolt type. The round eye swivel snaphook shall conform to dash No. 6-MIZE1 of MIL-S-43770.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

3.3.18 Fasteners, snap. The snap fasteners used on the floor unit wrench retainers shall conform to style 1, finish 2, regular-pronged socket, wood screw base stud, size 1 of MIL-F-10884.

3.3.19 Rings, dee. The dee rings shall conform to class 2 or 3, configuration X, style 1, size 1 by 7/8 inch and class 2, configuration H of MIL-R-3390.

3.3.20 Buckle, tongueless, 2 bar. The buckles shall conform to type II, style 1, class 3, size 1-inch of MIL-B-543.

3.3.21 Pins, tent, metal. The tent pins shall conform to type II of MIL-P-501.

* 3.3.22 Wrench, key. The hexagonal key wrenches for operating the rotolock fasteners shall be fabricated as shown on Drawing 5-4-188, from steel conforming to ASTM A 576 and A 675 and heat-treated to a hardness of 36-44 on the Rockwell C scale (see ASTM E 18). The key wrench shall be finished as specified for the steel tent pins in MIL-P-501.

3.3.23 Chains, safety and footstop. The safety chain shall conform to type II, class 6, steel, trade No. 1, and the footstop chain shall conform to type I, grade C, class 5, style 2, 7/64-inch of RR-C-271.

* 3.3.24 Buckle, slide, 1 inch with hook. The buckles, fabricated as shown on Drawing 5-4-186, shall be steel, hot-rolled sheet or strip conforming to QQ-S-700. The buckles shall be given a finish conforming to ASTM B 633, followed by bake enameling. The enamel shall conform to type II of TT-E-529. The color shall be black, and the coating shall level out to a uniform dry film thickness, without orange peel, wrinkles, drops, streaks, or areas of no film.

3.3.25 Hook, tiedown. The tiedown hook shall be steel, hot-rolled sheet or strip conforming to QQ-S-700. The hook shall be finished as specified in 3.4.24 and Drawing 5-4-186.

3.3.26 Latch and keeper, door. The door latch shall be of the commercial type easily operated from either the outside or inside of door. Latch and keeper shall be substantially the type indicated on Drawings 5-4-185 and 5-4-188, but any acceptable latch that meets the requirements may be used upon approval of the contracting officer.

3.3.27 Hinges, butt. The full mortise hinges, 2 1/2 inches by 2 1/2 inches, shall conform to type 2171H of FF-H-116. The butt hinges, 1 3/4 inches by 1 7/16 inches and 3 inches by 2 1/2 inches, shall be standard commercial products.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

3.3.28 Cleats, line. The line cleats shall be standard commercial products of the type, size, and material specified on Drawing 5-4-187.

* 3.3.29 Nails. The cement-coated, steel nails shall conform to style 2, 3/4 inch and style 6 of FF-N-105 in the sizes specified on the drawings.

3.3.30 Screws.

3.3.30.1 Wood. The wood screws shall be steel, of the type and size specified on the drawings and shall conform to FF-S-111.

3.3.30.2 Sheet metal. The sheet metal screws shall be standard commercial products of the type, size, and material specified on the drawings.

3.3.30.3 Finish. The screws shall be finished as specified in 3.4.16.1.

* 3.3.31 Tacks, upholsterers'. The galvanized steel tacks shall conform to FF-T-1813 in the sizes specified on the drawings.

3.3.32 Staples. Staples, 13/32 inch inside width by 11/32 inch inside length, fabricated from flat steel wire (0.022 inch thick by 0.051 inch wide), may be used at the option of the contractor in lieu of the upholsterers' tacks specified in 3.3.31. The staples shall be zinc electroplated.

3.3.33 Pins, cotter. The split cotter pins shall conform to type B of FF-P-386 in the size specified on the drawings.

3.3.34 Bolts, carriage, square neck. The carriage bolts shall conform to type I, class 1, style a of FF-B-584 in the sizes specified on the drawings.

3.3.35 Miscellaneous hardware. The machine bolts, wing nuts, washers, rivets, gate hooks, and screw eyes shall be standard commercial products of the types, sizes, and materials specified on the drawings.

3.3.36 Steel, sheet or strip. The steel sheet or strip, hot or cold rolled, commercial quality, in the carbon content specified on the drawings, shall conform to QQ-S-698 or QQ-S-700, as applicable.

* 3.3.37 Steel, bar stock. The steel bar stock in the carbon content specified on the drawings shall conform to ASTM A 108, A 576, or A 675, as applicable.

* 3.3.38 Tubing, steel. The round steel tubing shall conform to any type or condition of ASTM A 513 or ASTM A 519, in the dimensions and carbon content specified on Drawing 5-4-183.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

3.3.39 Switch, circuit breaker. The switch shall be a single pole circuit breaker incorporating thermal and magnetic operating mechanisms, rated at 15 amperes for use on 120/240 volts, alternating current. The switch shall be designed for manual resetting after tripping and shall be housed in a general purpose surface type I inclosure.

3.3.40 Fittings, electrical. The fittings shall conform to type I, class 4, style M, size 1/2 inch of W-F-406.

3.3.41 Cord, electric. The cord shall conform to type S, American Wire Gage size 14, 3-conductor of J-C-580.

3.3.42 Box, outlet. The outlet boxes shall be 3 1/4 inch octagonal type by 2 1/2 inch deep, surface-mounted type, with four 1/2-inch side knockouts and shall conform to type I of W-J-800.

3.3.43 Sockets, lamp. The lamp sockets shall be of the rubber covered, weatherproof type, molded on a cadmium-plated out box cover of suitable size to match the boxes specified in 3.3.42. The sockets accommodate lamps having a medium screw-type base and shall be rated at 600 watts, 600 volts.

3.3.44 Solder. Solder for electrical connections shall conform to composition Sn-60 of QQ-S-571.

3.3.45 Tape, friction. The electrical insulation friction tape shall conform to A-A-2094.

3.3.46 Primer. The primer shall conform to TT-P-636.

3.3.47 Enamel. The enamel shall conform to class A, color No. 24087 of TT-E-529.

3.3.48 Erection instructions. A copy of the erection instructions, to be furnished by the Government, shall be packed in each of the following shipping containers: End section, intermediate section, vestibule section, and the electrical outlet and switch assembly.

3.4 Construction. The construction shall conform in all respects to Drawings 5-4-183 through 5-4-188, 5-4-296, and 5-4-1261, and as specified herein.

3.4.1 Coated duck. The Olive Drab 7 coated duck shall be used for the outside (weather side) of the roof and end sections, guy bands, vestibule end and top covers, and blackout flaps and retainers. The light green coated duck

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

shall be used for the inside of the roof, the blankets, and the blanket lugs. The smooth side (or side having the thicker coating) of the coated duck shall be on the outside.

3.4.2 Stitching, machine.

3.4.2.1 Types. All types of stitching shall conform to FED-STD-751 as follows:

a. For all stitching except stitching indicated by "Z" on drawings - Type 301, 5 to 7 stitches per inch.

b. For stitching indicated by "Z" on drawings - Type 401, 5 to 7 stitches per inch. Chain portion of stitching shall not appear on outer surfaces of end or roof sections.

3.4.2.2 Thread breaks. Thread breaks in stitching shall be overstitched not less than 1 inch at each break on stitch type 301 and not less than 1 1/2 inches at each break on stitch type 401. Thread breaks noted during inspection shall be repaired by overstitching the existing stitching and the defective area for not less than 1 inch on type 301 stitching or 1 1/2 inches on type 401 stitching on each side of the break. The ends of repair stitchings are not required to be backstitched. Thread breaks in type 401 stitching may be overstitched with stitch type 301.

3.4.2.3 Stitching ends. Stitching at the ends shall be overstitched not less than 1 inch on stitch type 301, except where ends are turned under in a hem, where ends are held down by other stitching, or where stitching is performed automatically. When stitch patterns such as box, box with cross-stitch, "W" stitching, or straight line tacking are performed automatically, at least three or more tying, overlapping, or back stitches shall be used to secure the ends of stitching.

3.4.2.4 Skipped stitches. Two or more consecutively skipped stitches occurring in type 301 stitching shall be overstitched not less than 1 inch on each side of skips. Any skipped stitch in type 401 stitching shall be overstitched not less than 1 1/2 inches on each side of skip. Skipped stitches in type 401 stitching may be overstitched with type 301 stitching.

3.4.2.5 Lubrication. The addition of any lubricant to the polyester thread prior to or during the sewing operation is prohibited.

3.4.3 Setting of grommets. Holes punched to receive grommets shall be smaller than the outside diameter of the grommet barrel so that the barrel must be forced through the hole. The grommets shall be securely clinched without cutting the materials.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

indicated by "Z" on drawings stitches per inch

3.4.4 Setting of end clips. The webbing shall be inserted the full depth of the clip. The clips shall be securely attached without cutting the webbing, and the webbing shall lie flat at the point of entrance.

3.4.5 Serving of rope ends. The ends of the polyester rope used in hems of the roof sections, end sections, and vestibule top covers shall be finished in accordance with figure 3 of MIL-L-1709.

3.4.6 Arch segments. The arch segments shall be not less than 6-ply nor more than 16-ply laminated construction using wood specified in 3.3.12 and 3.3.12.1 and the adhesive specified in 3.3.8. Curvature of segment shall be formed during operation of lamination. Either edge or flat grain boards may be used, but the two types shall not be laminated together in a single segment. Predominance of grain direction in a board shall be the basis of segregation. Laminations shall be dressed to a uniform thickness and shall be free from skips in dressing, oil, crayon marks, or any foreign material that will interfere with bonding of the adhesive. The thickness variation of any lamination at the time of gluing shall not exceed 1/64 inch. Laminations shall be the full width of the arch, but laminations may be scarf-joined to conserve raw material. Scarf-joining shall not occur on the outer plies. Scarf-joining of laminations shall be with the same type of adhesive used in forming the curved segment. Scarf-joints shall be preglued before the final surfacing of laminations. The scarf-joints shall be of a type that provides a gluing surface not less than twelve times the area of a squared end of the board. In case the hooked or step type of scarf-joint is used, the steps must not exceed the 1/16 inch depth. The scarfed area must be free from knots or pitch pockets. The distance between scarf-joints in adjacent plies shall be at least 24 times the thickness of the lamination. There shall be a minimum of three laminations between scarf-joints occurring in the same cross section. Outer laminations shall not have a slope of grain that exceeds 1 inch in 12 inches.

3.4.6.1 Gluing. In order to ensure tight joints of maximum strength, the adhesive specified in 3.3.8 shall be adequately applied in a uniform manner as recommended by the adhesive manufacturer. Assembly periods, clamping or pressing time, and pressure shall be in accordance with the manufacturer's instructions. Test specimens shall show no sign of delamination or separation of glued joints when tested as specified in 4.5.3.

3.4.7 Units, floor. The floor units shall be fabricated from plywood specified in 3.3.13, with the good side of the plywood panel on the outside. Units shall be braced and reinforced, using wood specified in 3.3.12. All joints, except those formed by the closing panel (bottom floor panel), shall be glued tight and sound with the adhesive specified in 3.3.8, and all corners

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

shall be square in accordance with the best commercial practices. The gluing shall be done before prime coating. The units shall be insulated with the material specified in 3.3.7.

3.4.8 Vestibule frame. The vestibule frame shall be of plywood and wood construction using plywood specified in 3.3.13 and wood specified in 3.3.12, with the good side of the plywood on the outside. The frame shall consist of a side panel, door panel, door, covering retainer, and floor unit fabricated according to dimensions shown on the drawings and reinforced. The door shall be squarely hung and fitted with hinges and latch as shown on the drawings. The floor unit shall be reinforced and braced with all nail joints glued, using adhesive specified in 3.3.8. All hardware shall be rigidly attached in the manner and location shown on Drawing 5-4-187.

3.4.9 Door frames. A door frame shall be located in each end section. The frame shall be of wood construction using wood specified in 3.3.12. Each frame shall be equipped with a door, transom, plate, and cover for stovepipe opening plus necessary attaching and operating hardware. The door shall be of plywood (see 3.3.13) and wood construction and shall be insulated with the material specified in 3.3.7. The good side of the plywood shall be to the outside. All doors shall be squarely hung and shall operate freely on their hinges. All hardware shall be securely and rigidly attached, and all operating parts shall function as intended.

3.4.10 Windows. Windows shall be constructed as shown on the drawings and shall operate smoothly.

3.4.11 Purlins. Purlins shall be constructed from wood specified in 3.3.12. All hardware shall be rigidly and squarely attached.

3.4.12 Electrical outlet and switch assembly. The electrical outlet and switch assembly (lighting unit) shall conduct electrical power from an outside source through a circuit breaker switch assembly to lighting outlets when tested as specified in 4.5.4. The assembly shall be fabricated as shown on Drawing 5-4-296. One of the three conductors of the electric cord shall connect the switchbox and each outlet box to a grounded neutral system. Other electrical connections shall be twisted, soldered, and taped unless terminal screws are provided.

3.4.12.1 Setscrew connectors. Setscrew connectors UL approved for 600-volt service may be used, at the option of the contractor, in lieu of twisted, soldered, and taped electrical connections specified in 3.4.12 (see 6.6).

Source: https://assist.dla.mil -- Downloaded: 202640-17T13:38Z
Check the source to verify that this is the current version before use.

first article failure to pass any test shall be cause for rejection of the

3.4.13 Setting of rivets. All rivets shall be securely set with well-formed heads and without splitting of the wooden members. The amount of the rivet end stock to be headed over shall be in accordance with the rivet manufacturer's recommendations. On the following items, the rivets shall be bonded by spinning, or, at the option of the contractor, machine-driven drilled rivets may be used:

a. Arch purlins
b. End purlins
c. Vestibule top purlins
d. Vestibule end purlins
e. Leaf connectors "A" and "B" for end and center arch segments

When machine-driven drilled rivets are used, the depth of the recessed portion of the rivet, when set, shall not exceed 5/32 inch. Rivet heads on the other items may be formed by means other than those specified above, provided there is no splitting of the wooden member as a result of the riveting operation; however, if there is splitting, the rivet heads shall be formed as specified above.

3.4.14 Setting of screws. Wood and sheet metal screws shall be securely set and properly driven. When screws are driven by powered screwdrivers, care shall be given that screw threads shall not be stripped because of over driving. The driving of screws by means of a hammer shall not be permitted. The size of the pilot hole for insertion of screws shall be in accordance with the manufacturer's formula.

3.4.15 Welding. All welding shall be as specified on the drawings. Materials to be welded shall be clean and free from rust, scale, corrosion, oil, water, and other matter. Welds shall be sound and smooth, free from flash, and shall show good fusion.

3.4.16 Finish.

* 3.4.16.1 Metal components. After complete fabrication, prior to assembly, all metal components (with the exception of brass and bronze hardware, slide buckles, tiedown hooks, wrenches, cotter pins, staples, and components covered by referenced documents and the metal parts of the electrical assembly) shall be thoroughly cleaned of grease, dirt, scale, rust, and foreign matter and given a finish conforming to ASTM B 633. The cotter pins shall be given a finish conforming to ASTM B 633. All metal parts of the electrical outlet and switch assembly shall be galvanized according to the best commercial practices.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

3.4.16.2 Wood. After complete fabrication, prior to attachment of metal parts, all surfaces except glue joints shall be given a coat of primer specified in 3.3.46 and shall be allowed to dry thoroughly.

3.4.16.3 After assembly. After assembly of all metal parts to the wood components, all surfaces shall be given one coat of enamel specified in 3.3.47. The enamel shall level out to produce a smooth and uniform film without objectionable brush marks, orange peel, runs, wrinkles, drops, or areas of thin film or no film and shall be free from any trace of grit or coarse particles.

* 3.4.17 Repairs. Repairs to the cloth section, whenever necessary and when authorized by the contracting officer, shall be effected in accordance with Department of the Army Field Manual FM 10-16, except that hand sewn patches or cemented patches other than as specified will not be acceptable. Cemented patches on holes, cuts, or tears not more than 1 inch in diameter or length, using cement specified in MIL-C-2399, shall be permitted. A maximum of three cemented patches per tent shall be allowed without prior authorization by the contracting officer. All other repairs shall require contracting officer authorization.

3.5 Marking.

3.5.1 Component marking. As required, the nomenclature of certain components of the tent shall be printed or stenciled in the size of characters and color and in the locations shown on the drawings.

3.5.2 Identification. Identification marking shall conform to type IV, class 6 of DDD-L-20. In addition, the letters "US" shall be marked in the size of characters and in the location shown on the drawings and shall conform to type IV, class 9 of DDD-L-20. Class 9 markings shall be clearly legible after subjection to accelerated weathering.

3.6 Workmanship. Cloth components shall be clean and free from holes, cuts, tears, or cloth defects such as smashes, weak places, and broken or missing yarns. Webbing and tapes shall contain no frayed or scalloped edges, and rope components shall be free from cuts or abrasions. Thread tension shall be maintained so that there will be no loose stitching, and seam allowances shall be maintained with seams properly sewn so that no run-offs, twists, pleats, puckers, or open seams shall result. All thread ends shall be trimmed. Care shall be taken to see that no needle chews occur. Metal components shall be free from burrs, sharp edges, and corroded areas and shall not be broken or malformed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

* 4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this document shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirement in the document shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

* 4.1.1.1 Compliance. Prior to commencing production, the contractor shall submit to the contracting officer, or his authorized representative, satisfactory evidence that the tents he proposes to furnish under this document meet the applicable requirements of UL and NFPA as indicated in 4.1.1.1.1 and 4.1.1.1.2.

* 4.1.1.1.1 UL. Acceptable evidence of meeting the applicable requirements of UL standards shall be the UL label, the UL listing mark, or a certified test report from a recognized independent testing laboratory, acceptable to the Government, indicating that the electrical components of the offered tents have been tested and conform to the applicable requirements of UL Standards for Fire and Casualty Hazards.

* 4.1.1.1.2 NFPA. All wiring that is not specified by the standards of the Underwriters Laboratories shall conform to the National Electrical Code of the National Fire Protection Association in effect on date of invitation for bids, with the exception that the number of wires within the outlet boxes may exceed the number specified for that size box.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

* 4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for assuring that all specified dimensions have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point or at all points in the manufacturing process necessary to assure compliance with all dimensional requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

4.3 First article inspection. When a first article is required (see 3.1), it shall be examined for the defects specified in tables VI through XIII and shall be tested as specified in 4.4.4. The presence of any visual defect, any dimension not within the specified requirements, or failure to meet the test requirements shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this document or applicable purchase document.

4.4.1.1 Testing of components. In addition to the quality assurance provisions of the subsidiary documents, tests shall be performed on components and materials listed in table I for the characteristics shown. The inspection level shall be S-1, and the acceptable quality level (AQL) for requirements applicable to individual units, expressed in terms of defects per hundred units, shall be 6.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE I. Component tests

Component and lot expressed in terms of	Characteristic	Requirement paragraph	Test method	Number of determinations per sample unit	Results reported as	Sample unit
Insulation (1 pound)	Weight	3.3.7	Direct weighing	1	Pass or fail	20 by 12 inches
	Thickness	3.3.7	4.5.1.1	3	Nearest 1/16 inch	
	Compressional recovery	3.3.7.1	4.5.1.2	5	Nearest 1 percent	
Lumber (1 board foot)	Moisture content	3.3.12	4.5.2	3	Average of 3 determinations	1 component prior to milling

4.4.2 Process examination. Examination shall be made to determine that the following are as specified:

a. There shall be no lubrication of the polyester thread prior to or during the sewing operations for compliance with 3.4.2.5.

b. Holes punched to receive grommets are in compliance with 3.4.3.

c. Curvature of arch segments is correctly formed during lamination; edge and flat grained board are not laminated together in a single segment; gluing surfaces of scarf-joints are clean; scarf-joints have been preglued; depth of steps in scarf-joints (when applicable) are not more than 1/16 inch; and variations in thickness of plies do not exceed 1/64 inch for compliance with 3.4.6.

d. Gluing is done prior to prime coating for compliance with 3.4.7.

e. Setting of rivets is in compliance with 3.4.13.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

f. Size of pilot holes for insertion of screws is in compliance with 3.4.14.

g. Cleaning of metal parts and plating of components are in compliance with 3.4.16.1.

h. Application of primer and subsequent drying of primer prior to application of enamel are in compliance with 3.4.16.2.

i. Insulation for each roof blanket and end-section blanket shall be in one piece for compliance with 3.3.7.

Whenever nonconformance is noted, correction shall be made to the affected items and to the process.

4.4.3 Intermediate inspection.

4.4.3.1 Visual examination. Examination shall be made of intermediate products as specified in 4.4.3.1.1 through 4.4.3.1.3. The inspection level shall be S-4, and the AQL, expressed in terms of defects per hundred units, shall be 1.5 for major defects and 6.5 for total combined major and minor defects.

* 4.4.3.1.1 Visual examination of plies in arch segments. Visual examination shall be made, for defects in table II, of the plies used in arch segments after machining operations and immediately prior to gluing. The lot size shall be expressed in units of plies. The sample unit shall be one ply.

TABLE II. Classification of defects in material and workmanship of plies

Examine	Defect	Classification	
		Major	Minor
Wood	Not specified species	101	
	Any loose or unsound knot or hole	102	
	Any knot or pitch pocket within a scarfed area	103	
	Any sound tight knot (in other than scarfed area) more than 3/4 inch in diameter	104	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE II. Classification of defects in material and workmanship of plies - Continued

Examine	Defect	Classification	
		Major	Minor
Wood - Continued	More than two sound tight knots (in other than scarfed area) exceeding 1/2 inch in diameter in area of one square foot	105	
	Indication of brashness	106	
	Plain or hooked-type scarfed joint is used when the length of scarfed joint is less than 12 times the thickness of the lamination	107	
	Decay, rot, or doze	108	
	Bark, gum pocket, or larvae channel		201
	Split, crack, fracture, cross-break, loosened grain, through or end check, honeycomb, or shake	109	
	Plies not adequately dressed (e.g., they contain skips, oil, crayon marks, or other foreign matter)		202
	Step of hooked scarfed joint exceeds 1/16 inch in depth		203

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

* 4.4.3.1.2 Visual examination of arch assembly. Visual examination shall be made, for defects in table III, of arch assemblies after fabrication but prior to application of the primer and assembly of hardware components. The lot size shall be expressed in units of arch assemblies. The sample unit shall be three arch assemblies.

TABLE III. Classification of defects in material and workmanship of arch segments

Examine	Defect	Classification	
		Major	Minor
Arch assembly	Fracture, split, or hole (except where specified)	101	
	Any lamination not full width of the arch		201
	Joint in outer ply; joint in inner ply is not specified type		202
	Distance between scarf-joints in adjacent plies less than specified		203
	Less than three plies between joints in the same cross section		204
	Delamination	102	
	Less than six or more than sixteen ply construction	103	
	Segment not smoothly surfaced		205

* 4.4.3.1.3 Visual examination of plywood and lumber. Visual examination shall be made, for the defects in table IV, of sheets of plywood and wooden components after fabrication but prior to assembly and priming operations. The lot size shall be expressed in units of plywood. The sample unit shall be one sheet of plywood cut to the specified size and one wooden component of each type and size.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE IV. Classification of defects in material and workmanship of plywood and lumber

Examine	Defect	Classification	
		Major	Minor
Plywood			
General	Any delamination	101	
	Not sanded as required		201
	Any nonpermissible defect filled with plastic wood or other filler material	102	
	Brashness, doze, or decay	103	
	Warped	104	
Grade A veneer (PS 1)	Any knot or hole	105	
	Split, pitch pocket, or other open defect	106	
	Pitch streak more than 3/8 inch wide		202
	Patch not neat		203
	More than 18 patches in 4 feet by 8 feet area	107	
	Shim over or around patch	108	
	More than 2 patches used in any multiple repair		204
	Any patch or repair not parallel to the grain		205
	Single patch exceeds 2 1/4 inches in width		206
	Any patch multiple repair exceeds 7 inches in length and 1 inch in width		207
	Crack or check (filled or unfilled 1/32 inch or more wide)	109	
	Crack or check, not more than 1/32 inch wide, not filled with approved plastic filler		208
	Split or opening (filled or unfilled) 1/16 inch or more wide or 2 inches or more in length	110	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE IV. Classification of defects in material and workmanship of plywood and lumber - Continued

Examine	Defect	Classification	
		Major	Minor
Plywood - Continued			
Grade A veneer (PS 1) - Continued	Split or opening not more than 1/16 inch wide and not exceeding 2 inches in length, not filled with approved plastic material		209
	Chipped area or opening (filled or unfilled) more than 1/8 inch wide by 1/4 inch long	111	
	Chipped area or opening (filled or unfilled), not more than 1/8 inch wide by 1/4 inch long, not filled with approved filling material		210
Grade C veneer (PS 1)	Loose knot or knothole more than 1 inch in smallest dimension		211
	Open pitch pocket more than 1 inch wide		212
	Repair not neatly made		213
	Patch or plug exceeds 3 inches in width when used in multiple repair or exceeds 4 inches in width when used singly		214
	Patch or plug is not specified type		215
	Split more than 3/16 inch wide	112	
	Worm or borer hole more than 5/8 inch wide or more than 1 1/2 inches long	113	
	Any knot more than 1 1/2 inches long in smallest dimension		216
Grade 2 veneer (CS 35)	Sound tight knot more than 3/4 inch in diameter		217
	Unsound knot or hole	114	
	Unsound or rough burl		218
	Sound burl more than 1 inch in diameter		219
	Rough cut veneer		220
	Lap		221
	Crossbreak		222
	Bark pocket		223

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

TABLE IV. Classification of defects in material and workmanship of plywood and lumber - Continued

Examine	Defect	Classification	
		Major	Minor
Plywood - Continued			
Grade 2 veneer (CS 35) - Continued	Wormhole split or open joint not filled or patched		224
Grade 3 veneer (CS 35)	Any knot hole exceeding 3/4 inch in maximum diameter		225
	Any split or open joint more than 3/16 inch wide or extending more than one-half the length of the panel		226
	Crossbreak, more than 3/4 inch in length		227
	Rough cut (in area more than 2 inches square)		228
	Lap(s)		229
Lumber	Any unsound knot or hole	115	
	Any knot more than 3/4 inch in diameter	116	
	More than one knot exceeding 1/2 inch but not exceeding 3/4 inch in diameter occurring in area of 1 square foot		230
	More than two knots, not exceeding 1/2 inch in diameter, occurring in area of one square foot		231
	Bark, pitch pocket, or larvae channel		232
	Any rot, doze, or decay	117	
	Hole (except where required)	118	
	Warp		233

4.4.3.2 Dimensional examination. Examination shall be made to determine that the plies are the full width of the arch and that the dimensions of the scarfed joints are as specified. The lot size shall be expressed in units of arch assemblies. The sample unit shall be one arch assembly. Any dimension

Source: https://assist.dla.mil -- Downloaded: 2026l0-17T13:38Z
Check the source to verify that this is the currentversion before use.

not within the specified tolerances shall be classified as a defect. The inspection level shall be S-3, and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

4.4.3.3 Testing of intermediate products. Testing of the partially fabricated tent frame shall be performed in accordance with table V for the characteristics shown.

TABLE V. Testing of intermediate products

Component	Characteristic	Requirement paragraph	Test method	Number of determinations per sample unit	Results reported as
Wrench, key	Hardness	3.3.22	Standard commercial	3	Average of 3 det. to the nearest scale reading
Arch segment	Slope of grain (outer laminations)	3.4.6	Standard commercial	1 (each outer lamination)	Pass or fail
	Glued joint (delamination or separation and percent wood failure after break)	3.4.6.1	4.5.3	2	Pass or fail

4.4.3.3.1 Hardness of key wrench. The lot size shall be expressed in units of key wrenches. The sample unit shall be one wrench after fabrication but prior to application of finish. The inspection level shall be S-1, and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

4.4.3.3.2 Slope of grain and glued joint. The lot size shall be expressed in arch segments. The sample unit shall be one arch segment after fabrication and gluing prior to application of primer coat. The specimen for the glue test shall be cut from a glued arch segment. The inspection level shall be S-1, and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

4.4.4 End item inspection. The tents shall be examined as specified in 4.4.4.1 through 4.4.4.5 and tested as specified in 4.4.4.6. The lot shall consist of all completely fabricated tents with frames offered for inspection at one time. The sample unit shall be one complete tent with frame.

* 4.4.4.1 Visual examination of tent fabric sections. Examination shall be made of the tent fabric for the defects in table VI. The inspection level shall be II. The AQL's, expressed in terms of defects per hundred units, shall be as follows:

a. For end section - 10.0 for major defects, 25.0 for combined major and minor A defects, and 100.0 for total combined major and minor defects.

b. For roof section - 6.5 for major defects, 15.0 for combined major and minor A defects, and 65.0 for total combined major and minor defects.

c. For guy band - 2.5 for major defects, 6.5 for combined major and minor A defects, and 15.0 for total combined major and minor defects.

d. For vestibule and cover - 2.5 for major defects, 6.5 for combined major and minor A defects, and 10.0 for total combined major and minor defects.

TABLE VI. Classification of visual defects for tent fabric sections

Examine	Defect	Classification		
		Major	Minor A	Minor B
Cloth coated	Hole (except drill hole), cut, or tear	X		
	Scratch or abrasion mark	X		
	Exposed drill hole (i.e., not covered by attached parts)		X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VI. Classification of visual defects for tent fabric sections - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Tape and webbing	Edge frayed or scalloped		X	
Rope components	Cut or abrasion; eye splice omitted	X		
	Eye splice not as specified; free ends not finished as specified		X	
Hardware	Broken or malformed; protective finish omitted; corroded area; burrs or sharp edges	X		
	Not correct type or size (as applicable)		X	
	Missing	X		
	Not rigidly or securely attached in the manner and location shown on drawing		X	
	Operating parts do not function as intended		X	
Grommets	Clinched excessively tight, cutting fabric or insecurely clinched (i.e., grommet or washer becomes disengaged)	X		
	Improperly set; two or more teeth exposed inside of barrel; clinched loosely, causing grommet to rotate around hole			X
Slide buckle w/hook; buckle tongueless	Not securely assembled to chapes			X
End clips	Not securely clinched; webbing not flat at point of insertion			X
	Clinched excessively tight, cutting webbing		X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VI. Classification of visual defects for tent fabric sections - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Seams and stitching	Open seams on stitch type 301:			
	- more than 1/4 inch, but not more than 1 inch			X
	- more than 1 inch		X	
	Open seams on stitch type 401, except run-offs	X		
	Run-offs on stitch type 401:			
	- more than 1/2 inch, but not more than 1 inch			X
	- more than 1 inch		X	
NOTE:	A seam shall be classified as open when one or more stitches joining a seam are broken or when two or more consecutive skipped stitches or run-offs occur. On double stitched seams, a seam shall be considered open when either one or both sides of the seam are open.			
Seams	Badly twisted or pleated		X	
Raw edges	When securely caught in stitching (where required):			
	- more than 1 inch, but not more than 3 inches			X
	- more than 3 inches		X	
NOTE:	Raw edges not securely caught in stitching shall be classified as open seams.			
Run-offs (see open seams)				
Seam and stitch type	Wrong seam or stitch type	X		

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VI. Classification of visual defects for tent fabric sections - Continued

Examine	Defect	Classification	
		Major	Minor
			A B
Seams and stitching - Continued			
Stitch tension	Loose, resulting in a loosely exposed top or bottom (bobbin or looper) thread		X
	Tight, resulting in excessive tightness or puckering of fabric		X
Stitches per inch	One stitch less than minimum specified		X
	Two or more stitches less than minimum specified		X
	One or two stitches in excess of maximum specified		X
	Three or more stitches in excess of maximum specified		X
NOTE:	Variation in the number of stitches per inch caused by the operator's speeding up the machine and pulling the fabric in order to sew over heavy seams or heavy places or turning corners shall be classified as follows:		
	a. Within the minor "A" defect classification - minor B defect		
	b. Within the minor "B" defect classification - no defect		
Stitching margins; stitching gage	Not as specified		X

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VI. Classification of visual defects for tent fabric sections - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Seams and stitching - Continued				
Thread breaks	Overstitched less than 1 1/2 inches on stitch type 401; overstitched less than 1 inch on stitch type 301			X
NOTE:	Thread breaks not overstitched on each side of break as specified shall be classified as open seams.			
Stitching ends	Overstitched less than 1 inch (except where ends are held down by other stitching or turned under in a hem)		X	
Stitching indicated by "Z" on drawings	Chain portion of stitching shown on outside of tent section or cover		X	
Machine stitching	Needle chews	X		
	One or more required rows of stitching omitted, except on box-stitching	X		
	Box stitching incomplete:			
	- one end row of stitching omitted		X	
	- two end rows of stitching omitted	X		
	- any other row of stitching omitted	X		
	Length or width of boxstitching less than specified by more than 1/8 inch			X
Components and assembly	Any component part omitted (unless otherwise classified herein)	X		
	Any component part not fabricated of specified material	X		

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VI. Classification of visual defects for tent fabric sections - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Hems	Twisted or pleated (except on semi-circular hem of ends)			X
	Constructed with partial turnunder when double turnunder is required		X	
Reinforcement	Improperly applied, causing excessive fullness on reinforcements or reinforced parts			X
	Not securely stitched to reinforced parts on all sides, or not securely caught in seams or stitching of reinforced parts		X	
Lugs	Misplaced, failing to serve intended purpose	X		
	Constructed with less than 4 plies of fabric		X	
Mends, darns, or patches	Repairs not in accordance with Department of the Army Field Manual FM 10-16, or not authorized by the contracting officer (see 3.4.17)	X		
Marking	Omitted, incorrect, illegible, or misplaced; color of ink not as specified			X
	Noticeable grease or oil stains; thread ends not trimmed throughout			X

* 4.4.4.1.1 Visual examination of end section. Examination shall be made of the end sections for the defects in table VII. The inspection level shall be II, and the AQL, expressed in terms of defects per hundred units, shall be 10.0 for major defects, 25.0 for combined major and minor A defects, and 100.0 for total combined major and minor defects.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VII. Classification of visual defects for end section

Examine	Defect	Classification		
		Major	Minor	
			A	B
Bottom flaps	Inner end of flaps not finished as indicated in section M-M, Drawing 5-4-184		X	
Bottom edge of batt cover	Not securely caught in bottom hem of flaps (i.e., not caught in both rows of stitching)		X	
Bottom hems (outside)	Outer end of hems caught in stitching joining inner shell to outer shell and bottom flaps	X		
	Top edge of hems not stitched through both plies of flap at fold line		X	
Tiedown hook chapes	Chapes not stitched through bottom hem (i.e., stitched through a single ply of body only)	X		
Door frame edge of blanket halves	Pleated or badly gathered, causing excessive fullness on body of blanket halves; stitching joining outer shell to inner shell at door edge exposed beyond edge of molding		X	
	Edges of outer shell tacked to door frame or not caught in molding nails; any edge of blanket halves exposed beyond door frame molding	X		
Windows	Edges of screen exposed or cut edges of opening not turned under			X
	Set to body with top or bottom of frame unequal in distance from door frame		X	
	Edges of inner shell or outer shell of window opening not tacked to window frame or not caught in batten nails	X		

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE VII. Classification of visual defects for end section - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Windows - Continued	Edges of inner or outer shell of window openings pleated or badly gathered, causing excessive fullness on body	X		
	Any area of noninsulation around window frame	X		
Window blackout flaps	Flaps caught in unrelated retainer stitching causing failure of flaps to roll up	X		
Lug reinforcement and lugs	Lug reinforcements misplaced; failing to reinforce lugs; lug stitched through insulation and outer shell	X		
Buckle chape "B" and retainer	End of retainer stitched through single ply of outer shell only instead of through hem and edge of inner shell (except bottom end of door top retainer)	X		
	Retainer single ply construction		X	
	Chape strap attached to outside of retainer instead of inside		X	
Arch hinge reinforcement	Less than 3-ply construction	X		
Top panels at top of doorframe	Pleated or badly gathered along doorframe causing excessive fullness at peak of blanket			X
Transom blackout flap	Top edge of flap not caught in transom batten nails	X		
Snap bolt w/swivel round eye	Not securely fastened to end roof guy lines			X
	Spring tongue or snap jams or fails to function properly		X	

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

* 4.4.4.1.2 Visual examination of roof section. Examination shall be made of the roof section for the defects in table VIII. The inspection level shall be II, and the AQL, expressed in terms of defects per hundred units, shall be 6.5 for major defects, 15.0 for combined major and minor A defects, and 65.0 for total combined major and minor defects.

TABLE VIII. Classification of visual defects for roof section

Examine	Defect	Classification		
		Major	Minor A	Minor B
End flaps	Inner end of flaps not finished as indicated in section B-B, Drawing 5-4-186		X	
Bottom edge of batt cover	Not securely caught in bottom hem of flaps (i.e., not caught in both rows of stitching)		X	
Bottom hems (outside)	Outer end of hems caught in stitching joining inner shell to outer shell and bottom flap	X		
	Top edge of hems not stitched through both plies of flap at fold line		X	
Tiedown hook chapes	Chapes not stitched through bottom hem (i.e., stitched through a single ply of body only)	X		
Corner reinforcement	Ends of reinforcement not caught in both rows of hem stitching; lower edge of reinforcements uneven with ends of side hem by more than 1/8 inch			X
Lugs	Lug stitched through insulation and outer shell	X		

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

* 4.4.4.1.3 Visual examination of guy band. Examination shall be made of the guy band for the defects in table IX. The inspection level shall be II, and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

TABLE IX. Classification of visual defects for guy band

Examine	Defect	Classification	
		Major	Minor A B
Dee-rings	One inch, not securely held in eye splice of polyester rope; 1 1/2 inches, not securely attached to guy band or chapes not fully stitched on guy band through reinforcement		X
	Ends of reinforcement not stitched through guy band; less than 8 1/4 inches long		X

* 4.4.4.1.4 Visual examination of vestibule and cover. Examination shall be made of vestibule and cover for the defects in table X. The inspection level shall be II, and the AQL, expressed in terms of defects per hundred units, shall be 2.5 for major defects, 6.5 for combined major and minor A defects, and 10.0 for total combined major and minor defects.

TABLE X. Classification of visual defects for vestibule tops and end cover

Examine	Defect	Classification	
		Major	Minor A B
Vestibule and cover			
Buckle chape "A"	Any chape not stitched through body of cover and side hems or bottom reinforcement (i.e., stitched through a single ply of cover only)	X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE X. Classification of visual defects for vestibule tops and end cover - Continued

Examine	Defect	Classification		
		Major	Minor	
			A	B
Vestibule and cover - Continued				
Top end	Hem not caught in retainer steel binding screws	X		
	Attached to retainer with less than 8 sheet metal screws; pleated or badly gathered, causing excessive fullness on body of cover		X	
Bottom flap	Inserted portion of flap not flush with bottom edge of hem or not caught in three rows of stitching			X
Reinforcement "A"	Omitted or not attached to cover as specified	X		
Gussets	Not firmly riveted to retainer; secured with less than three rivets		X	
Purlin clip	Not firmly attached to retainer		X	
Vestibule top cover				
Buckle chape "A"	Any chape not stitched through cover reinforcements (i.e., stitched through a single ply of cover only)		X	
Flaps	Bottom edge of flap not flush with bottom edge of hem or not caught in three rows of stitching			X
Reinforcements "B"	Ends of edges of reinforcements not flush with fold lines of side or end hems, or not caught in three rows of side hem stitching or in both rows of end hem stitching			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

* 4.4.4.2 Dimensional examination of tent fabric sections. Examination shall be made of the tent fabric for the defects in table XI. The inspection level shall be S-4, and the AQL, expressed in terms of defects per hundred units, shall be 4.0 for major defects, 25.0 for combined major and minor A defects, and 65.0 for total combined major and minor defects.

TABLE XI. Classification of dimensional defects for tent fabric sections

Examine	Defect	Classification		
		Major	Minor A	Minor B
Overall dimensions of roof blankets, end blankets, guy bands, top and end vestibule covers	Smaller than nominal dimensions less applicable minus tolerance indicated on drawings	X		
	Larger than nominal dimensions and applicable plus tolerance indicated on drawings			X
Dimensions of components (unless otherwise specified)	Less than specified dimension: - by more than 1/4 inch but not more 1/2 inch			X
	- by more than 1/2 inch		X	
Location dimensions (unless otherwise specified)	Components set beyond specified location: - by more than 1/4 inch but not more than 1/2 inch			X
	- by more than 1/2 inch		X	
Webbing and tie tapes	Finished length less than specified by more than 1/2 inch			X
Rope components	Length of finished lines less than specified by more than 1 1/2 inches (except lug tie lines); lug tie lines less than specified by more than 3/4 inch			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

, or assembly at which they are required. For example, all the level

TABLE XI. Classification of dimensional defects for tent fabric sections - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Hems	Required to finish less than 3/4 inch in width, less than specified; hems required to finish 3/4 inch or more in width, less than specified by more than 1/4 inch			X
Reinforcements	Finished dimension less than specified by more than 1/2 inch			X
Window blackout flaps	Set with centerline of flaps off center of window by more than 3/8 inch; set with top end of flap less than 2 1/2 inches or more than 3 1/4 inches from upper edge of window top batten		X	
Buckle chape "B" and retainer	Retainer less than 3 3/4 inches wide			X
	Set beyond specified location by more than 1/2 inch			X
Arch hinge reinforcement	Set beyond location specified: - by more than 1 inch	X		
	- by more than 1/2 inch but not more than 1 inch		X	
Vents	Corners of vent opening set more than 3 1/2 inches apart		X	
	Finished dimension less than 3 3/4 inches on any side; set off center of blanket by more than 1/2 inch			X
Corner reinforcement	Lower edge of reinforcements uneven with ends of side hem by more than 1/8 inch			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

* 4.4.4.3 Visual examination of tent frame. Examination shall be made of the tent frame for the defects in table XII. The inspection level shall be II, and the AQL, expressed in terms of defects per hundred units, shall be 4.0 for major defects, 40.0 for combined major and minor A defects, and 100.0 for total combined major and minor defects.

TABLE XII. Classification of visual defects for tent frame

Examine	Defect	Classification		
		Major	Minor A	Minor B
Finish	Not finished or finish is not as specified	101		
	Finish is not smooth and uniform (e.g., contains brush marks, runs, wrinkles, drops or area of thick or thin film such that wood grain or primer shows through)		201	
	Not adherent (i.e., is blistered, peeling, or flaking)		202	
	Foreign matter embedded		203	
	Area of no film (e.g., enamel has not been applied or has been abraded, scuffed, scratched, or is otherwise removed)		204	
	Finish is not dry			205
	Electrical outlet and switch assembly are not galvanized	102		
	Any corrosion on metal component	103		
Material	Any component not fabricated of the specified material	104		
Construction and workmanship	Any component missing, torn, broken, bent out of shape, twisted, warped, malformed, or deformed	105		
	Splinter, fin, or sliver that may cause injury or damage fabric	106		
	Plywood panel is not one piece (unless otherwise specified)	107		

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE XII. Classification of visual defects for tent frame - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Construction and workmanship - Continued	Any joint not glued when required	108		
	Glue joint open all the way through: - more than 25 percent of entire length	109		
	- more than 10 percent but less than 25 percent of entire length		206	
	- 10 percent or less of entire length			207
	Any joint not securely fitted	110		
	Any operation omitted or not properly performed	111		
	Any functioning component or assembly that cannot be operated	112		
	Any functioning component or assembly that requires undue force to operate but will function		208	
	Any assembly hole missing, misplaced, or wrong size	113		
	Assembly not complete (e.g., finish strip, runner, or molding missing where required)		209	
Arch segments	Warped or sprung	114		
	Ferrule not lap seamed		210	
	Ferrule not tight to fit to wood member		211	
	Ferrule not a flush fit to end of arch segment		212	
	Ends of arch segments do not fit flush and smooth, or are out of alignment		213	
Assemblies	Good side of plywood is not on the outside when required		214	
	Door not squarely hung or does not operate freely on hinges	115		
	Latch does not engage keeper	116		

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE XII. Classification of visual defects for tent frame - Continued

Examine	Defect	Classification		
		Major	Minor A	Minor B
Construction and workmanship - Continued				
Assemblies - Continued	Door latch does not operate from either side of the door	117		
	Screen missing where required, or it is not specified type and size	118		
	Molding or weatherstrip is missing or is not specified type	119		
Hardware	Missing or not specified type	120		
	Out of position (e.g., companion parts do not mate)		215	
	Force required to join or lock mating parts		216	
	Not rigidly attached in the specified manner and/or location	121		
Bolts and nuts	Any missing or broken	122		
	Thread damaged or stripped	123		
	Not specified type or size		217	
	Bolt is not welded to hardware where required	124		
	Carriage bolt neck turns in hole			218
	Bolt not peened to retain nut where required	125		
	Excess bolt length not removed when required			219
	Any wing nut that does not turn freely			220
	Washer missing, when required		221	
	All wing nuts not on the same side of arch			222

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE XII. Classification of visual defects for tent frame - Continued

Examine	Defect	Classification	
		Major	Minor A B
Hardware - Continued			
Rivets	Improperly set, causing splitting of wood members		223
	Rivets not spun or not machine driven where required		224
	Rivet missing, not peened, or head broken off	126	
	Not specified type		225
	Burr missing where required	127	
	Rivet not set as required (i.e., is not loose or not drawn up tight as specified)		226
	Improperly peened, resulting in sharp, ragged edge		227
Pins	Wrong type or size	128	
	Damaged or bent out of shape		228
	Not secured as specified (e.g., by chain and cotter pin)	129	
	Not loose when required (e.g., cannot be removed from connectors)	130	
Screws, wood and metal	Any missing, broken, bent, or damaged	131	
	Not driven up tight (e.g., head cocked more than 1/32 inch)		229
	Not specified type or size (e.g., wood screws used in lieu of sheet metal screws)		230
Nails and tacks	Missing, broken, bent, or damaged	132	
	Run out or point protrudes		231
	Nailing pattern not as specified		232
Cotter pin	Missing or damaged	133	
	Not secured when required		233

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE XII. Classification of visual defects for tent frame - Continued

Examine	Defect	Classification		
		Major	Minor	
			A	B
Welds and welding	Missing where required	134		
	Not specified type		234	
	Metal burned or damaged in welding		235	
	Weld is porous, fractured, burned through, broken, not fused, or is otherwise not sound	135		
	Not smooth		236	
	Flux deposits not removed		237	
Electrical appliances	Any component missing or not the specified type (e.g., switch is not designed for manual resetting)	136		
	Not assembled as specified		238	
Marking	Missing, incorrect, incomplete, misplaced, illegible, wrong color or size			239

* 4.4.4.4 Dimensional examination of tent frame. Any dimension not within the specified tolerances shall be classified as a defect. The inspection level shall be S-3, and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

* 4.4.4.5 Examination of tent frame for defects in erection. Tent frames shall be erected to determine facility of assembly and fit of mating parts as specified on Drawing 5-4-181. Defects shall be scored in accordance with table XIII. The inspection level shall be S-1, and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

TABLE XIII. Examination of tent frame for defects in erection

Examine	Defect
Assembly	Any component that cannot be connected or joined with companion assembly
	Not readily assembled (i.e., assembly requires realignment of parts, drilling or enlargement of holes, use of drift pin or other mechanical means)
	Assembly hole missing or misplaced
	Undue force or special tool is required to effect assembly
	Door not squarely hung or does not operate freely
	Door reversed
	Door is not a close fit to jamb stops
	Any part or component buckled, bent out of shape, torn, or broken
	Any part or component missing or improperly assembled (check all bolts, nuts, pins, washers, gasket, locking device, blackout flap, screen, stovepipe opening plate, stovepipe plate cover, etc.)
	Component too loose or does not fit properly in mating component
	Component out of alignment
	All wing nuts are not on same side of arch
	Transom cannot be opened and locked in position by locking strap

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

4.4.4.6 End product testing. The electrical outlet and switch assembly shall be tested as specified in 4.5.4. The sample unit shall be one complete assembly, and one determination shall be made per sample unit. The results shall be reported as pass or fail, and any noncompliance shall be cause for rejection of all electrical outlet and switch assemblies in the lot. The inspection level shall be S-1.

4.4.5 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 2.5.

Examine	Defect
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application
Materials	Any component missing, damaged, or not as specified
Workmanship	Inadequate application of components, such as incomplete sealing or closure of flap, improper taping, loose strapping, or inadequate stapling Bulged or distorted container
Content	Number of components per container is more or less than specified

4.5 Methods of inspection.

4.5.1 Insulation.

4.5.1.1 Thickness. The thickness of the insulation shall be determined by a suitable gage or measuring device. Three determinations shall be made per sample unit, and the results shall be reported as the average of the three determinations to the nearest 1/16 inch.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

4.5.1.2 Compressional recovery.

4.5.1.2.1 Test apparatus. The test apparatus shall consist of the following:

a. A box of proper size to hold specimen. The sides of the box shall be so constructed that, when a straight edge is rested across the top of any two sides, the straight edge is parallel to the bottom of the box.

b. Straight edge.

c. Depth gage.

d. Aluminum cover plate weighing 0.9 gram per square inch.

e. Weight equivalent to one pound per square inch of sample area.

4.5.1.2.2 Specimens. The specimens shall be no smaller than 4 by 4 inches and shall be cut no nearer than 12 inches from any edge of the glass fiber batting.

4.5.1.2.3 Procedure. Allow specimen to relax on table with no weight on surface for 24 hours before testing for compressional recovery. Place specimen on box with cover plate on top of the specimen. Place straight edge across the top of box to serve as reference stop for depth gage. Determine initial thickness of specimen (thickness of specimen and cover plate minus thickness of cover plate equals thickness of specimen). Remove depth gage and straight edge. Compress specimen under a weight equivalent to one pound per square inch, evenly distributed over the whole surface of the specimen. Allow load to remain for one full minute. Remove weight from specimen. Permit specimen to relax for 15 seconds. Repeat this loading procedure two more times. Measure thickness of specimen within one minute after weight has been removed for final time.

4.5.1.2.4 Calculation. A minimum of five specimens shall be tested for each determination of compressive recovery.

$$\frac{\text{Thickness of specimen after compression}}{\text{Initial thickness of specimen}} \times 100 = \text{Percent compression recovery}$$

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

* 4.5.2 Moisture content. The moisture content of the lumber shall be determined in accordance with either the oven drying or the electrical moisture meter method referenced in ASTM D 2016. A moisture content of less than 8 or more than 12 percent shall be classified as a defect.

4.5.3 Arch (laminated segments), wet and dry cycle test. A specimen 6 inches long shall be cut from a finished arch segment. Ends of the specimen shall not be treated. Specimen shall be subjected to three wet and dry cycles, each cycle to consist of 16 hours of soaking in water at room temperature immediately followed by drying for 6 hours at a temperature of 125°F. After completion of the wet and dry cycle test, the specimen shall show no sign of delamination or separation of glued joints. The test specimens shall then be broken apart at the glue joints, and each joint shall show not less than 50 percent wood failure.

4.5.4 Electrical continuity. The completely assembled electrical outlet and switch assembly shall be tested for electrical continuity by means of bulbs, bells, voltmeter, or ammeter. Results shall be examined to determine compliance with the requirements specified in 3.4.12.

5. PACKAGING

5.1 Preservation. Preservation shall be level A.

5.1.1 Level A. Each switch and socket on the electrical outlet switch assembly shall be sealed with tape conforming to (type optional) class 1 of PPP-T-60, and the exposed tape surfaces coated with insulating compound conforming to MIL-V-13811.

5.2 Packing. Packing shall be level A.

5.2.1 Level A packing.

5.2.1.1 Electrical outlet and switch assembly, complete. Each complete electrical outlet and switch assembly, preserved as specified in 5.1, shall be packed in a snug-fitting nailed wood container conforming to class 2, style 2 or 4 of PPP-B-621. The contents shall be cushioned, blocked, and braced as applicable to prevent movement while in transit. Each shipping container shall be closed and reinforced with flat steel strapping conforming to type I, class B of QQ-S-781.

Source: https://assist.dla.mil -- Downloaded: 202640-17T13:38Z
Check the source to verify that this is the currentversion before use.

in their objec- procedures do not comply with system or do not ada

5.2.1.2 End section, complete. Each complete end section shall be packed in a box made up of its two floor units in the following manner:

4 each - Runners shall be placed flat, lengthwise, at one end on the bottom of one floor unit.

9 each - Purlins shall be placed flat, lengthwise, at the same end alongside the runners.

8 each - Tent pins shall be thoroughly dried and completely wrapped in not less than two thicknesses of 60 pound minimum basis weight kraft paper conforming to grade A of UU-P-268. The kraft paper wrap shall be securely sealed with gummed paper tape, minimum 2 inches in width, conforming to type III, grade B of PPP-T-45. The bundle of pins shall then be placed in the floor unit along with the runners and purlins.

2 each - End purlins shall be placed lengthwise on the bottom of the floor unit.

1 each - Guy band shall be neatly folded and placed across the unit at opposite end from the runners.

2 each - End guy lines shall be neatly folded and placed with the guy band.

1 each - Tent end section shall be neatly folded to fit into the floor unit and placed on top of the above items.

1 each - Tent roof section shall be neatly folded in the same manner and placed next in the floor unit.

The door handle on the tent end section shall be completely cushioned with cushioning material conforming to type II, class B of PPP-C-843. The contents shall be securely blocked and braced with lumber to prevent movement while in transit. The remaining floor unit shall then be placed on top of the first floor unit to form a box and the two floor units secured with the rotolock fasteners. The tiedown hook holes shall be covered with tape conforming to (type optional) class 1 of PPP-T-60.

5.2.1.2.1 Hardware protector cleats, reinforcements, skids and strapping. Two wood hardware protector cleats as shown on Drawing 5-4-182 shall be nailed, as specified, over the wing nuts at the end of each box. In addition, another wood cleat the same size as the hardware protector cleats, but without holes, shall be nailed to the same end of the box equidistant between the hardware protector cleats, with not fewer than six 3d cement-coated nails.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the currentversion before use.

Three wood cleats with no holes bored and of the same size as the hardware protector cleats shall be placed and nailed in the same position to the other end of the box. Two wood cleats, 11 inches long by 3 5/8 inches wide by 3/4 inch thick, shall be nailed to each side approximately 3 inches from the end of the box with no fewer than six 3d cement-coated nails. The box shall then be strapped with one steel strap 3/4 inch by 0.023 inch, type I, class B, conforming to QQ-S-781. The strap shall be centered around the perimeter of the box and shall pass over all cleats at the center. Not less than one galvanized staple shall be nailed to each cleat to hold the steel strap in place. Four steel straps 3/4 inch by 0.023 inch, type I, class B, conforming to QQ-S-781, shall be placed girthwise around each box, the two end straps to be placed approximately 5 inches from each end, and the other two equidistant from the two end straps. The two end straps shall pass over approximately the center of the side wood cleats. Not less than two galvanized staples shall be nailed to each side cleat to hold the straps in place. Four wood reinforcements 1/4 inch longer than the width of the box by 3 5/8 inches wide by 1 5/8 inches thick shall be placed under each girthwise strap on the top of the box. Four wood pieces (skids) 1/4 inch longer than the width of the box by 3 5/8 inches wide by 1 5/8 inches thick shall be placed under each girthwise strap on the bottom of the box. The girthwise straps shall be nailed to the top wood reinforcements and the bottom skids with galvanized staples placed not more than 24 inches apart. The strap shall indent the reinforcements and skids at the ends approximately 1/8 inch.

5.2.1.3 Intermediate sections, complete. Each complete intermediate section shall be packed in a box made up of its two floor units and the floor units provided with protector cleats, reinforcements, skids, and strapping in the same manner as specified in 5.2.1.2 for end section, except that the contents of floor units shall comprise the following items:

4 each - Runners

9 each - Purlins

4 each - Tent pins (bundles)

1 each - Guy band

1 each - Tent roof section

The contents shall be securely blocked and braced with lumber to prevent movement while in transit. The tiedown hook holes shall be covered with tape conforming to (type optional) class 1 of PPP-T-60.

Source: https://assist.dla.mil -- Downloaded: 202610-17T13:38Z
Check the source to verify that this is the current version before use.

* 5.2.1.4 Vestibule, complete. Each complete vestibule shall be packed in a snug-fitting nailed wood crate conforming to type II, style A of MIL-C-52950 in the following manner:

1 each - Vestibule side panel shall be packed, outside down, on the bottom of the crate. Internal blocking and bracing shall be provided to level the panel and protect its projections.

1 each - Vestibule panel and door shall be placed on top of the side panel. Internal blocking and bracing shall be provided to level the panel and protect the door lock and prevent damaging contact between panels.

1 each - Vestibule end cover shall be neatly folded and placed on the door and panel at one end of the crate.

1 each - Vestibule top purlin.

1 each - Vestibule end purlin.

1 each - Tie angle shall be placed flat alongside the end cover.

1 each - Vestibule top cover shall be placed on top of or alongside the purlins.

1 each - Vestibule floor unit shall be positioned over the above items and on top of the door panel. Care shall be exercised to ensure complete coverage of the covers, purlins, and angle. The unit shall then be adjusted so that it is against the side and end of the crate. Internal blocking and bracing shall be provided to hold the unit secure over the purlins, and other items and to prevent movement or damage in transit.

Internal wood blocking and bracing shall not depend on end grain nailing alone. Supplemental supporting cleats shall be provided to reinforce the blocks and prevent splitting of the blocking and bracing.

5.2.1.5 Arch, complete. Each complete arch with its arch pin and chain and chain footstop wired securely to the arch with not less than 0.072-inch annealed wire shall be folded and provided with dividers and crates for the protection of the arch ends as shown on the drawings.

5.3 Marking. In addition to any special marking required by the contract or purchase order, intermediate packs and shipping containers shall be marked in accordance with MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

5.3.1 Identification marking. Each box or crate shall be legibly stenciled as to identification (such as END SECTION, INTERMEDIATE SECTION, VESTIBULE), and only the top half of the floor units forming the boxes shall be legibly stenciled or printed showing list of contents.

5.3.2 Special marking. In addition to the specified marking, two sides of each box shall be legibly printed or stenciled in minimum 3/4-inch letters as follows:

USE NO HOOKS

STORE UNDER COVER

6. NOTES

6.1 Intended use. The insulated frame-type tent is intended for use in cold climates. This tent is expandable in increments of 4 feet. Vestibules may be used on one or both ends or may be deleted entirely, depending upon usage of the tent. For standardization purposes, the lighting harness assembly was designed for a tent 16 feet by 16 feet.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this document.
b. When a first article is required (see 3.1, 4.3, and 6.4).

6.3 Standard sample. For access to a standard sample of thread, address the contracting activity issuing the invitation for bids.

* 6.4 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in all acquisition instruments regarding arrangements for selection, inspection, and approval of the first article.

6.5 Coated duck material. The most economical width of finished coated duck to use in the manufacture of this shelter is as follows:

a. Coated duck, light green - 51 inches
b. Coated duck, Olive Drab 7 - 59 1/2 inches

Source: https://assist.dla.mil -- Downloaded: 20260-17T13:38Z
Check the source to verify that this is the current version before use.

6.6 Commercial products. The following commercial products have been found to meet the requirements of this document. This information is included for the convenience of those interested and is not intended to preclude the purchase of any items produced by other manufacturers that are in accordance with this document.

a. Door latch - Vonnegut No. 25, Vonnegut Hardware Co., Indianapolis, IN.
b. Set screw wire connectors - Ideal No. 11, Ideal Industries, Inc. Sycamore, IL.

6.7 Component listing. The tent, frame-type, insulated, sectional, with floor, 16 feet wide, M-1948, complete, consists of the following component parts:

a. One section, End, Complete, For Tent, Frame-Type, Insulated, Sectional, with Floor 16 feet wide, M-1948, Complete (Stock No. 8340-377-6609) consists of the following:

2 each - Floor unit, complete (Stock No. 8340-377-6596).

1 each - Section, end, tent, complete (Stock No. 8340-377-6590).

1 each - Section, roof, tent, complete (Stock No. 8340-377-6591).

1 each - Band, guy, complete (Stock No. 8340-030-1433).

2 each - Line, tent, 15 feet, with eye, 3/8-inch diameter (and guy line) (Stock No. 8340-252-2270).

9 each - Purlin, arch, 46 3/4 inches, complete (Stock No. 8340-359-2554).

2 each - Purlin, end complete (Stock No. 8340-183-0097).

8 each - Pin, tent, steel, 12 inch, M-1948 (Stock No. 8340-823-7451).

4 each - Runner, wood, 1 inch by 6 inch by 70 inches (Stock No. 8340-377-6607).

b. One section, Intermediate, Complete, for Tent, Frame Type, Insulated, Sectional, with Floor, 16 feet wide, M-1948, Complete (Stock No. 8340-377-6611) consists of the following:

2 each - Floor unit, complete (Stock No. 8340-377-6596).

1 each - Section, roof, tent, complete (Stock No. 8340-377-6591).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

1 each - Band, guy, complete (Stock No. 8340-030-1433).

9 each - Purlin, arch 46 3/4 inches, complete (Stock No. 8340-359-2554).

4 each - Pin, tent, steel, 12 inch, M-1948 (Stock No. 8340-823-7451).

4 each - Runner, wood, 1 inch by 6 inches by 70 inches (Stock No. 8340-377-6607).

c. One vestibule, complete, for Tent, Frame Type, Insulated, Sectional, with Floor, 16 feet wide, M-1948 Complete (Stock No. 8340-377-6612) consists of the following:

1 each - Cover, vestibule, end (Stock No. 8340-182-9300).

1 each - Cover, vestibule, top (Stock No. 8340-220-6518).

1 each - Panel and door, vestibule (Stock No. 8340-377-6604).

1 each - Panel, vestibule side (Stock No. 8340-377-6605).

1 each - Floor unit, vestibule (Stock No. 8340-377-6600).

1 each - Purlin, vestibule, top (Stock No. 8340-182-9316).

1 each - Purlin, vestibule, end (Stock No. 8340-182-9320).

1 each - Angle, tie (Drawing 5-4-187).

d. One arch, complete (Stock No. 8340-182-0436).

e. Number of arches required with the various sectional units (4-foot increments) to form a tent of various lengths are as follows:

2 each - Arches, complete, for the initial end section, complete (which includes first 4 foot increment of tent length)

1 each - Arch, complete, with each intermediate section, complete

1 each - Arch, complete, with the final end section, complete, which includes the last 4 foot increment of the tent

f. One each Electrical Outlet and Switch Assembly, Complete, for Tent, Frame-Type, Insulated, Sectional, with Floor, 16 feet wide, M-1948, complete (Stock No. 8340-508-0600).

Source: https://assist.dla.mil -- Downloaded: 20260-17T13:38Z
Check the source to verify that this is the current version before use.

6.8 Nomenclature. The approved nomenclature for identification marking and package marking shall be "Tent, Frame-Type, Insulated, Section".

* 6.9 International standardization agreements. Certain provisions of this document are the subject of international standardization agreement as cited in NATO, STANOG NO. 2882, relative to camouflage requirements for tents, shelters, and subsidiary components. When amendment, revision, or cancellation of this document is proposed that will affect or violate the international agreement concerned, the preparing activity will take appropriate reconciliation action through international standardization channels including departmental standardization offices, if required.

6.10 Changes from previous issue. The margins of this document are marked with an asterisk (*) to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only, and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content, as written, irrespective of the marginal notations and relationship of the last previous issue.

Custodians:

Army - GL
Navy - NU
Air Force - 99

Review activities:

Army - MD
Air Force - 82
DLA - CT

User activity:

Navy - MC

Preparing activity:

Army - GL

Project No. 8340-0478

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
US Army Natick Research and Development Center
Natick, Massachusetts 01760

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300
STRNC-ES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick Research and Development Center
ATTN: STRNC-ES
Natick, MA 01760

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions - Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-T-10168J	Tent, Frame-Type, Insulated, Sectional, With Floor, 16 Feet Wide, M1948, Complete

3a. NAME OF SUBMITTING ORGANIZATION

b. ADDRESS *(Street, City, State, ZIP Code)*

4. TYPE OF ORGANIZATION *(Mark one)*

- ☐ VENDOR
- ☐ USER
- ☐ MANUFACTURER
- ☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

NATICK/OP, 1 Apr 84

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:38Z
Check the source to verify that this is the current version before use.