25 September 1980
SUPERSEDING
MIL-C-55127C(EL)
5 August 1970

MILITARY SPECIFICATION

CONTROL, FREQUENCY SELECTOR C-2742( )/VRC

This specification is approved for use by Communications Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers one type of remote control unit, for use with Receiver-Transmitter RT-246( )/VRC in a tactical frequency-modulated communications system; designated as Control, Frequency Selector C-2742( )/VRC.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of Invitation for Bids, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

NN-P-71	Pallet, Material Handling, Wood, Stringer Construction, 2 Way and 4 Way (Partial)
PPP-B-20	Bag, Cotton
PPP-T-45	Tape, Gummed, Paper, Reinforced and Plain
PPP-T-97	Tape, Pressure-Sensitive Adhesive, Filament Reinforced.
PPP-F-320	Fiberboard, Corrugated and Solid, Sheet Stock (Container Grade) and Cut Shapes
PPP-B-566	Box, Folding, Paper board
PPP-B-585	Box, Wood, Wire bound
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, Nailed and Lock Corner

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Communications Research and Development Command, ATTN: DRDCO-CM, Fort Monmouth, New Jersey 07703, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

PPP-B-636	Box, Shipping, Fiberboard
PPP-B-640	Box, Fiberboard, Corrugated, Triple Wall
PPP-S-760	Strapping, Non-metallic, (And Connectors)
QQ-S-781	Cushioning, Material, Cellulosic

MILITARY

MIL-P-116	Preservation-packaging, Methods of
MIL-S-901	Shockproof Equipment, Class HI (High Impact), Shipload.
MIL-I-6869	Impregnants for Aluminum and Magnesium
MIL-P-11268	Parts, Materials and Processes Used in Electronic Equipment
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Electronic Equipment

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-147	Palletized Unit Loads
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects
MIL-STD-276	Impregnation of Porous Nonferrous Metal Castings
MIL-STD-454	Standard General Requirements for Electronic Equipments
MIL-STD-810	Environmental Test Methods
MIL-STD-1188	Commercial Packaging of Supplies and Equipment

DRAWINGS

ELECTRONICS COMMAND

SC-DL-415150	Control, Frequency Selector C-2742( )/VRC

(Copies of specifications, standards and drawings required by supplier in connection with specific procurement functions, should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:27Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Construction. The equipment shall be constructed in accordance with Drawing and Data List SC-DL-415150 and the requirements of this specification.

3.2 First Article. The contractor shall furnish four First Article samples of Control, Frequency Selector C-2742( )/VRC for approval, if required by the invitation for bids and contract (See 4.3)

3.3 Parts, Materials and Processes; General. In addition to the requirements of this specification, the requirements of MIL-P-11268, including the selection requirement therein shall apply.

3.4 Finish, Protective. Equipment shall be given protective finish in accordance with Specification MIL-F-14072. This includes finish of hardware, such as handles, hinges, screws, etc, and necessary touch up after mounting. The final paint film on Type I surfaces shall be forest green lusterless enamel.

3.5 Marking.

3.5.1 General. Marking shall conform to Specification MIL-M-13231. (See 4.4) Front panel marking shall be group I as described in that Specification.

3.5.2 Visibility. Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.5.3 Serial Numbers. Control, Frequency selector, C-2742( )/VRC shall be serial numbered.

3.6 Die Castings. (See 4.4).

3.6.1 Quality of Die Castings. Quality of die castings shall be as follows:

(a) Surface condition shall be clean, dry and free from chips.

(b) Cast surface finish shall be of a painting grade which allows some streaks and chill marks which can be covered and hidden by paint.

(c) Flash must be removed by grinding or filing.

(d) The casting, after impregnation, shall be air tight, and no leakage shall be allowed under a pressure of 10 psi gage.

Source: https://assist.dla.mil -- Downloaded: 20260-22T22:27Z
Check the source to verify that this is the current version before use.

(e) Flatness shall be as specified in the government furnished drawings.

(f) Dimensions shall be as specified in the government furnished drawings.

3.6.2 Impregnation of Aluminum Die Castings. All aluminum sand and die castings shall be impregnated in accordance with Standard MIL-STD-276, using impregnant material Type II per Specification MIL-I-6869. Castings which have been impregnated shall be marked "IMP". The impregnation shall be to correct general seepage only and shall not be used to correct poor foundry techniques or significant porosity (See 4.4).

3.7 Service Conditions. The equipment shall meet the following service conditions.

3.7.1 Temperature. The equipment shall be subjected to the temperature procedure as shown in Method 501 and 502 of MIL-STD-810. Measurements shall be taken with the equipment operating with 22-volt input and with 30-volt input.

(a) Low. During testing as specified in 4.12.1.1, the equipment shall meet the control function requirements of 3.9.

(b) High. During testing as specified in 4.12.1.2, the equipment shall meet the control function requirements of 3.9.

3.7.2 Humidity (Moisture Resistance). During testing as specified in 4.12.2, the equipment shall meet the control function requirements of 3.9.

3.7.3 Altitude (Elevation). The equipment shall meet the control function requirements of 3.9, both during and after testing as specified in 4.12.3.

3.7.4 Vibration and Shock.

3.7.4.1 Vibration, Internal. The equipment shall withstand vibration associated with vehicular transport as tested in accordance with para. 4.12.4. There shall be no physical damage and the equipment shall meet the requirements of paragraph 3.9.

3.7.4.2 Shock. The equipment shall be capable of meeting the requirements of Table I.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:27Z
Check the source to verify that this is the current version before use.

TABLE I - SHOCK

PARAGRAPH HEADING	PARAGRAPH	PERFORMANCE AFTER TEST
Shock, basic design	4.12.5	Specified performance. (Note A) No physical damage
Shock	4.12.6	Operable (Note A). Any physical damage shall be minor only, as classified in MIL-STD-252.

Note A: The equipment shall meet the following tests: Control Function (4.11)

3.7.5 Immersion. The equipment shall show no evidence of leakage after it is tested as specified in 4.12.7.

3.8 Preconditioning. (See 4.8)

3.8.1 Bounce Preconditioning. The equipment shall be capable of meeting the requirements herein, without subsequent processing, after subjection to the bounce preconditioning of 4.8.

3.9 Control Functions (See 4.11). The control shall provide the following operating functions:

3.9.1 Remote selection of any one of ten preset channels by operation of the CHAN SEL switch. (See 4.11.1)

3.9.2 Remote selection HI or LO transmit power level. (See 4.11.2)

3.9.3 Remote ON or OFF control of input dc power. (See 4.11.3)

3.9.4 When two Controls (C-2742( )/VRC) are interconnected, the second unit shall be capable of providing the same operating functions as the first, with the exception of the ON or OFF control of input dc power. (See 4.11.4)

3.10 Interchangeability. Like unit assemblies, subassemblies and replaceable parts shall conform to Requirement 7 of MIL-STD-454. (See 4.13)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

3.11 Air-Seal Test. When tested as specified in 4.9, the decrease in vacuum shall not exceed 0.01 pounds per square inch.

3.12 Technical Literature and Running Spare Parts. Technical literature and running spare parts shall be furnished if specified in the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order. (See 6.2)

3.13 Fungus. Equipment and assemblies shall show no evidence of viable fungus or corrosion * when subjected to 28 days of fungus test in accordance with 4.12.9.

*Corrosion is defined as any visible degradation that can be attributed to flaky, pitted, blistered, or otherwise loosened finish or metal surface.

3.14 Salt Fog. The equipment and assemblies shall be exposed, in their operating configuration, to 48 hours of salt fog in accordance with paragraph 4.12.8 and shall show no evidence of corrosion as evidenced by any visible degradation that can be attributed to flaky, pitted, blistered or otherwise loosened finish or metal surface. There shall also be no impairment of operation of any control feature of the equipment.

3.15 Workmanship. The equipment shall be manufactured and assembled in accordance with Requirement 9 of MIL-STD-454 and the applicable portions of the following paragraphs:

(a) In MIL-P-11268:

General requirements for plastic material and plastic parts.
Wiring and cabling, including:
- Slack.
- Protection.

Splicing.
Connections, general.
Grounding, general.
Shielding on wire and cable.
Soldering and brazing.
Cleaning of units.
General requirements for securing of parts.
Controls.
Self-tapping screws.

(b) In this specification:

3.4	Finish, protective
3.5	Marking
3.6	Die Casting

Source: https://assist.dla.mil -- Downloaded: 202640-22T22:27Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.2 Classification of Inspection. Inspection shall be classified as follows:

(a) First Article inspection (does not include packaging)(See 4.3)

(b) Inspection covered by subsidiary documents. (See 4.4)

(c) Quality conformance inspection.

(1) Quality conformance inspection of equipment before packaging (See 4.5).

(2) Quality conformance inspection of preparation for delivery. (See 4.15)

4.3 First Article Inspection. This inspection shall consist of the inspection specified in the subsidiary documents covering the item listed in 4.4, and the inspection specified for group A, group B and group C (See Tables III, IV and V respectively). The first article inspection shall be performed in the order shown in Table II according to the number of samples specified in the contract or order.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

TABLE II - Order of Environmental Tests

Inspection	NUMBER OF SAMPLES			
	Unit 1	Unit 2	Unit 3	Unit 4
Non-damaging				
Temperature				
Low				1
High				2
Altitude (elevation)				3
Potentially damaging				
Vibration (internal)	1			
Bounce	2			
Shock, basic design	3			
Humidity (Moisture-Resistance)		1		
Fungus			1	
Immersion	4			
Salt Fog				4

Note 1: Other first article inspection may precede, follow, or be interspersed between the non-damaging tests.

Note 2: The order on non-damaging tests and the choice of units subjected to the non-damaging tests may be varied if convenient, except that the vibration test should be performed on the same unit used for the bounce and shock tests.

Note 3: The vibration test shall be performed on the same unit used for the basic design and ballistic shock tests as shown for sample unit 1.

4.4 Inspection Covered by Subsidiary Documents. The following shall be inspected under the applicable subsidiary documents as part of the inspection of equipment before preparation for delivery:

Item	Where Required
Parts, Materials and Process used in Electronic Equipment	3.3
Finish	3.4
Marking	3.5
Casting Impregnation and Quality	3.6

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:27Z
Check the source to verify that this is the current version before use.

4.5 Quality Conformance Inspection of Equipment Before Packaging. Each equipment produced under this specification shall be subjected to bounce preconditioning (See 3.8) prior to selection of samples for inspection. The contractor shall perform the inspection specified in 4.6 and 4.7 through 4.7.2. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government - at its discretion - may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.9) Test equipment for Government verification inspection shall be made available by the contractor.

4.6 Group A Inspection. Each unit on contract or purchase order shall be inspected for conformance to the inspection specified in Table III. Discrete lots shall be formed from units that pass this inspection. Factors of lot composition not defined herein or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subjected to sampling inspection utilizing the procedures of MIL-STD-105, using the general inspection levels, and AQLs indicated in Table III. Group A inspection shall be performed in any order which is satisfactory to the government except that the air seal shall be last.

TABLE III - Group A Inspection

INSPECTION	REQ PARA	INSP PARA	AQL Major	AQL Minor
Visual and Mechanical	3.15	4.15	1%	4%
Electrical Control Functions				
Selection of present channels	3.9.1	4.11.1	1.0% for	
HI-LO power selection	3.9.2	4.11.2	the group	N/A
Power ON-OFF	3.9.3	4.11.3	combined	
Dual control	3.9.4	4.11.4		
Air Seal	3.11	4.9	1%	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

4.7 Group B Inspection. This inspection, including sampling, shall conform to Table IV and to the special procedures for small-sample inspection of Standard MIL-STD-105. Group B inspection shall normally be performed on inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection. Levels shall be S-4.

TABLE IV - Group B Inspection

INSPECTION	REQ PARA	INSP PARA	AQL
Interchangeability	3.10	4.13	6.5%
Immersion	3.7.5	4.12.7	10.0%

4.7.1 Order of Inspection Within Group B. Group B inspection shall be performed in any order which is satisfactory to the Government.

4.7.2 Group C Inspection. This inspection shall consist of the tests specified in Table V and shall be performed on sample units that have been subjected to and met Group A and Group B inspection. Sample units shall be selected in accordance with paragraph 4.7.2.1.

4.7.2.1 Sampling for Inspection of Equipment. Units selected for each Group C inspection shall be selected without regard to their quality in accordance with the following:

TABEL V - Group C Inspection

INSPECTION	REQUIREMENT PARAGRAPH	INSPECTION PARAGRAPH
Subgroup I		
Shock, basic design	3.7.4.2	4.12.5
Subgroup II		
Temperature	3.7.1	4.12.1
Moisture resistance	3.7.2	4.12.2
Altitude	3.7.3	4.12.3
Vibration internal	3.7.4.1	4.12.4
Shock ballistic	3.7.4.2	4.12.6

Source: https://assist.dla.mil -- Downloaded: 202640-22T22:27Z
Check the source to verify that this is the currentversion before use.

Subgroup III

Salt Fog	3.14 (*)	4.12.8
Fungus	3.13 (*)	4.12.9

* Unless otherwise specified in contract or order, a different sample unit shall be used for each of these tests.

4.7.2.1.1 Subgroup I. For this subgroup two units shall be selected from the first 50 production units for the first Group C inspection. For subsequent Group C inspection, two units from each successive 250, or two units per month if less than 250 are produced monthly, shall be selected.

4.7.2.1.2 Subgroup II. For this subgroup, two units shall be selected from the first 50 production units for the first Group C inspection. For subsequent Group C inspections, two units every 6 months shall be selected.

4.7.2.1.3 Subgroup III. For this subgroup two units shall be selected from the first production lot for the first Group C inspection.

4.7.3 Noncompliance. Actions relative to Group C failures shall be as specified in the contract or purchase order.

4.7.3.1 Reinspection of Conforming Group B and Group C Sample Units. Unless otherwise specified, sample units which have been subjected to and passed both group B and Group C inspection may be accepted on contract or order provided all damage is repaired and the sample units are resubjected to and pass group A inspection.

4.8 Bounce Preconditioning. The unit, with shock mounts (if any) removed or blocked, shall be placed on its cover on the table of the Package Tester, Type 1000-SC, as made by the L.A.B. Corporation, Skaneatales, New York, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32-inch-thick strip of material under one corner or edge of the unit to a distance of 3 inches as the unit bounces. The unit shall be subjected to this preconditioning for 1 minute. After bounce preconditioning, the unit shall not be repaired, cleaned, or otherwise changed prior to subjection to inspection. (See 3.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

4.9 Air-Seal Test. The equipment shall be opened and closed again in such manner as to break and remake the seal. Immediately thereafter, the equipment as field transported shall be subjected to a vacuum of 1 pound per square inch (1 pound per square inch less than the atmospheric pressure surrounding the equipment) applied to the interior of the transit case or to the interior of the equipment inclosure when no transit case is provided. The vacuum then shall be valved-off and the interior pressure measured during the ensuing period of 1 minute. During this 1-minute period the decrease in vacuum shall not exceed 0.01 pound. The gage used for measurement of the vacuum shall be of such accuracy that a difference of 0.01 pound can be determined readily. Control lamp cover shall be removed to provide connection for air seal test C-2742( )/VRC. (See 3.11)

4.10 Standard Test Conditions. Unless otherwise specified, all tests shall be conducted at 25.5 volts dc input and room ambient conditions of temperature and humidity.

4.11 Control Functions (See 3.9).

4.11.1 Selection of Preset Channels. With 25.5v dc applied to Unit; set CHAN SEL Switch to position 1, (extreme CC-W), operate the CONTROL SW and measure 25.5 volts dc at channel No. 1 lead. Repeat for all ten preset channel positions to determine compliance with 3.9.1.

4.11.2 HI-LO Power Section. Compliance with 3.9.2 shall be determined by turning the PWR SW switch to LO position and momentarily operating CONTROL SW. There shall be no continuity to ground at the HI power lead. Turn switch to HI position: there shall be continuity to ground at the HI power lead.

4.11.3 Power On-Off. Compliance with 3.9.3 shall be checked by the following method. With the switch in the OFF position, there shall be no continuity to ground at the power-on lead. With the switch to LO or HI position check for continuity at the power-on lead.

4.11.4 Dual Control (See 3.9.4). With two Controls (C-2742( )/VRC) interconnected, feed 22 volts dc to the first unit and operate CONTROL SW. The light on that unit shall be on, and the light on the second unit shall be out. When the CONTROL SW on the second unit is operated, the light on the second unit shall be on; and the light on the first shall be out. Repeat test on the first unit.

Source: https://assist.dla.mil -- Downloaded: 202640-22T22:27Z
Check the source to verify that this is the current version before use.

4.12 Service Test Conditions.

4.12.1 Temperature Test.

4.12.1.1 Low Temperature. The equipment shall be tested in accordance with Method 502, Procedure 1, of MIL-STD-810. The storage temperature shall be -80°F, and the operating temperature shall be -40°F. Prior to testing the equipment shall meet full specification performance for the measurements specified in 3.7.1a.

4.12.1.2 High Temperature. The equipment shall be tested in accordance with Method 501. Procedure II, of MIL-STD-810. The operating temperature shall be +150°F. Prior to testing the equipment shall meet full specification performance for the measurements specified in 3.7.1b.

4.12.2 Humidity (Moisture-Resistance) Test. The equipment shall be tested in accordance with Method 507, Procedure II of MIL-STD-810. Prior to testing the equipment shall meet full specification performance for the measurements specified in 3.7.2. Measurements shall be made during the periods shown on the figure for the cycle. Do not move equipment from the humidity chamber for measurements, and do not leave power on after measurements have been completed. If any equipment fails to meet the specified performance during cycling, it shall be realigned or readjusted once and the test continued. No repair or replacement of parts shall be permitted. If the equipment still fails to meet the specified performance during cycling or fails subsequently, it does not pass the test. In addition, if the equipment fails to meet specified requirements after final conditioning it does not pass the test. The test shall be performed with the cover off.

4.12.3 Altitude (Elevation) Test. The equipment shall be tested in accordance with Method 500, Procedure I of MIL-STD-810. Prior to testing the equipment shall meet full specification performance for the measurements specified in 3.7.3.

4.12.4 Vibration. The equipment shall be tested in accordance with Method 514. Procedure VIII, using Curve W, of MIL-STD-810. (See 3.7.4.1)

4.12.5 Shock, basic design. The equipment shall be tested in accordance with Method 516, procedure I, figure 516.2-1, parameters b and d of MIL-STD-810. (see 3.7.4.2)

4.12.6 Shock Test Ballistic.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

(a) Test Method. The test shall be conducted on the "Shock testing Machine for Light Weight Equipment" shown in Specification MIL-S-901. The control unit shall be secured in its normal operating position to test plate fixture 4a, figure 5 of MIL-S-901, by means of the same fasteners used for vehicular installation of the control. The test shall consist of a total of 9 blows: one each 1 foot blow, 3 foot blow, and 5 foot blow on the back, side and top of the test plate. As an alternative to reorienting the plate for the blows on the side of the plate, equivalent rotation of the control under test is permissable. (See 3.7.4.2).

(b) Performance. Upon completion of the test and before repairs are made, tests shall be made for compliance with the following test: Paragraph 4.11 (Control Functions).

4.12.7 Immersion Test (See 3.7.5). The equipment, as prepared for field transportation shall be tested in accordance with Method 512, Procedure I, of MIL-STD-810.

4.12.8 Salt Fog. The equipment and assemblies shall be exposed in their operating configuration to salt fog in accordance with Method 509, Procedure I of MIL-STD-810 for 48 hours. (See 3.14).

4.12.9 Fungus. The equipment and assemblies shall be subjected to 28 days of the fungus test specified in Method 508 of MIL-STD-810. For gasket or other non-hermetically sealed equipments, the parts and materials of the chassis shall be sprayed with the spore suspension. The interior of the case shall also be sprayed. Teh equipment shall be subjected to the test in this open condition for compliance with Paragraph 3.13.

4.13 Inspection For Interchangeability. The points listed below shall be gaged or measured to determine compliance with the physical interchangeability requirements of 3.10. When a listed dimension is not within specified or design limits it shall be considered a major defect.

(a) Case. The maximum overall outside dimensions and location of four mounting screw holes.

(b) Bottom Cover. The maximum overall outside dimension, length and width, and location of four mounting screws.

Source: https://assist.dla.mil -- Downloaded: 202640-22T22:27Z
Check the source to verify that this is the currentversion before use.

(c) Plug-In Relay. The maximum overall outside dimensions, location of mounting screw hole in reference to pins.

4.14 Visual and Mechanical Inspection. The equipment shall be examined for the defects listed in Standard MIL-STD-252.

4.15 Quality Conformance Inspection. Quality conformance inspection of Section 5 requirements shall be in accordance with Group A, Group B, and when required (see 6.1( )), the Group C (rough handling) requirements of MIL-P-116. Inspection lots shall be in accordance with MIL-P-116.

5. PACKAGING.

5.1 Packaging Requirements. The requirements for packaging shall be in accordance with SPI1G0031.

6. NOTES

6.1 Intended Use. The Control, Frequency Selectro C-2742( )/VRC is normally used as part of the AN/VRC-12 Vehicular communication system.

6.2 Ordering Data. Procurement documents should specify the following:

(a) Title, number, and date of this specification any any amendment thereto.

(b) Type required.

(c) Level A or level B preservation and packing (see section 5).

(d) Preproduction pack(s) as follows:

Makeup of pack(s).
Number of each kind of pack to be submitted.
Inspection to be performed thereon.

(e) Marking and shipping of samples.

(f) Place of final inspection

(g) Technical literature required. (See 3.12).

(h) Quantity of running spare parts required. (See 3.12).

(i) When rough handling test is required (see 4.15).

(j) Size data. Size limitations cited herein are based on the dimensions of the equipment for which these requirements were established. Requests to exceed these limitations must be supported by data indicating why limitations cannot be met and recommend a revised limitation.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:27Z
Check the source to verify that this is the current version before use.

6.3 Definitions.

6.3.1 Equipment Divisions. The terms used herein for equipment division conform to Standard MIL-STD-280.

6.3.2 Definitions. Inspection terms used herein conform to Standard MIL-STD-109. The following are abbreviated definitions selected from those given therein for immediate reference.

6.3.2.1 Inspection. Inspection is the examination or testing, or both, of supplies to determine compliance with applicable requirements. Sampling is an element of inspection.

6.3.2.2 Examination. Examination consists of simple, generally non-destructive determinations of compliance, without use of special testing equipment.

6.3.2.3 Testing. Testing consists of determinations of compliance, using technical means.

6.4 Humidity. Natural climatic extremes may include 100-percent relative humidity with condensation up to 4 hours at a time. This requirement (See 3.7.2) is specified by Standard MIL-STD-210. The moisture resistance test (See 4.12.2) using Standard MIL-STD-810 is a procedure that gives a practical test approximating the natural conditions.

6.5 Group C Inspection. Approval to ship may be withheld, at the discretion of the Government pending the decision from the contracting officer on the adequacy of corrective action (See 4.7.3).

6.6 Location of Air-Seal Test. It is desirable that the air-seal test (4.9) be performed at a location that will minimize handling (which might cause damage to the equipment) after this inspection is completed. Any preparation for shipment which would require breaking of the equipment seal should be accomplished prior to the air-seal test so that the seal may remain intact thereafter. It is recommended that the entire lot (including all previously inspected sample units) be sampled and inspected immediately prior to packaging.

6.7 Nomenclature. The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design: for example: C-2742W/VRC. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1)

Source: https://assist.dla.mil -- Downloaded: 20260-22T22:27Z
Check the source to verify that this is the current version before use.

6.8 Verification Inspection. Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

6.9 Environmental. Environmental pollution prevention measures are contained in the packaging material specifications referenced herein. Refer to material specifications or preparing activity for recommended disposability methods.

CUSTODIAN
ARMY-CR
REVIEW ACTIVITIES

PREPARING ACTIVITY
ARMY-CR
PROJECT NO. 5820-A715

☆U.S. GOVERNMENT PRINTING OFFICE: 1980—703-023/4497

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

HQ, USA CORADCOM
ATTN: DRDCO-COM-DM
Fort Monmouth, NJ 07703

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1426 1 OCT 76

EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:27Z
Check the source to verify that this is the current version before use.

FOLD

HQ. USA CORADCOM
ATTN: DRDCO-CM-DM
Fort Monmouth, NJ 07703

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

POSTAGE AND FEES PAID



HQ. USA CORADCOM
ATTN: DRDCO-CM-DM
Fort Monmouth, NJ 07703

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:27Z
Check the source to verify that this is the current version before use.