MILITARY SPECIFICATION

CONTAINER, AMMUNITION, METAL, PA: 17

1. SCOPE

1.1 This specification covers the metal parts for one type of Container designated as Container, Ammunition, Metal: PA17.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

TT-C-490 - Cleaning Methods and Pretreatment of Ferrous Surfaces for Organic Coatings

MILITARY

MIL-A-2550 - Ammunition and Special Weapons General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

FEDERAL

FED-STD-151 - Metals; Test Methods

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-171 - Systems for Preparation, Painting and Finishing Metal and Wood Surfaces
MIL-STD-414 - Sampling Procedures and Tables for Inspection by Variables for Percent Defective

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9224831 - Container, Ammunition, Metal, PA17

PUBLICATIONS

ARMY

ET-9224831 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts and assemblies.-The parts and assemblies shall comply with all requirements specified on Drawing (dwg.) 9224831, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Pressure retention.-The metal container shall withstand a positive internal pressure of 30 $\pm$ 1 psi with a leakage rate not greater than 0.1 psi for a period of 15 minutes when tested as specified in 4.4.2.

3.4 Functioning.-The cover of the container shall open, close and be removed without binding or requiring exertion of undue force. Gaskets shall not stick to top edges of bodies, be cut or split nor have shifted within the gasket retainer when the cover is removed when tested as specified in 4.4.9.

3.5 Welding.-The welds shall be reasonably uniform, smooth and free from craters. They shall exhibit characteristics of fusion, penetration, and soundness of weld deposits representative of good welding practice. All welding fluxes, scale and excessive weld spatter, acids or basic solution shall be completely removed prior to application of any finish. All welding shall be in

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

accordance with applicable specifications. All welding shall be performed by operators currently certified as Class B operators in accordance with Military Specification MIL-T-5021.

3.6 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, nicks, sharp edges, cracks, dirt, surface defects, grease, rust and other foreign matter.

3.7 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 in order to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchase by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certifcate shall be substantiated by evidence of the agent's authority to bind his

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

principal. Substantiation of the agent's autority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of the following:

Test	Sample
Gasket compression	Ten (10) Metal Containers
Pressure retention	Fifty (50) Metal Containers
Salt Spray	Two (2) Body Assemblies and Cover Assemblies, less gasket
Functioning	Twenty (20) Metal Container Assemblies

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "Lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications, and same specification revisions. Changes to the process, specifications, or drawings, not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the lot. Inspection lots shall comply with MIL-STD-105.

Unless otherwise approved by the Contracting Officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period, nor more than the largest monthly quantity contractually scheduled for delivery during the contract period. Inspection lots of components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size mutually covenient to both the contractor and the Government inspector. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with MIL-STD-105 (ABC-STD-105), except that, inspection for Critical defects shall be 100 percent. Contractor's sampling plans, if used, shall be approved by the Government, and shall provide,

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

as a minimum, the protection afforded the Government by the sampling plans in MIL-STD-105. Continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each Major defect and an AQL of 0.65 percent for each Minor defect except where 100% inspection is specified. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Cover (see dwg. 9223891)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Location of slots	Gage	01001
102.	Diameter between slots	Gage	01002
103.	Width of slots	Gage	01003
104.	Outside diameter	Gage	01004
Minor:	AQL 4.00 Percent		
201.	Thickness of bottom	Gage	01005
202.	Depth of counterbore	Gage	01006
203.	Thickness (alternate construction)	Gage	01007
204.	Diameter of largest hole	Gage	01008
205.	Diameter of second largest hole	Gage	01009
206.	Diameter of smallest hole	Gage	01010
207.	Improper weld	Visual	01011
208.	Evidence of poor workmanship	Visual	01012

4.3.2.2 Ring (See dwg. 9223880)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Largest inside diameter	Gage	02001
102.	Second largest inside diameter	Gage	02002
103.	Height of welded strip	Gage	02003
104.	Location of slots	Gage	02004
Minor:	AQL 1.50 Percent		
201.	Width of slots	Gage	02005
202.	Diameter between slots	Gage	02006
203.	Improper weld	Visual	02007
204.	Evidence of poor workmanship	Visual	02008

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

4.3.2.3 Body Assembly (see dwg. 9223874)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Location of ring	Gage	03001
102.	Gauge boss missing	Visual	03002
103.	Depth of container	Gage	03003
104.	Holes in container and gage block missing	Visual	03004
Minor:	AQL 1.50 Percent		
201.	Any part missing or improperly assembled	Visual	03005
202.	Improper weld	Visual	03006
203.	Evidence of poor workmanship	Visual	03007

4.3.2.4 Container, Ammunition, Metal: PA17 (see dwg. 9224831)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Any part missing or improperly assembled	Visual	04001
102.	Torque on equalizing pressure valve	Test	04002
Minor:	AQL 1.00 Percent		
201.	Protective finish missing	Visual	04003
202.	Evidence of poor workmanship	Visual	04004

4.3.3 Testing

4.3.3.1 Gasket compression (see dwg. 9224831), Major defect, Code No. 05001.-The sampling plan for this test shall be in accordance with MIL-STD-414, Part II, Section B with an AQL of 1.50 Percent. The test shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4.

4.3.3.2 Pressure retention (see paragraph 3.3), Major defect, Code No. 06001.-Twenty-five (25) metal containers shall be selected from each lot and subjected to this test. If one (1) or more containers fail to comply with the applicable requirements, the lot shall be rejected. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

4.3.3.3 Salt Spray (see dwg. 9224832 and 9223874, less gasket), Major defect, Code No. 07001.-The sampling and rejection criteria shall be in accordance with TT-C-490. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4.

4.3.3.4 Functioning (see para. 3.4), Major defect, Code No. 08001.-The sampling plan for this test shall be in accordance with MIL-STD-105, single plan, with an AQL of 1.00 percent. The test shall be performed as specified in 4.4.9.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 9229066 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.3 Government use of contractor's inspection and test equipment.-The contractor shall, when required by the Government, make available all inspection and test equipment necessary for determining conformance with the contract requirements. Personnel for operating the equipment, and verification of its accuracy shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures

4.4.1 Gasket compression.-The gage shown on the Equipment List will be used to determine the gasket compression. The following procedure will be used:

a. With the container resting on a surface plate or other suitable stabilized platform (see 6.5) place the cover on with the components in the unlatched position. Measure the height of the container from the platform to the top of the cover in 4 places, 2 readings being taken on each side of the box at 4 inches from the ends of the box. Add the measurements and divide by 4. This is the average closed height of the container.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

b. Without moving the container from the location used to determine the free height, close the container by engaging the hasps and latches. Remeasure the container at the same positions measured to determine the free height of the container. Add these measurements and divide by 4. This is the average closed height of the container.

c. Subtract the average closed height of the container from the average free height of the container. The result will be considered the gasket compression. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.2 Pressure retention.-The metal container shall be placed in the fixture shown on the Equipment List and a measured quantity of air shall be applied to produce the required air pressure. Observation shall be made for bubbles escaping from the interior of the container. This test in a non-destructive test. Parts so tested may be returned to the lot.

4.4.3 Salt spray.-The parts selected shall be subjected to the salt spray test in accordance with Standard No. 151, Method 811.1 using a 5% sodium chloride solution. This is a destructive test. Parts so tested shall not be returned to the lot.

4.4.4 Functioning.-The metal container assembly will be tested by opening and closing both latch assemblies to check functioning of hasp and latch assemblies and ease removal of cover. Also to assure that the gaskets are snug within the gasket retainer and that the gaskets do not adhere to the top edges of the bodies. This test is a non-destructive test. Parts so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Packing

5.1.1 Level C.-Pack individually in accordance with MIL-STD-1169.

5.2 Marking.-Marking of the carton or boxes shall be in accordance with MIL-STD-1169.

5.3 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

c. Provisions for submission of First Article Samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the number of drawings for Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.

MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.

mandatory Army designs, the contractor shall comply with and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor-prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND8. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-247

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:06Z
Check the source to verify that this is the current version before use.